

# PIC16(L)F1934/6/7 Data Sheet

28/40/44-Pin Flash-Based, 8-Bit CMOS Microcontrollers with LCD Driver and nanoWatt XLP Technology

#### Note the following details of the code protection feature on Microchip devices:

- Microchip products meet the specification contained in their particular Microchip Data Sheet.
- Microchip believes that its family of products is one of the most secure families of its kind on the market today, when used in the intended manner and under normal conditions.
- There are dishonest and possibly illegal methods used to breach the code protection feature. All of these methods, to our knowledge, require using the Microchip products in a manner outside the operating specifications contained in Microchip's Data Sheets. Most likely, the person doing so is engaged in theft of intellectual property.
- Microchip is willing to work with the customer who is concerned about the integrity of their code.
- Neither Microchip nor any other semiconductor manufacturer can guarantee the security of their code. Code protection does not
  mean that we are guaranteeing the product as "unbreakable."

Code protection is constantly evolving. We at Microchip are committed to continuously improving the code protection features of our products. Attempts to break Microchip's code protection feature may be a violation of the Digital Millennium Copyright Act. If such acts allow unauthorized access to your software or other copyrighted work, you may have a right to sue for relief under that Act.

Information contained in this publication regarding device applications and the like is provided only for your convenience and may be superseded by updates. It is your responsibility to ensure that your application meets with your specifications. MICROCHIP MAKES NO REPRESENTATIONS OR WARRANTIES OF ANY KIND WHETHER EXPRESS OR IMPLIED, WRITTEN OR ORAL, STATUTORY OR OTHERWISE, RELATED TO THE INFORMATION, INCLUDING BUT NOT LIMITED TO ITS CONDITION. QUALITY, PERFORMANCE, MERCHANTABILITY FITNESS FOR PURPOSE. Microchip disclaims all liability arising from this information and its use. Use of Microchip devices in life support and/or safety applications is entirely at the buyer's risk, and the buyer agrees to defend, indemnify and hold harmless Microchip from any and all damages, claims, suits, or expenses resulting from such use. No licenses are conveyed, implicitly or otherwise, under any Microchip intellectual property rights.

### Trademarks

The Microchip name and logo, the Microchip logo, dsPIC, Keeloq, Keeloq logo, MPLAB, PIC, PICmicro, PICSTART, PIC<sup>32</sup> logo, rfPIC and UNI/O are registered trademarks of Microchip Technology Incorporated in the U.S.A. and other countries.

FilterLab, Hampshire, HI-TECH C, Linear Active Thermistor, MXDEV, MXLAB, SEEVAL and The Embedded Control Solutions Company are registered trademarks of Microchip Technology Incorporated in the U.S.A.

Analog-for-the-Digital Age, Application Maestro, CodeGuard, dsPICDEM, dsPICDEM.net, dsPICworks, dsSPEAK, ECAN, ECONOMONITOR, FanSense, HI-TIDE, In-Circuit Serial Programming, ICSP, Mindi, MiWi, MPASM, MPLAB Certified logo, MPLIB, MPLINK, mTouch, Omniscient Code Generation, PICC, PICC-18, PICDEM, PICDEM.net, PICkit, PICtail, REAL ICE, rfLAB, Select Mode, Total Endurance, TSHARC, UniWinDriver, WiperLock and ZENA are trademarks of Microchip Technology Incorporated in the U.S.A. and other countries.

 $\ensuremath{\mathsf{SQTP}}$  is a service mark of Microchip Technology Incorporated in the U.S.A.

All other trademarks mentioned herein are property of their respective companies.

© 2008-2011, Microchip Technology Incorporated, Printed in the U.S.A., All Rights Reserved.

Printed on recycled paper.

ISBN: 978-1-61341-013-4

Microchip received ISO/TS-16949:2002 certification for its worldwide headquarters, design and wafer fabrication facilities in Chandler and Tempe, Arizona; Gresham, Oregon and design centers in California and India. The Company's quality system processes and procedures are for its PIC® MCUs and dsPIC® DSCs, KEŁLOQ® code hopping devices, Serial EEPROMs, microperipherals, nonvolatile memory and analog products. In addition, Microchip's quality system for the design and manufacture of development systems is ISO 9001:2000 certified.

# QUALITY MANAGEMENT SYSTEM CERTIFIED BY DNV ISO/TS 16949:2002



# 28/40/44-Pin Flash-Based, 8-Bit CMOS Microcontrollers with LCD Driver with nanoWatt XLP Technology

#### **Devices Included In This Data Sheet:**

- PIC16F1934
- PIC16LF1934
- PIC16F1936
- PIC16LF1936
- PIC16F1937
- PIC16LF1937

### Other PIC16(L)F193X Devices Available:

- PIC16(L)F1933 (DS41575)
- PIC16(L)F1938/9 (DS41574)

Note:

PIC16(L)F193X devices referred to in this data sheet apply to PIC16(L)F1934/6/7.

### **High-Performance RISC CPU:**

- · Only 49 Instructions to Learn:
  - All single-cycle instructions except branches
- · Operating Speed:
  - DC 32 MHz oscillator/clock input
  - DC 125 ns instruction cycle
- Up to 16K x 14 Words of Flash Program Memory
- Up to 1024 Bytes of Data Memory (RAM)
- Interrupt Capability with Automatic Context Saving
- 16-Level Deep Hardware Stack
- · Direct, Indirect and Relative Addressing modes
- Processor Read Access to Program Memory
- Pinout Compatible to other 28/40/44-pin
   PIC16CXXX and PIC16FXXX Microcontrollers

### **Special Microcontroller Features:**

- · Precision Internal Oscillator:
  - Factory calibrated to ±1%, typical
  - Software selectable frequency range from 32 MHz to 31 kHz
- · Power-Saving Sleep mode
- Power-on Reset (POR)
- Power-up Timer (PWRT) and Oscillator Start-up Timer (OST)
- Brown-out Reset (BOR)
  - Selectable between two trip points
  - Disable in Sleep option
- · Multiplexed Master Clear with Pull-up/Input Pin
- · Programmable Code Protection
- High Endurance Flash/EEPROM cell:
  - 100,000 write Flash endurance
  - 1,000,000 write EEPROM endurance
  - Flash/Data EEPROM retention: > 40 years
- · Wide Operating Voltage Range:
  - 1.8V-5.5V (PIC16F193X)
  - 1.8V-3.6V (PIC16LF193X)

### PIC16LF193X Low-Power Features:

- · Standby Current:
  - 60 nA @ 1.8V, typical
- · Operating Current:
  - 7.0 μA @ 32 kHz, 1.8V, typical (PIC16LF193X)
  - 150 μA @ 1 MHz, 1.8V, typical (PIC16LF193X)
- Timer1 Oscillator Current:
  - 600 nA @ 32 kHz, 1.8V, typical
- Low-Power Watchdog Timer Current:
  - 500 nA @ 1.8V, typical (PIC16LF193X)

### **Peripheral Features:**

- Up to 35 I/O Pins and 1 Input-only Pin:
  - High-current source/sink for direct LED drive
  - Individually programmable interrupt-on-pin change pins
  - Individually programmable weak pull-ups
- · Integrated LCD Controller:
  - Up to 96 segments
  - Variable clock input
  - Contrast control
  - Internal voltage reference selections
- Capacitive Sensing module (mTouch™)
  - Up to 16 selectable channels
- A/D Converter:
  - 10-bit resolution and up to 14 channels
  - Selectable 1.024/2.048/4.096V voltage reference
- Timer0: 8-Bit Timer/Counter with 8-Bit Programmable Prescaler
- · Enhanced Timer1
  - Dedicated low-power 32 kHz oscillator driver
  - 16-bit timer/counter with prescaler
  - External Gate Input mode with toggle and single shot modes
  - Interrupt-on-gate completion
- Timer2, 4, 6: 8-Bit Timer/Counter with 8-Bit Period Register, Prescaler and Postscaler
- Two Capture, Compare, PWM modules (CCP)
  - 16-bit Capture, max. resolution 125 ns
  - 16-bit Compare, max, resolution 125 ns
  - 10-bit PWM, max. frequency 31.25 kHz
- Three Enhanced Capture, Compare, PWM modules (ECCP)
  - 3 PWM time-base options
  - Auto-shutdown and auto-restart
  - PWM steering
  - Programmable dead-band delay

### Peripheral Features (Continued):


- Master Synchronous Serial Port (MSSP) with SPI and I<sup>2</sup>C™ with:
  - 7-bit address masking
  - SMBus/PMBus™ compatibility
  - Auto-wake-up on start
- Enhanced Universal Synchronous Asynchronous Receiver Transmitter (EUSART)
  - RS-232, RS-485 and LIN compatible
  - Auto-Baud Detect
- SR Latch (555 Timer):
  - Multiple Set/Reset input options
  - Emulates 555 Timer applications
- · 2 Comparators:
  - Rail-to-rail inputs/outputs
  - Power mode control
  - Software enable hysteresis
- · Voltage Reference module:
  - Fixed Voltage Reference (FVR) with 1.024V, 2.048V and 4.096V output levels
  - 5-bit rail-to-rail resistive DAC with positive and negative reference selection

### PIC16(L)F193X Family Types

| Device                    | Program Memory<br>Flash (words) | Data EEPROM<br>(bytes) | SRAM (bytes) | s,0/I | 10-bit A/D<br>(ch) | CapSense<br>(ch) | Comparators | Timers<br>8/16-bit | EUSART | I²C™/SPI | ECCP | CCP | ГСБ                  |
|---------------------------|---------------------------------|------------------------|--------------|-------|--------------------|------------------|-------------|--------------------|--------|----------|------|-----|----------------------|
| PIC16F1934<br>PIC16LF1934 | 4096                            | 256                    | 256          | 36    | 14                 | 16               | 2           | 4/1                | Yes    | Yes      | 3    | 2   | 24/4                 |
| PIC16F1936<br>PIC16LF1936 | 8192                            | 256                    | 512          | 25    | 11                 | 8                | 2           | 4/1                | Yes    | Yes      | 3    | 2   | 16 <sup>(1)</sup> /4 |
| PIC16F1937<br>PIC16LF1937 | 8192                            | 256                    | 512          | 36    | 14                 | 16               | 2           | 4/1                | Yes    | Yes      | 3    | 2   | 24/4                 |

Note 1: COM3 and SEG15 share the same physical pin on PIC16(L)F1936, therefore, SEG15 is not available when using 1/4 multiplex displays.

### Pin Diagram – 28-Pin SPDIP/SOIC/SSOP (PIC16(L)F1936)



### Pin Diagram – 28-Pin QFN/UQFN (PIC16(L)F1936)





TABLE 1: 28-PIN SUMMARY (PIC16(L)F1936)

| O <sub>I</sub> | 28-Pin SPDIP | 28-Pin QFN/UQFN | ANSEL | A/D           | Cap Sense | Comparator                       | SR Latch            | Timers             | CCP   | EUSART | MSSP              | ГСБ            | Interrupt   | Pull-up | Basic                                  |
|----------------|--------------|-----------------|-------|---------------|-----------|----------------------------------|---------------------|--------------------|---|--------|-------------------|----------------|-------------|---------|--|
| RA0            | 2            | 27              | Y     | AN0           |           | C12IN0-/<br>C2OUT <sup>(1)</sup> | SRNQ <sup>(1)</sup> | ı                  | ı   | _      | SS <sup>(1)</sup> | SEG12          |             |         | VCAP <sup>(2)</sup>                    |
| RA1            | 3            | 28              | Υ     | AN1           | _         | C12IN1-                          | _                   | _                  | _   | _      | _                 | SEG7           | _           | _       | _                                      |
| RA2            | 4            | 1               | Y     | AN2/<br>VREF- | ı         | C2IN+/<br>DACOUT                 | ı                   | I                  |   | _      | ı                 | COM2           | ı           |         | _                                      |
| RA3            | 5            | 2               | Υ     | AN3/<br>VREF+ | l         | C1IN+                            | 1                   | 1                  |   | _      | ı                 | SEG15/<br>COM3 | 1           | ı       | _                                      |
| RA4            | 6            | 3               | Υ     |               | CPS6      | C1OUT                            | SRQ                 | T0CKI              | CCP5  | _      | 1                 | SEG4           | 1           |         | -                                      |
| RA5            | 7            | 4               | Υ     | AN4           | CPS7      | C2OUT <sup>(1)</sup>             | SRNQ <sup>(1)</sup> |                    | _   | _      | SS <sup>(1)</sup> | SEG5           | _           | _       | VCAP <sup>(2)</sup>                    |
| RA6            | 10           | 7               | _     | _             | _         | _                                | _                   | _                  | _   | _      | _                 | SEG1           | _           | _       | OSC2/<br>CLKOUT<br><sub>VCAP</sub> (2) |
| RA7            | 9            | 6               | _     | _             | _         | _                                | _                   | _                  | _   | _      | _                 | SEG2           | _           | _       | OSC1/<br>CLKIN                         |
| RB0            | 21           | 18              | Υ     | AN12          | CPS0      | ı                                | SRI                 | I                  | CCP4  | _      | ı                 | SEG0           | INT/<br>IOC | Y       | _                                      |
| RB1            | 22           | 19              | Υ     | AN10          | CPS1      | C12IN3-                          | _                   |                    | P1C   | _      | _                 | VLCD1          | IOC         | Y       | _                                      |
| RB2            | 23           | 20              | Υ     | AN8           | CPS2      | _                                | _                   | _                  | P1B   | _      | _                 | VLCD2          | IOC         | Υ       | _                                      |
| RB3            | 24           | 21              | Υ     | AN9           | CPS3      | C12IN2-                          |                     |                    | CCP2 <sup>(1)</sup> /<br>P2A <sup>(1)</sup>                       | _      | -                 | VLCD3          | IOC         | Y       |  |
| RB4            | 25           | 22              | Y     | AN11          | CPS4      | _                                | _                   |                    | P1D   | _      | _                 | COM0           | IOC         | Y       | _                                      |
| RB5            | 26           | 23              | Y     | AN13          | CPS5      |                                  | 1                   | T1G <sup>(1)</sup> | P2B <sup>(1)</sup><br>CCP3 <sup>(1)</sup> /<br>P3A <sup>(1)</sup> | _      |                   | COM1           | IOC         | Y       |  |
| RB6            | 27           | 24              | I     | 1             | 1         | 1                                | 1                   | 1                  | 1   | _      | 1                 | SEG14          | IOC         | Y       | ICSPCLK/<br>ICDCLK                     |
| RB7            | 28           | 25              | _     | _             | _         | _                                | _                   | _                  | _   | _      | _                 | SEG13          | IOC         | Y       | ICSPDAT/<br>ICDDAT                     |
| RC0            | 11           | 8               | 1     | -             | 1         | 1                                | 1                   | T10SO/<br>T1CKI    | P2B <sup>(1)</sup>  | _      | 1                 | 1              | 1           | ı       | -                                      |
| RC1            | 12           | 9               | 1     | _             | _         | _                                |                     | T1OSI              | CCP2 <sup>(1)</sup> /<br>P2A <sup>(1)</sup>                       | _      |                   |                | _           | 1       | _                                      |
| RC2            | 13           | 10              | 1     | _             | _         | _                                | -                   | 1                  | CCP1/<br>P1A  | _      | -                 | SEG3           | _           | ı       | _                                      |
| RC3            | 14           | 11              | _     | _             |           | _                                | _                   |                    |   | _      | SCK/SCL           | SEG6           | _           | _       |  |
| RC4            | 15           | 12              | _     | _             |           | _                                | _                   | T1G <sup>(1)</sup> | _   | _      | SDI/SDA           | SEG11          | _           | _       | _                                      |
| RC5            | 16           | 13              | -     | _             | _         | -                                | ı                   | ı                  | _ ;   | _      | SDO               | SEG10          | _           | -       | _                                      |
| RC6            | 17           | 14              | 1     | _             | _         | _                                | _                   |                    | CCP3 <sup>(1)</sup><br>P3A <sup>(1)</sup>                         | TX/CK  | _                 | SEG9           | _           | _       | _                                      |
| RC7            | 18           | 15              | _     | _             |           |                                  | _                   | _                  | P3B   | RX/DT  | _                 | SEG8           | _           | _       |  |
| RE3            | 1            | 26              |       |               |           |                                  |                     |                    |   | _      |                   |                | <u>_</u>    | Υ       | MCLR/VPP                               |
| VDD            | 20           | 17              | _     | _             | _         | _                                | _                   |                    | -   | _      | _                 | _              | _           | _       | VDD                                    |
| Vss            | 8,<br>19     | 5,<br>16        |       |               | _         | —                                | _                   | _                  | _   | _      | _                 |                | _           |         | Vss                                    |


Note 1: Pin functions can be moved using the APFCON register.

<sup>2:</sup> PIC16F1936 devices only.


### Pin Diagram - 40-Pin PDIP (PIC16(L)F1934/7)




### Pin Diagram - 40-Pin UQFN 5X5 (PIC16(L)F1934/7)



### Pin Diagram - 44-Pin QFN (PIC16(L)F1934/7)



### Pin Diagram – 44-Pin TQFP (PIC16(L)F1934/7)



**TABLE 2:** 40/44-PIN SUMMARY(PIC16(L)F1934/7)

| IAD  |             |             |             |             |       |               |           | TIGE                             |                     | , ,                |   | -      |                   |            |             |         |                         |
|------|-------------|-------------|-------------|-------------|-------|---------------|-----------|----------------------------------|---------------------|--------------------|---|--------|-------------------|------------|-------------|---------|-------------------------|
| OJ   | 40-Pin PDIP | 40-Pin UQFN | 44-Pin TQFP | 44-Pin QFN  | ANSEL | A/D           | Cap Sense | Comparator                       | SR Latch            | Timers             | doo   | EUSART | MSSP              | ГСБ        | Interrupt   | Pull-up | Basic                   |
| RA0  | 2           | 17          | 19          | 19          | Υ     | AN0           | _         | C12IN0-/<br>C2OUT <sup>(1)</sup> | SRNQ <sup>(1)</sup> |                    |   | 1      | SS <sup>(1)</sup> | SEG12      | _           | -       | VCAP                    |
| RA1  | 3           | 18          | 20          | 20          | Υ     | AN1           | _         | C12IN1-                          | _                   | _                  | _   | _      | _                 | SEG7       | _           |         | _                       |
| RA2  | 4           | 19          | 21          | 21          | Υ     | AN2/<br>VREF- | _         | C2IN+/<br>DACOUT                 |                     | I                  | ı   | 1      | _                 | COM2       | _           | _       | 1                       |
| RA3  | 5           | 20          | 22          | 22          | Υ     | AN3/<br>VREF+ | _         | C1IN+                            |                     | _                  | _   | _      | _                 | SEG15      | -           | -       | -                       |
| RA4  | 6           | 21          | 23          | 23          | Υ     | _             | CPS6      | C10UT                            | SRQ                 | T0CKI              |   | _      | _                 | SEG4       | _           | _       | _                       |
| RA5  | 7           | 22          | 24          | 24          | Υ     | AN4           | CPS7      | C2OUT <sup>(1)</sup>             | SRNQ <sup>(1)</sup> | _                  | _   | _      | SS <sup>(1)</sup> | SEG5       | _           | _       | VCAP                    |
| RA6  | 14          | 29          | 31          | 33          | _     | _             | _         | _                                | _                   | _                  | _   | _      | _                 | SEG1       | _           | -       | OSC2/<br>CLKOUT<br>VCAP |
| RA7  | 13          | 28          | 30          | 32          | _     | _             | _         | _                                | _                   | _                  | _   | _      | _                 | SEG2       | _           | _       | OSC1/<br>CLKIN          |
| RB0  | 33          | 8           | 8           | 9           | Υ     | AN12          | CPS0      | _                                | SRI                 | _                  | _   | _      | _                 | SEG0       | INT/<br>IOC | Υ       | _                       |
| RB1  | 34          | 9           | 9           | 10          | Υ     | AN10          | CPS1      | C12IN3-                          | _                   | _                  | _   |        | _                 | VLCD1      | IOC         | Υ       | _                       |
| RB2  | 35          | 10          | 10          | 11          | Υ     | AN8           | CPS2      | _                                | _                   | _                  | _   | _      | _                 | VLCD2      | IOC         | Υ       | _                       |
| RB3  | 36          | 11          | 11          | 12          | Y     | AN9           | CPS3      | C12IN2-                          | _                   | _                  | CCP2 <sup>(1)</sup> /<br>P2A <sup>(1)</sup> | _      | _                 | VLCD3      | IOC         | Y       | _                       |
| RB4  | 37          | 12          | 14          | 14          | Υ     | AN11          | CPS4      | _                                | _                   | _                  | _   | _      | _                 | COM0       | IOC         | Υ       | _                       |
| RB5  | 38          | 13          | 15          | 15          | Υ     | AN13          | CPS5      | _                                | _                   | T1G <sup>(1)</sup> | CCP3 <sup>(1)</sup> /<br>P3A <sup>(1)</sup> | _      | _                 | COM1       | IOC         | Y       | _                       |
| RB6  | 39          | 14          | 16          | 16          | _     | _             | _         | _                                | _                   | _                  | _   | _      | _                 | SEG14      | IOC         | Υ       | ICSPCLK/<br>ICDCLK      |
| RB7  | 40          | 15          | 17          | 17          | _     | _             | _         | _                                | _                   | _                  | _   | _      | _                 | SEG13      | IOC         | Y       | ICSPDAT/<br>ICDDAT      |
| RC0  | 15          | 30          | 32          | 34          | _     | _             | _         | _                                | _                   | T10SO/<br>T1CKI    | P2B <sup>(1)</sup>                          | _      | _                 | _          | _           | _       | _                       |
| RC1  | 16          | 31          | 35          | 35          | _     | _             | _         | _                                | _                   | T1OSI              | CCP2 <sup>(1)</sup> /<br>P2A <sup>(1)</sup> | _      | _                 | _          | _           | _       | _                       |
| RC2  | 17          | 32          | 36          | 36          | _     | _             | _         | _                                | _                   | _                  | CCP1/<br>P1A                                | _      | _                 | SEG3       | _           | ı       | _                       |
| RC3  | 18          | 33          | 37          | 37          | _     | _             | _         |                                  | _                   |                    |   |        | SCK/SCL           | SEG6       | _           | _       |                         |
| RC4  | 23          | 38          | 42          | 42          | _     | _             | _         | _                                | _                   | T1G <sup>(1)</sup> | _   | _      | SDI/SDA           | SEG11      | _           | _       | _                       |
| RC5  | 24          | 39          | 43          | 43          | _     | _             |           |                                  | _                   |                    |   |        | SDO               | SEG10      | _           | _       |                         |
| RC6  | 25          | 40          | 44          | 44          | _     | _             |           | _                                | _                   | _                  | _   | TX/CK  | _                 | SEG9       | _           | _       | _                       |
| RC7  | 26          | 1           | 1           | 1           | _     | _             | _         |                                  | _                   |                    |   | RX/DT  | _                 | SEG8       | _           | _       | _                       |
| RD0  | 19          | 34          | 38          | 38          | Y     | _             | CPS8      | _                                | _                   | _                  | -   | _      | _                 | COM3       | _           |         | _                       |
| RD1  | 20          | 35          | 39          | 39          | Y     |               | CPS9      |                                  |                     | _                  | CCP4  |        |                   |            |             |         | _                       |
| RD2  | 21          | 36          | 40          | 40          | Y     | _             | CPS10     | _                                | _                   | _                  | P2B <sup>(1)</sup>                          | _      | _                 | —<br>CE046 | _           |         | _                       |
| RD3  | 22          | 37          | 41          | 41          | Y     | _             | CPS11     | _                                | _                   |                    | P2C   |        | _                 | SEG16      | _           | _       | _                       |
| RD4  | 27          | 2           | 2           | 2           | Y     | _             | CPS12     | _                                | _                   | _                  | P2D   | _      | _                 | SEG17      | _           | _       | _                       |
| RD5  | 28          | 3           | 3           | 3           | Y     |               | CPS13     | _                                | _                   | _                  | P1B   | _      | _                 | SEG18      |             | _       | _                       |
| RD6  | 29          | 4           | 4           | 4           | Y     | _             | CPS14     | _                                | _                   | _                  | P1C   | _      | _                 | SEG19      | _           |         | _                       |
| RD7  | 30          | 5           | 5           | 5           | Y     |               | CPS15     |                                  |                     |                    | P1D   |        | _                 | SEG20      | _           |         |                         |
| RE0  | 8           | 23          | 25          | 25          | Y     | AN5           | _         | _                                | _                   | _                  | CCP3 <sup>(1)</sup><br>P3A <sup>(1)</sup>   | _      | _                 | SEG21      | _           | _       | _                       |
| RE1  | 9           | 24          | 26          | 26          | Y     | AN6           | _         |                                  | _                   |                    | P3B   |        | _                 | SEG22      | _           | _       |                         |
| RE2  | 10          | 25          | 27          | 27          | Υ     | AN7           | _         | _                                | _                   | _                  | CCP5  | _      | _                 | SEG23      | _           | _       |                         |
| RE3  | 1           | 16          | 18          | 18          | _     | _             | _         | _                                | _                   | _                  | _   | _      | _                 | _          | _           | Υ       | MCLR/VPP                |
| VDD  | 11,<br>32   | 7,<br>26    | 7,<br>28    | 7,8,<br>28  | _     | _             | _         | _                                | _                   | _                  | _   | _      | _                 | _          | _           | -       | VDD                     |
| Vss  | 12,<br>31   | 6,<br>27    | 6,<br>29    | 6,30,<br>31 | _     | _             | _         | _                                | _                   | _                  | _   | _      | _                 | _          | _           | _       | Vss                     |
| Note |             | D: 0        |             |             |       |               |           | FCON regis                       | 4                   |                    |   |        |                   |            |             |         |                         |

Note 1: Pin functions can be moved using the APFCON register.

### **Table of Contents**

| 1.0   | Device Overview   | 15  |
|-------|---|-----|
| 2.0   | Enhanced Mid-Range CPU  | 23  |
| 3.0   | Memory Organization   | 25  |
| 4.0   | Device Configuration  | 61  |
| 5.0   | Oscillator Module (With Fail-Safe Clock Monitor)                          | 67  |
| 6.0   | Resets  | 85  |
| 7.0   | Interrupts  |     |
| 8.0   | Low Dropout (LDO) Voltage Regulator                                       | 107 |
| 9.0   | Power-Down Mode (Sleep)   |     |
| 10.0  | Watchdog Timer (WDT)  | 111 |
| 11.0  | Data EEPROM and Flash Program Memory Control                              | 115 |
|       | I/O Ports   |     |
| 13.0  | Interrupt-On-Change   | 151 |
| 14.0  | Fixed Voltage Reference   | 155 |
|       | Analog-to-Digital Converter (ADC) Module                                  |     |
|       | Temperature Indicator Module  |     |
| 17.0  | Digital-to-Analog Converter (DAC) Module                                  | 173 |
| 18.0  | Comparator Module   | 177 |
| 19.0  | SR Latch  | 187 |
| 20.0  | Timer0 Module   | 191 |
| 21.0  | Timer1 Module with Gate Control   | 197 |
|       | Timer2/4/6 Modules  |     |
| 23.0  | Capture/Compare/PWM Modules (ECCP1, ECCP2, ECCP3, CCP4, CCP5)             | 211 |
| 24.0  | Master Synchronous Serial Port (MSSP) Module                              | 239 |
|       | Enhanced Universal Synchronous Asynchronous Receiver Transmitter (EUSART) |     |
| 26.0  | Capacitive Sensing Module   | 319 |
| 27.0  | Liquid Crystal Display (LCD) Driver Module                                | 327 |
|       | In-Circuit Serial Programming™ (ICSP™)                                    |     |
| 29.0  | Instruction Set Summary   | 365 |
| 30.0  | Electrical Specifications   | 379 |
| 31.0  | DC and AC Characteristics Graphs and Charts                               | 411 |
|       | Development Support   |     |
| 33.0  | Packaging Information   | 443 |
|       | endix A: Data Sheet Revision History                                      |     |
| Appe  | endix B: Migrating From Other PIC® Devices                                | 459 |
| Index | X   | 461 |
| The N | Microchip Web Site  | 469 |
|       | omer Change Notification Service  |     |
| Custo | omer Support  | 469 |
| Read  | der Response  | 470 |
| Produ | uct Identification System   | 471 |

### TO OUR VALUED CUSTOMERS

It is our intention to provide our valued customers with the best documentation possible to ensure successful use of your Microchip products. To this end, we will continue to improve our publications to better suit your needs. Our publications will be refined and enhanced as new volumes and updates are introduced.

If you have any questions or comments regarding this publication, please contact the Marketing Communications Department via E-mail at **docerrors@microchip.com** or fax the **Reader Response Form** in the back of this data sheet to (480) 792-4150. We welcome your feedback.

#### **Most Current Data Sheet**

To obtain the most up-to-date version of this data sheet, please register at our Worldwide Web site at:

#### http://www.microchip.com

You can determine the version of a data sheet by examining its literature number found on the bottom outside corner of any page. The last character of the literature number is the version number, (e.g., DS30000A is version A of document DS30000).

#### **Errata**

An errata sheet, describing minor operational differences from the data sheet and recommended workarounds, may exist for current devices. As device/documentation issues become known to us, we will publish an errata sheet. The errata will specify the revision of silicon and revision of document to which it applies.

To determine if an errata sheet exists for a particular device, please check with one of the following:

- Microchip's Worldwide Web site; http://www.microchip.com
- · Your local Microchip sales office (see last page)

When contacting a sales office, please specify which device, revision of silicon and data sheet (include literature number) you are using.

### **Customer Notification System**

Register on our web site at www.microchip.com to receive the most current information on all of our products.

### 1.0 DEVICE OVERVIEW

The PIC16(L)F1934/6/7 are described within this data sheet. They are available in 28/40/44-pin packages. Figure 1-1 shows a block diagram of the PIC16(L)F1934/6/7 devices. Table 1-2 shows the pinout descriptions.

Reference Table 1-1 for peripherals available per device.

TABLE 1-1: DEVICE PERIPHERAL SUMMARY

| Peripheral              | PIC16F193X  | PIC16LF193X |   |
|-------------------------|-------------|-------------|---|
| ADC                     | •           | •           |   |
| Capacitive Sensing Mod  | dule        | •           | • |
| Digital-to-Analog Conve | erter (DAC) | •           | • |
| EUSART                  |             | •           | • |
| Fixed Voltage Reference | e (FVR)     | •           | • |
| LCD                     |             | •           | • |
| SR Latch                |             | •           | • |
| Temperature Indicator   |             | •           | • |
| Capture/Compare/PWM     | l Modules   |             |   |
|                         | ECCP1       | •           | • |
|                         | ECCP2       | •           | • |
|                         | ECCP3       | •           | • |
|                         | CCP4        | •           | • |
|                         | CCP5        | •           | • |
| Comparators             |             |             |   |
|                         | C1          | •           | • |
|                         | C2          | •           | • |
| Operational Amplifiers  |             |             |   |
|                         | OPA1        | •           | • |
|                         | OPA2        | •           | • |
| Master Synchronous Se   | erial Ports |             |   |
|                         | MSSP1       | •           | • |
| Timers                  |             |             |   |
|                         | Timer0      | •           | • |
|                         | Timer1      | •           | • |
|                         | Timer2      | •           | • |
|                         | Timer4      | •           | • |
|                         | Timer6      | •           | • |




TABLE 1-2: PIC16(L)F1934/6/7 PINOUT DESCRIPTION

| Name   | Function            | Input<br>Type | Output<br>Type | Description   |  |  |
|--|---------------------|---------------|----------------|---|--|--|
| RA0/AN0/C12IN0-/C2OUT <sup>(1)</sup> /                             | RA0                 | TTL           | CMOS           | General purpose I/O.  |  |  |
| SRNQ <sup>(1)</sup> /SS <sup>(1)</sup> /VCAP <sup>(2)</sup> /SEG12 | AN0                 | AN            | _              | A/D Channel 0 input.  |  |  |
|  | C12IN0-             | AN            | _              | Comparator C1 or C2 negative input.                           |  |  |
|  | C2OUT               | _             | CMOS           | Comparator C2 output.   |  |  |
|  | SRNQ                | _             | CMOS           | SR Latch inverting output.                                    |  |  |
|  | SS                  | ST            | _              | Slave Select input.   |  |  |
|  | VCAP                | Power         | Power          | Filter capacitor for Voltage Regulator (PIC16F1934/6/7 only)  |  |  |
|  | SEG12               | _             | AN             | LCD Analog output.  |  |  |
| RA1/AN1/C12IN1-/SEG7   | RA1                 | TTL           | CMOS           | General purpose I/O.  |  |  |
|  | AN1                 | AN            | _              | A/D Channel 1 input.  |  |  |
|  | C12IN1-             | AN            | _              | Comparator C1 or C2 negative input.                           |  |  |
|  | SEG7                | _             | AN             | LCD Analog output.  |  |  |
| RA2/AN2/C2IN+/VREF-/   | RA2                 | TTL           | CMOS           | General purpose I/O.  |  |  |
| DACOUT/COM2  | AN2                 | AN            | _              | A/D Channel 2 input.  |  |  |
|  | C2IN+               | AN            | _              | Comparator C2 positive input.                                 |  |  |
|  | VREF-               | AN            | _              | A/D Negative Voltage Reference input.                         |  |  |
|  | DACOUT              | _             | AN             | Voltage Reference output.                                     |  |  |
|  | COM2                | _             | AN             | LCD Analog output.  |  |  |
| RA3/AN3/C1IN+/VREF+/   | RA3                 | TTL           | CMOS           | General purpose I/O.  |  |  |
| COM3 <sup>(3)</sup> /SEG15   | AN3                 | AN            | _              | A/D Channel 3 input.  |  |  |
|  | C1IN+               | AN            | _              | Comparator C1 positive input.                                 |  |  |
|  | VREF+               | AN            | _              | A/D Voltage Reference input.                                  |  |  |
|  | COM3 <sup>(3)</sup> | _             | AN             | LCD Analog output.  |  |  |
|  | SEG15               | _             | AN             | LCD Analog output.  |  |  |
| RA4/C1OUT/CPS6/T0CKI/SRQ/  | RA4                 | TTL           | CMOS           | General purpose I/O.  |  |  |
| CCP5/SEG4  | C10UT               | _             | CMOS           | Comparator C1 output.   |  |  |
|  | CPS6                | AN            | _              | Capacitive sensing input 6.                                   |  |  |
|  | T0CKI               | ST            | _              | Timer0 clock input.   |  |  |
|  | SRQ                 | _             | CMOS           | SR Latch non-inverting output.                                |  |  |
|  | CCP5                | ST            | CMOS           | Capture/Compare/PWM5.   |  |  |
|  | SEG4                | _             | AN             | LCD Analog output.  |  |  |
| RA5/AN4/C2OUT <sup>(1)</sup> /CPS7/                                | RA5                 | TTL           | CMOS           | General purpose I/O.  |  |  |
| SRNQ <sup>(1)</sup> /SS <sup>(1)</sup> /VCAP <sup>(2)</sup> /SEG5  | AN4                 | AN            | _              | A/D Channel 4 input.  |  |  |
|  | C2OUT               | _             | CMOS           | Comparator C2 output.   |  |  |
|  | CPS7                | AN            | _              | Capacitive sensing input 7.                                   |  |  |
|  | SRNQ                | _             | CMOS           | SR Latch inverting output.                                    |  |  |
|  | SS                  | ST            | _              | Slave Select input.   |  |  |
|  | VCAP                | Power         | Power          | Filter capacitor for Voltage Regulator (PIC16F1934/6/7 only). |  |  |
|  | SEG5                | _             | AN             | LCD Analog output.  |  |  |

**Legend:** AN = Analog input or output CMOS = CMOS compatible input or output OD = Open Drain

TTL = TTL compatible input ST = Schmitt Trigger input with CMOS levels  $I^2C^{TM}$  = Schmitt Trigger input with  $I^2C$  HV = High Voltage XTAL = Crystal levels

- 2: PIC16F1934/6/7 devices only.
- 3: PIC16(L)F1936 devices only.
- 4: PORTD is available on PIC16(L)F1934/7 devices only.
- 5: RE<2:0> are available on PIC16(L)F1934/7 devices only.

TABLE 1-2: PIC16(L)F1934/6/7 PINOUT DESCRIPTION (CONTINUED)

| Name  | Function | Input<br>Type | Output<br>Type | Description   |
|---|----------|---------------|----------------|---|
| RA6/OSC2/CLKOUT/VCAP <sup>(2)</sup> /                                   | RA6      | TTL           | CMOS           | General purpose I/O.  |
| SEG1  | OSC2     | _             | XTAL           | Crystal/Resonator (LP, XT, HS modes).   |
|   | CLKOUT   | _             | CMOS           | Fosc/4 output.  |
|   | VCAP     | Power         | Power          | Filter capacitor for Voltage Regulator (PIC16F1934/6/7 only).                                   |
|   | SEG1     | _             | AN             | LCD Analog output.  |
| RA7/OSC1/CLKIN/SEG2   | RA7      | TTL           | CMOS           | General purpose I/O.  |
|   | OSC1     | XTAL          | _              | Crystal/Resonator (LP, XT, HS modes).   |
|   | CLKIN    | CMOS          | _              | External clock input (EC mode).   |
|   | SEG2     | _             | AN             | LCD Analog output.  |
| RB0/AN12/CPS0/CCP4/SRI/INT/<br>SEG0                                     | RB0      | TTL           | CMOS           | General purpose I/O. Individually controlled interrupt-on-change. Individually enabled pull-up. |
|   | AN12     | AN            | _              | A/D Channel 12 input.   |
|   | CPS0     | AN            | _              | Capacitive sensing input 0.   |
|   | CCP4     | ST            | CMOS           | Capture/Compare/PWM4.   |
|   | SRI      | _             | ST             | SR Latch input.   |
|   | INT      | ST            | _              | External interrupt.   |
|   | SEG0     | _             | AN             | LCD analog output.  |
| RB1/AN10/C12IN3-/CPS1/P1C/<br>VLCD1                                     | RB1      | TTL           | CMOS           | General purpose I/O. Individually controlled interrupt-on-change. Individually enabled pull-up. |
|   | AN10     | AN            | _              | A/D Channel 10 input.   |
|   | C12IN3-  | AN            | _              | Comparator C1 or C2 negative input.   |
|   | CPS1     | AN            | _              | Capacitive sensing input 1.   |
|   | P1C      | _             | CMOS           | PWM output.   |
|   | VLCD1    | AN            | _              | LCD analog input.   |
| RB2/AN8/CPS2/P1B/VLCD2  | RB2      | TTL           | CMOS           | General purpose I/O. Individually controlled interrupt-on-change. Individually enabled pull-up. |
|   | AN8      | AN            | _              | A/D Channel 8 input.  |
|   | CPS2     | AN            | _              | Capacitive sensing input 2.   |
|   | P1B      |               | CMOS           | PWM output.   |
|   | VLCD2    | AN            | _              | LCD analog input.   |
| RB3/AN9/C12IN2-/CPS3/<br>CCP2 <sup>(1)</sup> /P2A <sup>(1)</sup> /VLCD3 | RB3      | TTL           | CMOS           | General purpose I/O. Individually controlled interrupt-on-change. Individually enabled pull-up. |
|   | AN9      | AN            | _              | A/D Channel 9 input.  |
|   | C12IN2-  | AN            | _              | Comparator C1 or C2 negative input.   |
|   | CPS3     | AN            | _              | Capacitive sensing input 3.   |
|   | CCP2     | ST            | CMOS           | Capture/Compare/PWM2.   |
|   | P2A      | _             | CMOS           | PWM output.   |
|   | VLCD3    | AN            | _              | LCD analog input.   |

**Legend:** AN = Analog input or output CMOS = CMOS compatible input or output OD = Open Drain

TTL = TTL compatible input ST = Schmitt Trigger input with CMOS levels  $I^2C^{TM}$  = Schmitt Trigger input with  $I^2C$  HV = High Voltage XTAL = Crystal levels

- **2:** PIC16F1934/6/7 devices only.
- 3: PIC16(L)F1936 devices only.
- 4: PORTD is available on PIC16(L)F1934/7 devices only.
- 5: RE<2:0> are available on PIC16(L)F1934/7 devices only.

TABLE 1-2: PIC16(L)F1934/6/7 PINOUT DESCRIPTION (CONTINUED)

| Name  | Function | Input<br>Type    | Output<br>Type | Description   |
|---|----------|------------------|----------------|---|
| RB4/AN11/CPS4/P1D/COM0  | RB4      | TTL              | CMOS           | General purpose I/O. Individually controlled interrupt-on-change. Individually enabled pull-up. |
|   | AN11     | AN               | _              | A/D Channel 11 input.   |
|   | CPS4     | AN               | _              | Capacitive sensing input 4.   |
|   | P1D      | _                | CMOS           | PWM output.   |
|   | COM0     | _                | AN             | LCD Analog output.  |
| RB5/AN13/CPS5/P2B/CCP3 <sup>(1)</sup> /<br>P3A <sup>(1)</sup> /T1G <sup>(1)</sup> /COM1 | RB5      | TTL              | CMOS           | General purpose I/O. Individually controlled interrupt-on-change. Individually enabled pull-up. |
|   | AN13     | AN               | _              | A/D Channel 13 input.   |
|   | CPS5     | AN               | _              | Capacitive sensing input 5.   |
|   | P2B      | _                | CMOS           | PWM output.   |
|   | CCP3     | ST               | CMOS           | Capture/Compare/PWM3.   |
|   | P3A      | _                | CMOS           | PWM output.   |
|   | T1G      | ST               | _              | Timer1 Gate input.  |
|   | COM1     | _                | AN             | LCD Analog output.  |
| RB6/ICSPCLK/ICDCLK/SEG14  | RB6      | TTL              | CMOS           | General purpose I/O. Individually controlled interrupt-on-change. Individually enabled pull-up. |
|   | ICSPCLK  | ST               | _              | Serial Programming Clock.   |
|   | ICDCLK   | ST               | _              | In-Circuit Debug Clock.   |
|   | SEG14    | _                | AN             | LCD Analog output.  |
| RB7/ICSPDAT/ICDDAT/SEG13  | RB7      | TTL              | CMOS           | General purpose I/O. Individually controlled interrupt-on-change. Individually enabled pull-up. |
|   | ICSPDAT  | ST               | CMOS           | ICSP™ Data I/O.   |
|   | ICDDAT   | ST               | CMOS           | In-Circuit Data I/O.  |
|   | SEG13    | _                | AN             | LCD Analog output.  |
| RC0/T1OSO/T1CKI/P2B <sup>(1)</sup>  | RC0      | ST               | CMOS           | General purpose I/O.  |
|   | T10S0    | XTAL             | XTAL           | Timer1 oscillator connection.   |
|   | T1CKI    | ST               | _              | Timer1 clock input.   |
|   | P2B      | _                | CMOS           | PWM output.   |
| RC1/T1OSI/CCP2 <sup>(1)</sup> /P2A <sup>(1)</sup>                                       | RC1      | ST               | CMOS           | General purpose I/O.  |
|   | T10SI    | XTAL             | XTAL           | Timer1 oscillator connection.   |
|   | CCP2     | ST               | CMOS           | Capture/Compare/PWM2.   |
|   | P2A      | _                | CMOS           | PWM output.   |
| RC2/CCP1/P1A/SEG3   | RC2      | ST               | CMOS           | General purpose I/O.  |
|   | CCP1     | ST               | CMOS           | Capture/Compare/PWM1.   |
|   | P1A      | _                | CMOS           | PWM output.   |
|   | SEG3     | _                | AN             | LCD Analog output.  |
| RC3/SCK/SCL/SEG6  | RC3      | ST               | CMOS           | General purpose I/O.  |
|   | SCK      | ST               | CMOS           | SPI clock.  |
|   | SCL      | I <sup>2</sup> C | OD             | I <sup>2</sup> C™ clock.  |
|   | SEG6     | _                | AN             | LCD Analog output.  |

**Legend:** AN = Analog input or output CMOS = CMOS compatible input or output OD = Open Drain

TTL = TTL compatible input ST = Schmitt Trigger input with CMOS levels I<sup>2</sup>C™ = Schmitt Trigger input with I<sup>2</sup>C HV = High Voltage XTAL = Crystal levels

- 2: PIC16F1934/6/7 devices only.
- 3: PIC16(L)F1936 devices only.
- 4: PORTD is available on PIC16(L)F1934/7 devices only.
- 5: RE<2:0> are available on PIC16(L)F1934/7 devices only.

TABLE 1-2: PIC16(L)F1934/6/7 PINOUT DESCRIPTION (CONTINUED)

| Name                                  | Function | Input<br>Type    | Output<br>Type | Description                          |
|---------------------------------------|----------|------------------|----------------|--------------------------------------|
| RC4/SDI/SDA/T1G <sup>(1)</sup> /SEG11 | RC4      | ST               | CMOS           | General purpose I/O.                 |
|                                       | SDI      | ST               | _              | SPI data input.                      |
|                                       | SDA      | I <sup>2</sup> C | OD             | I <sup>2</sup> C™ data input/output. |
|                                       | T1G      | ST               | _              | Timer1 Gate input.                   |
|                                       | SEG11    | _                | AN             | LCD Analog output.                   |
| RC5/SDO/SEG10                         | RC5      | ST               | CMOS           | General purpose I/O.                 |
|                                       | SDO      | _                | CMOS           | SPI data output.                     |
|                                       | SEG10    | _                | AN             | LCD Analog output.                   |
| RC6/TX/CK/CCP3/P3A/SEG9               | RC6      | ST               | CMOS           | General purpose I/O.                 |
|                                       | TX       | _                | CMOS           | USART asynchronous transmit.         |
|                                       | CK       | ST               | CMOS           | USART synchronous clock.             |
|                                       | CCP3     | ST               | CMOS           | Capture/Compare/PWM3.                |
|                                       | P3A      | _                | CMOS           | PWM output.                          |
|                                       | SEG9     | _                | AN             | LCD Analog output.                   |
| RC7/RX/DT/P3B/SEG8                    | RC7      | ST               | CMOS           | General purpose I/O.                 |
|                                       | RX       | ST               | _              | USART asynchronous input.            |
|                                       | DT       | ST               | CMOS           | USART synchronous data.              |
|                                       | P3B      | _                | CMOS           | PWM output.                          |
|                                       | SEG8     | _                | AN             | LCD Analog output.                   |
| RD0 <sup>(4)</sup> /CPS8/COM3         | RD0      | ST               | CMOS           | General purpose I/O.                 |
|                                       | CPS8     | AN               | _              | Capacitive sensing input 8.          |
|                                       | COM3     | _                | AN             | LCD analog output.                   |
| RD1 <sup>(4)</sup> /CPS9/CCP4         | RD1      | ST               | CMOS           | General purpose I/O.                 |
|                                       | CPS9     | AN               | _              | Capacitive sensing input 9.          |
|                                       | CCP4     | ST               | CMOS           | Capture/Compare/PWM4.                |
| RD2 <sup>(4)</sup> /CPS10/P2B         | RD2      | ST               | CMOS           | General purpose I/O.                 |
|                                       | CPS10    | AN               | _              | Capacitive sensing input 10.         |
|                                       | P2B      | _                | CMOS           | PWM output.                          |
| RD3 <sup>(4)</sup> /CPS11/P2C/SEG16   | RD3      | ST               | CMOS           | General purpose I/O.                 |
|                                       | CPS11    | AN               | _              | Capacitive sensing input 11.         |
|                                       | P2C      | _                | CMOS           | PWM output.                          |
|                                       | SEG16    | _                | AN             | LCD analog output.                   |
| RD4 <sup>(4)</sup> /CPS12/P2D/SEG17   | RD4      | ST               | CMOS           | General purpose I/O.                 |
|                                       | CPS12    | AN               | _              | Capacitive sensing input 12.         |
|                                       | P2D      | _                | CMOS           | PWM output.                          |
|                                       | SEG17    | _                | AN             | LCD analog output.                   |
| RD5 <sup>(4)</sup> /CPS13/P1B/SEG18   | RD5      | ST               | CMOS           | General purpose I/O.                 |
|                                       | CPS13    | AN               | _              | Capacitive sensing input 13.         |
|                                       | P1D      | _                | CMOS           | PWM output.                          |
|                                       | SEG18    | _                | AN             | LCD analog output.                   |

**Legend:** AN = Analog input or output CMOS = CMOS compatible input or output OD = Open Drain

TTL = TTL compatible input ST = Schmitt Trigger input with CMOS levels  $I^2C^{TM}$  = Schmitt Trigger input with  $I^2C$  HV = High Voltage XTAL = Crystal levels

Note 1: Pin function is selectable via the APFCON register.

2: PIC16F1934/6/7 devices only.

3: PIC16(L)F1936 devices only.

4: PORTD is available on PIC16(L)F1934/7 devices only.

5: RE<2:0> are available on PIC16(L)F1934/7 devices only.

TABLE 1-2: PIC16(L)F1934/6/7 PINOUT DESCRIPTION (CONTINUED)

| Name  | Function | Input<br>Type                           | Output<br>Type | Description                         |
|---|----------|---|----------------|-------------------------------------|
| RD6 <sup>(4)</sup> /CPS14/P1C/SEG19                               | RD6      | ST                                      | CMOS           | General purpose I/O.                |
|   | CPS14    | CPS14 AN — Capacitive sensing input 14. |                | Capacitive sensing input 14.        |
|   | P1C      | P1C — CMOS PWM output.                  |                | PWM output.                         |
|   | SEG19    | _                                       | AN             | LCD analog output.                  |
| RD7 <sup>(4)</sup> /CPS15/P1D/SEG20                               | RD7      | ST                                      | CMOS           | General purpose I/O.                |
|   | CPS15    | AN                                      | _              | Capacitive sensing input 15.        |
|   | P1D      | _                                       | CMOS           | PWM output.                         |
|   | SEG20    | _                                       | AN             | LCD analog output.                  |
| RE0 <sup>(5)</sup> /AN5/P3A <sup>(1)</sup> /CCP3 <sup>(1)</sup> / | RE0      | ST                                      | CMOS           | General purpose I/O.                |
| SEG21   | AN5      | AN                                      | _              | A/D Channel 5 input.                |
|   | P3A      | _                                       | CMOS           | PWM output.                         |
|   | CCP3     | CCP3 ST CMOS Capture/Compare/PWM3.      |                | Capture/Compare/PWM3.               |
|   | SEG21    | _                                       | AN             | LCD analog output.                  |
| RE1 <sup>(5)</sup> /AN6/P3B/SEG22                                 | RE1      | ST                                      | CMOS           | General purpose I/O.                |
|   | AN6      | AN                                      | _              | A/D Channel 6 input.                |
|   | P3B      | _                                       | CMOS           | PWM output.                         |
|   | SEG22    | _                                       | AN             | LCD analog output.                  |
| RE2 <sup>(5)</sup> /AN7/CCP5/SEG23                                | RE2      | ST                                      | CMOS           | General purpose I/O.                |
|   | AN7      | AN                                      | _              | A/D Channel 7 input.                |
|   | CCP5     | ST                                      | CMOS           | Capture/Compare/PWM5.               |
|   | SEG23    | _                                       | AN             | LCD analog output.                  |
| RE3/MCLR/VPP  | RE3      | TTL                                     | _              | General purpose input.              |
|   | MCLR     | ST                                      | _              | Master Clear with internal pull-up. |
|   | VPP      | HV                                      | _              | Programming voltage.                |
| VDD   | VDD      | Power                                   | _              | Positive supply.                    |
| Vss   | Vss      | Power                                   | _              | Ground reference.                   |

**Legend:** AN = Analog input or output CMOS = CMOS compatible input or output OD = Open Drain

TTL = TTL compatible input ST = Schmitt Trigger input with CMOS levels  $I^2C^{TM}$  = Schmitt Trigger input with  $I^2C$  HV = High Voltage XTAL = Crystal levels

- 2: PIC16F1934/6/7 devices only.
- 3: PIC16(L)F1936 devices only.
- 4: PORTD is available on PIC16(L)F1934/7 devices only.
- 5: RE<2:0> are available on PIC16(L)F1934/7 devices only.

**NOTES:** 

### 2.0 ENHANCED MID-RANGE CPU

This family of devices contain an enhanced mid-range 8-bit CPU core. The CPU has 49 instructions. Interrupt capability includes automatic context saving. The hardware stack is 16 levels deep and has Overflow and Underflow Reset capability. Direct, Indirect, and Relative Addressing modes are available. Two File Select Registers (FSRs) provide the ability to read program and data memory.

- · Automatic Interrupt Context Saving
- · 16-level Stack with Overflow and Underflow
- · File Select Registers
- · Instruction Set

### 2.1 Automatic Interrupt Context Saving

During interrupts, certain registers are automatically saved in shadow registers and restored when returning from the interrupt. This saves stack space and user code. See Section 7.5 "Automatic Context Saving", for more information.

### 2.2 16-level Stack with Overflow and Underflow

These devices have an external stack memory 15 bits wide and 16 words deep. A Stack Overflow or Underflow will set the appropriate bit (STKOVF or STKUNF) in the PCON register, and if enabled will cause a software Reset. See section **Section 3.4 "Stack"** for more details.


### 2.3 File Select Registers

There are two 16-bit File Select Registers (FSR). FSRs can access all file registers and program memory, which allows one Data Pointer for all memory. When an FSR points to program memory, there is 1 additional instruction cycle in instructions using INDF to allow the data to be fetched. General purpose memory can now also be addressed linearly, providing the ability to access contiguous data larger than 80 bytes. There are also new instructions to support the FSRs. See Section 3.5 "Indirect Addressing" for more details.

### 2.4 Instruction Set

There are 49 instructions for the enhanced mid-range CPU to support the features of the CPU. See Section 29.0 "Instruction Set Summary" for more details.

FIGURE 2-1: CORE BLOCK DIAGRAM



### 3.0 MEMORY ORGANIZATION

There are three types of memory in PIC16(L)F1934/6/7 devices: Data Memory, Program Memory and Data EEPROM Memory<sup>(1)</sup>.

- · Program Memory
- · Data Memory
  - Core Registers
  - Special Function Registers
  - General Purpose RAM
  - Common RAM
  - Device Memory Maps
  - Special Function Registers Summary
- Data EEPROM memory<sup>(1)</sup>

Note 1: The data EEPROM memory and the method to access Flash memory through the EECON registers is described in Section 11.0 "Data EEPROM and Flash Program Memory Control".

The following features are associated with access and control of program memory and data memory:

- · PCL and PCLATH
- Stack
- · Indirect Addressing

### 3.1 Program Memory Organization

The enhanced mid-range core has a 15-bit program counter capable of addressing 32K x 14 program memory space. Table 3-1 shows the memory sizes implemented for the PIC16(L)F1934/6/7 family. Accessing a location above these boundaries will cause a wrap-around within the implemented memory space. The Reset vector is at 0000h and the interrupt vector is at 0004h (see Figures 3-1 and 3-2).

TABLE 3-1: DEVICE SIZES AND ADDRESSES

| Device                 | Program Memory Space (Words) | Last Program Memory Address |
|------------------------|------------------------------|-----------------------------|
| PIC16F1934/PIC16LF1934 | 4,096                        | 0FFFh                       |
| PIC16F1936/PIC16LF1936 | 8,192                        | 1FFFh                       |
| PIC16F1937/PIC16LF1937 | 8,192                        | 1FFFh                       |

FIGURE 3-1: PROGRAM MEMORY MAP
AND STACK FOR
4KW PARTS





FIGURE 3-2: PROGRAM MEMORY MAP
AND STACK FOR
8KW PARTS



### 3.1.1 READING PROGRAM MEMORY AS DATA

There are two methods of accessing constants in program memory. The first method is to use tables of RETLW instructions. The second method is to set an FSR to point to the program memory.

#### 3.1.1.1 RETLW Instruction

The RETLW instruction can be used to provide access to tables of constants. The recommended way to create such a table is shown in Example 3-1.

#### **EXAMPLE 3-1:** RETLW INSTRUCTION

```
constants
   BRW
                      ;Add Index in W to
                     ;program counter to
                     ;select data
                    ;Index0 data
   RETLW DATA0
   RETLW DATA1
                     ;Index1 data
   RETLW DATA2
   RETLW DATA3
my_function
   ;... LOTS OF CODE...
   MOVLW DATA_INDEX
   call constants
   ;... THE CONSTANT IS IN W
```

The BRW instruction makes this type of table very simple to implement. If your code must remain portable with previous generations of microcontrollers, then the BRW instruction is not available so the older table read method must be used.

#### 3.1.1.2 Indirect Read with FSR

The program memory can be accessed as data by setting bit 7 of the FSRxH register and reading the matching INDFx register. The MOVIW instruction will place the lower 8 bits of the addressed word in the W register. Writes to the program memory cannot be performed via the INDF registers. Instructions that access the program memory via the FSR require one extra instruction cycle to complete. Example 3-2 demonstrates accessing the program memory via an FSR.

The HIGH directive will set bit<7> if a label points to a location in program memory.

### EXAMPLE 3-2: ACCESSING PROGRAM MEMORY VIA FSR

```
constants
   RETLW DATA0
                       ;Index0 data
   RETLW DATA1
                      ;Index1 data
   RETLW DATA2
   RETLW DATA3
my_function
   ;... LOTS OF CODE...
   MOVLW LOW constants
          FSR1L
   MOVWF
   MOVLW
          HIGH constants
          FSR1H
   MOVWF
   MOVIW
          0[FSR1]
;THE PROGRAM MEMORY IS IN W
```

### 3.2 Data Memory Organization

The data memory is partitioned in 32 memory banks with 128 bytes in a bank. Each bank consists of (Figure 3-3):

- · 12 core registers
- · 20 Special Function Registers (SFR)
- Up to 80 bytes of General Purpose RAM (GPR)
- · 16 bytes of common RAM

The active bank is selected by writing the bank number into the Bank Select Register (BSR). Unimplemented memory will read as '0'. All data memory can be accessed either directly (via instructions that use the file registers) or indirectly via the two File Select Registers (FSR). See Section 3.5 "Indirect Addressing" for more information.

#### 3.2.1 CORE REGISTERS

The core registers contain the registers that directly affect the basic operation of the PIC16(L)F1934/6/7. These registers are listed below:

- INDF0
- INDF1
- PCL
- STATUS
- FSR0 Low
- FSR0 High
- FSR1 Low
- FSR1 High
- BSR
- WREG
- PCLATH
- INTCON

**Note:** The core registers are the first 12 addresses of every data memory bank.

### 3.2.1.1 STATUS Register

The STATUS register, shown in Register 3-1, contains:

- · the arithmetic status of the ALU
- · the Reset status

The STATUS register can be the destination for any instruction, like any other register. If the STATUS register is the destination for an instruction that affects the Z, DC or C bits, then the write to these three bits is disabled. These bits are set or cleared according to the device logic. Furthermore, the  $\overline{\text{TO}}$  and  $\overline{\text{PD}}$  bits are not writable. Therefore, the result of an instruction with the STATUS register as destination may be different than intended.

For example, CLRF STATUS will clear the upper three bits and set the Z bit. This leaves the STATUS register as '000u uluu' (where u = unchanged).

It is recommended, therefore, that only BCF, BSF, SWAPF and MOVWF instructions are used to alter the STATUS register, because these instructions do not affect any Status bits. For other instructions not affecting any Status bits (Refer to Section 29.0 "Instruction Set Summary").

Note 1: The <u>C and DC</u> bits operate as Borrow and Digit Borrow out bits, respectively, in subtraction.

### **REGISTER 3-1: STATUS: STATUS REGISTER**

| U-0   | U-0 | U-0 | R-1/q | R-1/q | R/W-0/u | R/W-0/u           | R/W-0/u          |
|-------|-----|-----|-------|-------|---------|-------------------|------------------|
| _     | _   | _   | TO    | PD    | Z       | DC <sup>(1)</sup> | C <sup>(1)</sup> |
| bit 7 |     |     |       |       |         |                   | bit 0            |

| Legend:              |                      |   |
|----------------------|----------------------|---|
| R = Readable bit     | W = Writable bit     | U = Unimplemented bit, read as '0'                    |
| u = Bit is unchanged | x = Bit is unknown   | -n/n = Value at POR and BOR/Value at all other Resets |
| '1' = Bit is set     | '0' = Bit is cleared | q = Value depends on condition                        |

| bit 7-5 | Unimplemented: Read as '0'   |
|---------|------------------------------|
| DIL 1-0 | Ollilible Heliteu. Neau as V |

bit 4 **TO:** Time-out bit

1 = After power-up, CLRWDT instruction or SLEEP instruction

0 = A WDT time-out occurred

bit 3 **PD:** Power-down bit

1 = After power-up or by the CLRWDT instruction

0 = By execution of the SLEEP instruction

bit 2 Z: Zero bit

1 = The result of an arithmetic or logic operation is zero

0 = The result of an arithmetic or logic operation is not zero

bit 1 DC: Digit Carry/Digit Borrow bit (ADDWF, ADDLW, SUBLW, SUBWF instructions)(1)

1 = A carry-out from the 4th low-order bit of the result occurred

0 = No carry-out from the 4th low-order bit of the result

bit 0 C: Carry/Borrow bit<sup>(1)</sup> (ADDWF, ADDLW, SUBLW, SUBWF instructions)<sup>(1)</sup>

1 = A carry-out from the Most Significant bit of the result occurred

0 = No carry-out from the Most Significant bit of the result occurred

Note 1: For Borrow, the polarity is reversed. A subtraction is executed by adding the two's complement of the second operand. For rotate (RRF, RLF) instructions, this bit is loaded with either the high-order or low-order bit of the source register.

### 3.2.2 SPECIAL FUNCTION REGISTER

The Special Function Registers (SFR) are registers used by the application to control the desired operation of peripheral functions in the device. The registers associated with the operation of the peripherals are described in the appropriate peripheral chapter of this data sheet.

### 3.2.3 GENERAL PURPOSE RAM

There are up to 80 bytes of GPR in each data memory bank.

### 3.2.3.1 Linear Access to GPR

The general purpose RAM can be accessed in a non-banked method via the FSRs. This can simplify access to large memory structures. See **Section 3.5.2** "Linear Data Memory" for more information.

#### 3.2.4 COMMON RAM

There are 16 bytes of common RAM accessible from all banks.

FIGURE 3-3: BANKED MEMORY PARTITIONING

| PARTITIONING                                  |
|---|
| Memory Region                                 |
| Core Registers<br>(12 bytes)                  |
| Special Function Registers (20 bytes maximum) |
|   |
| General Purpose RAM<br>(80 bytes maximum)     |
|   |
|   |
| Common RAM<br>(16 bytes)                      |
|   |

### 3.2.5 DEVICE MEMORY MAPS

The memory maps for the device family are as shown in Table 3-2.

TABLE 3-2: MEMORY MAP TABLES

| Device      | Banks | Table No.             |  |  |  |  |  |
|-------------|-------|-----------------------|--|--|--|--|--|
| PIC16F1934  | 0-7   | Table 3-3             |  |  |  |  |  |
| PIC16LF1934 | 8-15  | Table 3-4, Table 3-10 |  |  |  |  |  |
|             | 16-23 | Table 3-7             |  |  |  |  |  |
|             | 23-31 | Table 3-8, Table 3-11 |  |  |  |  |  |
| PIC16F1936  | 0-7   | Table 3-5             |  |  |  |  |  |
| PIC16LF1936 | 8-15  | Table 3-6, Table 3-9  |  |  |  |  |  |
|             | 16-23 | Table 3-7             |  |  |  |  |  |
|             | 23-31 | Table 3-8, Table 3-11 |  |  |  |  |  |
| PIC16F1937  | 0-7   | Table 3-5             |  |  |  |  |  |
| PIC16LF1937 | 8-15  | Table 3-6, Table 3-10 |  |  |  |  |  |
|             | 16-23 | Table 3-7             |  |  |  |  |  |
|             | 23-31 | Table 3-8, Table 3-11 |  |  |  |  |  |

| TABLE 3-3: PIC16(L)F1934 MEMORY MAP, BANKS | 0-7 |
|--|-----|
|--|-----|

|              | BANK 0               | •            | BANK 1                                     |              | BANK 2                                     |              | BANK 3                       |              | BANK 4                       |              | BANK 5                       |              | BANK 6                       |              | BANK 7                       |
|--------------|----------------------|--------------|--|--------------|--|--------------|------------------------------|--------------|------------------------------|--------------|------------------------------|--------------|------------------------------|--------------|------------------------------|
| 000h         | INDF0                | 080h         | INDF0                                      | 100h         | INDF0                                      | 180h         | INDF0                        | 200h         | INDF0                        | 280h         | INDF0                        | 300h         | INDF0                        | 380h         | INDF0                        |
| 001h         | INDF1                | 081h         | INDF1                                      | 101h         | INDF1                                      | 181h         | INDF1                        | 201h         | INDF1                        | 281h         | INDF1                        | 301h         | INDF1                        | 381h         | INDF1                        |
| 002h         | PCL                  | 082h         | PCL  | 102h         | PCL  | 182h         | PCL                          | 202h         | PCL                          | 282h         | PCL                          | 302h         | PCL                          | 382h         | PCL                          |
| 003h         | STATUS               | 083h         | STATUS                                     | 103h         | STATUS                                     | 183h         | STATUS                       | 203h         | STATUS                       | 283h         | STATUS                       | 303h         | STATUS                       | 383h         | STATUS                       |
| 004h         | FSR0L                | 084h         | FSR0L                                      | 104h         | FSR0L                                      | 184h         | FSR0L                        | 204h         | FSR0L                        | 284h         | FSR0L                        | 304h         | FSR0L                        | 384h         | FSR0L                        |
| 005h         | FSR0H                | 085h         | FSR0H                                      | 105h         | FSR0H                                      | 185h         | FSR0H                        | 205h         | FSR0H                        | 285h         | FSR0H                        | 305h         | FSR0H                        | 385h         | FSR0H                        |
| 006h         | FSR1L                | 086h         | FSR1L                                      | 106h         | FSR1L                                      | 186h         | FSR1L                        | 206h         | FSR1L                        | 286h         | FSR1L                        | 306h         | FSR1L                        | 386h         | FSR1L                        |
| 007h         | FSR1H                | 087h         | FSR1H                                      | 107h         | FSR1H                                      | 187h         | FSR1H                        | 207h         | FSR1H                        | 287h         | FSR1H                        | 307h         | FSR1H                        | 387h         | FSR1H                        |
| 008h         | BSR                  | 088h         | BSR  | 108h         | BSR  | 188h         | BSR                          | 208h         | BSR                          | 288h         | BSR                          | 308h         | BSR                          | 388h         | BSR                          |
| 009h         | WREG                 | 089h         | WREG                                       | 109h         | WREG                                       | 189h         | WREG                         | 209h         | WREG                         | 289h         | WREG                         | 309h         | WREG                         | 389h         | WREG                         |
| 00Ah         | PCLATH               | 08Ah         | PCLATH                                     | 10Ah         | PCLATH                                     | 18Ah         | PCLATH                       | 20Ah         | PCLATH                       | 28Ah         | PCLATH                       | 30Ah         | PCLATH                       | 38Ah         | PCLATH                       |
| 00Bh         | INTCON               | 08Bh         | INTCON                                     | 10Bh         | INTCON                                     | 18Bh         | INTCON                       | 20Bh         | INTCON                       | 28Bh         | INTCON                       | 30Bh         | INTCON                       | 38Bh         | INTCON                       |
| 00Ch         | PORTA                | 08Ch         | TRISA                                      | 10Ch         | LATA                                       | 18Ch         | ANSELA                       | 20Ch         | _                            | 28Ch         | _                            | 30Ch         | _                            | 38Ch         | _                            |
| 00Dh         | PORTB                | 08Dh         | TRISB                                      | 10Dh         | LATB                                       | 18Dh         | ANSELB                       | 20Dh         | WPUB                         | 28Dh         | _                            | 30Dh         | _                            | 38Dh         | _                            |
| 00Eh         | PORTC                | 08Eh         | TRISC                                      | 10Eh         | LATC                                       | 18Eh         |                              | 20Eh         | _                            | 28Eh         | _                            | 30Eh         | _                            | 38Eh         | _                            |
| 00Fh         | PORTD <sup>(1)</sup> | 08Fh         | TRISD <sup>(1)</sup>                       | 10Fh         | LATD <sup>(1)</sup>                        | 18Fh         | ANSELD <sup>(1)</sup>        | 20Fh         | _                            | 28Fh         | _                            | 30Fh         | _                            | 38Fh         | _                            |
| 010h         | PORTE                | 090h         | TRISE                                      | 110h         | LATE <sup>(1)</sup>                        | 190h         | ANSELE <sup>(1)</sup>        | 210h         | WPUE                         | 290h         | _                            | 310h         | _                            | 390h         | _                            |
| 011h         | PIR1                 | 091h         | PIE1                                       | 111h         | CM1CON0                                    | 191h         | EEADRL                       | 211h         | SSPBUF                       | 291h         | CCPR1L                       | 311h         | CCPR3L                       | 391h         | _                            |
| 012h         | PIR2                 | 092h         | PIE2                                       | 112h         | CM1CON1                                    | 192h         | EEADRH                       | 212h         | SSPADD                       | 292h         | CCPR1H                       | 312h         | CCPR3H                       | 392h         | _                            |
| 013h         | PIR3                 | 093h         | PIE3                                       | 113h         | CM2CON0                                    | 193h         | EEDATL                       | 213h         | SSPMSK                       | 293h         | CCP1CON                      | 313h         | CCP3CON                      | 393h         |                              |
| 014h         | _                    | 094h         | _  | 114h         | CM2CON1                                    | 194h         | EEDATH                       | 214h         | SSPSTAT                      | 294h         | PWM1CON                      | 314h         | PWM3CON                      | 394h         | IOCBP                        |
| 015h         | TMR0                 | 095h         | OPTION_REG                                 | 115h         | CMOUT                                      | 195h         | EECON1                       | 215h         | SSPCON1                      | 295h         | CCP1AS                       | 315h         | CCP3AS                       | 395h         | IOCBN                        |
| 016h         | TMR1L                | 096h         | PCON                                       | 116h         | BORCON                                     | 196h         | EECON2                       | 216h         | SSPCON2                      | 296h         | PSTR1CON                     | 316h         | PSTR3CON                     | 396h         | IOCBF                        |
| 017h         | TMR1H                | 097h         | WDTCON                                     | 117h         | FVRCON                                     | 197h         |                              | 217h         | SSPCON3                      | 297h         | _                            | 317h         | _                            | 397h         | _                            |
| 018h         | T1CON                | 098h         | OSCTUNE                                    | 118h         | DACCON0                                    | 198h         |                              | 218h         | _                            | 298h         | CCPR2L                       | 318h         | CCPR4L                       | 398h         | _                            |
| 019h         | T1GCON               | 099h         | OSCCON                                     | 119h         | DACCON1                                    | 199h         | RCREG                        | 219h         | _                            | 299h         | CCPR2H                       | 319h         | CCPR4H                       | 399h         | _                            |
| 01Ah         | TMR2                 | 09Ah         | OSCSTAT                                    | 11Ah         | SRCON0                                     | 19Ah         | TXREG                        | 21Ah         | _                            | 29Ah         | CCP2CON                      | 31Ah         | CCP4CON                      | 39Ah         | _                            |
| 01Bh         | PR2                  | 09Bh         | ADRESL                                     | 11Bh         | SRCON1                                     | 19Bh         | SPBRGL                       | 21Bh         | _                            | 29Bh         | PWM2CON                      | 31Bh         | _                            | 39Bh         | _                            |
| 01Ch         | T2CON                | 09Ch         | ADRESH                                     | 11Ch         | _  | 19Ch         | SPBRGH                       | 21Ch         | _                            | 29Ch         | CCP2AS                       | 31Ch         | CCPR5L                       | 39Ch         | _                            |
| 01Dh         | _                    | 09Dh         | ADCON0                                     | 11Dh         | APFCON                                     | 19Dh         | RCSTA                        | 21Dh         | _                            | 29Dh         | PSTR2CON                     | 31Dh         | CCPR5H                       | 39Dh         | _                            |
| 01Eh         | CPSCON0              | 09Eh         | ADCON1                                     | 11Eh         | _  | 19Eh         | TXSTA                        | 21Eh         | _                            | 29Eh         | CCPTMRS0                     | 31Eh         | CCP5CON                      | 39Eh         | _                            |
| 01Fh         | CPSCON1              | 09Fh         | _  | 11Fh         | _  | 19Fh         | BAUDCTR                      | 21Fh         | _                            | 29Fh         | CCPTMRS1                     | 31Fh         | _                            | 39Fh         | _                            |
| 020h         |                      | 0A0h         |  | 120h         |  | 1A0h         |                              | 220h         |                              | 2A0h         |                              | 320h         |                              | 3A0h         |                              |
|              | General<br>Purpose   |              | General<br>Purpose<br>Register<br>80 Bytes |              | General<br>Purpose<br>Register<br>80 Bytes |              | Unimplemented<br>Read as '0' |
| 06Fh         | Register<br>96 Bytes | 0EFh         |  | 16Fh         |  | 1EFh         |                              | 26Fh         |                              | 2EFh         |                              | 36Fh         |                              | 3EFh         |                              |
| 070h<br>07Fh | •                    | 0F0h<br>0FFh | Accesses<br>70h – 7Fh                      | 170h<br>17Fh | Accesses<br>70h – 7Fh                      | 1F0h<br>1FFh | Accesses<br>70h – 7Fh        | 270h<br>27Fh | Accesses<br>70h – 7Fh        | 2F0h<br>2FFh | Accesses<br>70h – 7Fh        | 370h<br>37Fh | Accesses<br>70h – 7Fh        | 3F0h<br>3FFh | Accesses<br>70h – 7Fh        |

Legend:

= Unimplemented data memory locations, read as '0'.

Note 1: Not available on PIC16(L)F1936.

TABLE 3-4: PIC16(L)F1934 MEMORY MAP, BANKS 8-15

|        | BANK 8                       |      | BANK 9                       |       | BANK 10                      |        | BANK 11                      |       | BANK 12                      |        | BANK 13                      |      | BANK 14                      |      | BANK 15                     |
|--------|------------------------------|------|------------------------------|-------|------------------------------|--------|------------------------------|-------|------------------------------|--------|------------------------------|------|------------------------------|------|-----------------------------|
| 400h   | INDF0                        | 480h | INDF0                        | 500h  | INDF0                        | 580h   | INDF0                        | 600h  | INDF0                        | 680h   | INDF0                        | 700h | INDF0                        | 780h | INDF0                       |
| 401h   | INDF1                        | 481h | INDF1                        | 501h  | INDF1                        | 581h   | INDF1                        | 601h  | INDF1                        | 681h   | INDF1                        | 701h | INDF1                        | 781h | INDF1                       |
| 402h   | PCL                          | 482h | PCL                          | 502h  | PCL                          | 582h   | PCL                          | 602h  | PCL                          | 682h   | PCL                          | 702h | PCL                          | 782h | PCL                         |
| 403h   | STATUS                       | 483h | STATUS                       | 503h  | STATUS                       | 583h   | STATUS                       | 603h  | STATUS                       | 683h   | STATUS                       | 703h | STATUS                       | 783h | STATUS                      |
| 404h   | FSR0L                        | 484h | FSR0L                        | 504h  | FSR0L                        | 584h   | FSR0L                        | 604h  | FSR0L                        | 684h   | FSR0L                        | 704h | FSR0L                        | 784h | FSR0L                       |
| 405h   | FSR0H                        | 485h | FSR0H                        | 505h  | FSR0H                        | 585h   | FSR0H                        | 605h  | FSR0H                        | 685h   | FSR0H                        | 705h | FSR0H                        | 785h | FSR0H                       |
| 406h   | FSR1L                        | 486h | FSR1L                        | 506h  | FSR1L                        | 586h   | FSR1L                        | 606h  | FSR1L                        | 686h   | FSR1L                        | 706h | FSR1L                        | 786h | FSR1L                       |
| 407h   | FSR1H                        | 487h | FSR1H                        | 507h  | FSR1H                        | 587h   | FSR1H                        | 607h  | FSR1H                        | 687h   | FSR1H                        | 707h | FSR1H                        | 787h | FSR1H                       |
| 408h   | BSR                          | 488h | BSR                          | 508h  | BSR                          | 588h   | BSR                          | 608h  | BSR                          | 688h   | BSR                          | 708h | BSR                          | 788h | BSR                         |
| 409h   | WREG                         | 489h | WREG                         | 509h  | WREG                         | 589h   | WREG                         | 609h  | WREG                         | 689h   | WREG                         | 709h | WREG                         | 789h | WREG                        |
| 40Ah   | PCLATH                       | 48Ah | PCLATH                       | 50Ah  | PCLATH                       | 58Ah   | PCLATH                       | 60Ah  | PCLATH                       | 68Ah   | PCLATH                       | 70Ah | PCLATH                       | 78Ah | PCLATH                      |
| 40Bh   | INTCON                       | 48Bh | INTCON                       | 50Bh  | INTCON                       | 58Bh   | INTCON                       | 60Bh  | INTCON                       | 68Bh   | INTCON                       | 70Bh | INTCON                       | 78Bh | INTCON                      |
| 40Ch   | _                            | 48Ch | _                            | 50Ch  | _                            | 58Ch   | _                            | 60Ch  | _                            | 68Ch   | _                            | 70Ch | _                            | 78Ch | _                           |
| 40Dh   | _                            | 48Dh | _                            | 50Dh  | _                            | 58Dh   | _                            | 60Dh  | _                            | 68Dh   | _                            | 70Dh | _                            | 78Dh | _                           |
| 40Eh   | _                            | 48Eh | _                            | 50Eh  | _                            | 58Eh   | _                            | 60Eh  | _                            | 68Eh   | _                            | 70Eh | _                            | 78Eh | _                           |
| 40Fh   | _                            | 48Fh | _                            | 50Fh  | _                            | 58Fh   | _                            | 60Fh  | _                            | 68Fh   | _                            | 70Fh | _                            | 78Fh | _                           |
| 410h   | _                            | 490h | _                            | 510h  | _                            | 590h   | _                            | 610h  | _                            | 690h   | _                            | 710h | _                            | 790h | _                           |
| 411h   | _                            | 491h | _                            | 511h  | _                            | 591h   | _                            | 611h  | _                            | 691h   | _                            | 711h | _                            | 791h |                             |
| 412h   | _                            | 492h | _                            | 512h  | _                            | 592h   | _                            | 612h  | _                            | 692h   | _                            | 712h | _                            | 792h |                             |
| 413h   | _                            | 493h | _                            | 513h  | _                            | 593h   | _                            | 613h  | _                            | 693h   | _                            | 713h | _                            | 793h |                             |
| 414h   | _                            | 494h | _                            | 514h  | _                            | 594h   | _                            | 614h  | _                            | 694h   | _                            | 714h | _                            | 794h |                             |
| 415h   | TMR4                         | 495h | _                            | 515h  | _                            | 595h   | _                            | 615h  | _                            | 695h   | _                            | 715h | _                            | 795h |                             |
| 416h   | PR4                          | 496h | _                            | 516h  | _                            | 596h   | _                            | 616h  | _                            | 696h   | _                            | 716h | _                            | 796h |                             |
| 417h   | T4CON                        | 497h | _                            | 517h  | _                            | 597h   | _                            | 617h  | _                            | 697h   | _                            | 717h | _                            | 797h |                             |
| 418h   | _                            | 498h | _                            | 518h  | _                            | 598h   | _                            | 618h  | _                            | 698h   | _                            | 718h | _                            | 798h |                             |
| 419h   | _                            | 499h | _                            | 519h  | _                            | 599h   | _                            | 619h  | _                            | 699h   | _                            | 719h | _                            | 799h |                             |
| 41Ah   | _                            | 49Ah | _                            | 51Ah  | _                            | 59Ah   | _                            | 61Ah  | _                            | 69Ah   | _                            | 71Ah | _                            | 79Ah | Coo Toble 2.0 or            |
| 41Bh   | _                            | 49Bh | _                            | 51Bh  | _                            | 59Bh   | _                            | 61Bh  | _                            | 69Bh   | _                            | 71Bh | _                            | 79Bh | See Table 3-9 or Table 3-10 |
| 41Ch   | TMR6                         | 49Ch | _                            | 51Ch  | _                            | 59Ch   | _                            | 61Ch  | _                            | 69Ch   | _                            | 71Ch | _                            | 79Ch | 14515 5 15                  |
| 41Dh   | PR6                          | 49Dh | _                            | 51Dh  | _                            | 59Dh   | _                            | 61Dh  | _                            | 69Dh   | _                            | 71Dh | _                            | 79Dh |                             |
| 41Eh   | T6CON                        | 49Eh | _                            | 51Eh  | _                            | 59Eh   | _                            | 61Eh  | _                            | 69Eh   | _                            | 71Eh | _                            | 79Eh |                             |
| 41Fh   | _                            | 49Fh | _                            | 51Fh  | _                            | 59Fh   | _                            | 61Fh  | _                            | 69Fh   | _                            | 71Fh | _                            | 79Fh |                             |
| 420h   |                              | 4A0h |                              | 520h  |                              | 5A0h   |                              | 620h  |                              | 6A0h   |                              | 720h |                              | 7A0h |                             |
|        | Unimplemented<br>Read as '0' |      | Unimplemented<br>Read as '0' |       | Unimplemented<br>Read as '0' |        | Unimplemented<br>Read as '0' |       | Unimplemented<br>Read as '0' |        | Unimplemented<br>Read as '0' |      | Unimplemented<br>Read as '0' |      |                             |
| 46Fh   |                              | 4EFh |                              | 56Fh  |                              | 5EFh   |                              | 66Fh  |                              | 6EFh   |                              | 76Fh |                              | 7EFh |                             |
| 470h   |                              | 4F0h |                              | 570h  |                              | 5F0h   |                              | 670h  |                              | 6F0h   |                              | 770h |                              | 7F0h |                             |
| ., 0.1 | Accesses                     | 0.1  | Accesses                     | 0.011 | Accesses                     | 0. 0.1 | Accesses                     | 0.011 | Accesses                     | 0. 011 | Accesses                     |      | Accesses                     | 0.1  | Accesses                    |
|        | 70h – 7Fh                    |      | 70h – 7Fh                    |       | 70h – 7Fh                    |        | 70h – 7Fh                    |       | 70h – 7Fh                    |        | 70h – 7Fh                    |      | 70h – 7Fh                    |      | 70h – 7Fh                   |
| 4751   |                              | 4FFh | -                            | 57Fh  |                              |        | -                            | 075   |                              | OFF!   |                              | 7751 | -                            | 755  | -                           |
| 47Fh   |                              | 4660 |                              | 5/FI  |                              | 5FFh   |                              | 67Fh  |                              | 6FFh   |                              | 77Fh |                              | 7FFh |                             |

**Legend:** = Unimplemented data memory locations, read as '0'.

| TABL         | .E 3-5: P            | IC16(        | L)F1936/193          | 7 ME         | MORY MAP,           | BAN          | KS 0-7                |              |                     |              |                     |              |                      |              |                           |
|--------------|----------------------|--------------|----------------------|--------------|---------------------|--------------|-----------------------|--------------|---------------------|--------------|---------------------|--------------|----------------------|--------------|---------------------------|
|              | BANK 0               | •            | BANK 1               |              | BANK 2              |              | BANK 3                |              | BANK 4              |              | BANK 5              |              | BANK 6               |              | BANK 7                    |
| 000h         | INDF0                | 080h         | INDF0                | 100h         | INDF0               | 180h         | INDF0                 | 200h         | INDF0               | 280h         | INDF0               | 300h         | INDF0                | 380h         | INDF0                     |
| 001h         | INDF1                | 081h         | INDF1                | 101h         | INDF1               | 181h         | INDF1                 | 201h         | INDF1               | 281h         | INDF1               | 301h         | INDF1                | 381h         | INDF1                     |
| 002h         | PCL                  | 082h         | PCL                  | 102h         | PCL                 | 182h         | PCL                   | 202h         | PCL                 | 282h         | PCL                 | 302h         | PCL                  | 382h         | PCL                       |
| 003h         | STATUS               | 083h         | STATUS               | 103h         | STATUS              | 183h         | STATUS                | 203h         | STATUS              | 283h         | STATUS              | 303h         | STATUS               | 383h         | STATUS                    |
| 004h         | FSR0L                | 084h         | FSR0L                | 104h         | FSR0L               | 184h         | FSR0L                 | 204h         | FSR0L               | 284h         | FSR0L               | 304h         | FSR0L                | 384h         | FSR0L                     |
| 005h         | FSR0H                | 085h         | FSR0H                | 105h         | FSR0H               | 185h         | FSR0H                 | 205h         | FSR0H               | 285h         | FSR0H               | 305h         | FSR0H                | 385h         | FSR0H                     |
| 006h         | FSR1L                | 086h         | FSR1L                | 106h         | FSR1L               | 186h         | FSR1L                 | 206h         | FSR1L               | 286h         | FSR1L               | 306h         | FSR1L                | 386h         | FSR1L                     |
| 007h         | FSR1H                | 087h         | FSR1H                | 107h         | FSR1H               | 187h         | FSR1H                 | 207h         | FSR1H               | 287h         | FSR1H               | 307h         | FSR1H                | 387h         | FSR1H                     |
| 008h         | BSR                  | 088h         | BSR                  | 108h         | BSR                 | 188h         | BSR                   | 208h         | BSR                 | 288h         | BSR                 | 308h         | BSR                  | 388h         | BSR                       |
| 009h         | WREG                 | 089h         | WREG                 | 109h         | WREG                | 189h         | WREG                  | 209h         | WREG                | 289h         | WREG                | 309h         | WREG                 | 389h         | WREG                      |
| 00Ah         | PCLATH               | 08Ah         | PCLATH               | 10Ah         | PCLATH              | 18Ah         | PCLATH                | 20Ah         | PCLATH              | 28Ah         | PCLATH              | 30Ah         | PCLATH               | 38Ah         | PCLATH                    |
| 00Bh         | INTCON               | 08Bh         | INTCON               | 10Bh         | INTCON              | 18Bh         | INTCON                | 20Bh         | INTCON              | 28Bh         | INTCON              | 30Bh         | INTCON               | 38Bh         | INTCON                    |
| 00Ch         | PORTA                | 08Ch         | TRISA                | 10Ch         | LATA                | 18Ch         | ANSELA                | 20Ch         | _                   | 28Ch         | _                   | 30Ch         | _                    | 38Ch         | _                         |
| 00Dh         | PORTB                | 08Dh         | TRISB                | 10Dh         | LATB                | 18Dh         | ANSELB                | 20Dh         | WPUB                | 28Dh         | _                   | 30Dh         | _                    | 38Dh         | _                         |
| 00Eh         | PORTC                | 08Eh         | TRISC                | 10Eh         | LATC                | 18Eh         | _                     | 20Eh         |                     | 28Eh         |                     | 30Eh         | _                    | 38Eh         | _                         |
| 00Fh         | PORTD <sup>(1)</sup> | 08Fh         | TRISD <sup>(1)</sup> | 10Fh         | LATD <sup>(1)</sup> | 18Fh         | ANSELD <sup>(1)</sup> | 20Fh         | _                   | 28Fh         | _                   | 30Fh         | _                    | 38Fh         | _                         |
| 010h         | PORTE                | 090h         | TRISE                | 110h         | LATE <sup>(1)</sup> | 190h         | ANSELE <sup>(1)</sup> | 210h         | WPUE                | 290h         |                     | 310h         | _                    | 390h         | _                         |
| 011h         | PIR1                 | 091h         | PIE1                 | 111h         | CM1CON0             | 191h         | EEADRL                | 211h         | SSPBUF              | 291h         | CCPR1L              | 311h         | CCPR3L               | 391h         | _                         |
| 012h         | PIR2                 | 092h         | PIE2                 | 112h         | CM1CON1             | 192h         | EEADRH                | 212h         | SSPADD              | 292h         | CCPR1H              | 312h         | CCPR3H               | 392h         | _                         |
| 013h         | PIR3                 | 093h         | PIE3                 | 113h         | CM2CON0             | 193h         | EEDATL                | 213h         | SSPMSK              | 293h         | CCP1CON             | 313h         | CCP3CON              | 393h         | _                         |
| 014h         |                      | 094h         | _                    | 114h         | CM2CON1             | 194h         | EEDATH                | 214h         | SSPSTAT             | 294h         | PWM1CON             | 314h         | PWM3CON              | 394h         | IOCBP                     |
| 015h         | TMR0                 | 095h         | OPTION_REG           | 115h         | CMOUT               | 195h         | EECON1                | 215h         | SSPCON1             | 295h         | CCP1AS              | 315h         | CCP3AS               | 395h         | IOCBN                     |
| 016h         | TMR1L                | 096h         | PCON                 | 116h         | BORCON              | 196h         | EECON2                | 216h         | SSPCON2             | 296h         | PSTR1CON            | 316h         | PSTR3CON             | 396h         | IOCBF                     |
| 017h         | TMR1H                | 097h         | WDTCON               | 117h         | FVRCON              | 197h         | _                     | 217h         | SSPCON3             | 297h         | _                   | 317h         | _                    | 397h         | _                         |
| 018h         | T1CON                | 098h         | OSCTUNE              | 118h         | DACCON0             | 198h         | _                     | 218h         |                     | 298h         | CCPR2L              | 318h         | CCPR4L               | 398h         | _                         |
| 019h         | T1GCON               | 099h         | OSCCON               | 119h         | DACCON1             | 199h         | RCREG                 | 219h         |                     | 299h         | CCPR2H              | 319h         | CCPR4H               | 399h         | _                         |
| 01Ah         | TMR2                 | 09Ah         | OSCSTAT              | 11Ah         | SRCON0              | 19Ah         | TXREG                 | 21Ah         |                     | 29Ah         | CCP2CON             | 31Ah         | CCP4CON              | 39Ah         | _                         |
| 01Bh         | PR2                  | 09Bh         | ADRESL               | 11Bh         | SRCON1              | 19Bh         | SPBRGL                | 21Bh         |                     | 29Bh         | PWM2CON             | 31Bh         | _                    | 39Bh         | _                         |
| 01Ch         | T2CON                | 09Ch         | ADRESH               | 11Ch         | <del>_</del>        | 19Ch         | SPBRGH                | 21Ch         |                     | 29Ch         | CCP2AS              | 31Ch         | CCPR5L               | 39Ch         | _                         |
| 01Dh         |                      | 09Dh         | ADCON0               | 11Dh         | APFCON              | 19Dh         | RCSTA                 | 21Dh         |                     | 29Dh         | PSTR2CON            | 31Dh         | CCPR5H               | 39Dh         | _                         |
| 01Eh         | CPSCON0              | 09Eh         | ADCON1               | 11Eh         |                     | 19Eh         | TXSTA                 | 21Eh         |                     | 29Eh         | CCPTMRS0            | 31Eh         | CCP5CON              | 39Eh         | _                         |
| 01Fh<br>020h | CPSCON1              | 09Fh<br>0A0h | _                    | 11Fh<br>120h | _                   | 19Fh<br>1A0h | BAUDCON               | 21Fh<br>220h | _                   | 29Fh<br>2A0h | CCPTMRS1            | 31Fh<br>320h | _                    | 39Fh<br>3A0h | _                         |
| 02011        |                      | UAUII        |                      | 12011        |                     | IAUII        |                       | 22011        |                     | ZAUN         |                     | 32011        | General Purpose      | SAUII        |                           |
|              |                      |              | General              |              | General             |              | General               |              | General             |              | General             | 32Fh         | Register<br>16 Bytes |              | l la incola na costa d    |
|              |                      |              | Purpose<br>Register  |              | Purpose<br>Register |              | Purpose<br>Register   |              | Purpose<br>Register |              | Purpose<br>Register |              | 10 Bytoo             |              | Unimplemented Read as '0' |
|              | General<br>Purpose   |              | 80 Bytes             |              | 80 Bytes            |              | 80 Bytes              |              | 80 Bytes            |              | 80 Bytes            | 330h         | Unimplemented        |              | ricad as o                |
| 0051         | Register             | ٥٦٦١         | ,                    | 4051         | ,                   | 4551         | •                     | 0051         | ,                   | 055          | ,                   | 2656         | Read as '0'          | 3EFh         |                           |
| 06Fh         | 96 Bytes             | 0EFh         |                      | 16Fh         |                     | 1EFh<br>1F0h |                       | 26Fh<br>270h |                     | 2EFh<br>2F0h |                     | 36Fh         |                      |              |                           |
| 070h         |                      | 0F0h         | Accesses             | 170h         | Accesses            | irun         | Accesses              | 2/Un         | Accesses            | ∠run         | Accesses            | 370h         | Accesses             | 3F0h         | Accesses                  |
|              |                      |              | 70h – 7Fh            |              | 70h – 7Fh           |              | 70h – 7Fh             |              | 70h – 7Fh           |              | 70h – 7Fh           |              | 70h – 7Fh            |              | 70h – 7Fh                 |
| 07Fh         |                      | 0FFh         |                      | 17Fh         |                     | 1FFh         |                       | 27Fh         |                     | 2FFh         |                     | 37Fh         | _                    | 3FFh         |                           |
| ٠, ١١١       |                      | ا `` · · ا ل |                      |              |                     | 1F           |                       | J ~[         |                     | ا '' · · · ل |                     | ] ~          |                      | ~· · · · ·   |                           |

gend: = Unimplemented data memory locations, read as '0'.

Note 1: Not available on PIC16(L)F1936.

TABLE 3-6: PIC16(L)F1936/1937 MEMORY MAP, BANKS 8-15

|      | BANK 8                       |      | BANK 9                       |      | BANK 10                      |      | BANK 11                      |      | BANK 12                      |      | BANK 13                      |      | BANK 14                      |      | BANK 15                     |
|------|------------------------------|------|------------------------------|------|------------------------------|------|------------------------------|------|------------------------------|------|------------------------------|------|------------------------------|------|-----------------------------|
| 400h | INDF0                        | 480h | INDF0                        | 500h | INDF0                        | 580h | INDF0                        | 600h | INDF0                        | 680h | INDF0                        | 700h | INDF0                        | 780h | INDF0                       |
| 401h | INDF1                        | 481h | INDF1                        | 501h | INDF1                        | 581h | INDF1                        | 601h | INDF1                        | 681h | INDF1                        | 701h | INDF1                        | 781h | INDF1                       |
| 402h | PCL                          | 482h | PCL                          | 502h | PCL                          | 582h | PCL                          | 602h | PCL                          | 682h | PCL                          | 702h | PCL                          | 782h | PCL                         |
| 403h | STATUS                       | 483h | STATUS                       | 503h | STATUS                       | 583h | STATUS                       | 603h | STATUS                       | 683h | STATUS                       | 703h | STATUS                       | 783h | STATUS                      |
| 404h | FSR0L                        | 484h | FSR0L                        | 504h | FSR0L                        | 584h | FSR0L                        | 604h | FSR0L                        | 684h | FSR0L                        | 704h | FSR0L                        | 784h | FSR0L                       |
| 405h | FSR0H                        | 485h | FSR0H                        | 505h | FSR0H                        | 585h | FSR0H                        | 605h | FSR0H                        | 685h | FSR0H                        | 705h | FSR0H                        | 785h | FSR0H                       |
| 406h | FSR1L                        | 486h | FSR1L                        | 506h | FSR1L                        | 586h | FSR1L                        | 606h | FSR1L                        | 686h | FSR1L                        | 706h | FSR1L                        | 786h | FSR1L                       |
| 407h | FSR1H                        | 487h | FSR1H                        | 507h | FSR1H                        | 587h | FSR1H                        | 607h | FSR1H                        | 687h | FSR1H                        | 707h | FSR1H                        | 787h | FSR1H                       |
| 408h | BSR                          | 488h | BSR                          | 508h | BSR                          | 588h | BSR                          | 608h | BSR                          | 688h | BSR                          | 708h | BSR                          | 788h | BSR                         |
| 409h | WREG                         | 489h | WREG                         | 509h | WREG                         | 589h | WREG                         | 609h | WREG                         | 689h | WREG                         | 709h | WREG                         | 789h | WREG                        |
| 40Ah | PCLATH                       | 48Ah | PCLATH                       | 50Ah | PCLATH                       | 58Ah | PCLATH                       | 60Ah | PCLATH                       | 68Ah | PCLATH                       | 70Ah | PCLATH                       | 78Ah | PCLATH                      |
| 40Bh | INTCON                       | 48Bh | INTCON                       | 50Bh | INTCON                       | 58Bh | INTCON                       | 60Bh | INTCON                       | 68Bh | INTCON                       | 70Bh | INTCON                       | 78Bh | INTCON                      |
| 40Ch | _                            | 48Ch |                              | 50Ch | _                            | 58Ch | _                            | 60Ch | _                            | 68Ch |                              | 70Ch | _                            | 78Ch | _                           |
| 40Dh | _                            | 48Dh | _                            | 50Dh |                              | 58Dh | _                            | 60Dh | _                            | 68Dh | _                            | 70Dh | _                            | 78Dh | _                           |
| 40Eh | _                            | 48Eh |                              | 50Eh | _                            | 58Eh |                              | 60Eh | _                            | 68Eh |                              | 70Eh | _                            | 78Eh | _                           |
| 40Fh | _                            | 48Fh |                              | 50Fh | _                            | 58Fh | _                            | 60Fh | _                            | 68Fh |                              | 70Fh | _                            | 78Fh | _                           |
| 410h | _                            | 490h | -                            | 510h | _                            | 590h | _                            | 610h | _                            | 690h |                              | 710h | _                            | 790h | _                           |
| 411h | _                            | 491h | _                            | 511h |                              | 591h | _                            | 611h | _                            | 691h | _                            | 711h | _                            | 791h |                             |
| 412h | _                            | 492h | _                            | 512h |                              | 592h | _                            | 612h | _                            | 692h | _                            | 712h | _                            | 792h |                             |
| 413h | _                            | 493h | _                            | 513h |                              | 593h | _                            | 613h | _                            | 693h | _                            | 713h | _                            | 793h |                             |
| 414h | _                            | 494h | _                            | 514h |                              | 594h | _                            | 614h | _                            | 694h | _                            | 714h | _                            | 794h |                             |
| 415h | TMR4                         | 495h | _                            | 515h |                              | 595h | _                            | 615h | _                            | 695h | _                            | 715h | _                            | 795h |                             |
| 416h | PR4                          | 496h | _                            | 516h |                              | 596h | _                            | 616h | _                            | 696h | _                            | 716h | _                            | 796h |                             |
| 417h | T4CON                        | 497h | _                            | 517h |                              | 597h | _                            | 617h | _                            | 697h | _                            | 717h | _                            | 797h |                             |
| 418h | _                            | 498h | _                            | 518h |                              | 598h | _                            | 618h | _                            | 698h | _                            | 718h | _                            | 798h |                             |
| 419h | _                            | 499h | _                            | 519h |                              | 599h | _                            | 619h | _                            | 699h | _                            | 719h | _                            | 799h |                             |
| 41Ah | _                            | 49Ah | _                            | 51Ah | _                            | 59Ah | _                            | 61Ah | _                            | 69Ah | _                            | 71Ah | _                            | 79Ah | O T-bl- 0 0                 |
| 41Bh | _                            | 49Bh | _                            | 51Bh | _                            | 59Bh | _                            | 61Bh | _                            | 69Bh | _                            | 71Bh | _                            | 79Bh | See Table 3-9 or Table 3-10 |
| 41Ch | TMR6                         | 49Ch | _                            | 51Ch | _                            | 59Ch | _                            | 61Ch | _                            | 69Ch | _                            | 71Ch | _                            | 79Ch | Table 5 To                  |
| 41Dh | PR6                          | 49Dh | _                            | 51Dh |                              | 59Dh | _                            | 61Dh | _                            | 69Dh | _                            | 71Dh | _                            | 79Dh |                             |
| 41Eh | T6CON                        | 49Eh | _                            | 51Eh | _                            | 59Eh | _                            | 61Eh | _                            | 69Eh | _                            | 71Eh | _                            | 79Eh |                             |
| 41Fh | _                            | 49Fh | _                            | 51Fh | _                            | 59Fh | _                            | 61Fh | _                            | 69Fh | _                            | 71Fh | _                            | 79Fh |                             |
| 420h |                              | 4A0h |                              | 520h |                              | 5A0h |                              | 620h |                              | 6A0h |                              | 720h |                              | 7A0h |                             |
|      | Unimplemented<br>Read as '0' |      |                             |
| 46Fh |                              | 4EFh |                              | 56Fh |                              | 5EFh |                              | 66Fh |                              | 6EFh |                              | 76Fh |                              | 7EFh |                             |
| 470h |                              | 4F0h |                              | 570h |                              | 5F0h |                              | 670h |                              | 6F0h |                              | 770h |                              | 7F0h |                             |
|      | Accesses                     |      | Accesses                    |
|      | 70h – 7Fh                    |      | 70h – 7Fh                   |
| 47Fh |                              | 4FFh |                              | 57Fh |                              | 5FFh |                              | 67Fh |                              | 6FFh |                              | 77Fh |                              | 7FFh |                             |

**Legend:** = Unimplemented data memory locations, read as '0'.

| ŏ             |
|---------------|
| 4             |
| $\overline{}$ |
| ×             |
| $\alpha$      |
| m             |
| Ξ.            |
| င္က           |
| ö             |
| æ             |
| ပ္ပ           |
| ũ             |
|               |

**TABLE 3-7:** PIC16(L)F1934/6/7 MEMORY MAP, BANKS 16-23

|      | BANK 16                      | •    | BANK 17                      |      | BANK 18                      |      | BANK 19                      |      | BANK 20                      |      | BANK 21                      |      | BANK 22                      |      | BANK 23                      |
|------|------------------------------|------|------------------------------|------|------------------------------|------|------------------------------|------|------------------------------|------|------------------------------|------|------------------------------|------|------------------------------|
| 800h | INDF0                        | 880h | INDF0                        | 900h | INDF0                        | 980h | INDF0                        | A00h | INDF0                        | A80h | INDF0                        | B00h | INDF0                        | B80h | INDF0                        |
| 801h | INDF1                        | 881h | INDF1                        | 901h | INDF1                        | 981h | INDF1                        | A01h | INDF1                        | A81h | INDF1                        | B01h | INDF1                        | B81h | INDF1                        |
| 802h | PCL                          | 882h | PCL                          | 902h | PCL                          | 982h | PCL                          | A02h | PCL                          | A82h | PCL                          | B02h | PCL                          | B82h | PCL                          |
| 803h | STATUS                       | 883h | STATUS                       | 903h | STATUS                       | 983h | STATUS                       | A03h | STATUS                       | A83h | STATUS                       | B03h | STATUS                       | B83h | STATUS                       |
| 804h | FSR0L                        | 884h | FSR0L                        | 904h | FSR0L                        | 984h | FSR0L                        | A04h | FSR0L                        | A84h | FSR0L                        | B04h | FSR0L                        | B84h | FSR0L                        |
| 805h | FSR0H                        | 885h | FSR0H                        | 905h | FSR0H                        | 985h | FSR0H                        | A05h | FSR0H                        | A85h | FSR0H                        | B05h | FSR0H                        | B85h | FSR0H                        |
| 806h | FSR1L                        | 886h | FSR1L                        | 906h | FSR1L                        | 986h | FSR1L                        | A06h | FSR1L                        | A86h | FSR1L                        | B06h | FSR1L                        | B86h | FSR1L                        |
| 807h | FSR1H                        | 887h | FSR1H                        | 907h | FSR1H                        | 987h | FSR1H                        | A07h | FSR1H                        | A87h | FSR1H                        | B07h | FSR1H                        | B87h | FSR1H                        |
| 808h | BSR                          | 888h | BSR                          | 908h | BSR                          | 988h | BSR                          | A08h | BSR                          | A88h | BSR                          | B08h | BSR                          | B88h | BSR                          |
| 809h | WREG                         | 889h | WREG                         | 909h | WREG                         | 989h | WREG                         | A09h | WREG                         | A89h | WREG                         | B09h | WREG                         | B89h | WREG                         |
| 80Ah | PCLATH                       | 88Ah | PCLATH                       | 90Ah | PCLATH                       | 98Ah | PCLATH                       | A0Ah | PCLATH                       | A8Ah | PCLATH                       | B0Ah | PCLATH                       | B8Ah | PCLATH                       |
| 80Bh | INTCON                       | 88Bh | INTCON                       | 90Bh | INTCON                       | 98Bh | INTCON                       | A0Bh | INTCON                       | A8Bh | INTCON                       | B0Bh | INTCON                       | B8Bh | INTCON                       |
| 80Ch | -                            | 88Ch | _                            | 90Ch | -                            | 98Ch | _                            | A0Ch | _                            | A8Ch | _                            | B0Ch | _                            | B8Ch | _                            |
| 80Dh | -                            | 88Dh | _                            | 90Dh |                              | 98Dh |                              | A0Dh | _                            | A8Dh |                              | B0Dh | _                            | B8Dh | _                            |
| 80Eh | _                            | 88Eh | _                            | 90Eh |                              | 98Eh | _                            | A0Eh | _                            | A8Eh |                              | B0Eh | _                            | B8Eh | _                            |
| 80Fh | -                            | 88Fh | _                            | 90Fh |                              | 98Fh |                              | A0Fh | _                            | A8Fh |                              | B0Fh | _                            | B8Fh | _                            |
| 810h |                              | 890h | _                            | 910h | 1                            | 990h |                              | A10h | _                            | A90h |                              | B10h | _                            | B90h | _                            |
| 811h | _                            | 891h | _                            | 911h |                              | 991h | _                            | A11h | _                            | A91h | _                            | B11h | _                            | B91h | _                            |
| 812h | _                            | 892h | _                            | 912h |                              | 992h | _                            | A12h | _                            | A92h | _                            | B12h | _                            | B92h | _                            |
| 813h | -                            | 893h | _                            | 913h | -                            | 993h | _                            | A13h | _                            | A93h | _                            | B13h | _                            | B93h | _                            |
| 814h | -                            | 894h | _                            | 914h | -                            | 994h | _                            | A14h | _                            | A94h | _                            | B14h | _                            | B94h | _                            |
| 815h | _                            | 895h | _                            | 915h | _                            | 995h | _                            | A15h | _                            | A95h | _                            | B15h | _                            | B95h | _                            |
| 816h | -                            | 896h | _                            | 916h |                              | 996h |                              | A16h | _                            | A96h |                              | B16h | _                            | B96h | _                            |
| 817h | _                            | 897h | _                            | 917h | _                            | 997h | _                            | A17h | _                            | A97h | _                            | B17h | _                            | B97h | _                            |
| 818h | _                            | 898h | _                            | 918h |                              | 998h | _                            | A18h | _                            | A98h | _                            | B18h | _                            | B98h | _                            |
| 819h | -                            | 899h | _                            | 919h | -                            | 999h | _                            | A19h | _                            | A99h | _                            | B19h | _                            | B99h | _                            |
| 81Ah | -                            | 89Ah | _                            | 91Ah | -                            | 99Ah | _                            | A1Ah | _                            | A9Ah | _                            | B1Ah | _                            | B9Ah | _                            |
| 81Bh | -                            | 89Bh | _                            | 91Bh | _                            | 99Bh | -                            | A1Bh | _                            | A9Bh | _                            | B1Bh | _                            | B9Bh | _                            |
| 81Ch | _                            | 89Ch | _                            | 91Ch |                              | 99Ch | _                            | A1Ch | _                            | A9Ch | _                            | B1Ch | _                            | B9Ch | _                            |
| 81Dh | _                            | 89Dh | _                            | 91Dh |                              | 99Dh | _                            | A1Dh | _                            | A9Dh | _                            | B1Dh | _                            | B9Dh | _                            |
| 81Eh | _                            | 89Eh | _                            | 91Eh |                              | 99Eh | _                            | A1Eh | _                            | A9Eh | _                            | B1Eh | _                            | B9Eh | _                            |
| 81Fh | -                            | 89Fh | _                            | 91Fh | -                            | 99Fh | _                            | A1Fh | _                            | A9Fh | _                            | B1Fh | _                            | B9Fh | _                            |
| 820h |                              | 8A0h |                              | 920h |                              | 9A0h |                              | A20h |                              | AA0h |                              | B20h |                              | BA0h |                              |
|      | Unimplemented<br>Read as '0' |
| 86Fh |                              | 8EFh |                              | 96Fh |                              | 9EFh |                              | A6Fh |                              | AEFh |                              | B6Fh |                              | BEFh |                              |
| 870h |                              | 8F0h |                              | 970h |                              | 9F0h |                              | A70h |                              | AF0h |                              | B70h |                              | BF0h |                              |
|      | Accesses                     |
|      | 70h – 7Fh                    |
| 87Fh |                              | 8FFh |                              | 97Fh |                              | 9FFh |                              | A7Fh |                              | AFFh |                              | B7Fh |                              | BFFh |                              |

= Unimplemented data memory locations, read as '0'.

TABLE 3-8: PIC16(L)F1934/6/7 MEMORY MAP, BANKS 24-31

|      | BANK 24                      |      | BANK 25                      |      | BANK 26                      |      | BANK 27                      |      | BANK 28                      |      | BANK 29                      |      | BANK 30                      |      | BANK 31        |
|------|------------------------------|------|------------------------------|------|------------------------------|------|------------------------------|------|------------------------------|------|------------------------------|------|------------------------------|------|----------------|
| C00h | INDF0                        | C80h | INDF0                        | D00h | INDF0                        | D80h | INDF0                        | E00h | INDF0                        | E80h | INDF0                        | F00h | INDF0                        | F80h | INDF0          |
| C01h | INDF1                        | C81h | INDF1                        | D01h | INDF1                        | D81h | INDF1                        | E01h | INDF1                        | E81h | INDF1                        | F01h | INDF1                        | F81h | INDF1          |
| C02h | PCL                          | C82h | PCL                          | D02h | PCL                          | D82h | PCL                          | E02h | PCL                          | E82h | PCL                          | F02h | PCL                          | F82h | PCL            |
| C03h | STATUS                       | C83h | STATUS                       | D03h | STATUS                       | D83h | STATUS                       | E03h | STATUS                       | E83h | STATUS                       | F03h | STATUS                       | F83h | STATUS         |
| C04h | FSR0L                        | C84h | FSR0L                        | D04h | FSR0L                        | D84h | FSR0L                        | E04h | FSR0L                        | E84h | FSR0L                        | F04h | FSR0L                        | F84h | FSR0L          |
| C05h | FSR0H                        | C85h | FSR0H                        | D05h | FSR0H                        | D85h | FSR0H                        | E05h | FSR0H                        | E85h | FSR0H                        | F05h | FSR0H                        | F85h | FSR0H          |
| C06h | FSR1L                        | C86h | FSR1L                        | D06h | FSR1L                        | D86h | FSR1L                        | E06h | FSR1L                        | E86h | FSR1L                        | F06h | FSR1L                        | F86h | FSR1L          |
| C07h | FSR1H                        | C87h | FSR1H                        | D07h | FSR1H                        | D87h | FSR1H                        | E07h | FSR1H                        | E87h | FSR1H                        | F07h | FSR1H                        | F87h | FSR1H          |
| C08h | BSR                          | C88h | BSR                          | D08h | BSR                          | D88h | BSR                          | E08h | BSR                          | E88h | BSR                          | F08h | BSR                          | F88h | BSR            |
| C09h | WREG                         | C89h | WREG                         | D09h | WREG                         | D89h | WREG                         | E09h | WREG                         | E89h | WREG                         | F09h | WREG                         | F89h | WREG           |
| C0Ah | PCLATH                       | C8Ah | PCLATH                       | D0Ah | PCLATH                       | D8Ah | PCLATH                       | E0Ah | PCLATH                       | E8Ah | PCLATH                       | F0Ah | PCLATH                       | F8Ah | PCLATH         |
| C0Bh | INTCON                       | C8Bh | INTCON                       | D0Bh | INTCON                       | D8Bh | INTCON                       | E0Bh | INTCON                       | E8Bh | INTCON                       | F0Bh | INTCON                       | F8Bh | INTCON         |
| C0Ch | _                            | C8Ch | _                            | D0Ch | _                            | D8Ch | _                            | E0Ch | 1                            | E8Ch | _                            | F0Ch | _                            | F8Ch |                |
| C0Dh | _                            | C8Dh | _                            | D0Dh | _                            | D8Dh | _                            | E0Dh | 1                            | E8Dh | _                            | F0Dh | _                            | F8Dh |                |
| C0Eh | _                            | C8Eh | _                            | D0Eh | _                            | D8Eh | _                            | E0Eh | 1                            | E8Eh | _                            | F0Eh | _                            | F8Eh |                |
| C0Fh | _                            | C8Fh | _                            | D0Fh | _                            | D8Fh | _                            | E0Fh | I                            | E8Fh | _                            | F0Fh | _                            | F8Fh |                |
| C10h | _                            | C90h | _                            | D10h | _                            | D90h | _                            | E10h | I                            | E90h | _                            | F10h | _                            | F90h |                |
| C11h | _                            | C91h | _                            | D11h | _                            | D91h | _                            | E11h | 1                            | E91h | _                            | F11h | _                            | F91h |                |
| C12h | _                            | C92h | _                            | D12h | _                            | D92h | _                            | E12h | 1                            | E92h | _                            | F12h | _                            | F92h |                |
| C13h | _                            | C93h | _                            | D13h | _                            | D93h | _                            | E13h | 1                            | E93h | _                            | F13h | _                            | F93h |                |
| C14h | _                            | C94h | _                            | D14h | _                            | D94h | _                            | E14h | _                            | E94h | _                            | F14h | _                            | F94h |                |
| C15h | _                            | C95h | _                            | D15h | _                            | D95h | _                            | E15h |                              | E95h | _                            | F15h | _                            | F95h |                |
| C16h | _                            | C96h | _                            | D16h | _                            | D96h | _                            | E16h | I                            | E96h | _                            | F16h | _                            | F96h |                |
| C17h | _                            | C97h | _                            | D17h | _                            | D97h | _                            | E17h | I                            | E97h | _                            | F17h | _                            | F97h |                |
| C18h | _                            | C98h | _                            | D18h | _                            | D98h | _                            | E18h | _                            | E98h | _                            | F18h | _                            | F98h | See Table 3-11 |
| C19h | _                            | C99h |                              | D19h |                              | D99h | _                            | E19h | _                            | E99h | _                            | F19h | _                            | F99h |                |
| C1Ah | _                            | C9Ah |                              | D1Ah |                              | D9Ah | _                            | E1Ah | _                            | E9Ah | _                            | F1Ah | _                            | F9Ah |                |
| C1Bh | _                            | C9Bh |                              | D1Bh |                              | D9Bh | _                            | E1Bh | _                            | E9Bh | _                            | F1Bh | _                            | F9Bh |                |
| C1Ch | _                            | C9Ch | _                            | D1Ch | _                            | D9Ch | _                            | E1Ch | _                            | E9Ch | _                            | F1Ch | _                            | F9Ch |                |
| C1Dh | _                            | C9Dh | _                            | D1Dh | _                            | D9Dh | _                            | E1Dh | 1                            | E9Dh | _                            | F1Dh | _                            | F9Dh |                |
| C1Eh | _                            | C9Eh | _                            | D1Eh | _                            | D9Eh | _                            | E1Eh | 1                            | E9Eh | _                            | F1Eh | _                            | F9Eh |                |
| C1Fh | _                            | C9Fh | _                            | D1Fh | _                            | D9Fh | _                            | E1Fh | 1                            | E9Fh | _                            | F1Fh | _                            | F9Fh |                |
| C20h |                              | CA0h |                              | D20h |                              | DA0h |                              | E20h |                              | EA0h |                              | F20h |                              | FA0h |                |
|      | Unimplemented<br>Read as '0' |      |                |
| C6Fh |                              | CEFh |                              | D6Fh |                              | DEFh |                              | E6Fh |                              | EEFh |                              | F6Fh |                              | FEFh |                |
| C70h |                              | CF0h |                              | D70h |                              | DF0h |                              | E70h |                              | EF0h |                              | F70h |                              | FF0h |                |
|      | Accesses                     |      | Accesses       |
|      | 70h – 7Fh                    |      | 70h – 7Fh      |
| CFFh |                              | CFFh |                              | D7Fh |                              | DFFh |                              | E7Fh |                              | EFFh |                              | F7Fh |                              | FFFh |                |
| L    | - Hainad                     | L    |                              |      |                              | ,    |                              | 11   |                              | ,    |                              | ,    |                              | L    |                |

**Legend:** = Unimplemented data memory locations, read as '0'.

TABLE 3-9: PIC16(L)F1936 MEMORY MAP, BANK 15

|          |               | Bank 15              |                            |
|----------|---------------|----------------------|----------------------------|
| Γ        | 791h          | LCDCON               |                            |
|          | 792h          | LCDPS                |                            |
|          | 793h          | LCDREF               |                            |
| l        | 794h          | LCDCST               |                            |
| l        | 795h          | LCDRL                |                            |
|          | 796h          | _                    |                            |
|          | 797h          | _                    |                            |
|          | 798h          | LCDSE0               |                            |
|          | 799h          | LCDSE1               |                            |
| l        | 79Ah          | _                    |                            |
|          | 79Bh          | _                    |                            |
|          | 79Ch          | _                    |                            |
|          | 79Dh          | _                    |                            |
|          | 79Eh          | _                    |                            |
|          | 79Fh          | _                    |                            |
|          | 7A0h          | LCDDATA0             |                            |
|          | 7A1h          | LCDDATA1             |                            |
|          | 7A2h          |                      |                            |
|          | 7A3h<br>7A4h  | LCDDATA3<br>LCDDATA4 |                            |
| F        | 7A411<br>7A5h | LCDDATA4             |                            |
| F        | 7A311<br>7A6h | LCDDATA6             |                            |
|          | 7A7h          | LCDDATA7             |                            |
|          | 7A8h          | _                    |                            |
|          | 7A9h          | LCDDATA9             |                            |
| <u> </u> | 7AAh          | LCDDATA10            |                            |
| <u> </u> | 7ABh          | _                    |                            |
|          | 7ACh          | _                    |                            |
| -        | 7ADh          | _                    |                            |
| -        | 7AEh          | _                    |                            |
| <u> </u> | 7AFh          | _                    |                            |
|          | 7B0h          | _                    |                            |
|          | 7B1h          | _                    |                            |
|          | 7B2h          | _                    |                            |
|          | 7B3h          | _                    |                            |
|          | 7B4h          | _                    |                            |
|          | 7B5h          | _                    |                            |
| -        | 7B6h          | _                    |                            |
|          | 7B7h          | _                    |                            |
|          | 7B8h          |                      |                            |
|          |               | Unimplemented        |                            |
|          |               | Read as '0'          |                            |
|          |               |                      |                            |
|          | 7EFh          |                      |                            |
| Lege     |               |                      | ata memory locations, read |
|          | as            | '0'.                 |                            |
|          |               |                      |                            |

TABLE 3-10: PIC16(L)F1934/7 MEMORY MAP, BANK 15

| MAI, BANK 13 |                        |                            |  |  |  |  |  |  |  |  |  |
|--------------|------------------------|----------------------------|--|--|--|--|--|--|--|--|--|
|              | Bank 15                |                            |  |  |  |  |  |  |  |  |  |
| 791h         | LCDCON                 |                            |  |  |  |  |  |  |  |  |  |
| 792h         | LCDPS                  |                            |  |  |  |  |  |  |  |  |  |
| 793h         | LCDREF                 |                            |  |  |  |  |  |  |  |  |  |
| 794h         | LCDCST                 |                            |  |  |  |  |  |  |  |  |  |
| 795h         | LCDRL                  |                            |  |  |  |  |  |  |  |  |  |
| 796h         | _                      |                            |  |  |  |  |  |  |  |  |  |
| 797h         | _                      |                            |  |  |  |  |  |  |  |  |  |
| 798h         | LCDSE0                 |                            |  |  |  |  |  |  |  |  |  |
| 799h         | LCDSE1                 |                            |  |  |  |  |  |  |  |  |  |
| 79Ah         | LCDSE2                 |                            |  |  |  |  |  |  |  |  |  |
| 79Bh         | _                      |                            |  |  |  |  |  |  |  |  |  |
| 79Ch         | _                      |                            |  |  |  |  |  |  |  |  |  |
| 79Dh         | _                      |                            |  |  |  |  |  |  |  |  |  |
| 79Eh         | _                      |                            |  |  |  |  |  |  |  |  |  |
| 79En         | _                      |                            |  |  |  |  |  |  |  |  |  |
| 7A0h         | LCDDATA0               |                            |  |  |  |  |  |  |  |  |  |
| 7A1h         | LCDDATA1               |                            |  |  |  |  |  |  |  |  |  |
| 7A2h         | LCDDATA2               |                            |  |  |  |  |  |  |  |  |  |
| 7A3h         | LCDDATA3               |                            |  |  |  |  |  |  |  |  |  |
| 7A4h<br>7A5h | LCDDATA4<br>LCDDATA5   |                            |  |  |  |  |  |  |  |  |  |
| 7A6h         | LCDDATA6               |                            |  |  |  |  |  |  |  |  |  |
| 7A7h         | LCDDATA7               |                            |  |  |  |  |  |  |  |  |  |
| 7A8h         | LCDDATA8               |                            |  |  |  |  |  |  |  |  |  |
| 7A9h         | LCDDATA9               |                            |  |  |  |  |  |  |  |  |  |
| 7AAh<br>7ABh | LCDDATA10<br>LCDDATA11 |                            |  |  |  |  |  |  |  |  |  |
| 7ACh         | _                      |                            |  |  |  |  |  |  |  |  |  |
| 7ADh         | _                      |                            |  |  |  |  |  |  |  |  |  |
| 7AEh         | _                      |                            |  |  |  |  |  |  |  |  |  |
| 7AFh         | _                      |                            |  |  |  |  |  |  |  |  |  |
|              | _                      |                            |  |  |  |  |  |  |  |  |  |
| 7B0h         | _                      |                            |  |  |  |  |  |  |  |  |  |
| 7B1h         | _                      |                            |  |  |  |  |  |  |  |  |  |
| 7B2h         | _                      |                            |  |  |  |  |  |  |  |  |  |
| 7B3h         | _                      |                            |  |  |  |  |  |  |  |  |  |
| 7B4h         | _                      |                            |  |  |  |  |  |  |  |  |  |
| 7B5h         | _                      |                            |  |  |  |  |  |  |  |  |  |
| 7B6h         | _                      |                            |  |  |  |  |  |  |  |  |  |
| 7B7h         | _                      |                            |  |  |  |  |  |  |  |  |  |
| 7B8h         |                        |                            |  |  |  |  |  |  |  |  |  |
|              | Unimplemented          |                            |  |  |  |  |  |  |  |  |  |
|              | Read as '0'            |                            |  |  |  |  |  |  |  |  |  |
|              |                        |                            |  |  |  |  |  |  |  |  |  |
| 7EFh         |                        |                            |  |  |  |  |  |  |  |  |  |
| Legend:      | = Unimplemented d      | ata memory locations, read |  |  |  |  |  |  |  |  |  |
|              | '0'.                   | ,                          |  |  |  |  |  |  |  |  |  |
|              |                        |                            |  |  |  |  |  |  |  |  |  |
|              |                        |                            |  |  |  |  |  |  |  |  |  |

### TABLE 3-11: PIC16(L)F1934/6/7 MEMORY MAP, BANK 31

|      |      | Bank 31                      |                        |
|------|------|------------------------------|------------------------|
|      | F8Ch |                              |                        |
|      |      | Unimplemented<br>Read as '0' |                        |
|      | FE3h |                              |                        |
|      | FE4h | STATUS_SHAD                  |                        |
|      | FE5h | WREG_SHAD                    |                        |
|      | FE6h | BSR_SHAD                     |                        |
|      | FE7h | PCLATH_SHAD                  |                        |
|      | FE8h | FSR0L_SHAD                   |                        |
|      | FE9h | FSR0H_SHAD                   |                        |
|      | FEAh | FSR1L_SHAD                   |                        |
|      | FEBh | FSR1H_SHAD                   |                        |
|      | FECh | _                            |                        |
|      | FEDh | STKPTR                       |                        |
|      | FEEh | TOSL                         |                        |
|      | FEFh | TOSH                         |                        |
| Lege | end: | = Unimplemented data         | memory locations, read |

as '0'.

### 3.2.6 SPECIAL FUNCTION REGISTERS SUMMARY

The Special Function Register Summary for the device family are as follows:

| Device            | Bank(s) | Page No. |
|-------------------|---------|----------|
|                   | 0       | 39       |
|                   | 1       | 40       |
|                   | 2       | 41       |
|                   | 3       | 42       |
|                   | 4       | 43       |
|                   | 5       | 44       |
| PIC16(L)F1934/6/7 | 6       | 45       |
|                   | 7       | 46       |
|                   | 8       | 47       |
|                   | 9-14    | 48       |
|                   | 15      | 49       |
|                   | 16-30   | 51       |
|                   | 31      | 52       |

TABLE 3-12: SPECIAL FUNCTION REGISTER SUMMARY

| Address                | Name    | Bit 7                      | Bit 6   | Bit 5           | Bit 4           | Bit 3          | Bit 2              | Bit 1              | Bit 0              | Value on POR, BOR | Value on all other |
|------------------------|---------|----------------------------|---|-----------------|-----------------|----------------|--------------------|--------------------|--------------------|-------------------|--------------------|
|                        |         |                            |   |                 |                 |                |                    |                    |                    | TON, BOK          | Resets             |
| Bank 0                 |         |                            |   |                 |                 |                |                    |                    |                    |                   |                    |
| 000h <sup>(2)</sup>    | INDF0   | Addressing (not a physical |   | ses contents o  | of FSR0H/FSF    | ROL to address | data memory        | /                  |                    | xxxx xxxx         | xxxx xxxx          |
| 001h <sup>(2)</sup>    | INDF1   | Addressing (not a physic   |   | ses contents o  | of FSR1H/FSF    | R1L to address | data memory        | /                  |                    | xxxx xxxx         | xxxx xxxx          |
| 002h <sup>(2)</sup>    | PCL     | Program Co                 | unter (PC) Le   | ast Significant | Byte            |                |                    |                    |                    | 0000 0000         | 0000 0000          |
| 003h <sup>(2)</sup>    | STATUS  | _                          | _   | _               | TO              | PD             | Z                  | DC                 | С                  | 1 1000            | q quuu             |
| 004h <sup>(2)</sup>    | FSR0L   | Indirect Data              | a Memory Add  | dress 0 Low Po  | ointer          |                |                    |                    |                    | 0000 0000         | uuuu uuuu          |
| 005h <sup>(2)</sup>    | FSR0H   | Indirect Data              | a Memory Add  |                 | 0000 0000       | 0000 0000      |                    |                    |                    |                   |                    |
| 006h <sup>(2)</sup>    | FSR1L   | Indirect Data              | a Memory Add  | dress 1 Low Po  | ointer          |                |                    |                    |                    | 0000 0000         | uuuu uuuu          |
| 007h <sup>(2)</sup>    | FSR1H   | Indirect Data              | a Memory Add  | dress 1 High P  | ointer          |                |                    |                    |                    | 0000 0000         | 0000 0000          |
| 008h <sup>(2)</sup>    | BSR     | _                          | _   | _               |                 | E              | BSR<4:0>           |                    |                    | 0 0000            | 0 0000             |
| 009h <sup>(2)</sup>    | WREG    | Working Re                 | gister  |                 |                 |                |                    |                    |                    | 0000 0000         | uuuu uuuu          |
| 00Ah <sup>(1, 2)</sup> | PCLATH  | _                          | Write Buffer f  | or the upper 7  | bits of the Pro | ogram Counter  | •                  |                    |                    | -000 0000         | -000 0000          |
| 00Bh <sup>(2)</sup>    | INTCON  | GIE                        | PEIE  | TMR0IE          | INTE            | IOCIE          | TMR0IF             | INTF               | IOCIF              | 0000 0000         | 0000 0000          |
| 00Ch                   | PORTA   | PORTA Data                 | a Latch when  | written: PORT   | A pins when r   | ead            |                    |                    |                    | xxxx xxxx         | uuuu uuuu          |
| 00Dh                   | PORTB   | PORTB Dat                  | a Latch when  | written: PORT   | B pins when r   | ead            |                    |                    |                    | xxxx xxxx         | uuuu uuuu          |
| 00Eh                   | PORTC   | PORTC Dat                  | a Latch when  | written: PORT   | C pins when     | read           |                    |                    |                    | xxxx xxxx         | uuuu uuuu          |
| 00Fh <sup>(3)</sup>    | PORTD   | PORTD Dat                  | a Latch when  | written: PORT   | TD pins when    | read           |                    |                    |                    | xxxx xxxx         | uuuu uuuu          |
| 010h                   | PORTE   | _                          | ı   | _               | _               | RE3            | RE2 <sup>(3)</sup> | RE1 <sup>(3)</sup> | RE0 <sup>(3)</sup> | xxxx              | uuuu               |
| 011h                   | PIR1    | TMR1GIF                    | ADIF  | RCIF            | TXIF            | SSPIF          | CCP1IF             | TMR2IF             | TMR1IF             | 0000 0000         | 0000 0000          |
| 012h                   | PIR2    | OSFIF                      | C2IF  | C1IF            | EEIF            | BCLIF          | LCDIF              | _                  | CCP2IF             | 0000 00-0         | 0000 00-0          |
| 013h                   | PIR3    | _                          | CCP5IF  | CCP4IF          | CCP3IF          | TMR6IF         | _                  | TMR4IF             | _                  | -000 0-0-         | -000 0-0-          |
| 014h                   | _       | Unimplemen                 | nted  |                 |                 |                |                    |                    |                    | _                 | _                  |
| 015h                   | TMR0    | Timer0 Mod                 | ule Register  |                 |                 |                |                    |                    |                    | xxxx xxxx         | uuuu uuuu          |
| 016h                   | TMR1L   | Holding Reg                | gister for the L  | east Significar | nt Byte of the  | 16-bit TMR1 R  | egister            |                    |                    | xxxx xxxx         | uuuu uuuu          |
| 017h                   | TMR1H   | Holding Reg                | gister for the M  | lost Significan | t Byte of the 1 | 6-bit TMR1 Re  | egister            |                    |                    | xxxx xxxx         | uuuu uuuu          |
| 018h                   | T1CON   | TMR10                      | CS<1:0>   | T1CKP           | PS<1:0>         | T10SCEN        | T1SYNC             | _                  | TMR10N             | 0000 00-0         | uuuu uu-u          |
| 019h                   | T1GCON  | TMR1GE                     | TMR1GE T1GPOL T1GTM T1GSPM T1GGO/DONE T1GVAL T1GSS<1:0> |                 |                 |                |                    |                    | 0000 0x00          | uuuu uxuu         |                    |
| 01Ah                   | TMR2    | Timer2 Mod                 | Fimer2 Module Register                                  |                 |                 |                |                    |                    |                    |                   | 0000 0000          |
| 01Bh                   | PR2     | Timer2 Perio               | Timer2 Period Register                                  |                 |                 |                |                    |                    |                    | 1111 1111         | 1111 1111          |
| 01Ch                   | T2CON   | _                          |   |                 |                 |                |                    |                    | PS<1:0>            | -000 0000         | -000 0000          |
| 01Dh                   | _       | Unimplemented              |   |                 |                 |                |                    |                    | _                  | _                 |                    |
| 01Eh                   | CPSCON0 | CPSON                      | _   | _               | _               | CPSRNG1        | CPSRNG0            | CPSOUT             | T0XCS              | 0 0000            | 0 0000             |
| 01Fh                   | CPSCON1 | _                          | _   | _               | _               |                | CPSCH              | <3:0>              | •                  | 0000              | 0000               |

**Legend:** x = unknown, u = unchanged, q = value depends on condition, - = unimplemented, read as '0', r = reserved. Shaded locations are unimplemented, read as '0'.

- 2: These registers can be addressed from any bank.
- 3: These registers/bits are not implemented on PIC16(L)F1936 devices, read as '0'.
- 4: Unimplemented, read as '1'.

TABLE 3-12: SPECIAL FUNCTION REGISTER SUMMARY (CONTINUED)

| Address                | Name           | Bit 7                   | Bit 6                 | Bit 5           | Bit 4           | Bit 3          | Bit 2                 | Bit 1     | Bit 0     | Value on<br>POR, BOR | Value on all<br>other<br>Resets |
|------------------------|----------------|-------------------------|-----------------------|-----------------|-----------------|----------------|-----------------------|-----------|-----------|----------------------|---------------------------------|
| Bank 1                 |                |                         |                       |                 |                 |                |                       |           |           |                      |                                 |
| 080h <sup>(2)</sup>    | INDF0          | Addressing (not a physi |                       | ses contents o  | of FSR0H/FSF    | ROL to address | data memor            | /         |           | xxxx xxxx            | xxxx xxxx                       |
| 081h <sup>(2)</sup>    | INDF1          | Addressing (not a physi |                       | ses contents o  | of FSR1H/FSF    | R1L to address | data memor            | /         |           | xxxx xxxx            | xxxx xxxx                       |
| 082h <sup>(2)</sup>    | PCL            | Program Co              | ounter (PC) Le        | ast Significant | Byte            |                |                       |           |           | 0000 0000            | 0000 0000                       |
| 083h <sup>(2)</sup>    | STATUS         | _                       | - <u> </u>            |                 |                 |                |                       |           |           |                      | q quuu                          |
| 084h <sup>(2)</sup>    | FSR0L          | Indirect Data           | a Memory Ado          | dress 0 Low Po  | ointer          |                |                       |           |           | 0000 0000            | uuuu uuuu                       |
| 085h <sup>(2)</sup>    | FSR0H          | Indirect Data           | a Memory Ado          |                 | 0000 0000       | 0000 0000      |                       |           |           |                      |                                 |
| 086h <sup>(2)</sup>    | FSR1L          | Indirect Data           | a Memory Ado          |                 | 0000 0000       | uuuu uuuu      |                       |           |           |                      |                                 |
| 087h <sup>(2)</sup>    | FSR1H          | Indirect Data           | a Memory Ado          | lress 1 High P  | ointer          |                |                       |           |           | 0000 0000            | 0000 0000                       |
| 088h <sup>(2)</sup>    | BSR            | _                       | _                     | _               |                 |                | BSR<4:0>              |           |           | 0 0000               | 0 0000                          |
| 089h <sup>(2)</sup>    | WREG           | Working Re              | gister                | •               | •               |                |                       |           |           | 0000 0000            | uuuu uuuu                       |
| 08Ah <sup>(1, 2)</sup> | PCLATH         | _                       | Write Buffer f        | or the upper 7  | bits of the Pro | ogram Counte   | r                     |           |           | -000 0000            | -000 0000                       |
| 08Bh <sup>(2)</sup>    | INTCON         | GIE                     | PEIE                  | TMR0IE          | INTE            | IOCIE          | TMR0IF                | INTF      | IOCIF     | 0000 0000            | 0000 0000                       |
| 08Ch                   | TRISA          | PORTA Dat               | a Direction Re        | gister          |                 | •              | •                     |           |           | 1111 1111            | 1111 1111                       |
| 08Dh                   | TRISB          | PORTB Dat               | a Direction Re        | gister          |                 |                |                       |           |           | 1111 1111            | 1111 1111                       |
| 08Eh                   | TRISC          | PORTC Dat               | a Direction Re        | egister         |                 |                |                       |           |           | 1111 1111            | 1111 1111                       |
| 08Fh <sup>(3)</sup>    | TRISD          | PORTD Dat               | a Direction Re        | egister         |                 |                |                       |           |           | 1111 1111            | 1111 1111                       |
| 090h                   | TRISE          | _                       | _                     | _               | _               | _(4)           | TRISE2 <sup>(3)</sup> | TRISE1(3) | TRISE0(3) | 1111                 | 1111                            |
| 091h                   | PIE1           | TMR1GIE                 | ADIE                  | RCIE            | TXIE            | SSPIE          | CCP1IE                | TMR2IE    | TMR1IE    | 0000 0000            | 0000 0000                       |
| 092h                   | PIE2           | OSFIE                   | C2IE                  | C1IE            | EEIE            | BCLIE          | LCDIE                 | _         | CCP2IE    | 0000 00-0            | 0000 00-0                       |
| 093h                   | PIE3           | _                       | CCP5IE                | CCP4IE          | CCP3IE          | TMR6IE         | _                     | TMR4IE    | _         | -000 0-0-            | -000 0-0-                       |
| 094h                   | _              | Unimpleme               | nted                  |                 |                 | •              | 1                     |           | 1         | _                    | _                               |
| 095h                   | OPTION_R<br>EG | WPUEN                   | INTEDG                | TMROCS          | TMROSE          | PSA            |                       | PS<2:0>   |           | 1111 1111            | 1111 1111                       |
| 096h                   | PCON           | STKOVF                  | STKUNF                | _               | _               | RMCLR          | RI                    | POR       | BOR       | 00 11qq              | qq qquu                         |
| 097h                   | WDTCON         | _                       | _                     |                 | V               | VDTPS<4:0>     | •                     |           | SWDTEN    | 01 0110              | 01 0110                         |
| 098h                   | OSCTUNE        | _                       | _                     |                 |                 | TUN<5          | :0>                   |           |           | 00 0000              | 00 0000                         |
| 099h                   | OSCCON         | SPLLEN                  |                       | IRCF            | <3:0>           |                | _                     | SCS       | <1:0>     | 0011 1-00            | 0011 1-00                       |
| 09Ah                   | OSCSTAT        | T10SCR                  | PLLR                  |                 |                 |                |                       | -0p0 0p00 | qqqq qq0- |                      |                                 |
| 09Bh                   | ADRESL         | A/D Result I            | Register Low          |                 |                 |                |                       |           |           | xxxx xxxx            | uuuu uuuu                       |
| 09Ch                   | ADRESH         |                         | Register High         |                 |                 |                |                       |           | xxxx xxxx | uuuu uuuu            |                                 |
| 09Dh                   | ADCON0         | _                       | CHS<4:0> GO/DONE ADON |                 |                 |                |                       |           | ADON      | -000 0000            | -000 0000                       |
| 09Eh                   | ADCON1         | ADFM                    |                       |                 |                 |                |                       |           | ADPREF0   | 0000 -000            | 0000 -000                       |
| 09Fh                   | _              | Unimpleme               | nted                  |                 |                 | 1              |                       | 1         |           | _                    | _                               |

Legend: x = unknown, u = unchanged, q = value depends on condition, - = unimplemented, read as '0', r = reserved. Shaded locations are unimplemented, read as '0'.

- 2: These registers can be addressed from any bank.
- 3: These registers/bits are not implemented on PIC16(L)F1936 devices, read as '0'.
- 4: Unimplemented, read as '1'.

TABLE 3-12: SPECIAL FUNCTION REGISTER SUMMARY (CONTINUED)

| Address                | Name    | Bit 7                      | Bit 6          | Bit 5           | Bit 4           | Bit 3          | Bit 2                | Bit 1                | Bit 0                | Value on<br>POR, BOR | Value on all<br>other<br>Resets |
|------------------------|---------|----------------------------|----------------|-----------------|-----------------|----------------|----------------------|----------------------|----------------------|----------------------|---------------------------------|
| Bank 2                 |         |                            |                |                 |                 |                |                      |                      |                      |                      |                                 |
| 100h <sup>(2)</sup>    | INDF0   | Addressing (not a physical |                | ses contents o  | of FSR0H/FSF    | ROL to address | data memory          | /                    |                      | xxxx xxxx            | xxxx xxxx                       |
| 101h <sup>(2)</sup>    | INDF1   | Addressing (not a physic   |                | ses contents o  | of FSR1H/FSR    | R1L to address | data memory          | /                    |                      | xxxx xxxx            | xxxx xxxx                       |
| 102h <sup>(2)</sup>    | PCL     | Program Co                 | unter (PC) Le  | ast Significant | Byte            |                |                      |                      |                      | 0000 0000            | 0000 0000                       |
| 103h <sup>(2)</sup>    | STATUS  | _                          | _              | _               | TO              | PD             | Z                    | DC                   | С                    | 1 1000               | q quuu                          |
| 104h <sup>(2)</sup>    | FSR0L   | Indirect Data              | a Memory Add   | •               | 0000 0000       | uuuu uuuu      |                      |                      |                      |                      |                                 |
| 105h <sup>(2)</sup>    | FSR0H   | Indirect Data              | a Memory Add   | lress 0 High P  | ointer          |                |                      |                      |                      | 0000 0000            | 0000 0000                       |
| 106h <sup>(2)</sup>    | FSR1L   | Indirect Data              | a Memory Add   | dress 1 Low Po  | ointer          |                |                      |                      |                      | 0000 0000            | uuuu uuuu                       |
| 107h <sup>(2)</sup>    | FSR1H   | Indirect Data              | a Memory Add   | lress 1 High P  | ointer          |                |                      |                      |                      | 0000 0000            | 0000 0000                       |
| 108h <sup>(2)</sup>    | BSR     | _                          | _              | _               |                 | [              | BSR<4:0>             |                      |                      | 0 0000               | 0 0000                          |
| 109h <sup>(2)</sup>    | WREG    | Working Re                 | gister         | •               | •               |                |                      |                      |                      | 0000 0000            | uuuu uuuu                       |
| 10Ah <sup>(1, 2)</sup> | PCLATH  | _                          | Write Buffer f | or the upper 7  | bits of the Pro | ogram Counter  | •                    |                      |                      | -000 0000            | -000 0000                       |
| 10Bh <sup>(2)</sup>    | INTCON  | GIE                        | PEIE           | TMR0IE          | INTE            | IOCIE          | TMR0IF               | INTF                 | IOCIF                | 0000 0000            | 0000 0000                       |
| 10Ch                   | LATA    | PORTA Data                 | a Latch        |                 |                 |                |                      |                      | •                    | xxxx xxxx            | uuuu uuuu                       |
| 10Dh                   | LATB    | PORTB Dat                  | a Latch        |                 |                 |                |                      |                      |                      | xxxx xxxx            | uuuu uuuu                       |
| 10Eh                   | LATC    | PORTC Dat                  | a Latch        |                 |                 |                |                      |                      |                      | xxxx xxxx            | uuuu uuuu                       |
| 10Fh <sup>(3)</sup>    | LATD    | PORTD Dat                  | a Latch        |                 |                 |                |                      |                      |                      | xxxx xxxx            | uuuu uuuu                       |
| 110h                   | LATE    | _                          | _              | _               | _               | _              | LATE2 <sup>(3)</sup> | LATE1 <sup>(3)</sup> | LATE0 <sup>(3)</sup> | xxx                  | uuu                             |
| 111h                   | CM1CON0 | C10N                       | C10UT          | C10E            | C1POL           | _              | C1SP                 | C1HYS                | C1SYNC               | 0000 -100            | 0000 -100                       |
| 112h                   | CM1CON1 | C1INTP                     | C1INTN         | C1PCH1          | C1PCH0          | _              | _                    | C1NCI                | H<1:0>               | 000000               | 000000                          |
| 113h                   | CM2CON0 | C2ON                       | C2OUT          | C2OE            | C2POL           | _              | C2SP                 | C2HYS                | C2SYNC               | 0000 -100            | 0000 -100                       |
| 114h                   | CM2CON1 | C2INTP                     | C2INTN         | C2PCH1          | C2PCH0          | _              | _                    | C2NCI                | H<1:0>               | 000000               | 000000                          |
| 115h                   | CMOUT   | _                          | _              | _               | _               | _              | _                    | MC2OUT               | MC1OUT               | 00                   | 00                              |
| 116h                   | BORCON  | SBOREN                     | _              | _               | _               | _              | _                    | _                    | BORRDY               | 1q                   | uu                              |
| 117h                   | FVRCON  | FVREN                      | FVRRDY         | TSEN            | TSRNG           | CDAFVR1        | CDAFVR0              | ADFVI                | R<1:0>               | 0q00 0000            | 0q00 0000                       |
| 118h                   | DACCON0 | DACEN                      | DACLPS         | DACOE           |                 | DACPS          | S<1:0>               |                      | DACNSS               | 000- 00-0            | 000- 00-0                       |
| 119h                   | DACCON1 |                            |                |                 |                 | D              | ACR<4:0>             |                      | •                    | 0 0000               | 0 0000                          |
| 11Ah                   | SRCON0  | SRLEN                      | SRCLK2         | SRCLK1          | SRCLK0          | SRQEN          | SRNQEN               | SRPS                 | SRPR                 | 0000 0000            | 0000 0000                       |
| 11Bh                   | SRCON1  | SRSPE                      | SRSCKE         | SRSC2E          | SRSC1E          | SRRPE          | SRRCKE               | SRRC2E               | SRRC1E               | 0000 0000            | 0000 0000                       |
| 11Ch                   | _       | Unimplemen                 | nted           |                 |                 |                |                      |                      | •                    | _                    | _                               |
| 11Dh                   | APFCON  | _                          | CCP3SEL        | T1GSEL          | P2BSEL          | SRNQSEL        | C2OUTSEL             | SSSEL                | CCP2SEL              | -000 0000            | -000 0000                       |
| 11Eh                   | _       | Unimplemen                 | Jnimplemented  |                 |                 |                |                      |                      |                      |                      | _                               |
| 11Fh                   | _       | Unimplemen                 | nted           |                 |                 |                |                      |                      |                      | _                    | _                               |

**Legend:** x = unknown, u = unchanged, q = value depends on condition, -= unimplemented, read as '0', r = reserved.

Shaded locations are unimplemented, read as '0'.

- 2: These registers can be addressed from any bank.
- 3: These registers/bits are not implemented on PIC16(L)F1936 devices, read as '0'.
- 4: Unimplemented, read as '1'.

#### **TABLE 3-12:** SPECIAL FUNCTION REGISTER SUMMARY (CONTINUED)

| Address                | Name    | Bit 7                      | Bit 6                                     | Bit 5           | Bit 4           | Bit 3           | Bit 2         | Bit 1  | Bit 0 | Value on<br>POR, BOR | Value on all<br>other<br>Resets |
|------------------------|---------|----------------------------|---|-----------------|-----------------|-----------------|---------------|--------|-------|----------------------|---------------------------------|
| Bank 3                 |         |                            |   |                 |                 |                 |               |        |       |                      |                                 |
| 180h <sup>(2)</sup>    | INDF0   | Addressing<br>(not a physi |   | ses contents    | of FSR0H/FSF    | ROL to address  | data memor    | y      |       | xxxx xxxx            | xxxx xxxx                       |
| 181h <sup>(2)</sup>    | INDF1   | Addressing (not a physi    |   | ses contents    | of FSR1H/FSF    | 21L to address  | data memor    | у      |       | xxxx xxxx            | xxxx xxxx                       |
| 182h <sup>(2)</sup>    | PCL     | Program Co                 | ounter (PC) Le                            | ast Significan  | t Byte          |                 |               |        |       | 0000 0000            | 0000 0000                       |
| 183h <sup>(2)</sup>    | STATUS  | _                          |   |                 |                 |                 |               |        |       |                      | q quuu                          |
| 184h <sup>(2)</sup>    | FSR0L   | Indirect Data              | ndirect Data Memory Address 0 Low Pointer |                 |                 |                 |               |        |       |                      | uuuu uuuu                       |
| 185h <sup>(2)</sup>    | FSR0H   | Indirect Data              | a Memory Add                              | dress 0 High F  | ointer          |                 |               |        |       | 0000 0000            | 0000 0000                       |
| 186h <sup>(2)</sup>    | FSR1L   | Indirect Data              | a Memory Ado                              | dress 1 Low P   | ointer          |                 |               |        |       | 0000 0000            | uuuu uuuu                       |
| 187h <sup>(2)</sup>    | FSR1H   | Indirect Data              | a Memory Add                              | dress 1 High F  | ointer          |                 |               |        |       | 0000 0000            | 0000 0000                       |
| 188h <sup>(2)</sup>    | BSR     | _                          | _   | _               |                 | E               | BSR<4:0>      |        |       | 0 0000               | 0 0000                          |
| 189h <sup>(2)</sup>    | WREG    | Working Re                 | gister                                    |                 |                 |                 |               |        |       | 0000 0000            | uuuu uuuu                       |
| 18Ah <sup>(1, 2)</sup> | PCLATH  | _                          | Write Buffer f                            | for the upper 7 | bits of the Pro | ogram Counter   | •             |        |       | -000 0000            | -000 0000                       |
| 18Bh <sup>(2)</sup>    | INTCON  | GIE                        | PEIE                                      | TMR0IE          | INTE            | IOCIE           | TMR0IF        | INTF   | IOCIF | 0000 0000            | 0000 0000                       |
| 18Ch                   | ANSELA  | _                          | _   | ANSA5           | ANSA4           | ANSA3           | ANSA2         | ANSA1  | ANSA0 | 11 1111              | 11 1111                         |
| 18Dh                   | ANSELB  | _                          | _   | ANSB5           | ANSB4           | ANSB3           | ANSB2         | ANSB1  | ANSB0 | 11 1111              | 11 1111                         |
| 18Eh                   | _       | Unimpleme                  | nted                                      | •               | •               |                 |               | •      | •     | _                    | _                               |
| 18Fh <sup>(3)</sup>    | ANSELD  | ANSD7                      | ANSD6                                     | ANSD5           | ANSD4           | ANSD3           | ANSD2         | ANSD1  | ANSD0 | 1111 1111            | 1111 1111                       |
| 190h <sup>(3)</sup>    | ANSELE  | _                          | _   | _               | _               | _               | ANSE2         | ANSE1  | ANSE0 | 111                  | 111                             |
| 191h                   | EEADRL  | EEPROM /                   | Program Mem                               | nory Address F  | Register Low E  | Byte            |               |        |       | 0000 0000            | 0000 0000                       |
| 192h                   | EEADRH  | _                          | EEPROM / P                                | rogram Memo     | ory Address Re  | egister High By | rte           |        |       | -000 0000            | -000 0000                       |
| 193h                   | EEDATL  | EEPROM /                   | Program Mem                               | ory Read Dat    | a Register Lov  | v Byte          |               |        |       | xxxx xxxx            | uuuu uuuu                       |
| 194h                   | EEDATH  | _                          | _   | EEPROM / P      | rogram Memo     | ry Read Data    | Register High | n Byte |       | xx xxxx              | uu uuuu                         |
| 195h                   | EECON1  | EEPGD                      | CFGS                                      | LWLO            | FREE            | WRERR           | WREN          | WR     | RD    | 0000 x000            | 0000 q000                       |
| 196h                   | EECON2  | EEPROM c                   | ontrol register                           | 2               |                 |                 |               |        |       | 0000 0000            | 0000 0000                       |
| 197h                   | _       | Unimpleme                  | nted                                      |                 |                 |                 |               |        |       | _                    | _                               |
| 198h                   | _       | Unimpleme                  | nted                                      |                 |                 |                 |               |        |       | _                    | _                               |
| 199h                   | RCREG   | USART Red                  | ceive Data Re                             | gister          |                 |                 |               |        |       | 0000 0000            | 0000 0000                       |
| 19Ah                   | TXREG   | USART Tra                  | nsmit Data Re                             | gister          |                 |                 |               |        |       | 0000 0000            | 0000 0000                       |
| 19Bh                   | SPBRGL  |                            | BRG<7:0>                                  |                 |                 |                 |               |        |       | 0000 0000            | 0000 0000                       |
| 19Ch                   | SPBRGH  |                            |   |                 | BRG<1           | 5:8>            |               |        |       | 0000 0000            | 0000 0000                       |
| 19Dh                   | RCSTA   | SPEN                       | RX9                                       | SREN            | CREN            | ADDEN           | FERR          | OERR   | RX9D  | 0000 000x            | 0000 000x                       |
| 19Eh                   | TXSTA   | CSRC                       | TX9                                       | TXEN            | SYNC            | SENDB           | BRGH          | TRMT   | TX9D  | 0000 0010            | 0000 0010                       |
| 19Fh                   | BAUDCON | ABDOVF                     | RCIDL                                     | _               | SCKP            | BRG16           | _             | WUE    | ABDEN | 01-0 0-00            | 01-0 0-00                       |

 ${\bf x}$  = unknown,  ${\bf u}$  = unchanged,  ${\bf q}$  = value depends on condition, - = unimplemented, read as '0',  ${\bf r}$  = reserved. Shaded locations are unimplemented, read as '0'. Legend:

Note The upper byte of the program counter is not directly accessible. PCLATH is a holding register for the PC<14:8>, whose contents are transferred to the upper byte of the program counter.

These registers can be addressed from any bank. 2:

These registers/bits are not implemented on PIC16(L)F1936 devices, read as '0'. 3:

Unimplemented, read as '1'.

TABLE 3-12: SPECIAL FUNCTION REGISTER SUMMARY (CONTINUED)

| Address                | Name    | Bit 7        | Bit 6                                    | Bit 5           | Bit 4           | Bit 3          | Bit 2      | Bit 1 | Bit 0 | Value on<br>POR, BOR | Value on all<br>other<br>Resets |
|------------------------|---------|--------------|--|-----------------|-----------------|----------------|------------|-------|-------|----------------------|---------------------------------|
| Bank 4                 |         |              |  |                 |                 |                |            |       |       |                      |                                 |
| 200h <sup>(2)</sup>    | INDF0   |              | this location u                          | ses contents o  | of FSR0H/FSR    | ROL to address | data memor | у     |       | xxxx xxxx            | xxxx xxxx                       |
| 201h <sup>(2)</sup>    | INDF1   |              | this location u                          | ses contents o  | of FSR1H/FSR    | R1L to address | data memor | у     |       | xxxx xxxx            | xxxx xxxx                       |
| 202h <sup>(2)</sup>    | PCL     | Program Co   | ounter (PC) Le                           | ast Significant | t Byte          |                |            |       |       | 0000 0000            | 0000 0000                       |
| 203h <sup>(2)</sup>    | STATUS  | _            | _  | С               | 1 1000          | q quuu         |            |       |       |                      |                                 |
| 204h <sup>(2)</sup>    | FSR0L   | Indirect Dat | lirect Data Memory Address 0 Low Pointer |                 |                 |                |            |       |       |                      | uuuu uuuu                       |
| 205h <sup>(2)</sup>    | FSR0H   | Indirect Dat | irect Data Memory Address 0 High Pointer |                 |                 |                |            |       |       |                      | 0000 0000                       |
| 206h <sup>(2)</sup>    | FSR1L   | Indirect Dat | a Memory Add                             | dress 1 Low Po  | ointer          |                |            |       |       | 0000 0000            | uuuu uuuu                       |
| 207h <sup>(2)</sup>    | FSR1H   | Indirect Dat | a Memory Add                             | dress 1 High P  | ointer          |                |            |       |       | 0000 0000            | 0000 0000                       |
| 208h <sup>(2)</sup>    | BSR     | _            | _  | _               |                 | E              | BSR<4:0>   |       |       | 0 0000               | 0 0000                          |
| 209h <sup>(2)</sup>    | WREG    | Working Re   | gister                                   |                 |                 |                |            |       |       | 0000 0000            | uuuu uuuu                       |
| 20Ah <sup>(1, 2)</sup> | PCLATH  | _            | Write Buffer t                           | for the upper 7 | bits of the Pro | ogram Counter  | -          |       |       | -000 0000            | -000 0000                       |
| 20Bh <sup>(2)</sup>    | INTCON  | GIE          | PEIE                                     | TMR0IE          | INTE            | IOCIE          | TMR0IF     | INTF  | IOCIF | 0000 0000            | 0000 0000                       |
| 20Ch                   | _       | Unimpleme    | nted                                     |                 |                 |                | •          |       |       | _                    | _                               |
| 20Dh                   | WPUB    | WPUB7        | WPUB6                                    | WPUB5           | WPUB4           | WPUB3          | WPUB2      | WPUB1 | WPUB0 | 1111 1111            | 1111 1111                       |
| 20Eh                   | _       | Unimpleme    | nted                                     |                 |                 |                |            |       |       | _                    | _                               |
| 20Fh                   | _       | Unimpleme    | nted                                     |                 |                 |                |            |       |       | _                    | _                               |
| 210h                   | WPUE    | _            | _  | _               | _               | WPUE3          | _          | _     | _     | 1                    | 1                               |
| 211h                   | SSPBUF  | Synchronou   | us Serial Port I                         | Receive Buffer  | r/Transmit Reg  | jister         |            |       |       | xxxx xxxx            | uuuu uuuu                       |
| 212h                   | SSPADD  |              |  |                 | ADD<            | 7:0>           |            |       |       | 0000 0000            | 0000 0000                       |
| 213h                   | SSPMSK  |              |  |                 | MSK<            | 7:0>           |            |       |       | 1111 1111            | 1111 1111                       |
| 214h                   | SSPSTAT | SMP          | CKE                                      | D/Ā             | Р               | S              | R/W        | UA    | BF    | 0000 0000            | 0000 0000                       |
| 215h                   | SSPCON1 | WCOL         | SSPOV                                    | SSPEN           | CKP             |                | SSPM<      | 3:0>  | 1     | 0000 0000            | 0000 0000                       |
| 216h                   | SSPCON2 | GCEN         | ACKSTAT                                  | ACKDT           | ACKEN           | RCEN           | PEN        | RSEN  | SEN   | 0000 0000            | 0000 0000                       |
| 217h                   | SSPCON3 | ACKTIM       | PCIE                                     | SCIE            | BOEN            | SDAHT          | SBCDE      | AHEN  | DHEN  | 0000 0000            | 0000 0000                       |
| 218h                   | _       | Unimpleme    | nted                                     |                 |                 | 1              | l          |       |       | _                    | _                               |
| 219h                   | _       | Unimpleme    | nted                                     |                 |                 |                |            |       |       | _                    | _                               |
| 21Ah                   | _       | Unimpleme    | nted                                     |                 |                 |                |            |       |       | _                    | _                               |
| 21Bh                   | _       | Unimpleme    | implemented                              |                 |                 |                |            |       |       |                      | _                               |
| 21Ch                   | _       | Unimpleme    | implemented                              |                 |                 |                |            |       |       |                      | _                               |
| 21Dh                   | _       | Unimpleme    | nted                                     |                 |                 |                |            |       |       | _                    | _                               |
| 21Eh                   | _       | Unimpleme    | implemented                              |                 |                 |                |            |       |       |                      | _                               |
| 21Fh                   | _       | Unimpleme    | nted                                     |                 |                 |                |            |       |       | _                    | _                               |
|                        |         |              |  |                 |                 |                |            |       |       |                      |                                 |

**Legend:** x = unknown, u = unchanged, q = value depends on condition, - = unimplemented, read as '0', <math>x = reserved. Shaded locations are unimplemented, read as '0'.

- **2:** These registers can be addressed from any bank.
- 3: These registers/bits are not implemented on PIC16(L)F1936 devices, read as '0'.
- 4: Unimplemented, read as '1'.

### TABLE 3-12: SPECIAL FUNCTION REGISTER SUMMARY (CONTINUED)

| Address                | Name         | Bit 7                    | Bit 6                      | Bit 5           | Bit 4           | Bit 3         | Bit 2       | Bit 1   | Bit 0     | Value on<br>POR, BOR | Value on all<br>other<br>Resets |
|------------------------|--------------|--------------------------|----------------------------|-----------------|-----------------|---------------|-------------|---------|-----------|----------------------|---------------------------------|
| Bank 5                 |              |                          |                            |                 |                 |               |             |         |           |                      |                                 |
| 280h <sup>(2)</sup>    | INDF0        | Addressing (not a physic |                            | ses contents o  | of FSR0H/FSR    | OL to address | data memory | /       |           | xxxx xxxx            | xxxx xxxx                       |
| 281h <sup>(2)</sup>    | INDF1        | Addressing (not a physic |                            | ses contents o  | of FSR1H/FSR    | 1L to address | data memory | /       |           | xxxx xxxx            | xxxx xxxx                       |
| 282h <sup>(2)</sup>    | PCL          | Program Co               | ounter (PC) Le             | ast Significant | Byte            |               |             |         |           | 0000 0000            | 0000 0000                       |
| 283h <sup>(2)</sup>    | STATUS       | _                        | <u>TO</u> <u>PD</u> z DC C |                 |                 |               |             |         |           |                      |                                 |
| 284h <sup>(2)</sup>    | FSR0L        | Indirect Data            | a Memory Add               | lress 0 Low Po  | ointer          | •             | •           | •       |           | 0000 0000            | uuuu uuuu                       |
| 285h <sup>(2)</sup>    | FSR0H        | Indirect Data            | a Memory Add               | lress 0 High P  | ointer          |               |             |         |           | 0000 0000            | 0000 0000                       |
| 286h <sup>(2)</sup>    | FSR1L        | Indirect Data            | a Memory Add               | 0000 0000       | uuuu uuuu       |               |             |         |           |                      |                                 |
| 287h <sup>(2)</sup>    | FSR1H        | Indirect Data            | a Memory Add               | Iress 1 High P  | ointer          |               |             |         |           | 0000 0000            | 0000 0000                       |
| 288h <sup>(2)</sup>    | BSR          | _                        | _                          | _               |                 | [             | BSR<4:0>    |         |           | 0 0000               | 0 0000                          |
| 289h <sup>(2)</sup>    | WREG         | Working Re               | gister                     |                 | I               |               |             |         |           | 0000 0000            | uuuu uuuu                       |
| 28Ah <sup>(1, 2)</sup> | PCLATH       | _                        | Write Buffer f             | or the upper 7  | bits of the Pro | ogram Counter | •           |         |           | -000 0000            | -000 0000                       |
| 28Bh <sup>(2)</sup>    | INTCON       | GIE                      | PEIE                       | TMR0IE          | INTE            | IOCIE         | TMR0IF      | INTF    | IOCIF     | 0000 0000            | 0000 0000                       |
| 28Ch                   | _            | Unimplemen               | nted                       |                 |                 | Į.            | ·           | I.      |           | _                    | _                               |
| 28Dh                   | _            | Unimplemen               | nted                       |                 |                 |               |             |         |           | _                    | _                               |
| 28Eh                   | _            | Unimplemen               | nted                       |                 |                 |               |             |         |           | _                    | _                               |
| 28Fh                   | _            | Unimplemen               | nted                       |                 |                 |               |             |         |           | _                    | _                               |
| 290h                   | _            | Unimplemen               | nted                       |                 |                 |               |             |         |           | _                    | _                               |
| 291h                   | CCPR1L       | Capture/Co               | mpare/PWM R                | Register 1 (LSI | 3)              |               |             |         |           | xxxx xxxx            | uuuu uuuu                       |
| 292h                   | CCPR1H       | Capture/Cor              | mpare/PWM R                | Register 1 (MS  | B)              |               |             |         |           | xxxx xxxx            | uuuu uuuu                       |
| 293h                   | CCP1CON      | P1M                      | l<1:0>                     | DC1E            | I<1:0>          |               | CCP1M       | <3:0>   |           | 0000 0000            | 0000 0000                       |
| 294h                   | PWM1CON      | P1RSEN                   |                            |                 | Р               | 1DC<6:0>      |             |         |           | 0000 0000            | 0000 0000                       |
| 295h                   | CCP1AS       | CCP1ASE                  |                            | CCP1AS<2:0      | >               | PSS1A         | C<1:0>      | PSS1B   | D<1:0>    | 0000 0000            | 0000 0000                       |
| 296h                   | PSTR1CON     | _                        | _                          | _               | STR1SYNC        | STR1D         | STR1C       | STR1B   | STR1A     | 0 0001               | 0 0001                          |
| 297h                   | _            | Unimplemen               | nted                       |                 |                 | l             | l           | l       | 1         | _                    | _                               |
| 298h                   | CCPR2L       | Capture/Co               | mpare/PWM R                | Register 2 (LSI | 3)              |               |             |         |           | xxxx xxxx            | uuuu uuuu                       |
| 299h                   | CCPR2H       | Capture/Cor              | mpare/PWM R                | Register 2 (MS  | B)              |               |             |         |           | xxxx xxxx            | uuuu uuuu                       |
| 29Ah                   | CCP2CON      | P2M                      | l<1:0>                     | DC2E            | I<1:0>          |               | CCP2M       | <3:0>   |           | 0000 0000            | 0000 0000                       |
| 29Bh                   | PWM2CON      | P2RSEN                   | P2RSEN P2DC<6:0>           |                 |                 |               |             |         | 0000 0000 | 0000 0000            |                                 |
| 29Ch                   | CCP2AS       | CCP2ASE                  |                            | CCP2AS<2:0>     |                 |               |             |         | 0000 0000 | 0000 0000            |                                 |
| 29Dh                   | PSTR2CON     | _                        | _                          | _               | STR2SYNC        | STR2D         | STR2C       | STR2B   | STR2A     | 0 0001               | 0 0001                          |
| 29Eh                   | CCPTMRS<br>0 | C4TSEL1                  | C4TSEL0                    | C3TSEL1         | C3TSEL0         | C2TSEL1       | C2TSEL0     | C1TSEL1 | C1TSEL0   | 0000 0000            | 0000 0000                       |
| 29Fh                   | CCPTMRS<br>1 | _                        | _                          | _               | _               | _             | _           | C5TSE   | L<1:0>    | 00                   | 00                              |

**Legend:** x = unknown, u = unchanged, q = value depends on condition, -= unimplemented, read as '0', x = reserved. Shaded locations are unimplemented, read as '0'.

- 2: These registers can be addressed from any bank.
- 3: These registers/bits are not implemented on PIC16(L)F1936 devices, read as '0'.
- 4: Unimplemented, read as '1'.

TABLE 3-12: SPECIAL FUNCTION REGISTER SUMMARY (CONTINUED)

| Address                | Name     | Bit 7                    | Bit 6                                | Bit 5           | Bit 4           | Bit 3         | Bit 2      | Bit 1 | Bit 0  | Value on<br>POR, BOR | Value on all<br>other<br>Resets |
|------------------------|----------|--------------------------|--------------------------------------|-----------------|-----------------|---------------|------------|-------|--------|----------------------|---------------------------------|
| Bank 6                 |          |                          |                                      |                 |                 |               |            |       |        |                      |                                 |
| 300h <sup>(2)</sup>    | INDF0    | Addressing (not a physic |                                      | ses contents o  | of FSR0H/FSR    | OL to address | data memor | /     |        | xxxx xxxx            | xxxx xxxx                       |
| 301h <sup>(2)</sup>    | INDF1    | Addressing (not a physic |                                      | ses contents o  | of FSR1H/FSR    | 1L to address | data memor | /     |        | xxxx xxxx            | xxxx xxxx                       |
| 302h <sup>(2)</sup>    | PCL      | Program Co               | unter (PC) Le                        | ast Significant | Byte            |               |            |       |        | 0000 0000            | 0000 0000                       |
| 303h <sup>(2)</sup>    | STATUS   | _                        | _                                    | _               | TO              | PD            | Z          | DC    | С      | 1 1000               | q quuu                          |
| 304h <sup>(2)</sup>    | FSR0L    | Indirect Data            | a Memory Add                         | dress 0 Low Po  | ointer          |               |            |       |        | 0000 0000            | uuuu uuuu                       |
| 305h <sup>(2)</sup>    | FSR0H    | Indirect Data            | a Memory Add                         |                 | 0000 0000       | 0000 0000     |            |       |        |                      |                                 |
| 306h <sup>(2)</sup>    | FSR1L    | Indirect Data            | a Memory Add                         |                 | 0000 0000       | uuuu uuuu     |            |       |        |                      |                                 |
| 307h <sup>(2)</sup>    | FSR1H    | Indirect Data            | a Memory Add                         | dress 1 High P  | ointer          |               |            |       |        | 0000 0000            | 0000 0000                       |
| 308h <sup>(2)</sup>    | BSR      | _                        | _                                    | _               |                 | E             | BSR<4:0>   |       |        | 0 0000               | 0 0000                          |
| 309h <sup>(2)</sup>    | WREG     | Working Re               | gister                               |                 |                 |               |            |       |        | 0000 0000            | uuuu uuuu                       |
| 30Ah <sup>(1, 2)</sup> | PCLATH   | _                        | Write Buffer 1                       | for the upper 7 | bits of the Pro | ogram Counter | •          |       |        | -000 0000            | -000 0000                       |
| 30Bh <sup>(2)</sup>    | INTCON   | GIE                      | PEIE                                 | TMR0IE          | INTE            | IOCIE         | TMR0IF     | INTF  | IOCIF  | 0000 0000            | 0000 0000                       |
| 30Ch                   | _        | Unimplemen               | nted                                 |                 |                 |               |            |       |        | _                    | _                               |
| 30Dh                   | _        | Unimplemen               | nted                                 |                 |                 |               |            |       |        | _                    | _                               |
| 30Eh                   | _        | Unimplemen               | nted                                 |                 |                 |               |            |       |        | _                    | _                               |
| 30Fh                   | _        | Unimplemen               | nted                                 |                 |                 |               |            |       |        | _                    | _                               |
| 310h                   | _        | Unimplemen               | nted                                 |                 |                 |               |            |       |        | _                    | _                               |
| 311h                   | CCPR3L   | Capture/Cor              | mpare/PWM F                          | Register 3 (LSI | 3)              |               |            |       |        | xxxx xxxx            | uuuu uuuu                       |
| 312h                   | CCPR3H   | Capture/Cor              | mpare/PWM F                          | Register 3 (MS  | B)              |               |            |       |        | xxxx xxxx            | uuuu uuuu                       |
| 313h                   | CCP3CON  | P3M                      | <1:0>                                | DC3E            | S<1:0>          |               | CCP3M      | <1:0> |        | 0000 0000            | 0000 0000                       |
| 314h                   | PWM3CON  | P3RSEN                   |                                      |                 | P               | 23DC<6:0>     |            |       |        | 0000 0000            | 0000 0000                       |
| 315h                   | CCP3AS   | CCP3ASE                  |                                      | CCP3AS<2:0>     | >               | PSS3A         | C<1:0>     | PSS3B | D<1:0> | 0000 0000            | 0000 0000                       |
| 316h                   | PSTR3CON | _                        | _                                    | _               | STR3SYNC        | STR3D         | STR3C      | STR3B | STR3A  | 0 0001               | 0 0001                          |
| 317h                   | _        | Unimplemen               | nted                                 |                 |                 |               |            |       |        | _                    | _                               |
| 318h                   | CCPR4L   | Capture/Cor              | mpare/PWM F                          | Register 4 (LSF | 3)              |               |            |       |        | xxxx xxxx            | uuuu uuuu                       |
| 319h                   | CCPR4H   | Capture/Cor              | mpare/PWM F                          | Register 4 (MS  | B)              |               |            |       |        | xxxx xxxx            | uuuu uuuu                       |
| 31Ah                   | CCP4CON  | _                        | - DC4B<1:0> CCP4M<3:0>               |                 |                 |               |            |       |        |                      | 00 0000                         |
| 31Bh                   | _        | Unimplemen               | nted                                 |                 | _               | _             |            |       |        |                      |                                 |
| 31Ch                   | CCPR5L   | Capture/Cor              | mpare/PWM F                          |                 | xxxx xxxx       | uuuu uuuu     |            |       |        |                      |                                 |
| 31Dh                   | CCPR5H   | Capture/Cor              | Capture/Compare/PWM Register 5 (MSB) |                 |                 |               |            |       |        |                      |                                 |
| 31Eh                   | CCP5CON  | _                        | _                                    |                 | 00 0000         | 00 0000       |            |       |        |                      |                                 |
| 31Fh                   | _        | Unimplemen               | nted                                 |                 |                 |               |            |       |        | _                    | _                               |

**Legend:** x = unknown, u = unchanged, q = value depends on condition, -= unimplemented, read as '0', x = reserved. Shaded locations are unimplemented, read as '0'.

- 2: These registers can be addressed from any bank.
- 3: These registers/bits are not implemented on PIC16(L)F1936 devices, read as '0'.
- 4: Unimplemented, read as '1'.

#### **TABLE 3-12:** SPECIAL FUNCTION REGISTER SUMMARY (CONTINUED)

| Address                | Name   | Bit 7                    | Bit 6           | Bit 5           | Bit 4           | Bit 3          | Bit 2       | Bit 1  | Bit 0  | Value on<br>POR, BOR | Value on all<br>other<br>Resets |
|------------------------|--------|--------------------------|-----------------|-----------------|-----------------|----------------|-------------|--------|--------|----------------------|---------------------------------|
| Bank 7                 |        |                          |                 |                 |                 |                |             |        |        |                      |                                 |
| 380h <sup>(2)</sup>    | INDF0  | Addressing (not a physic |                 | ses contents o  | of FSR0H/FSF    | ROL to address | data memory | /      |        | xxxx xxxx            | xxxx xxxx                       |
| 381h <sup>(2)</sup>    | INDF1  | Addressing (not a physic | this location u | ses contents o  | of FSR1H/FSR    | R1L to address | data memory | /      |        | xxxx xxxx            | xxxx xxxx                       |
| 382h <sup>(2)</sup>    | PCL    | Program Co               | ounter (PC) Le  | ast Significant | Byte            |                |             |        |        | 0000 0000            | 0000 0000                       |
| 383h <sup>(2)</sup>    | STATUS | _                        | _               | С               | 1 1000          | q quuu         |             |        |        |                      |                                 |
| 384h <sup>(2)</sup>    | FSR0L  | Indirect Data            | a Memory Add    |                 | 0000 0000       | uuuu uuuu      |             |        |        |                      |                                 |
| 385h <sup>(2)</sup>    | FSR0H  | Indirect Data            | a Memory Add    | dress 0 High P  | ointer          |                |             |        |        | 0000 0000            | 0000 0000                       |
| 386h <sup>(2)</sup>    | FSR1L  | Indirect Data            | a Memory Add    | dress 1 Low Po  | ointer          |                |             |        |        | 0000 0000            | uuuu uuuu                       |
| 387h <sup>(2)</sup>    | FSR1H  | Indirect Data            | a Memory Add    | dress 1 High P  | ointer          |                |             |        |        | 0000 0000            | 0000 0000                       |
| 388h <sup>(2)</sup>    | BSR    | _                        | _               | _               |                 |                | BSR<4:0>    |        |        | 0 0000               | 0 0000                          |
| 389h <sup>(2)</sup>    | WREG   | Working Re               | gister          |                 |                 |                |             |        |        | 0000 0000            | uuuu uuuu                       |
| 38Ah <sup>(1, 2)</sup> | PCLATH | _                        | Write Buffer f  | or the upper 7  | bits of the Pro | ogram Counter  | r           |        |        | -000 0000            | -000 0000                       |
| 38Bh <sup>(2)</sup>    | INTCON | GIE                      | PEIE            | TMR0IE          | INTE            | IOCIE          | TMR0IF      | INTF   | IOCIF  | 0000 0000            | 0000 0000                       |
| 38Ch                   | _      | Unimplemen               | nted            | •               | •               |                |             |        |        | _                    | _                               |
| 38Dh                   | _      | Unimplemen               | nted            |                 |                 |                |             |        |        | _                    | _                               |
| 38Eh                   | _      | Unimplemen               | nted            |                 |                 |                |             |        |        | _                    | _                               |
| 38Fh                   | _      | Unimplemen               | nted            |                 |                 |                |             |        |        | _                    | _                               |
| 390h                   | _      | Unimplemen               | nted            |                 |                 |                |             |        |        | _                    | _                               |
| 391h                   | _      | Unimplemen               | nted            |                 |                 |                |             |        |        | _                    | _                               |
| 392h                   | _      | Unimplemen               | nted            |                 |                 |                |             |        |        | _                    | _                               |
| 393h                   | _      | Unimplemen               | nted            |                 |                 |                |             |        |        | _                    | _                               |
| 394h                   | IOCBP  | IOCBP7                   | IOCBP6          | IOCBP5          | IOCBP4          | IOCBP3         | IOCBP2      | IOCBP1 | IOCBP0 | 0000 0000            | 0000 0000                       |
| 395h                   | IOCBN  | IOCBN7                   | IOCBN6          | IOCBN5          | IOCBN4          | IOCBN3         | IOCBN2      | IOCBN1 | IOCBN0 | 0000 0000            | 0000 0000                       |
| 396h                   | IOCBF  | IOCBF7                   | IOCBF6          | IOCBF5          | IOCBF4          | IOCBF3         | IOCBF2      | IOCBF1 | IOCBF0 | 0000 0000            | 0000 0000                       |
| 397h                   | _      | Unimplemen               | nted            | •               | •               |                |             |        |        | _                    | _                               |
| 398h                   | _      | Unimplemen               | nted            |                 |                 |                |             |        |        | _                    | _                               |
| 399h                   | _      | Unimplemen               | nted            |                 |                 |                |             |        |        | _                    | _                               |
| 39Ah                   | _      | Unimplemen               | Inimplemented   |                 |                 |                |             |        |        | _                    | _                               |
| 39Bh                   | _      | Unimplemen               | nimplemented    |                 |                 |                |             |        |        |                      | _                               |
| 39Ch                   | _      | Unimplemen               | Inimplemented — |                 |                 |                |             |        |        |                      | _                               |
| 39Dh                   | _      | Unimplemen               | nted            |                 |                 |                |             |        |        | _                    | _                               |
| 39Eh                   | _      | Unimplemen               | implemented —   |                 |                 |                |             |        |        |                      |                                 |
| 39Fh                   | _      | Unimplemen               | nted            |                 |                 |                |             |        |        | _                    | _                               |

 ${\bf x}$  = unknown,  ${\bf u}$  = unchanged,  ${\bf q}$  = value depends on condition, - = unimplemented, read as '0',  ${\bf r}$  = reserved. Shaded locations are unimplemented, read as '0'. Legend:

Note 1: The upper byte of the program counter is not directly accessible. PCLATH is a holding register for the PC<14:8>, whose contents are transferred to the upper byte of the program counter.

These registers can be addressed from any bank. 2:

These registers/bits are not implemented on PIC16(L)F1936 devices, read as '0'. 3:

Unimplemented, read as '1'.

TABLE 3-12: SPECIAL FUNCTION REGISTER SUMMARY (CONTINUED)

|                        | <u> </u> | 1                        |  | 1               | 1            |                | 1           | _ <i>_,</i> |         |                      |                                 |
|------------------------|----------|--------------------------|--|-----------------|--------------|----------------|-------------|-------------|---------|----------------------|---------------------------------|
| Address                | Name     | Bit 7                    | Bit 6  | Bit 5           | Bit 4        | Bit 3          | Bit 2       | Bit 1       | Bit 0   | Value on<br>POR, BOR | Value on all<br>other<br>Resets |
| Bank 8                 |          |                          |  |                 |              |                |             |             |         |                      |                                 |
| 400h <sup>(2)</sup>    | INDF0    | Addressing (not a physic |  | ses contents o  | of FSR0H/FSF | ROL to address | data memory | /           |         | xxxx xxxx            | xxxx xxxx                       |
| 401h <sup>(2)</sup>    | INDF1    | Addressing (not a physic |  | ses contents o  | of FSR1H/FSF | R1L to address | data memory | /           |         | xxxx xxxx            | xxxx xxxx                       |
| 402h <sup>(2)</sup>    | PCL      | Program Co               | unter (PC) Le  | ast Significant | Byte         |                |             |             |         | 0000 0000            | 0000 0000                       |
| 403h <sup>(2)</sup>    | STATUS   | _                        | _  | С               | 1 1000       | q quuu         |             |             |         |                      |                                 |
| 404h <sup>(2)</sup>    | FSR0L    | Indirect Data            | a Memory Add   | dress 0 Low Po  | ointer       | •              | •           |             |         | 0000 0000            | uuuu uuuu                       |
| 405h <sup>(2)</sup>    | FSR0H    | Indirect Data            | a Memory Add   | dress 0 High P  | ointer       |                |             |             |         | 0000 0000            | 0000 0000                       |
| 406h <sup>(2)</sup>    | FSR1L    | Indirect Data            |  | 0000 0000       | uuuu uuuu    |                |             |             |         |                      |                                 |
| 407h <sup>(2)</sup>    | FSR1H    | Indirect Data            | direct Data Memory Address 1 High Pointer                |                 |              |                |             |             |         |                      | 0000 0000                       |
| 408h <sup>(2)</sup>    | BSR      | _                        | _  | _               |              | E              | BSR<4:0>    |             |         | 0 0000               | 0 0000                          |
| 409h <sup>(2)</sup>    | WREG     | Working Re               | orking Register  |                 |              |                |             |             |         |                      | uuuu uuuu                       |
| 40Ah <sup>(1, 2)</sup> | PCLATH   | _                        | Write Buffer for the upper 7 bits of the Program Counter |                 |              |                |             |             |         |                      | -000 0000                       |
| 40Bh <sup>(2)</sup>    | INTCON   | GIE                      | PEIE   | TMR0IE          | INTE         | IOCIE          | TMR0IF      | INTF        | IOCIF   | 0000 0000            | 0000 0000                       |
| 40Ch                   | _        | Unimplemen               | nted   |                 | _            | _              |             |             |         |                      |                                 |
| 40Dh                   | _        | Unimplemen               | Unimplemented  |                 |              |                |             |             |         |                      | _                               |
| 40Eh                   | _        | Unimplemen               | nted   |                 |              |                |             |             |         | _                    | _                               |
| 40Fh                   | _        | Unimplemen               | nted   |                 |              |                |             |             |         | _                    | _                               |
| 410h                   | _        | Unimplemen               | nted   |                 |              |                |             |             |         | _                    | _                               |
| 411h                   | _        | Unimplemen               | nted   |                 |              |                |             |             |         | _                    | _                               |
| 412h                   | _        | Unimplemen               | nted   |                 |              |                |             |             |         | _                    | _                               |
| 413h                   | _        | Unimplemen               | nted   |                 |              |                |             |             |         | _                    | _                               |
| 414h                   | _        | Unimplemen               | nted   |                 |              |                |             |             |         | _                    | _                               |
| 415h                   | TMR4     | Timer4 Mod               | ule Register   |                 |              |                |             |             |         | 0000 0000            | 0000 0000                       |
| 416h                   | PR4      | Timer4 Perio             | od Register  |                 |              |                |             |             |         | 1111 1111            | 1111 1111                       |
| 417h                   | T4CON    | _                        |  | T4OUT           | PS<3:0>      |                | TMR4ON      | T4CKF       | PS<1:0> | -000 0000            | -000 0000                       |
| 418h                   | _        | Unimplemen               | nted   |                 |              |                |             |             |         | _                    | _                               |
| 419h                   | _        | Unimplemen               | nted   |                 |              |                |             |             |         | _                    | _                               |
| 41Ah                   | _        | Unimplemen               | nted   |                 |              |                |             |             |         | _                    | _                               |
| 41Bh                   | _        | Unimplemen               | nted   |                 |              |                |             |             |         | _                    | _                               |
| 41Ch                   | TMR6     | Timer6 Mod               | ule Register   |                 |              |                |             |             |         | 0000 0000            | 0000 0000                       |
| 41Dh                   | PR6      | Timer6 Peri              | od Register  |                 |              |                |             |             |         | 1111 1111            | 1111 1111                       |
| 41Eh                   | T6CON    | _                        |  | T6OUT           | PS<3:0>      |                | TMR6ON      | T6CKF       | PS<1:0> | -000 0000            | -000 0000                       |
| 41Fh                   | _        | Unimplemen               | nted   |                 |              |                |             |             |         | _                    | _                               |

**Legend:** x = unknown, u = unchanged, q = value depends on condition, - = unimplemented, read as '0', <math>x = reserved. Shaded locations are unimplemented, read as '0'.

- 2: These registers can be addressed from any bank.
- 3: These registers/bits are not implemented on PIC16(L)F1936 devices, read as '0'.
- 4: Unimplemented, read as '1'.

### TABLE 3-12: SPECIAL FUNCTION REGISTER SUMMARY (CONTINUED)

| Address                          | Name   | Bit 7  | Bit 6  | Bit 5          | Bit 4        | Bit 3          | Bit 2       | Bit 1 | Bit 0    | Value on<br>POR, BO | Value on all<br>other<br>Resets |
|----------------------------------|--------|--|--|----------------|--------------|----------------|-------------|-------|----------|---------------------|---------------------------------|
| Banks 9                          | -14    | •  |  |                | •            | •              |             |       |          | •                   | •                               |
| x00h/<br>x80h <sup>(2)</sup>     | INDF0  |  | this location u cal register)                            | ses contents o | of FSR0H/FSF | ROL to address | data memory | У     |          | xxxx xxx            | x xxxx xxxx                     |
| x00h/<br>x81h <sup>(2)</sup>     | INDF1  |  | this location u cal register)                            | ses contents o | of FSR1H/FSF | R1L to address | data memory | У     |          | xxxx xxx            | x xxxx xxxx                     |
| x02h/<br>x82h <sup>(2)</sup>     | PCL    | Program Co                                   | ounter (PC) Le   |                | 0000 000     | 0 0000 0000    |             |       |          |                     |                                 |
| x03h/<br>x83h <sup>(2)</sup>     | STATUS | _  | _  | _              | TO           | PD             | Z           | DC    | С        | 1 100               | 0q quuu                         |
| x04h/<br>x84h <sup>(2)</sup>     | FSR0L  | Indirect Data                                | ndirect Data Memory Address 0 Low Pointer                |                |              |                |             |       |          |                     | 0 uuuu uuuu                     |
| x05h/<br>x85h <sup>(2)</sup>     | FSR0H  | Indirect Data                                | ndirect Data Memory Address 0 High Pointer               |                |              |                |             |       |          |                     | 0 0000 0000                     |
| x06h/<br>x86h <sup>(2)</sup>     | FSR1L  | Indirect Data                                | Indirect Data Memory Address 1 Low Pointer               |                |              |                |             |       |          |                     | 0 uuuu uuuu                     |
| x07h/<br>x87h <sup>(2)</sup>     | FSR1H  | Indirect Data                                | a Memory Ado   | lress 1 High P | ointer       |                |             |       |          | 0000 000            | 0 0000 0000                     |
| x08h/<br>x88h <sup>(2)</sup>     | BSR    | _  | _  | _              |              | E              | 3SR<4:0>    |       |          | 0 000               | 00 0000                         |
| x09h/<br>x89h <sup>(2)</sup>     | WREG   | Working Re                                   | gister   |                |              |                |             |       |          | 0000 000            | 0 uuuu uuuu                     |
| x0Ah/<br>x8Ah <sup>(1),(2)</sup> | PCLATH | _  | Write Buffer for the upper 7 bits of the Program Counter |                |              |                |             |       |          | -000 000            | 0 -000 0000                     |
| x0Bh/<br>x8Bh <sup>(2)</sup>     | INTCON | GIE PEIE TMR0IE INTE IOCIE TMR0IF INTF IOCIF |  |                |              |                |             |       | 0000 000 | 0 0000 0000         |                                 |
| x0Ch/<br>x8Ch                    | _      | Unimpleme                                    | Unimplemented  |                |              |                |             |       |          | _                   | _                               |
| x1Fh/<br>x9Fh                    |        |  |  |                |              |                |             |       |          |                     |                                 |

**Legend:** x = unknown, u = unchanged, q = value depends on condition, - = unimplemented, read as '0', r = reserved. Shaded locations are unimplemented, read as '0'.

- 2: These registers can be addressed from any bank.
- 3: These registers/bits are not implemented on PIC16(L)F1936 devices, read as '0'.
- 4: Unimplemented, read as '1'.

TABLE 3-12: SPECIAL FUNCTION REGISTER SUMMARY (CONTINUED)

| Address                | Name                  | Bit 7         | Bit 6                                     | Bit 5           | Bit 4           | Bit 3          | Bit 2                   | Bit 1         | Bit 0         | Value on<br>POR, BOR | Value on all<br>other<br>Resets |
|------------------------|-----------------------|---------------|---|-----------------|-----------------|----------------|-------------------------|---------------|---------------|----------------------|---------------------------------|
| Bank 15                |                       | •             | •   | •               | •               | •              | •                       | •             |               |                      | •                               |
| 780h <sup>(2)</sup>    | INDF0                 |               | this location u                           | ses contents o  | of FSR0H/FSF    | ROL to address | data memor              | у             |               | xxxx xxxx            | xxxx xxxx                       |
| 781h <sup>(2)</sup>    | INDF1                 |               | this location u                           | ses contents o  | of FSR1H/FSF    | R1L to address | data memor              | у             |               | xxxx xxxx            | xxxx xxxx                       |
| 782h <sup>(2)</sup>    | PCL                   | Program Co    | ounter (PC) Le                            | ast Significant | t Byte          |                |                         |               |               | 0000 0000            | 0000 0000                       |
| 783h <sup>(2)</sup>    | STATUS                | _             | TO PD Z DC C                              |                 |                 |                |                         |               |               |                      |                                 |
| 784h <sup>(2)</sup>    | FSR0L                 | Indirect Dat  | ndirect Data Memory Address 0 Low Pointer |                 |                 |                |                         |               |               |                      |                                 |
| 785h <sup>(2)</sup>    | FSR0H                 | Indirect Dat  | a Memory Add                              | 0000 0000       | 0000 0000       |                |                         |               |               |                      |                                 |
| 786h <sup>(2)</sup>    | FSR1L                 | Indirect Dat  | a Memory Add                              |                 | 0000 0000       | uuuu uuuu      |                         |               |               |                      |                                 |
| 787h <sup>(2)</sup>    | FSR1H                 | Indirect Dat  | a Memory Add                              |                 | 0000 0000       | 0000 0000      |                         |               |               |                      |                                 |
| 788h <sup>(2)</sup>    | BSR                   | _             |   |                 |                 |                |                         |               |               |                      | 0 0000                          |
| 789h <sup>(2)</sup>    | WREG                  | Working Re    | gister                                    |                 |                 |                |                         |               |               | 0000 0000            | uuuu uuuu                       |
| 78Ah <sup>(1, 2)</sup> | PCLATH                | _             | Write Buffer f                            | or the upper 7  | bits of the Pro | ogram Counter  | r                       |               |               | -000 0000            | -000 0000                       |
| 78Bh <sup>(2)</sup>    | INTCON                | GIE           | PEIE                                      | TMR0IE          | INTE            | IOCIE          | TMR0IF                  | INTF          | IOCIF         | 0000 0000            | 0000 0000                       |
| 78Ch                   | _                     | Unimpleme     | nted                                      |                 |                 |                |                         | 1             | l             | _                    | _                               |
| 78Dh                   | _                     | Unimplemented |   |                 |                 |                |                         |               |               | _                    | _                               |
| 78Eh                   | _                     | Unimplemented |   |                 |                 |                |                         |               |               | _                    | _                               |
| 78Fh                   | _                     | Unimpleme     | Jnimplemented                             |                 |                 |                |                         |               |               |                      |                                 |
| 790h                   | _                     |               | Unimplemented                             |                 |                 |                |                         |               |               |                      |                                 |
| 791h                   | LCDCON                | LCDEN         | SLPEN                                     | WERR            | _               | CS<            | 1:0>                    | 000- 0011     | 000- 0011     |                      |                                 |
| 792h                   | LCDPS                 | WFT           | BIASMD                                    | LCDA            | WA              |                | <1:0> LMUX<1:0> LP<3:0> |               |               | 0000 0000            | 0000 0000                       |
| 793h                   | LCDREF                | LCDIRE        | LCDIRS                                    | LCDIRI          | _               | VLCD3PE        | 1                       | VLCD1PE       | _             | 000- 000-            | 000- 000-                       |
| 794h                   | LCDCST                | _             | _   | _               |                 | _              |                         | CDCST<2:0>    | <u> </u><br>> | 000                  | 000                             |
| 795h                   | LCDRL                 | IRIA          | NP<1:0>                                   | I RI B          | P<1:0>          | _              |                         | LRLAT<2:0>    |               | 0000 -000            | 0000 -000                       |
| 796h                   | _                     | Unimpleme     |   |                 |                 |                |                         |               |               | _                    | _                               |
| 797h                   | _                     | Unimpleme     |   |                 |                 |                |                         |               |               | _                    | _                               |
| 798h                   | LCDSE0                | Ommpleme      | illou                                     |                 | SE<7            | ·0>            |                         |               |               | 0000 0000            | uuuu uuuu                       |
| 799h                   | LCDSE1                |               |   |                 | SE<15           |                |                         |               |               | 0000 0000            | uuuu uuuu                       |
| 79Ah                   | LCDSE2 <sup>(3)</sup> |               |   |                 | SE<23           |                |                         |               |               | 0000 0000            | uuuu uuuu                       |
| 79Bh                   | _                     | Unimpleme     | ntad                                      |                 | OL \20          | . 10-          |                         |               |               |                      |                                 |
| 79Ch                   |                       | Unimpleme     |   |                 |                 |                |                         |               |               |                      | _                               |
| 79Dh                   |                       | Unimpleme     |   |                 |                 |                |                         |               |               |                      |                                 |
| 79Eh                   |                       | Unimpleme     |   |                 |                 |                |                         |               |               |                      | _                               |
| 79EII                  |                       | Unimpleme     |   |                 |                 |                |                         |               |               |                      | _                               |
| 79FII<br>7A0h          | LCDDATA0              | SEG7          | SEG6                                      | SEG5            | SEG4            | SEG3           | SEG2                    | SEG1          | SEG0          | xxxx xxxx            | uuuu uuuu                       |
|                        |                       | COM0          | COM0                                      | COM0            | COM0            | COM0           | COM0                    | COM0          | COM0          |                      |                                 |
| 7A1h                   | LCDDATA1              | SEG15<br>COM0 | SEG14<br>COM0                             | SEG13<br>COM0   | SEG12<br>COM0   | SEG11<br>COM0  | SEG10<br>COM0           | SEG9<br>COM0  | SEG8<br>COM0  | xxxx xxxx            | uuuu uuuu                       |
| 7A2h                   | LCDDATA2 <sup>(</sup> | SEG23<br>COM0 | SEG22<br>COM0                             | SEG21<br>COM0   | SEG20<br>COM0   | SEG19<br>COM0  | SEG18<br>COM0           | SEG17<br>COM0 | SEG16<br>COM0 | xxxx xxxx            | uuuu uuuu                       |
| 7A3h                   | LCDDATA3              | SEG7<br>COM1  | SEG6<br>COM1                              | SEG5<br>COM1    | SEG4<br>COM1    | SEG3<br>COM1   | SEG2<br>COM1            | SEG1<br>COM1  | SEG0<br>COM1  | xxxx xxxx            | uuuu uuuu                       |
| 7A4h                   | LCDDATA4              | SEG15<br>COM1 | SEG14<br>COM1                             | SEG13<br>COM1   | SEG12<br>COM1   | SEG11<br>COM1  | SEG10<br>COM1           | SEG9<br>COM1  | SEG8<br>COM1  | xxxx xxxx            | uuuu uuuu                       |
| 7A5h                   | LCDDATA5 <sup>(</sup> | SEG23<br>COM1 | SEG22<br>COM1                             | SEG21<br>COM1   | SEG20<br>COM1   | SEG19<br>COM1  | SEG18<br>COM1           | SEG17<br>COM1 | SEG16<br>COM1 | xxxx xxxx            | uuuu uuuu                       |
|                        | 1                     | 1             | 1   | 1               | 1               | l              | 1                       | 1             |               | 1                    | 1                               |

**Legend:** x = unknown, u = unchanged, q = value depends on condition, - = unimplemented, read as '0', r = reserved. Shaded locations are unimplemented, read as '0'.

- 2: These registers can be addressed from any bank.
- 3: These registers/bits are not implemented on PIC16(L)F1936 devices, read as '0'.
- 4: Unimplemented, read as '1'.

TABLE 3-12: SPECIAL FUNCTION REGISTER SUMMARY (CONTINUED)

| Address           | Name                   | Bit 7         | Bit 6         | Bit 5         | Bit 4         | Bit 3         | Bit 2         | Bit 1         | Bit 0         | Value on<br>POR, BOR | Value on all<br>other<br>Resets |
|-------------------|------------------------|---------------|---------------|---------------|---------------|---------------|---------------|---------------|---------------|----------------------|---------------------------------|
| Bank 15           | Bank 15 (Continued)    |               |               |               |               |               |               |               |               |                      |                                 |
| 7A6h              | LCDDATA6               | SEG7<br>COM2  | SEG6<br>COM2  | SEG5<br>COM2  | SEG4<br>COM2  | SEG3<br>COM2  | SEG2<br>COM2  | SEG1<br>COM2  | SEG0<br>COM2  | xxxx xxxx            | uuuu uuuu                       |
| 7A7h              | LCDDATA7               | SEG15<br>COM2 | SEG14<br>COM2 | SEG13<br>COM2 | SEG12<br>COM2 | SEG11<br>COM2 | SEG10<br>COM2 | SEG9<br>COM2  | SEG8<br>COM2  | xxxx xxxx            | uuuu uuuu                       |
| 7A8h              | LCDDATA8 <sup>(</sup>  | SEG23<br>COM2 | SEG22<br>COM2 | SEG21<br>COM2 | SEG20<br>COM2 | SEG19<br>COM2 | SEG18<br>COM2 | SEG17<br>COM2 | SEG16<br>COM2 | xxxx xxxx            | uuuu uuuu                       |
| 7A9h              | LCDDATA9               | SEG7<br>COM3  | SEG6<br>COM3  | SEG5<br>COM3  | SEG4<br>COM3  | SEG3<br>COM3  | SEG2<br>COM3  | SEG1<br>COM3  | SEG0<br>COM3  | xxxx xxxx            | uuuu uuuu                       |
| 7AAh              | LCDDATA1<br>0          | SEG15<br>COM3 | SEG14<br>COM3 | SEG13<br>COM3 | SEG12<br>COM3 | SEG11<br>COM3 | SEG10<br>COM3 | SEG9<br>COM3  | SEG8<br>COM3  | xxxx xxxx            | uuuu uuuu                       |
| 7ABh              | LCDDATA11 <sup>(</sup> | SEG23<br>COM3 | SEG22<br>COM3 | SEG21<br>COM3 | SEG20<br>COM3 | SEG19<br>COM3 | SEG18<br>COM3 | SEG17<br>COM3 | SEG16<br>COM3 | xxxx xxxx            | uuuu uuuu                       |
| 7ACh<br>—<br>7EFh | _                      | Unimpleme     | nted          |               |               |               |               |               |               | _                    | _                               |

Legend: x = unknown, u = unchanged, q = value depends on condition, - = unimplemented, read as '0', r = reserved. Shaded locations are unimplemented, read as '0'.

- 2: These registers can be addressed from any bank.
- 3: These registers/bits are not implemented on PIC16(L)F1936 devices, read as '0'.
- 4: Unimplemented, read as '1'.

TABLE 3-12: SPECIAL FUNCTION REGISTER SUMMARY (CONTINUED)

| Address                             | Name   | Bit 7  | Bit 6  | Bit 5           | Bit 4        | Bit 3          | Bit 2      | Bit 1 | Bit 0     | Value on<br>POR, BOR | Value on all<br>other<br>Resets |
|-------------------------------------|--------|--|--|-----------------|--------------|----------------|------------|-------|-----------|----------------------|---------------------------------|
| Banks 1                             | 6-30   |  |  |                 |              |                |            |       |           |                      |                                 |
| x00h/<br>x80h <sup>(2)</sup>        | INDF0  |  | this location u cal register)                            | ses contents o  | of FSR0H/FSF | ROL to address | data memor | У     |           | xxxx xxxx            | xxxx xxxx                       |
| x00h/<br>x81h <sup>(2)</sup>        | INDF1  |  | this location u cal register)                            | ses contents o  | of FSR1H/FSF | R1L to address | data memor | У     |           | xxxx xxxx            | xxxx xxxx                       |
| x02h/<br>x82h <sup>(2)</sup>        | PCL    | Program Co                                   | ounter (PC) Le   | ast Significant | t Byte       |                |            |       |           | 0000 0000            | 0000 0000                       |
| x03h/<br>x83h <sup>(2)</sup>        | STATUS | _  | _  | _               | TO           | PD             | Z          | DC    | С         | 1 1000               | q quuu                          |
| x04h/<br>x84h <sup>(2)</sup>        | FSR0L  | Indirect Dat                                 | ndirect Data Memory Address 0 Low Pointer                |                 |              |                |            |       |           |                      | uuuu uuuu                       |
| x05h/<br>x85h <sup>(2)</sup>        | FSR0H  | Indirect Dat                                 | ndirect Data Memory Address 0 High Pointer               |                 |              |                |            |       |           |                      | 0000 0000                       |
| x06h/<br>x86h <sup>(2)</sup>        | FSR1L  | Indirect Dat                                 | Indirect Data Memory Address 1 Low Pointer               |                 |              |                |            |       |           |                      | uuuu uuuu                       |
| x07h/<br>x87h <sup>(2)</sup>        | FSR1H  | Indirect Dat                                 | a Memory Ado   | dress 1 High P  | ointer       |                |            |       |           | 0000 0000            | 0000 0000                       |
| x08h/<br>x88h <sup>(2)</sup>        | BSR    | _  | _  | _               |              | Į.             | 3SR<4:0>   |       |           | 0 0000               | 0 0000                          |
| x09h/<br>x89h <sup>(2)</sup>        | WREG   | Working Re                                   | gister   |                 |              |                |            |       |           | 0000 0000            | uuuu uuuu                       |
| x0Ah/<br>x8Ah <sup>(1),(2)</sup>    | PCLATH | _  | Write Buffer for the upper 7 bits of the Program Counter |                 |              |                |            |       |           | -000 0000            | -000 0000                       |
| x0Bh/<br>x8Bh <sup>(2)</sup>        | INTCON | GIE PEIE TMR0IE INTE IOCIE TMR0IF INTF IOCIF |  |                 |              |                |            |       | 0000 0000 | 0000 0000            |                                 |
| x0Ch/<br>x8Ch<br>—<br>x1Fh/<br>x9Fh | _      | Unimpleme                                    | nted   |                 |              |                |            |       |           | _                    | _                               |

**Legend:** x = unknown, u = unchanged, q = value depends on condition, -= unimplemented, read as '0', x = reserved. Shaded locations are unimplemented, read as '0'.

- 2: These registers can be addressed from any bank.
- 3: These registers/bits are not implemented on PIC16(L)F1936 devices, read as '0'.
- 4: Unimplemented, read as '1'.

### TABLE 3-12: SPECIAL FUNCTION REGISTER SUMMARY (CONTINUED)

| Address                  | Name            | Bit 7   | Bit 6  | Bit 5           | Bit 4          | Bit 3          | Bit 2        | Bit 1   | Bit 0     | Value on<br>POR, BOR | Value on all<br>other<br>Resets |
|--------------------------|-----------------|---|--|-----------------|----------------|----------------|--------------|---------|-----------|----------------------|---------------------------------|
| Bank 31                  |                 |   |  |                 |                |                |              |         |           |                      |                                 |
| F80h <sup>(2)</sup>      | INDF0           | _   | this location u<br>ical register)                        | ses contents o  | of FSR0H/FSR   | ROL to address | data memor   | у       |           | xxxx xxxx            | xxxx xxxx                       |
| F81h <sup>(2)</sup>      | INDF1           |   | this location u  | ses contents o  | of FSR1H/FSF   | R1L to address | data memor   | у       |           | xxxx xxxx            | xxxx xxxx                       |
| F82h <sup>(2)</sup>      | PCL             | Program Co  | ounter (PC) Le   | ast Significan  | t Byte         |                |              |         |           | 0000 0000            | 0000 0000                       |
| F83h <sup>(2)</sup>      | STATUS          | _   | _  | С               | 1 1000         | q quuu         |              |         |           |                      |                                 |
| F84h <sup>(2)</sup>      | FSR0L           | Indirect Dat  | a Memory Add   |                 | 0000 0000      | uuuu uuuu      |              |         |           |                      |                                 |
| F85h <sup>(2)</sup>      | FSR0H           | Indirect Dat  | a Memory Add   |                 | 0000 0000      | 0000 0000      |              |         |           |                      |                                 |
| F86h <sup>(2)</sup>      | FSR1L           | Indirect Dat  | a Memory Ado   |                 | 0000 0000      | uuuu uuuu      |              |         |           |                      |                                 |
| F87h <sup>(2)</sup>      | FSR1H           | Indirect Dat  | a Memory Ado   |                 | 0000 0000      | 0000 0000      |              |         |           |                      |                                 |
| F88h <sup>(2)</sup>      | BSR             | _   | _  | _               |                | E              | BSR<4:0>     |         |           | 0 0000               | 0 0000                          |
| F89h <sup>(2)</sup>      | WREG            | Working Re  | gister   |                 | •              |                |              |         |           | 0000 0000            | uuuu uuuu                       |
| F8Ah <sup>(1),(2</sup> ) | PCLATH          | _   | Write Buffer for the upper 7 bits of the Program Counter |                 |                |                |              |         |           |                      | -000 0000                       |
| F8Bh <sup>(2)</sup>      | INTCON          | GIE   | PEIE   | TMR0IE          | INTE           | IOCIE          | TMR0IF       | INTF    | IOCIF     | 0000 0000            | 0000 0000                       |
| F8Ch                     | _               | Unimpleme   | Unimplemented  |                 |                |                |              |         |           |                      |                                 |
| FE3h                     |                 |   |  | ı               | 1              | 1              | •            |         |           |                      |                                 |
| FE4h                     | STATUS_<br>SHAD |   |  |                 |                |                | Z_SHAD       | DC_SHAD | C_SHAD    | xxx                  | uuu                             |
| FE5h                     | WREG_<br>SHAD   | Working Re  | gister Normal  | (Non-ICD) Sh    | adow           |                |              |         |           | xxxx xxxx            | uuuu uuuu                       |
| FE6h                     | BSR_<br>SHAD    |   |  |                 | Bank Select I  | Register Norm  | al (Non-ICD) | Shadow  |           | x xxxx               | u uuuu                          |
| FE7h                     | PCLATH_         |   | Program Cou  | ınter Latch Hiç | gh Register No | ormal (Non-ICE | D) Shadow    |         |           | -xxx xxxx            | uuuu uuuu                       |
|                          | SHAD            | –   | L  |                 |                |                |              |         |           |                      |                                 |
| FE8h                     | FSR0L_<br>SHAD  | Indirect Dat  | a Memory Ado   | iress 0 Low P   | ointer Normal  | (Non-ICD) Sha  | adow         |         |           | xxxx xxxx            | uuuu uuuu                       |
| FE9h                     | FSR0H_<br>SHAD  | Indirect Dat  | a Memory Ado   | lress 0 High F  | ointer Normal  | (Non-ICD) Sh   | adow         |         |           | xxxx xxxx            | uuuu uuuu                       |
| FEAh                     | FSR1L_          | Indirect Dat  | a Memory Ado   | dress 1 Low P   | ointer Normal  | (Non-ICD) Sha  | adow         |         |           | xxxx xxxx            | uuuu uuuu                       |
|                          | SHAD            |   |  |                 |                |                |              |         |           |                      |                                 |
| FEBh                     | FSR1H_<br>SHAD  | Indirect Data Memory Address 1 High Pointer Normal (Non-ICD) Shadow |  |                 |                |                |              |         | xxxx xxxx | uuuu uuuu            |                                 |
| FECh                     | _               | Unimpleme   | Unimplemented  |                 |                |                |              |         |           | _                    | _                               |
| FEDh                     | STKPTR          | _   | — — Current Stack pointer                                |                 |                |                |              |         |           | 1 1111               | 1 1111                          |
| FEEh                     | TOSL            | Top of Stack  | k Low byte   |                 | !              |                |              |         |           | xxxx xxxx            | uuuu uuuu                       |
|                          |                 | Top of Stack High byte  |  |                 |                |                |              |         |           | ļ                    |                                 |

**Legend:** x = unknown, u = unchanged, q = value depends on condition, - = unimplemented, read as '0', x = reserved. Shaded locations are unimplemented, read as '0'.

Note 1: The upper byte of the program counter is not directly accessible. PCLATH is a holding register for the PC<14:8>, whose contents are transferred to the upper byte of the program counter.

2: These registers can be addressed from any bank.


3: These registers/bits are not implemented on PIC16(L)F1936 devices, read as '0'.

4: Unimplemented, read as '1'.

### 3.3 PCL and PCLATH

The Program Counter (PC) is 15 bits wide. The low byte comes from the PCL register, which is a readable and writable register. The high byte (PC<14:8>) is not directly readable or writable and comes from PCLATH. On any Reset, the PC is cleared. Figure 3-4 shows the five situations for the loading of the PC.

FIGURE 3-4: LOADING OF PC IN DIFFERENT SITUATIONS



### 3.3.1 MODIFYING PCL

Executing any instruction with the PCL register as the destination simultaneously causes the Program Counter PC<14:8> bits (PCH) to be replaced by the contents of the PCLATH register. This allows the entire contents of the program counter to be changed by writing the desired upper 7 bits to the PCLATH register. When the lower 8 bits are written to the PCL register, all 15 bits of the program counter will change to the values contained in the PCLATH register and those being written to the PCL register.

### 3.3.2 COMPUTED GOTO

A computed GOTO is accomplished by adding an offset to the program counter (ADDWF PCL). When performing a table read using a computed GOTO method, care should be exercised if the table location crosses a PCL memory boundary (each 256-byte block). Refer to Application Note AN556, "Implementing a Table Read" (DS00556).

#### 3.3.3 COMPUTED FUNCTION CALLS

A computed function CALL allows programs to maintain tables of functions and provide another way to execute state machines or look-up tables. When performing a table read using a computed function CALL, care should be exercised if the table location crosses a PCL memory boundary (each 256-byte block).

If using the CALL instruction, the PCH<2:0> and PCL registers are loaded with the operand of the CALL instruction. PCH<6:3> is loaded with PCLATH<6:3>.

The CALLW instruction enables computed calls by combining PCLATH and W to form the destination address. A computed CALLW is accomplished by loading the W register with the desired address and executing CALLW. The PCL register is loaded with the value of W and PCH is loaded with PCLATH.

#### 3.3.4 BRANCHING

The branching instructions add an offset to the PC. This allows relocatable code and code that crosses page boundaries. There are two forms of branching,  $_{\rm BRW}$  and  $_{\rm BRA}$ . The PC will have incremented to fetch the next instruction in both cases. When using either branching instruction, a PCL memory boundary may be crossed.

If using BRW, load the W register with the desired unsigned address and execute BRW. The entire PC will be loaded with the address PC + 1 + W.

If using BRA, the entire PC will be loaded with PC + 1 +, the signed value of the operand of the BRA instruction.

#### 3.4 Stack

All devices have a 16-level x 15-bit wide hardware stack (refer to Figure 3-1 and Figure 3-2). The stack space is not part of either program or data space. The PC is PUSHed onto the stack when CALL or CALLW instructions are executed or an interrupt causes a branch. The stack is POPed in the event of a RETURN, RETLW or a RETFIE instruction execution. PCLATH is not affected by a PUSH or POP operation.

The stack operates as a circular buffer if the STVREN bit is programmed to '0' (Configuration Word 2). This means that after the stack has been PUSHed sixteen times, the seventeenth PUSH overwrites the value that was stored from the first PUSH. The eighteenth PUSH overwrites the second PUSH (and so on). The STKOVF and STKUNF flag bits will be set on an Overflow/Underflow, regardless of whether the Reset is enabled.

Note 1: There are no instructions/mnemonics called PUSH or POP. These are actions that occur from the execution of the CALL, CALLW, RETURN, RETLW and RETFIE instructions or the vectoring to an interrupt address.

#### 3.4.1 ACCESSING THE STACK


The stack is available through the TOSH, TOSL and STKPTR registers. STKPTR is the current value of the Stack Pointer. TOSH:TOSL register pair points to the TOP of the stack. Both registers are read/writable. TOS is split into TOSH and TOSL due to the 15-bit size of the PC. To access the stack, adjust the value of STKPTR, which will position TOSH:TOSL, then read/write to TOSH:TOSL. STKPTR is 5 bits to allow detection of overflow and underflow.


**Note:** Care should be taken when modifying the STKPTR while interrupts are enabled.


During normal program operation, CALL, CALLW and Interrupts will increment STKPTR while RETLW, RETURN, and RETFIE will decrement STKPTR. At any time STKPTR can be inspected to see how much stack is left. The STKPTR always points at the currently used place on the stack. Therefore, a CALL or CALLW will increment the STKPTR and then write the PC, and a return will unload the PC and then decrement the STKPTR.


Reference Figure 3-5 through Figure 3-8 for examples of accessing the stack.

FIGURE 3-5: ACCESSING THE STACK EXAMPLE 1









### 3.4.2 OVERFLOW/UNDERFLOW RESET

If the STVREN bit in Configuration Word 2 is programmed to '1', the device will be reset if the stack is PUSHed beyond the sixteenth level or POPed beyond the first level, setting the appropriate bits (STKOVF or STKUNF, respectively) in the PCON register.

### 3.5 Indirect Addressing

The INDFn registers are not physical registers. Any instruction that accesses an INDFn register actually accesses the register at the address specified by the File Select Registers (FSR). If the FSRn address specifies one of the two INDFn registers, the read will return '0' and the write will not occur (though Status bits may be affected). The FSRn register value is created by the pair FSRnH and FSRnL.

The FSR registers form a 16-bit address that allows an addressing space with 65536 locations. These locations are divided into three memory regions:


- Traditional Data Memory
- Linear Data Memory
- · Program Flash Memory

FIGURE 3-9: **INDIRECT ADDRESSING** 0x0000 0x0000 **Traditional Data Memory** 0x0FFF 0x0FFF 0x1000 Reserved 0x1FFF 0x2000 Linear **Data Memory** 0x29AF 0x29B0 Reserved **FSR** 0x7FFF Address 0x8000 0x0000 Range **Program** Flash Memory 0xFFFF 0x7FFF Note: Not all memory regions are completely implemented. Consult device memory tables for memory limits.

### 3.5.1 TRADITIONAL DATA MEMORY

The traditional data memory is a region from FSR address 0x000 to FSR address 0xFFF. The addresses correspond to the absolute addresses of all SFR, GPR and common registers.

FIGURE 3-10: TRADITIONAL DATA MEMORY MAP




#### 3.5.2 LINEAR DATA MEMORY

The linear data memory is the region from FSR address 0x2000 to FSR address 0x29AF. This region is a virtual region that points back to the 80-byte blocks of GPR memory in all the banks.

Unimplemented memory reads as 0x00. Use of the linear data memory region allows buffers to be larger than 80 bytes because incrementing the FSR beyond one bank will go directly to the GPR memory of the next bank.

The 16 bytes of common memory are not included in the linear data memory region.


FIGURE 3-11: LINEAR DATA MEMORY MAP



### 3.5.3 PROGRAM FLASH MEMORY

To make constant data access easier, the entire program Flash memory is mapped to the upper half of the FSR address space. When the MSB of FSRnH is set, the lower 15 bits are the address in program memory which will be accessed through INDF. Only the lower 8 bits of each memory location is accessible via INDF. Writing to the program Flash memory cannot be accomplished via the FSR/INDF interface. All instructions that access program Flash memory via the FSR/INDF interface will require one additional instruction cycle to complete.

FIGURE 3-12: PROGRAM FLASH MEMORY MAP



**NOTES:** 

### 4.0 DEVICE CONFIGURATION

Device Configuration consists of Configuration Word 1 and Configuration Word 2, Code Protection and Device ID.

### 4.1 Configuration Words

There are several Configuration Word bits that allow different oscillator and memory protection options. These are implemented as Configuration Word 1 at 8007h and Configuration Word 2 at 8008h.

Note: The DEBUG bit in Configuration Word 2 is managed automatically by device development tools including debuggers and programmers. For normal device operation, this bit should be maintained as a '1'.

### **REGISTER 4-1: CONFIGURATION WORD 1**

| R/P-1/1 | R/P-1/1 | R/P-1/1  | R/P-1/1 | R/P-1/1 | R/P-1/1 | R/P-1/1 |
|---------|---------|----------|---------|---------|---------|---------|
| FCMEN   | IESO    | CLKOUTEN | BOREN1  | BOREN0  | CPD     | CP      |
| bit 13  |         |          |         |         |         | bit 7   |

| R/P-1/1 |
|---------|---------|---------|---------|---------|---------|---------|
| MCLRE   | PWRTE   | WDTE1   | WDTE0   | FOSC2   | FOSC1   | FOSC0   |
| bit 6   |         |         |         |         |         | bit 0   |

Legend:

bit 11

R = Readable bit P = Programmable bit U = Unimplemented bit, read as '1'
'0' = Bit is cleared '1' = Bit is set -n = Value when blank or after Bulk Erase

bit 13 FCMEN: Fail-Safe Clock Monitor Enable bit

1 = Fail-Safe Clock Monitor is enabled

0 = Fail-Safe Clock Monitor is disabled

bit 12 IESO: Internal External Switchover bit

1 = Internal/External Switchover mode is enabled 0 = Internal/External Switchover mode is disabled

CLKOUTEN: Clock Out Enable bit

1 = CLKOUT function is disabled. I/O or oscillator function on RA6/CLKOUT

0 = CLKOUT function is enabled on RA6/CLKOUT

bit 10-9 BOREN<1:0>: Brown-out Reset Enable bits(1)

11 = BOR enabled

10 = BOR enabled during operation and disabled in Sleep 01 = BOR controlled by SBOREN bit of the PCON register

00 = BOR disabled

bit 8 CPD: Data Code Protection bit<sup>(2)</sup>

1 = Data memory code protection is disabled0 = Data memory code protection is enabled

bit 7 **CP**: Code Protection bit<sup>(3)</sup>

1 = Program memory code protection is disabled0 = Program memory code protection is enabled

bit 6 MCLRE: RE3/MCLR/VPP Pin Function Select bit

If LVP bit = 1:

This bit is ignored.

If LVP bit = 0:

1 = RE3/ $\overline{MCLR}$ /VPP pin function is  $\overline{MCLR}$ ; Weak pull-up enabled.

0 = RE3/MCLR/VPP pin function is digital input; MCLR internally disabled; Weak pull-up under control of WPUE3 bit..

bit 5 **PWRTE**: Power-up Timer Enable bit<sup>(1)</sup>

1 = PWRT disabled

0 = PWRT enabled

bit 4-3 WDTE<1:0>: Watchdog Timer Enable bit

11 = WDT enabled

10 = WDT enabled while running and disabled in Sleep

01 = WDT controlled by the SWDTEN bit in the WDTCON register

00 = WDT disabled

Note 1: Enabling Brown-out Reset does not automatically enable Power-up Timer.

2: The entire data EEPROM will be erased when the code protection is turned off during an erase.

3: The entire program memory will be erased when the code protection is turned off.

### REGISTER 4-1: CONFIGURATION WORD 1 (CONTINUED)

bit 2-0 FOSC<2:0>: Oscillator Selection bits

111 = ECH: External Clock, High-Power mode: CLKIN on RA7/OSC1/CLKIN 110 = ECM: External Clock, Medium-Power mode: CLKIN on RA7/OSC1/CLKIN 101 = ECL: External Clock, Low-Power mode: CLKIN on RA7/OSC1/CLKIN

100 = INTOSC oscillator: I/O function on RA7/OSC1/CLKIN 011 = EXTRC oscillator: RC function on RA7/OSC1/CLKIN

010 = HS oscillator: High-speed crystal/resonator on RA6/OSC2/CLKOUT pin and RA7/OSC1/CLKIN

001 = XT oscillator: Crystal/resonator on RA6/OSC2/CLKOUT pin and RA7/OSC1/CLKIN 000 = LP oscillator: Low-power crystal on RA6/OSC2/CLKOUT pin and RA7/OSC1/CLKIN

Note 1: Enabling Brown-out Reset does not automatically enable Power-up Timer.

2: The entire data EEPROM will be erased when the code protection is turned off during an erase.

3: The entire program memory will be erased when the code protection is turned off.

### REGISTER 4-2: CONFIGURATION WORD 2

| R/P-1/1            | R/P-1/1              | U-1 | R/P-1/1 | R/P-1/1 | R/P-1/1 | U-1   |
|--------------------|----------------------|-----|---------|---------|---------|-------|
| LVP <sup>(1)</sup> | DEBUG <sup>(3)</sup> | _   | BORV    | STVREN  | PLLEN   | _     |
| bit 13             |                      |     |         |         |         | bit 7 |

| U-1   | R/P-1/1                    | R/P-1/1 | U-1 | U-1 | R/P-1/1 | R/P-1/1 |
|-------|----------------------------|---------|-----|-----|---------|---------|
| _     | VCAPEN<1:0> <sup>(2)</sup> |         | _   | _   | WRT1    | WRT0    |
| bit 6 |                            |         |     |     |         | bit 0   |

Legend:

R = Readable bit P = Programmable bit U = Unimplemented bit, read as '1'
'0' = Bit is cleared '1' = Bit is set -n = Value when blank or after Bulk Erase

bit 13 LVP: Low-Voltage Programming Enable bit<sup>(1)</sup>

1 = Low-voltage programming enabled

 $0 = \text{High-voltage on } \overline{\text{MCLR}}/\text{VPP}$  must be used for programming

bit 12 **DEBUG**: In-Circuit Debugger Mode bit<sup>(3)</sup>

1 = In-Circuit Debugger disabled, RB6/ICSPCLK and RB7/ICSPDAT are general purpose I/O pins 0 = In-Circuit Debugger enabled, RB6/ICSPCLK and RB7/ICSPDAT are dedicated to the debugger

bit 11 **Unimplemented:** Read as '1'

bit 10 BORV: Brown-out Reset Voltage Selection bit

1 = Brown-out Reset voltage set to 1.9V 0 = Brown-out Reset voltage set to 2.5V

bit 9 STVREN: Stack Overflow/Underflow Reset Enable bit

1 = Stack Overflow or Underflow will cause a Reset0 = Stack Overflow or Underflow will not cause a Reset

bit 8 PLLEN: PLL Enable bit

1 = 4xPLL enabled 0 = 4xPLL disabled

bit 7-6 **Unimplemented:** Read as '1'

bit 5-4 **VCAPEN<1:0>:** Voltage Regulator Capacitor Enable bits<sup>(2)</sup>

00 = VCAP functionality is enabled on RA0
 01 = VCAP functionality is enabled on RA5
 10 = VCAP functionality is enabled on RA6

11 = No capacitor on VCAP pin

bit 3-2 **Unimplemented:** Read as '1'

bit 1-0 WRT<1:0>: Flash Memory Self-Write Protection bits

4 kW Flash memory PIC16(L)F1934 only):

11 = Write protection off

10 = 000h to 1FFh write-protected, 200h to FFFh may be modified by EECON control

01 = 000h to 7FFh write-protected, 800h to FFFh may be modified by EECON control

00 = 000h to FFFh write-protected, no addresses may be modified by EECON control

8 kW Flash memory (PIC16(L)F1936 and PIC16(L)F1937 only):

11 = Write protection off

10 = 000h to 1FFh write-protected, 200h to 1FFFh may be modified by EECON control

01 = 000h to FFFh write-protected, 1000h to 1FFFh may be modified by EECON control

00 = 000h to 1FFFh write-protected, no addresses may be modified by EECON control

Note 1: The LVP bit cannot be programmed to '0' when Programming mode is entered via LVP.

2: Reads as '11' on PIC16LF193X only.

3: The DEBUG bit in Configuration Word is managed automatically by device development tools including debuggers and programmers. For normal device operation, this bit should be maintained as a '1'.

### 4.2 Code Protection

Code protection allows the device to be protected from unauthorized access. Program memory protection and data EEPROM protection are controlled independently. Internal access to the program memory and data EEPROM are unaffected by any code protection setting.

#### 4.2.1 PROGRAM MEMORY PROTECTION

The entire program memory space is protected from external reads and writes by the  $\overline{CP}$  bit in Configuration Word 1. When  $\overline{CP}$  = 0, external reads and writes of program memory are inhibited and a read will return all '0's. The CPU can continue to read program memory, regardless of the protection bit settings. Writing the program memory is dependent upon the write protection setting. See Section 4.3 "Write Protection" for more information.

### 4.2.2 DATA EEPROM PROTECTION

The entire data EEPROM is protected from external reads and writes by the  $\overline{CPD}$  bit. When  $\overline{CPD}$  = 0, external reads and writes of data EEPROM are inhibited. The CPU can continue to read and write data EEPROM regardless of the protection bit settings.

### 4.3 Write Protection

Write protection allows the device to be protected from unintended self-writes. Applications, such as bootloader software, can be protected while allowing other regions of the program memory to be modified.

The WRT<1:0> bits in Configuration Word 2 define the size of the program memory block that is protected.

### 4.4 User ID

Four memory locations (8000h-8003h) are designated as ID locations where the user can store checksum or other code identification numbers. These locations are readable and writable during normal execution. See Section 4.5 "Device ID and Revision ID" for more information on accessing these memory locations. For more information on checksum calculation, see the "PIC16F193X/LF193X/PIC16F194X/LF194X/PIC16LF 190X Memory Programming Specification" (DS41397).

### 4.5 Device ID and Revision ID

The memory location 8006h is where the Device ID and Revision ID are stored. The upper nine bits hold the Device ID. The lower five bits hold the Revision ID. See Section 11.5 "User ID, Device ID and Configuration Word Access" for more information on accessing these memory locations.

Development tools, such as device programmers and debuggers, may be used to read the Device ID and Revision ID.

### REGISTER 4-3: DEVICEID: DEVICE ID REGISTER<sup>(1)</sup>

| R      | R    | R    | R    | R    | R    | R     |
|--------|------|------|------|------|------|-------|
| DEV8   | DEV7 | DEV6 | DEV5 | DEV4 | DEV3 | DEV2  |
| bit 13 |      |      |      |      |      | bit 7 |

| R     | R    | R    | R    | R    | R    | R     |
|-------|------|------|------|------|------|-------|
| DEV1  | DEV0 | REV4 | REV3 | REV2 | REV1 | REV0  |
| bit 6 |      |      |      |      |      | bit 0 |

| Legend:           |                  | U = Unimplemented bit, read as '0' |
|-------------------|------------------|------------------------------------|
| R = Readable bit  | W = Writable bit | '0' = Bit is cleared               |
| -n = Value at POR | '1' = Bit is set | x = Bit is unknown                 |

bit 13-5 **DEV<8:0>:** Device ID bits 100011010 = PIC16F1934 100011011 = PIC16F1936 100011100 = PIC16F1937 100100010 = PIC16LF1934

100100010 = FIC16LF1936 100100100 = PIC16LF1937

bit 4-0 **REV<4:0>:** Revision ID bits

These bits are used to identify the revision.

Note 1: This location cannot be written.

### 5.0 OSCILLATOR MODULE (WITH FAIL-SAFE CLOCK MONITOR)

### 5.1 Overview

The oscillator module has a wide variety of clock sources and selection features that allow it to be used in a wide range of applications while maximizing performance and minimizing power consumption. Figure 5-1 illustrates a block diagram of the oscillator module.

Clock sources can be supplied from external oscillators, quartz crystal resonators, ceramic resonators and Resistor-Capacitor (RC) circuits. In addition, the system clock source can be supplied from one of two internal oscillators and PLL circuits, with a choice of speeds selectable via software. Additional clock features include:

- Selectable system clock source between external or internal sources via software.
- Two-Speed Start-up mode, which minimizes latency between external oscillator start-up and code execution.
- Fail-Safe Clock Monitor (FSCM) designed to detect a failure of the external clock source (LP, XT, HS, EC or RC modes) and switch automatically to the internal oscillator.
- Oscillator Start-up Timer (OST) ensures stability of crystal oscillator sources

The oscillator module can be configured in one of eight clock modes.


- ECL External Clock Low-Power mode (0 MHz to 0.5 MHz)
- ECM External Clock Medium-Power mode (0.5 MHz to 4 MHz)
- 3. ECH External Clock High-Power mode (4 MHz to 32 MHz)
- 4. LP 32 kHz Low-Power Crystal mode.
- 5. XT Medium Gain Crystal or Ceramic Resonator Oscillator mode (up to 4 MHz)
- HS High Gain Crystal or Ceramic Resonator mode (4 MHz to 20 MHz)
- 7. RC External Resistor-Capacitor (RC).
- 8. INTOSC Internal oscillator (31 kHz to 32 MHz).

Clock Source modes are selected by the FOSC<2:0> bits in the Configuration Word 1. The FOSC bits determine the type of oscillator that will be used when the device is first powered.

The EC clock mode relies on an external logic level signal as the device clock source. The LP, XT, and HS clock modes require an external crystal or resonator to be connected to the device. Each mode is optimized for a different frequency range. The RC clock mode requires an external resistor and capacitor to set the oscillator frequency.

The INTOSC internal oscillator block produces low, medium, and high frequency clock sources, designated LFINTOSC, MFINTOSC, and HFINTOSC. (see Internal Oscillator Block, Figure 5-1). A wide selection of device clock frequencies may be derived from these three clock sources.

FIGURE 5-1: SIMPLIFIED PIC® MCU CLOCK SOURCE BLOCK DIAGRAM



### 5.2 Clock Source Types

Clock sources can be classified as external or internal.

External clock sources rely on external circuitry for the clock source to function. Examples are: oscillator modules (EC mode), quartz crystal resonators or ceramic resonators (LP, XT and HS modes) and Resistor-Capacitor (RC) mode circuits.

Internal clock sources are contained internally within the oscillator module. The internal oscillator block has two internal oscillators and a dedicated Phase-Lock Loop (HFPLL) that are used to generate three internal system clock sources: the 16 MHz High-Frequency Internal Oscillator (HFINTOSC), 500 kHz (MFINTOSC) and the 31 kHz Low-Frequency Internal Oscillator (LFINTOSC).

The system clock can be selected between external or internal clock sources via the System Clock Select (SCS) bits in the OSCCON register. See **Section 5.3** "Clock Switching" for additional information.

### 5.2.1 EXTERNAL CLOCK SOURCES

An external clock source can be used as the device system clock by performing one of the following actions:

- Program the FOSC<2:0> bits in the Configuration Word 1 to select an external clock source that will be used as the default system clock upon a device Reset.
- Write the SCS<1:0> bits in the OSCCON register to switch the system clock source to:
  - Timer1 Oscillator during run-time, or
  - An external clock source determined by the value of the FOSC bits.

See Section 5.3 "Clock Switching" for more information.

### 5.2.1.1 EC Mode


The External Clock (EC) mode allows an externally generated logic level signal to be the system clock source. When operating in this mode, an external clock source is connected to the OSC1 input. OSC2/CLKOUT is available for general purpose I/O or CLKOUT. Figure 5-2 shows the pin connections for EC mode.

EC mode has 3 power modes to select from through Configuration Word 1:

- High power, 4-32 MHz (FOSC = 111)
- Medium power, 0.5-4 MHz (FOSC = 110)
- Low power, 0-0.5 MHz (FOSC = 101)

The Oscillator Start-up Timer (OST) is disabled when EC mode is selected. Therefore, there is no delay in operation after a Power-on Reset (POR) or wake-up from Sleep. Because the PIC® MCU design is fully static, stopping the external clock input will have the effect of halting the device while leaving all data intact. Upon restarting the external clock, the device will resume operation as if no time had elapsed.

FIGURE 5-2: EXTERNAL CLOCK (EC) MODE OPERATION



### 5.2.1.2 LP, XT, HS Modes

The LP, XT and HS modes support the use of quartz crystal resonators or ceramic resonators connected to OSC1 and OSC2 (Figure 5-3). The three modes select a low, medium or high gain setting of the internal inverter-amplifier to support various resonator types and speed.


**LP** Oscillator mode selects the lowest gain setting of the internal inverter-amplifier. LP mode current consumption is the least of the three modes. This mode is designed to drive only 32.768 kHz tuning-fork type crystals (watch crystals).

XT Oscillator mode selects the intermediate gain setting of the internal inverter-amplifier. XT mode current consumption is the medium of the three modes. This mode is best suited to drive resonators with a medium drive level specification.

**HS** Oscillator mode selects the highest gain setting of the internal inverter-amplifier. HS mode current consumption is the highest of the three modes. This mode is best suited for resonators that require a high drive setting.


Figure 5-3 and Figure 5-4 show typical circuits for quartz crystal and ceramic resonators, respectively.

# FIGURE 5-3: QUARTZ CRYSTAL OPERATION (LP, XT OR HS MODE)



- Note 1: A series resistor (Rs) may be required for quartz crystals with low drive level.
  - 2: The value of RF varies with the Oscillator mode selected (typically between 2 M $\Omega$  to 10 M $\Omega$ ).
- Note 1: Quartz crystal characteristics vary according to type, package and manufacturer. The user should consult the manufacturer data sheets for specifications and recommended application.
  - **2:** Always verify oscillator performance over the VDD and temperature range that is expected for the application.
  - **3:** For oscillator design assistance, reference the following Microchip Applications Notes:
    - AN826, "Crystal Oscillator Basics and Crystal Selection for rfPIC<sup>®</sup> and PIC<sup>®</sup> Devices" (DS00826)
    - AN849, "Basic PIC® Oscillator Design" (DS00849)
    - AN943, "Practical PIC® Oscillator Analysis and Design" (DS00943)
    - AN949, "Making Your Oscillator Work" (DS00949)

# FIGURE 5-4: CERAMIC RESONATOR OPERATION (XT OR HS MODE)



- **Note 1:** A series resistor (Rs) may be required for ceramic resonators with low drive level.
  - 2: The value of RF varies with the Oscillator mode selected (typically between 2 M $\Omega$  to 10 M $\Omega$ ).
  - **3:** An additional parallel feedback resistor (RP) may be required for proper ceramic resonator operation.

### 5.2.1.3 Oscillator Start-up Timer (OST)

If the oscillator module is configured for LP, XT or HS modes, the Oscillator Start-up Timer (OST) counts 1024 oscillations from OSC1. This occurs following a Power-on Reset (POR) and when the Power-up Timer (PWRT) has expired (if configured), or a wake-up from Sleep. During this time, the program counter does not increment and program execution is suspended. The OST ensures that the oscillator circuit, using a quartz crystal resonator or ceramic resonator, has started and is providing a stable system clock to the oscillator module.

In order to minimize latency between external oscillator start-up and code execution, the Two-Speed Clock Start-up mode can be selected (see **Section 5.4** "Two-Speed Clock Start-up Mode").

### 5.2.1.4 4X PLL

The oscillator module contains a 4X PLL that can be used with both external and internal clock sources to provide a system clock source. The input frequency for the 4X PLL must fall within specifications. See the PLL Clock Timing specifications in the applicable Electrical Specifications Chapter.

The 4X PLL may be enabled for use by one of two methods:


- Program the PLLEN bit in Configuration Word 2 to a '1'.
- 2. Write the SPLLEN bit in the OSCCON register to a '1'. If the PLLEN bit in Configuration Word 2 is programmed to a '1', then the value of SPLLEN is ignored.

#### 5.2.1.5 TIMER1 Oscillator

The Timer1 Oscillator is a separate crystal oscillator that is associated with the Timer1 peripheral. It is optimized for timekeeping operations with a 32.768 kHz crystal connected between the T1OSO and T1OSI device pins.

The Timer1 Oscillator can be used as an alternate system clock source and can be selected during run-time using clock switching. Refer to **Section 5.3 "Clock Switching"** for more information.

FIGURE 5-5: QUARTZ CRYSTAL OPERATION (TIMER1 OSCILLATOR)



- Note 1: Quartz crystal characteristics vary according to type, package and manufacturer. The user should consult the manufacturer data sheets for specifications and recommended application.
  - **2:** Always verify oscillator performance over the VDD and temperature range that is expected for the application.
  - **3:** For oscillator design assistance, reference the following Microchip Applications Notes:
    - AN826, "Crystal Oscillator Basics and Crystal Selection for rfPIC<sup>®</sup> and PIC<sup>®</sup> Devices" (DS00826)
    - AN849, "Basic PIC® Oscillator Design" (DS00849)
    - AN943, "Practical PIC® Oscillator Analysis and Design" (DS00943)
    - AN949, "Making Your Oscillator Work" (DS00949)
    - TB097, "Interfacing a Micro Crystal MS1V-T1K 32.768 kHz Tuning Fork Crystal to a PIC16F690/SS" (DS91097)
    - AN1288, "Design Practices for Low-Power External Oscillators" (DS01288)


#### 5.2.1.6 External RC Mode

The external Resistor-Capacitor (RC) modes support the use of an external RC circuit. This allows the designer maximum flexibility in frequency choice while keeping costs to a minimum when clock accuracy is not required.

The RC circuit connects to OSC1. OSC2/CLKOUT is available for general purpose I/O or CLKOUT. The function of the OSC2/CLKOUT pin is determined by the state of the CLKOUTEN bit in Configuration Word 1.

Figure 5-6 shows the external RC mode connections.

FIGURE 5-6: EXTERNAL RC MODES



The RC oscillator frequency is a function of the supply voltage, the resistor (REXT) and capacitor (CEXT) values and the operating temperature. Other factors affecting the oscillator frequency are:

- · threshold voltage variation
- · component tolerances
- · packaging variations in capacitance

The user also needs to take into account variation due to tolerance of external RC components used.

#### 5.2.2 INTERNAL CLOCK SOURCES

The device may be configured to use the internal oscillator block as the system clock by performing one of the following actions:

- Program the FOSC<2:0> bits in Configuration
  Word 1 to select the INTOSC clock source, which
  will be used as the default system clock upon a
  device Reset.
- Write the SCS<1:0> bits in the OSCCON register to switch the system clock source to the internal oscillator during run-time. See Section 5.3 "Clock Switching" for more information.

In **INTOSC** mode, OSC1/CLKIN is available for general purpose I/O. OSC2/CLKOUT is available for general purpose I/O or CLKOUT.

The function of the OSC2/CLKOUT pin is determined by the state of the CLKOUTEN bit in Configuration Word 1.

The internal oscillator block has two independent oscillators and a dedicated Phase-Lock Loop, HFPLL that can produce one of three internal system clock sources.

- The HFINTOSC (High-Frequency Internal Oscillator) is factory calibrated and operates at 16 MHz. The HFINTOSC source is generated from the 500 kHz MFINTOSC source and the dedicated Phase-Lock Loop, HFPLL. The frequency of the HFINTOSC can be user-adjusted via software using the OSCTUNE register (Register 5-3).
- 2. The **MFINTOSC** (Medium-Frequency Internal Oscillator) is factory calibrated and operates at 500 kHz. The frequency of the MFINTOSC can be user-adjusted via software using the OSCTUNE register (Register 5-3).
- The LFINTOSC (Low-Frequency Internal Oscillator) is uncalibrated and operates at 31 kHz.

#### 5.2.2.1 HFINTOSC

The High-Frequency Internal Oscillator (HFINTOSC) is a factory calibrated 16 MHz internal clock source. The frequency of the HFINTOSC can be altered via software using the OSCTUNE register (Register 5-3).

The output of the HFINTOSC connects to a postscaler and multiplexer (see Figure 5-1). One of nine frequencies derived from the HFINTOSC can be selected via software using the IRCF<3:0> bits of the OSCCON register. See Section 5.2.2.7 "Internal Oscillator Clock Switch Timing" for more information.

The HFINTOSC is enabled by:

- Configure the IRCF<3:0> bits of the OSCCON register for the desired HF frequency, and
- FOSC<2:0> = 100, or
- Set the System Clock Source (SCS) bits of the OSCCON register to '1x'.

The High-Frequency Internal Oscillator Ready bit (HFIOFR) of the OSCSTAT register indicates when the HFINTOSC is running and can be utilized.

The High-Frequency Internal Oscillator Status Locked bit (HFIOFL) of the OSCSTAT register indicates when the HFINTOSC is running within 2% of its final value.

The High-Frequency Internal Oscillator Status Stable bit (HFIOFS) of the OSCSTAT register indicates when the HFINTOSC is running within 0.5% of its final value.

#### 5.2.2.2 MFINTOSC

The Medium-Frequency Internal Oscillator (MFINTOSC) is a factory calibrated 500 kHz internal clock source. The frequency of the MFINTOSC can be altered via software using the OSCTUNE register (Register 5-3).

The output of the MFINTOSC connects to a postscaler and multiplexer (see Figure 5-1). One of nine frequencies derived from the MFINTOSC can be selected via software using the IRCF<3:0> bits of the OSCCON register. See Section 5.2.2.7 "Internal Oscillator Clock Switch Timing" for more information.

The MFINTOSC is enabled by:

- Configure the IRCF<3:0> bits of the OSCCON register for the desired HF frequency, and
- FOSC<2:0> = 100, or
- Set the System Clock Source (SCS) bits of the OSCCON register to '1x'

The Medium-Frequency Internal Oscillator Ready bit (MFIOFR) of the OSCSTAT register indicates when the MFINTOSC is running and can be utilized.

## 5.2.2.3 Internal Oscillator Frequency Adjustment

The 500 kHz internal oscillator is factory calibrated. This internal oscillator can be adjusted in software by writing to the OSCTUNE register (Register 5-3). Since the HFINTOSC and MFINTOSC clock sources are derived from the 500 kHz internal oscillator a change in the OSCTUNE register value will apply to both.

The default value of the OSCTUNE register is '0'. The value is a 5-bit two's complement number. A value of 0Fh will provide an adjustment to the maximum frequency. A value of 10h will provide an adjustment to the minimum frequency.

When the OSCTUNE register is modified, the oscillator frequency will begin shifting to the new frequency. Code execution continues during this shift. There is no indication that the shift has occurred.

OSCTUNE does not affect the LFINTOSC frequency. Operation of features that depend on the LFINTOSC clock source frequency, such as the Power-up Timer (PWRT), Watchdog Timer (WDT), Fail-Safe Clock Monitor (FSCM) and peripherals, are *not* affected by the change in frequency.

#### 5.2.2.4 LFINTOSC

The Low-Frequency Internal Oscillator (LFINTOSC) is an uncalibrated 31 kHz internal clock source.

The output of the LFINTOSC connects to a postscaler and multiplexer (see Figure 5-1). Select 31 kHz, via software, using the IRCF<3:0> bits of the OSCCON register. See **Section 5.2.2.7** "Internal Oscillator Clock Switch Timing" for more information. The LFINTOSC is also the frequency for the Power-up Timer (PWRT), Watchdog Timer (WDT) and Fail-Safe Clock Monitor (FSCM).

The LFINTOSC is enabled by selecting 31 kHz (IRCF<3:0> bits of the OSCCON register = 000) as the system clock source (SCS bits of the OSCCON register = 1x), or when any of the following are enabled:

- Configure the IRCF<3:0> bits of the OSCCON register for the desired LF frequency, and
- FOSC<2:0> = 100, or
- Set the System Clock Source (SCS) bits of the OSCCON register to '1x'

Peripherals that use the LFINTOSC are:

- Power-up Timer (PWRT)
- Watchdog Timer (WDT)
- Fail-Safe Clock Monitor (FSCM)

The Low-Frequency Internal Oscillator Ready bit (LFIOFR) of the OSCSTAT register indicates when the LFINTOSC is running and can be utilized.

## 5.2.2.5 Internal Oscillator Frequency Selection

The system clock speed can be selected via software using the Internal Oscillator Frequency Select bits IRCF<3:0> of the OSCCON register.

The output of the 16 MHz HFINTOSC and 31 kHz LFINTOSC connects to a postscaler and multiplexer (see Figure 5-1). The Internal Oscillator Frequency Select bits IRCF<3:0> of the OSCCON register select the frequency output of the internal oscillators. One of the following frequencies can be selected via software:

- 32 MHz (requires 4X PLL)
- 16 MHz
- 8 MHz
- 4 MHz
- 2 MHz
- 1 MHz500 kHz (Default after Reset)
- 250 kHz
- 125 kHz
- 62.5 kHz
- 31.25 kHz
- 31 kHz (LFINTOSC)

Note: Following any Reset, the IRCF<3:0> bits of the OSCCON register are set to '0111' and the frequency selection is set to 500 kHz. The user can modify the IRCF bits to select a different frequency.

The IRCF<3:0> bits of the OSCCON register allow duplicate selections for some frequencies. These duplicate choices can offer system design trade-offs. Lower power consumption can be obtained when changing oscillator sources for a given frequency. Faster transition times can be obtained between frequency changes that use the same oscillator source.

## 5.2.2.6 32 MHz Internal Oscillator Frequency Selection

The Internal Oscillator Block can be used with the 4X PLL associated with the External Oscillator Block to produce a 32 MHz internal system clock source. The following settings are required to use the 32 MHz internal clock source:

- The FOSC bits in Configuration Word 1 must be set to use the INTOSC source as the device system clock (FOSC<2:0> = 100).
- The SCS bits in the OSCCON register must be cleared to use the clock determined by FOSC<2:0> in Configuration Word 1 (SCS<1:0> = 00).
- The IRCF bits in the OSCCON register must be set to the 8 MHz HFINTOSC set to use (IRCF<3:0> = 1110).
- The SPLLEN bit in the OSCCON register must be set to enable the 4xPLL, or the PLLEN bit of the Configuration Word 2 must be programmed to a '1'.

Note: When using the PLLEN bit of the Configuration Word 2, the 4xPLL cannot be disabled by software and the 8 MHz HFINTOSC option will no longer be available.

The 4xPLL is not available for use with the internal oscillator when the SCS bits of the OSCCON register are set to '1x'. The SCS bits must be set to '00' to use the 4xPLL with the internal oscillator.

## 5.2.2.7 Internal Oscillator Clock Switch Timing


When switching between the HFINTOSC, MFINTOSC and the LFINTOSC, the new oscillator may already be shut down to save power (see Figure 5-7). If this is the case, there is a delay after the IRCF<3:0> bits of the OSCCON register are modified before the frequency selection takes place. The OSCSTAT register will reflect the current active status of the HFINTOSC, MFINTOSC and LFINTOSC oscillators. The sequence of a frequency selection is as follows:

- IRCF<3:0> bits of the OSCCON register are modified.
- If the new clock is shut down, a clock start-up delay is started.
- Clock switch circuitry waits for a falling edge of the current clock.
- The current clock is held low and the clock switch circuitry waits for a rising edge in the new clock.
- The new clock is now active.
- 6. The OSCSTAT register is updated as required.
- 7. Clock switch is complete.

See Figure 5-7 for more details.

If the internal oscillator speed is switched between two clocks of the same source, there is no start-up delay before the new frequency is selected. Clock switching time delays are shown in Table 5-1.

Start-up delay specifications are located in the oscillator tables in the applicable Electrical Specifications Chapter.



### 5.3 Clock Switching

The system clock source can be switched between external and internal clock sources via software using the System Clock Select (SCS) bits of the OSCCON register. The following clock sources can be selected using the SCS bits:

- Default system oscillator determined by FOSC bits in Configuration Word 1
- · Timer1 32 kHz crystal oscillator
- Internal Oscillator Block (INTOSC)

## 5.3.1 SYSTEM CLOCK SELECT (SCS) BITS

The System Clock Select (SCS) bits of the OSCCON register selects the system clock source that is used for the CPU and peripherals.

- When the SCS bits of the OSCCON register = 00, the system clock source is determined by value of the FOSC<2:0> bits in the Configuration Word 1.
- When the SCS bits of the OSCCON register = 01, the system clock source is the Timer1 oscillator.
- When the SCS bits of the OSCCON register = 1x, the system clock source is chosen by the internal oscillator frequency selected by the IRCF<3:0> bits of the OSCCON register. After a Reset, the SCS bits of the OSCCON register are always cleared.

Note: Any automatic clock switch, which may occur from Two-Speed Start-up or Fail-Safe Clock Monitor, does not update the SCS bits of the OSCCON register. The user can monitor the OSTS bit of the OSCSTAT register to determine the current system clock source.

When switching between clock sources, a delay is required to allow the new clock to stabilize. These oscillator delays are shown in Table 5-1.

## 5.3.2 OSCILLATOR START-UP TIME-OUT STATUS (OSTS) BIT

The Oscillator Start-up Time-out Status (OSTS) bit of the OSCSTAT register indicates whether the system clock is running from the external clock source, as defined by the FOSC<2:0> bits in the Configuration Word 1, or from the internal clock source. In particular, OSTS indicates that the Oscillator Start-up Timer (OST) has timed out for LP, XT or HS modes. The OST does not reflect the status of the Timer1 oscillator.

#### 5.3.3 TIMER1 OSCILLATOR

The Timer1 oscillator is a separate crystal oscillator associated with the Timer1 peripheral. It is optimized for timekeeping operations with a 32.768 kHz crystal connected between the T1OSO and T1OSI device pins.

The Timer1 oscillator is enabled using the T1OSCEN control bit in the T1CON register. See **Section 21.0** "Timer1 Module with Gate Control" for more information about the Timer1 peripheral.

## 5.3.4 TIMER1 OSCILLATOR READY (T1OSCR) BIT

The user must ensure that the Timer1 oscillator is ready to be used before it is selected as a system clock source. The Timer1 Oscillator Ready (T1OSCR) bit of the OSCSTAT register indicates whether the Timer1 oscillator is ready to be used. After the T1OSCR bit is set, the SCS bits can be configured to select the Timer1 oscillator.

## 5.4 Two-Speed Clock Start-up Mode

Two-Speed Start-up mode provides additional power savings by minimizing the latency between external oscillator start-up and code execution. In applications that make heavy use of the Sleep mode, Two-Speed Start-up will remove the external oscillator start-up time from the time spent awake and can reduce the overall power consumption of the device. This mode allows the application to wake-up from Sleep, perform a few instructions using the INTOSC internal oscillator block as the clock source and go back to Sleep without waiting for the external oscillator to become stable.

Two-Speed Start-up provides benefits when the oscillator module is configured for LP, XT or HS modes. The Oscillator Start-up Timer (OST) is enabled for these modes and must count 1024 oscillations before the oscillator can be used as the system clock source.

If the oscillator module is configured for any mode other than LP, XT or HS mode, then Two-Speed Start-up is disabled. This is because the external clock oscillator does not require any stabilization time after POR or an exit from Sleep.

If the OST count reaches 1024 before the device enters Sleep mode, the OSTS bit of the OSCSTAT register is set and program execution switches to the external oscillator. However, the system may never operate from the external oscillator if the time spent awake is very short.

Note:

Executing a SLEEP instruction will abort the oscillator start-up time and will cause the OSTS bit of the OSCSTAT register to remain clear.

## 5.4.1 TWO-SPEED START-UP MODE CONFIGURATION

Two-Speed Start-up mode is configured by the following settings:

- IESO (of the Configuration Word 1) = 1; Internal/External Switchover bit (Two-Speed Start-up mode enabled).
- SCS (of the OSCCON register) = 00.
- FOSC<2:0> bits in the Configuration Word 1 configured for LP, XT or HS mode.

Two-Speed Start-up mode is entered after:

- Power-on Reset (POR) and, if enabled, after Power-up Timer (PWRT) has expired, or
- · Wake-up from Sleep.

TABLE 5-1: OSCILLATOR SWITCHING DELAYS

| ., .,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,, | , • • •   | , , , , , , , , , , , , , , , , , , ,           |                                  |
|---|---|---|----------------------------------|
| Switch From                             | Switch To   | Frequency                                       | Oscillator Delay                 |
| Sleep/POR                               | LFINTOSC <sup>(1)</sup> MFINTOSC <sup>(1)</sup> HFINTOSC <sup>(1)</sup> | 31 kHz<br>31.25 kHz-500 kHz<br>31.25 kHz-16 MHz | Oscillator Warm-up Delay (TWARM) |
| Sleep/POR                               | EC, RC <sup>(1)</sup>   | DC – 32 MHz                                     | 2 cycles                         |
| LFINTOSC                                | EC, RC <sup>(1)</sup>   | DC – 32 MHz                                     | 1 cycle of each                  |
| Sleep/POR                               | Timer1 Oscillator<br>LP, XT, HS <sup>(1)</sup>                          | 32 kHz-20 MHz                                   | 1024 Clock Cycles (OST)          |
| Any clock source                        | MFINTOSC <sup>(1)</sup><br>HFINTOSC <sup>(1)</sup>                      | 31.25 kHz-500 kHz<br>31.25 kHz-16 MHz           | 2 μs (approx.)                   |
| Any clock source                        | LFINTOSC <sup>(1)</sup>   | 31 kHz  | 1 cycle of each                  |
| Any clock source                        | Timer1 Oscillator   | 32 kHz  | 1024 Clock Cycles (OST)          |
| PLL inactive                            | PLL active  | 16-32 MHz                                       | 2 ms (approx.)                   |

Note 1: PLL inactive.


## 5.4.2 TWO-SPEED START-UP SEQUENCE

- 1. Wake-up from Power-on Reset or Sleep.
- 2. Instructions begin execution by the internal oscillator at the frequency set in the IRCF<3:0> bits of the OSCCON register.
- 3. OST enabled to count 1024 clock cycles.
- OST timed out, wait for falling edge of the internal oscillator.
- 5. OSTS is set.
- 6. System clock held low until the next falling edge of new clock (LP, XT or HS mode).
- System clock is switched to external clock source.

## 5.4.3 CHECKING TWO-SPEED CLOCK STATUS

Checking the state of the OSTS bit of the OSCSTAT register will confirm if the microcontroller is running from the external clock source, as defined by the FOSC<2:0> bits in the Configuration Word 1, or the internal oscillator.


## FIGURE 5-8: TWO-SPEED START-UP



#### 5.5 Fail-Safe Clock Monitor

The Fail-Safe Clock Monitor (FSCM) allows the device to continue operating should the external oscillator fail. The FSCM can detect oscillator failure any time after the Oscillator Start-up Timer (OST) has expired. The FSCM is enabled by setting the FCMEN bit in the Configuration Word 1. The FSCM is applicable to all external Oscillator modes (LP, XT, HS, EC, Timer1 oscillator and RC).

FIGURE 5-9: FSCM BLOCK DIAGRAM



#### 5.5.1 FAIL-SAFE DETECTION

The FSCM module detects a failed oscillator by comparing the external oscillator to the FSCM sample clock. The sample clock is generated by dividing the LFINTOSC by 64. See Figure 5-9. Inside the fail detector block is a latch. The external clock sets the latch on each falling edge of the external clock. The sample clock clears the latch on each rising edge of the sample clock. A failure is detected when an entire half-cycle of the sample clock elapses before the external clock goes low.

### 5.5.2 FAIL-SAFE OPERATION

When the external clock fails, the FSCM switches the device clock to an internal clock source and sets the bit flag OSFIF of the PIR2 register. Setting this flag will generate an interrupt if the OSFIE bit of the PIE2 register is also set. The device firmware can then take steps to mitigate the problems that may arise from a failed clock. The system clock will continue to be sourced from the internal clock source until the device firmware successfully restarts the external oscillator and switches back to external operation.

The internal clock source chosen by the FSCM is determined by the IRCF<3:0> bits of the OSCCON register. This allows the internal oscillator to be configured before a failure occurs.

#### 5.5.3 FAIL-SAFE CONDITION CLEARING

The Fail-Safe condition is cleared after a Reset, executing a SLEEP instruction or changing the SCS bits of the OSCCON register. When the SCS bits are changed, the OST is restarted. While the OST is running, the device continues to operate from the INTOSC selected in OSCCON. When the OST times out, the Fail-Safe condition is cleared and the device will be operating from the external clock source. The Fail-Safe condition must be cleared before the OSFIF flag can be cleared.


#### 5.5.4 RESET OR WAKE-UP FROM SLEEP

The FSCM is designed to detect an oscillator failure after the Oscillator Start-up Timer (OST) has expired. The OST is used after waking up from Sleep and after any type of Reset. The OST is not used with the EC or RC clock modes so that the FSCM will be active as soon as the Reset or wake-up has completed. When the FSCM is enabled, the Two-Speed Start-up is also enabled. Therefore, the device will always be executing code while the OST is operating.

Note: Due to the wide range of oscillator start-up times, the Fail-Safe circuit is not active during oscillator start-up (i.e., after exiting Reset or Sleep). After an appropriate amount of time, the user should check the Status bits in the OSCSTAT register to verify the oscillator start-up and that the system clock switchover has successfully completed.



this example have been chosen for clarity.



## 5.6 Oscillator Control Registers

### REGISTER 5-1: OSCCON: OSCILLATOR CONTROL REGISTER

| R/W-0/0 | R/W-0/0   | R/W-1/1 | R/W-1/1 | R/W-1/1 | U-0   | R/W-0/0 | R/W-0/0 |
|---------|-----------|---------|---------|---------|-------|---------|---------|
| SPLLEN  | IRCF<3:0> |         |         |         | _     | SCS     | <1:0>   |
| bit 7   |           |         |         |         | bit 0 |         |         |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown

'1' = Bit is set '0' = Bit is cleared

U = Unimplemented bit, read as '0'

-n/n = Value at POR and BOR/Value at all other Resets

bit 7 **SPLLEN:** Software PLL Enable bit

If PLLEN in Configuration Word 1 = 1:

SPLLEN bit is ignored. 4x PLL is always enabled (subject to oscillator requirements)

If PLLEN in Configuration Word 1 = 0:

1 = 4x PLL is enabled 0 = 4x PLL is disabled

bit 6-3 IRCF<3:0>: Internal Oscillator Frequency Select bits

000x = 31 kHz LF 0010 = 31.25 kHz MF  $0011 = 31.25 \text{ kHz HF}^{(1)}$  0100 = 62.5 kHz MF0101 = 125 kHz MF

0110 **= 250** kHz MF

0111 = 500 kHz MF (default upon Reset)

1000 = 125 kHz HF<sup>(1)</sup> 1001 = 250 kHz HF<sup>(1)</sup> 1010 = 500 kHz HF<sup>(1)</sup> 1011 = 1 MHz HF 1100 = 2 MHz HF

1100 = 2 MHz HF 1101 = 4 MHz HF

1110 = 8 MHz or 32 MHz HF(see Section 5.2.2.1 "HFINTOSC")

1111 = 16 MHz HF

bit 2 **Unimplemented:** Read as '0'

bit 1-0 SCS<1:0>: System Clock Select bits

1x = Internal oscillator block

01 = Timer1 oscillator

00 = Clock determined by FOSC<2:0> in Configuration Word 1.

Note 1: Duplicate frequency derived from HFINTOSC.

### REGISTER 5-2: OSCSTAT: OSCILLATOR STATUS REGISTER

| R-1/q  | R-0/q | R-q/q | R-0/q  | R-0/q  | R-q/q  | R-0/0  | R-0/q  |
|--------|-------|-------|--------|--------|--------|--------|--------|
| T10SCR | PLLR  | OSTS  | HFIOFR | HFIOFL | MFIOFR | LFIOFR | HFIOFS |
| bit 7  |       |       |        |        |        |        | bit 0  |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared q = Conditional

bit 7 T10SCR: Timer1 Oscillator Ready bit

<u>If T10SCEN = 1</u>:

1 = Timer1 oscillator is ready

0 = Timer1 oscillator is not ready If T1OSCEN = 0:

1 = Timer1 clock source is always ready

bit 6 PLLR 4x PLL Ready bit

1 = 4x PLL is ready

0 = 4x PLL is not ready

bit 5 OSTS: Oscillator Start-up Time-out Status bit

1 = Running from the clock defined by the FOSC<2:0> bits of the Configuration Word 1

0 = Running from an internal oscillator (FOSC<2:0> = 100)

bit 4 HFIOFR: High-Frequency Internal Oscillator Ready bit

1 = HFINTOSC is ready
0 = HFINTOSC is not ready

bit 3 **HFIOFL:** High-Frequency Internal Oscillator Locked bit

1 = HFINTOSC is at least 2% accurate 0 = HFINTOSC is not 2% accurate

bit 2 MFIOFR: Medium-Frequency Internal Oscillator Ready bit

1 = MFINTOSC is ready
0 = MFINTOSC is not ready

bit 1 LFIOFR: Low-Frequency Internal Oscillator Ready bit

1 = LFINTOSC is ready 0 = LFINTOSC is not ready

bit 0 HFIOFS: High-Frequency Internal Oscillator Stable bit

1 = HFINTOSC is at least 0.5% accurate 0 = HFINTOSC is not 0.5% accurate

## REGISTER 5-3: OSCTUNE: OSCILLATOR TUNING REGISTER

| U-0   | U-0 | R/W-0/0 | R/W-0/0 | R/W-0/0 | R/W-0/0 | R/W-0/0 | R/W-0/0 |
|-------|-----|---------|---------|---------|---------|---------|---------|
| _     | _   |         |         | TUN     | <5:0>   |         |         |
| bit 7 |     |         |         |         |         |         | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-6 **Unimplemented:** Read as '0'

bit 5-0 **TUN<4:0>:** Frequency Tuning bits

011111 = Maximum frequency

011110 =

•

•

000001 =

000000 = Oscillator module is running at the factory-calibrated frequency.

111111 =

•

•

100000 = Minimum frequency

### TABLE 5-2: SUMMARY OF REGISTERS ASSOCIATED WITH CLOCK SOURCES

| Name    | Bit 7  | Bit 6  | Bit 5 | Bit 4               | Bit 3  | Bit 2  | Bit 1  | Bit 0                 | Register on Page |
|---------|--------|--------|-------|---------------------|--------|--------|--------|-----------------------|------------------|
| OSCCON  | SPLLEN |        | IRCF  | IRCF<3:0> — SCS<1:0 |        |        |        |                       | 81               |
| OSCSTAT | T10SCR | PLLR   | OSTS  | HFIOFR              | HFIOFL | MFIOFR | LFIOFR | HFIOFS                | 82               |
| OSCTUNE | _      | _      |       |                     | TUN    | <5:0>  |        |                       | 83               |
| PIE2    | OSFIE  | C2IE   | C1IE  | EEIE                | BCLIE  | LCDIE  | _      | CCP2IE <sup>(1)</sup> | 100              |
| PIR2    | OSFIF  | C2IF   | C1IF  | EEIF                | BCLIF  | LCDIF  | _      | CCP2IF <sup>(1)</sup> | 103              |
| T1CON   | TMR1C  | S<1:0> | T1CKP | T1CKPS<1:0> T1OSCE  |        |        | _      | TMR10N                | 203              |

**Legend:** — = unimplemented location, read as '0'. Shaded cells are not used by clock sources.

Note 1: PIC16F1934 only.

## TABLE 5-3: SUMMARY OF CONFIGURATION WORD WITH CLOCK SOURCES

| Name    | Bits | Bit -/7 | Bit -/6 | Bit 13/5 | Bit 12/4              | Bit 11/3 | Bit 10/2  | Bit 9/1 | Bit 8/0 | Register on Page |
|---------|------|---------|---------|----------|-----------------------|----------|-----------|---------|---------|------------------|
| 0015104 | 13:8 | _       | _       | FCMEN    | IESO                  | CLKOUTEN | BOREI     | N<1:0>  | CPD     |                  |
| CONFIG1 | 7:0  | CP      | MCLRE   | PWRTE    | WDTE                  | E<1:0>   | FOSC<2:0> |         |         | 62               |
| CONFICE | 13:8 | _       | _       | LVP      | DEBUG                 | _        | BORV      | STVREN  | PLLEN   | 0.4              |
| CONFIG2 | 7:0  | _       | _       | VCAPEN   | N<1:0> <sup>(1)</sup> | _        | _         | WRT     | <1:0>   | 64               |

Legend: — = unimplemented location, read as '0'. Shaded cells are not used by clock sources.

Note 1: PIC16F1934/6/7 only.

NOTES:

## 6.0 RESETS


There are multiple ways to reset this device:

- Power-on Reset (POR)
- · Brown-out Reset (BOR)
- MCLR Reset
- · WDT Reset
- RESET instruction
- · Stack Overflow
- · Stack Underflow
- Programming mode exit

To allow VDD to stabilize, an optional power-up timer can be enabled to extend the Reset time after a BOR or POR event.

A simplified block diagram of the On-Chip Reset Circuit is shown in Figure 6-1.

FIGURE 6-1: SIMPLIFIED BLOCK DIAGRAM OF ON-CHIP RESET CIRCUIT



### 6.1 Power-on Reset (POR)

The POR circuit holds the device in Reset until VDD has reached an acceptable level for minimum operation. Slow rising VDD, fast operating speeds or analog performance may require greater than minimum VDD. The PWRT, BOR or MCLR features can be used to extend the start-up period until all device operation conditions have been met.

### 6.1.1 POWER-UP TIMER (PWRT)

The Power-up Timer provides a nominal 64 ms timeout on POR or Brown-out Reset.

The device is held in Reset as long as PWRT is active. The PWRT delay allows additional time for the VDD to rise to an acceptable level. The Power-up Timer is enabled by clearing the PWRTE bit in Configuration Word 1.

The Power-up Timer starts after the release of the POR and BOR.

For additional information, refer to Application Note AN607, "Power-up Trouble Shooting" (DS00607).

## 6.2 Brown-Out Reset (BOR)

The BOR circuit holds the device in Reset when VDD reaches a selectable minimum level. Between the POR and BOR, complete voltage range coverage for execution protection can be implemented.

The Brown-out Reset module has four operating modes controlled by the BOREN<1:0> bits in Configuration Word 1. The four operating modes are:

- · BOR is always on
- · BOR is off when in Sleep
- · BOR is controlled by software
- · BOR is always off

Refer to Table 6-3 for more information.

The Brown-out Reset voltage level is selectable by configuring the BORV bit in Configuration Word 2.

A VDD noise rejection filter prevents the BOR from triggering on small events. If VDD falls below VBOR for a duration greater than parameter TBORDC, the device will reset. See Figure 6-2 for more information.

TABLE 6-1: BOR OPERATING MODES

| BOREN<1:0> | SBOREN | Device Mode | BOR Mode | Device Operation upon release of POR  Device Operation up wake- up fro |                         |
|------------|--------|-------------|----------|--|-------------------------|
| 11         | х      | Х           | Active   | Waits for B  | OR ready <sup>(1)</sup> |
| 1.0        | 77     | Awake       | Active   | Waits for BOR ready  |                         |
| 10         | X      | Sleep       | Disabled |  |                         |
| 0.1        | 1      | Х           | Active   | Begins immediately   |                         |
| 01         | 0      | ^           | Disabled | Begins immediately   |                         |
| 00         | Х      | X           | Disabled | Begins im  | nmediately              |

**Note 1:** Even though this case specifically waits for the BOR, the BOR is already operating, so there is no delay in start-up.

#### 6.2.1 BOR IS ALWAYS ON

When the BOREN bits of Configuration Word 1 are set to '11', the BOR is always on. The device start-up will be delayed until the BOR is ready and VDD is higher than the BOR threshold.

BOR protection is active during Sleep. The BOR does not delay wake-up from Sleep.

## 6.2.2 BOR IS OFF IN SLEEP

When the BOREN bits of Configuration Word 1 are set to '10', the BOR is on, except in Sleep. The device start-up will be delayed until the BOR is ready and VDD is higher than the BOR threshold.

BOR protection is not active during Sleep. The device wake-up will be delayed until the BOR is ready.


#### 6.2.3 BOR CONTROLLED BY SOFTWARE

When the BOREN bits of Configuration Word 1 are set to '01', the BOR is controlled by the SBOREN bit of the BORCON register. The device start-up is not delayed by the BOR ready condition or the VDD level.

BOR protection begins as soon as the BOR circuit is ready. The status of the BOR circuit is reflected in the BORRDY bit of the BORCON register.

BOR protection is unchanged by Sleep.

## FIGURE 6-2: BROWN-OUT SITUATIONS



#### REGISTER 6-1: BORCON: BROWN-OUT RESET CONTROL REGISTER

| R/W-1/u | U-0 | U-0 | U-0 | U-0 | U-0 | U-0 | R-q/u  |
|---------|-----|-----|-----|-----|-----|-----|--------|
| SBOREN  | _   | _   | _   | _   | _   | _   | BORRDY |
| bit 7   | •   | •   | •   | •   | •   | •   | bit 0  |

| Legend:              |                      |   |
|----------------------|----------------------|---|
| R = Readable bit     | W = Writable bit     | U = Unimplemented bit, read as '0'                    |
| u = Bit is unchanged | x = Bit is unknown   | -n/n = Value at POR and BOR/Value at all other Resets |
| '1' = Bit is set     | '0' = Bit is cleared | q = Value depends on condition                        |

bit 7 SBOREN: Software Brown-out Reset Enable bit

If BOREN <1:0> in Configuration Word  $1 \neq 01$ :

SBOREN is read/write, but has no effect on the BOR.

If BOREN <1:0> in Configuration Word 1 = 01:

1 = BOR Enabled

0 = BOR Disabled

bit 6-1 **Unimplemented:** Read as '0'

bit 0 BORRDY: Brown-out Reset Circuit Ready Status bit

1 = The Brown-out Reset circuit is active

0 = The Brown-out Reset circuit is inactive

### 6.3 MCLR

The MCLR is an optional external input that can reset the device. The MCLR function is controlled by the MCLRE bit of Configuration Word 1 and the LVP bit of Configuration Word 2 (Table 6-2).

TABLE 6-2: MCLR CONFIGURATION

| MCLRE | LVP | MCLR     |
|-------|-----|----------|
| 0     | 0   | Disabled |
| 1     | 0   | Enabled  |
| x     | 1   | Enabled  |

## 6.3.1 MCLR ENABLED

When MCLR is enabled and the pin is held low, the device is held in Reset. The MCLR pin is connected to VDD through an internal weak pull-up.

The device has a noise filter in the MCLR Reset path. The filter will detect and ignore small pulses.

### 6.3.2 MCLR DISABLED

When MCLR is disabled, the pin functions as a general purpose input and the internal weak pull-up is under software control. See Section 12.6 "PORTE Registers" for more information.

## 6.4 Watchdog Timer (WDT) Reset

The Watchdog Timer generates a Reset if the firmware does not issue a CLRWDT instruction within the time-out period. The  $\overline{10}$  and  $\overline{PD}$  bits in the STATUS register are changed to indicate the WDT Reset. See **Section 10.0** "Watchdog Timer" for more information.

#### 6.5 RESET Instruction

A RESET instruction will cause a device Reset. The RI bit in the PCON register will be set to '0'. See Table 6-4 for default conditions after a RESET instruction has occurred.

#### 6.6 Stack Overflow/Underflow Reset

The device can reset when the Stack Overflows or Underflows. The STKOVF or STKUNF bits of the PCON register indicate the Reset condition. These Resets are enabled by setting the STVREN bit in Configuration Word 2. See Section 3.4.2 "Overflow/Underflow Reset" for more information.

## 6.7 Programming Mode Exit

Upon exit of Programming mode, the device will behave as if a POR had just occurred.

### 6.8 Power-Up Timer

The Power-up Timer optionally delays device execution after a BOR or POR event. This timer is typically used to allow VDD to stabilize before allowing the device to start running.

The Power-up Timer is controlled by the PWRTE bit of Configuration Word 1.


## 6.9 Start-up Sequence

Upon the release of a POR or BOR, the following must occur before the device will begin executing:

- 1. Power-up Timer runs to completion (if enabled).
- Oscillator start-up timer runs to completion (if required for oscillator source).
- 3. MCLR must be released (if enabled).

The total time-out will vary based on oscillator configuration and Power-up Timer configuration. See Section 5.0 "Oscillator Module (With Fail-Safe Clock Monitor)" for more information.

The Power-up Timer and oscillator start-up timer run independently of MCLR Reset. If MCLR is kept low long enough, the Power-up Timer and oscillator start-up timer will expire. Upon bringing MCLR high, the device will begin execution immediately (see Figure 6-3). This is useful for testing purposes or to synchronize more than one device operating in parallel.



## 6.10 Determining the Cause of a Reset

Upon any Reset, multiple bits in the STATUS and PCON register are updated to indicate the cause of the Reset. Table 6-3 and Table 6-4 show the Reset conditions of these registers.

TABLE 6-3: RESET STATUS BITS AND THEIR SIGNIFICANCE

| STKOVF | STKUNF | RMCLR | RI | POR | BOR | то | PD | Condition                          |
|--------|--------|-------|----|-----|-----|----|----|------------------------------------|
| 0      | 0      | 1     | 1  | 0   | х   | 1  | 1  | Power-on Reset                     |
| 0      | 0      | 1     | 1  | 0   | х   | 0  | х  | Illegal, TO is set on POR          |
| 0      | 0      | 1     | 1  | 0   | х   | х  | 0  | Illegal, PD is set on POR          |
| 0      | 0      | 1     | 1  | u   | 0   | 1  | 1  | Brown-out Reset                    |
| u      | u      | u     | u  | u   | u   | 0  | u  | WDT Reset                          |
| u      | u      | u     | u  | u   | u   | 0  | 0  | WDT Wake-up from Sleep             |
| u      | u      | u     | u  | u   | u   | 1  | 0  | Interrupt Wake-up from Sleep       |
| u      | u      | 0     | u  | u   | u   | u  | u  | MCLR Reset during normal operation |
| u      | u      | 0     | u  | u   | u   | 1  | 0  | MCLR Reset during Sleep            |
| u      | u      | u     | 0  | u   | u   | u  | u  | RESET Instruction Executed         |
| 1      | u      | u     | u  | u   | u   | u  | u  | Stack Overflow Reset (STVREN = 1)  |
| u      | 1      | u     | u  | u   | u   | u  | u  | Stack Underflow Reset (STVREN = 1) |

TABLE 6-4: RESET CONDITION FOR SPECIAL REGISTERS(2)

| Condition                          | Program<br>Counter    | STATUS<br>Register | PCON<br>Register |
|------------------------------------|-----------------------|--------------------|------------------|
| Power-on Reset                     | 0000h                 | 1 1000             | 00 110x          |
| MCLR Reset during normal operation | 0000h                 | u uuuu             | uu 0uuu          |
| MCLR Reset during Sleep            | 0000h                 | 1 0uuu             | uu 0uuu          |
| WDT Reset                          | 0000h                 | 0 uuuu             | uu uuuu          |
| WDT Wake-up from Sleep             | PC + 1                | 0 0uuu             | uu uuuu          |
| Brown-out Reset                    | 0000h                 | 1 1uuu             | 00 11u0          |
| Interrupt Wake-up from Sleep       | PC + 1 <sup>(1)</sup> | 1 0uuu             | uu uuuu          |
| RESET Instruction Executed         | 0000h                 | u uuuu             | uu u0uu          |
| Stack Overflow Reset (STVREN = 1)  | 0000h                 | u uuuu             | 1u uuuu          |
| Stack Underflow Reset (STVREN = 1) | 0000h                 | u uuuu             | u1 uuuu          |

**Legend:** u = unchanged, x = unknown, - = unimplemented bit, reads as '0'.

**Note 1:** When the wake-up is due to an interrupt and Global Enable bit (GIE) is set, the return address is pushed on the stack and PC is loaded with the interrupt vector (0004h) after execution of PC + 1.

2: If a Status bit is not implemented, that bit will be read as '0'.

## 6.11 Power Control (PCON) Register

The Power Control (PCON) register contains flag bits to differentiate between a:

- Power-on Reset (POR)
- Brown-out Reset (BOR)
- Reset Instruction Reset (RI)
- Stack Overflow Reset (STKOVF)
- Stack Underflow Reset (STKUNF)
- MCLR Reset (RMCLR)

The PCON register bits are shown in Register 6-2.

### REGISTER 6-2: PCON: POWER CONTROL REGISTER

| R/W/HS-0/q | R/W/HS-0/q | U-0 | U-0 | R/W/HC-1/q | R/W/HC-1/q | R/W/HC-q/u | R/W/HC-q/u |
|------------|------------|-----|-----|------------|------------|------------|------------|
| STKOVF     | STKUNF     | -   | -   | RMCLR      | RI         | POR        | BOR        |
| bit 7      |            |     |     |            |            |            | bit 0      |

| Legend:                         |                      |   |  |  |
|---------------------------------|----------------------|---|--|--|
| HC = Bit is cleared by hardware |                      | HS = Bit is set by hardware                           |  |  |
| R = Readable bit                | W = Writable bit     | U = Unimplemented bit, read as '0'                    |  |  |
| u = Bit is unchanged            | x = Bit is unknown   | -m/n = Value at POR and BOR/Value at all other Resets |  |  |
| '1' = Bit is set                | '0' = Bit is cleared | q = Value depends on condition                        |  |  |

| bit 7   | STKOVF: Stack Overflow Flag bit  1 = A Stack Overflow occurred  0 = A Stack Overflow has not occurred or set to '0' by firmware  |
|---------|--|
| bit 6   | STKUNF: Stack Underflow Flag bit  1 = A Stack Underflow occurred  0 = A Stack Underflow has not occurred or set to '0' by firmware   |
| bit 5-4 | Unimplemented: Read as '0'   |
| bit 3   | RMCLR: MCLR Reset Flag bit   |
|         | 1 = A $\overline{\text{MCLR}}$ Reset has not occurred or set to '1' by firmware<br>0 = A $\overline{\text{MCLR}}$ Reset has occurred (set to '0' in hardware when a $\overline{\text{MCLR}}$ Reset occurs) |
| bit 2   | RI: RESET Instruction Flag bit   |
|         | 1 = A RESET instruction has not been executed or set to '1' by firmware 0 = A RESET instruction has been executed (set to '0' in hardware upon executing a RESET instruction)                              |
| bit 1   | POR: Power-on Reset Status bit   |
|         | <ul><li>1 = No Power-on Reset occurred</li><li>0 = A Power-on Reset occurred (must be set in software after a Power-on Reset occurs)</li></ul>   |
| bit 0   | BOR: Brown-out Reset Status bit  |
|         | <ul><li>1 = No Brown-out Reset occurred</li><li>0 = A Brown-out Reset occurred (must be set in software after a Power-on Reset or Brown-out Reset occurs)</li></ul>  |

TABLE 6-5: SUMMARY OF REGISTERS ASSOCIATED WITH RESETS

| Name   | Bit 7  | Bit 6  | Bit 5 | Bit 4      | Bit 3 | Bit 2 | Bit 1 | Bit 0  | Register on Page |
|--------|--------|--------|-------|------------|-------|-------|-------|--------|------------------|
| BORCON | SBOREN | _      | _     |            | _     | _     | _     | BORRDY | 87               |
| PCON   | STKOVF | STKUNF | _     | _          | RMCLR | RI    | POR   | BOR    | 91               |
| STATUS | _      | 1      | -     | TO         | PD    | Z     | DC    | С      | 29               |
| WDTCON | _      | _      |       | WDTPS<4:0> |       |       |       |        | 113              |

**Legend:** — = unimplemented location, read as '0'. Shaded cells are not used by Resets.

Note 1: Other (non Power-up) Resets include MCLR Reset and Watchdog Timer Reset during normal operation.

## 7.0 INTERRUPTS

The interrupt feature allows certain events to preempt normal program flow. Firmware is used to determine the source of the interrupt and act accordingly. Some interrupts can be configured to wake the MCU from Sleep mode.


This chapter contains the following information for Interrupts:

- Operation
- · Interrupt Latency
- · Interrupts During Sleep
- INT Pin
- · Automatic Context Saving

Many peripherals produce Interrupts. Refer to the corresponding chapters for details.

A block diagram of the interrupt logic is shown in Figure 7-1.

FIGURE 7-1: INTERRUPT LOGIC



### 7.1 Operation

Interrupts are disabled upon any device Reset. They are enabled by setting the following bits:

- · GIE bit of the INTCON register
- Interrupt Enable bit(s) for the specific interrupt event(s)
- PEIE bit of the INTCON register (if the Interrupt Enable bit of the interrupt event is contained in the PIE1, PIE2 and PIE3 registers)

The INTCON, PIR1, PIR2 and PIR3 registers record individual interrupts via interrupt flag bits. Interrupt flag bits will be set, regardless of the status of the GIE, PEIE and individual interrupt enable bits.

The following events happen when an interrupt event occurs while the GIE bit is set:

- · Current prefetched instruction is flushed
- · GIE bit is cleared
- Current Program Counter (PC) is pushed onto the stack
- Critical registers are automatically saved to the shadow registers (See Section 7.5 "Automatic Context Saving")
- · PC is loaded with the interrupt vector 0004h

The firmware within the Interrupt Service Routine (ISR) should determine the source of the interrupt by polling the interrupt flag bits. The interrupt flag bits must be cleared before exiting the ISR to avoid repeated interrupts. Because the GIE bit is cleared, any interrupt that occurs while executing the ISR will be recorded through its interrupt flag, but will not cause the processor to redirect to the interrupt vector.

The RETFIE instruction exits the ISR by popping the previous address from the stack, restoring the saved context from the shadow registers and setting the GIE bit.

For additional information on a specific interrupt's operation, refer to its peripheral chapter.

- Note 1: Individual interrupt flag bits are set, regardless of the state of any other enable bits.
  - 2: All interrupts will be ignored while the GIE bit is cleared. Any interrupt occurring while the GIE bit is clear will be serviced when the GIE bit is set again.

### 7.2 Interrupt Latency

Interrupt latency is defined as the time from when the interrupt event occurs to the time code execution at the interrupt vector begins. The latency for synchronous interrupts is 3 or 4 instruction cycles. For asynchronous interrupts, the latency is 3 to 5 instruction cycles, depending on when the interrupt occurs. See Figure 7-2 and Figure 7-3 for more details.





FIGURE 7-3: INT PIN INTERRUPT TIMING



- Note 1: INTF flag is sampled here (every Q1).
  - 2: Asynchronous interrupt latency = 3-5 TcY. Synchronous latency = 3-4 TcY, where TcY = instruction cycle time. Latency is the same whether Inst (PC) is a single cycle or a 2-cycle instruction.
  - 3: CLKOUT not available in all Oscillator modes.
  - 4: For minimum width of INT pulse, refer to AC specifications in the applicable Electrical Specifications Chapter.
  - 5: INTF is enabled to be set any time during the Q4-Q1 cycles.

## 7.3 Interrupts During Sleep

Some interrupts can be used to wake from Sleep. To wake from Sleep, the peripheral must be able to operate without the system clock. The interrupt source must have the appropriate Interrupt Enable bit(s) set prior to entering Sleep.

On waking from Sleep, if the GIE bit is also set, the processor will branch to the interrupt vector. Otherwise, the processor will continue executing instructions after the SLEEP instruction. The instruction directly after the SLEEP instruction will always be executed before branching to the ISR. Refer to Section 9.0 "Power-Down Mode (Sleep)" for more details.

### 7.4 INT Pin

The INT pin can be used to generate an asynchronous edge-triggered interrupt. This interrupt is enabled by setting the INTE bit of the INTCON register. The INTEDG bit of the OPTION\_REG register determines on which edge the interrupt will occur. When the INTEDG bit is set, the rising edge will cause the interrupt. When the INTEDG bit is clear, the falling edge will cause the interrupt. The INTF bit of the INTCON register will be set when a valid edge appears on the INT pin. If the GIE and INTE bits are also set, the processor will redirect program execution to the interrupt vector.

## 7.5 Automatic Context Saving

Upon entering an interrupt, the return PC address is saved on the stack. Additionally, the following registers are automatically saved in the Shadow registers:

- · W register
- STATUS register (except for TO and PD)
- · BSR register
- · FSR registers
- · PCLATH register

Upon exiting the Interrupt Service Routine, these registers are automatically restored. Any modifications to these registers during the ISR will be lost. If modifications to any of these registers are desired, the corresponding Shadow register should be modified and the value will be restored when exiting the ISR. The Shadow registers are available in Bank 31 and are readable and writable. Depending on the user's application, other registers may also need to be saved.

## 7.6 Interrupt Control Registers

### 7.6.1 INTCON REGISTER

The INTCON register is a readable and writable register, which contains the various enable and flag bits for TMR0 register overflow, interrupt-on-change and external INT pin interrupts.

Interrupt flag bits are set when an interrupt condition occurs, regardless of the state of its corresponding enable bit or the Global Enable bit, GIE, of the INTCON register. User software should ensure the appropriate interrupt flag bits are clear prior to enabling an interrupt.

### REGISTER 7-1: INTCON: INTERRUPT CONTROL REGISTER

| R/W-0/0 | R-0/0 |
|---------|---------|---------|---------|---------|---------|---------|-------|
| GIE     | PEIE    | TMR0IE  | INTE    | IOCIE   | TMR0IF  | INTF    | IOCIF |
| bit 7   |         |         |         |         |         |         | bit 0 |

Note:

| Legend:              |                      |   |
|----------------------|----------------------|---|
| R = Readable bit     | W = Writable bit     | U = Unimplemented bit, read as '0'                    |
| u = Bit is unchanged | x = Bit is unknown   | -n/n = Value at POR and BOR/Value at all other Resets |
| '1' = Bit is set     | '0' = Bit is cleared |   |
|                      |                      |   |

| bit 7 | GIE: Global Interrupt Enable bit  |
|-------|---|
|       | <ul><li>1 = Enables all active interrupts</li><li>0 = Disables all interrupts</li></ul>   |
| bit 6 | <b>PEIE:</b> Peripheral Interrupt Enable bit  1 = Enables all active peripheral interrupts  0 = Disables all peripheral interrupts  |
| bit 5 | <b>TMR0IE:</b> Timer0 Overflow Interrupt Enable bit  1 = Enables the Timer0 interrupt  0 = Disables the Timer0 interrupt  |
| bit 4 | INTE: INT External Interrupt Enable bit  1 = Enables the INT external interrupt  0 = Disables the INT external interrupt  |
| bit 3 | IOCIE: Interrupt-on-Change Enable bit  1 = Enables the interrupt-on-change  0 = Disables the interrupt-on-change  |
| bit 2 | <b>TMR0IF:</b> Timer0 Overflow Interrupt Flag bit  1 = TMR0 register has overflowed  0 = TMR0 register did not overflow   |
| bit 1 | INTF: INT External Interrupt Flag bit  1 = The INT external interrupt occurred  0 = The INT external interrupt did not occur  |
| bit 0 | IOCIF: Interrupt-on-Change Interrupt Flag bit  1 = When at least one of the interrupt-on-change pins changed state  0 = None of the interrupt-on-change pins have changed state |

**Note 1:** The IOCIF Flag bit is read-only and cleared when all the Interrupt-on-Change flags in the IOCBF register have been cleared by software.

## 7.6.2 PIE1 REGISTER

The PIE1 register contains the interrupt enable bits, as shown in Register 7-2.

**Note:** Bit PEIE of the INTCON register must be set to enable any peripheral interrupt.

## REGISTER 7-2: PIE1: PERIPHERAL INTERRUPT ENABLE REGISTER 1

| R/W-0/0 |
|---------|---------|---------|---------|---------|---------|---------|---------|
| TMR1GIE | ADIE    | RCIE    | TXIE    | SSPIE   | CCP1IE  | TMR2IE  | TMR1IE  |
| bit 7   |         |         |         |         |         |         | bit 0   |

| Legend:              |                      |   |
|----------------------|----------------------|---|
| R = Readable bit     | W = Writable bit     | U = Unimplemented bit, read as '0'                    |
| u = Bit is unchanged | x = Bit is unknown   | -n/n = Value at POR and BOR/Value at all other Resets |
| '1' = Bit is set     | '0' = Bit is cleared |   |

| . 2.0.0000 | 2 21.10 0.000.00  |
|------------|---|
|            |   |
| bit 7      | TMR1GIE: Timer1 Gate Interrupt Enable bit                         |
|            | 1 = Enables the Timer1 Gate Acquisition interrupt                 |
|            | 0 = Disables the Timer1 Gate Acquisition interrupt                |
| bit 6      | ADIE: A/D Converter (ADC) Interrupt Enable bit                    |
|            | 1 = Enables the ADC interrupt                                     |
|            | 0 = Disables the ADC interrupt                                    |
| bit 5      | RCIE: USART Receive Interrupt Enable bit                          |
|            | 1 = Enables the USART receive interrupt                           |
|            | 0 = Disables the USART receive interrupt                          |
| bit 4      | TXIE: USART Transmit Interrupt Enable bit                         |
|            | 1 = Enables the USART transmit interrupt                          |
|            | 0 = Disables the USART transmit interrupt                         |
| bit 3      | <b>SSPIE:</b> Synchronous Serial Port (MSSP) Interrupt Enable bit |
|            | 1 = Enables the MSSP interrupt                                    |
|            | 0 = Disables the MSSP interrupt                                   |
| bit 2      | CCP1IE: CCP1 Interrupt Enable bit                                 |
|            | 1 = Enables the CCP1 interrupt                                    |
|            | 0 = Disables the CCP1 interrupt                                   |
| bit 1      | TMR2IE: TMR2 to PR2 Match Interrupt Enable bit                    |
|            | 1 = Enables the Timer2 to PR2 match interrupt                     |
|            | 0 = Disables the Timer2 to PR2 match interrupt                    |
| bit 0      | TMR1IE: Timer1 Overflow Interrupt Enable bit                      |
|            | 1 = Enables the Timer1 overflow interrupt                         |
|            | 0 = Disables the Timer1 overflow interrupt                        |

## 7.6.3 PIE2 REGISTER

The PIE2 register contains the interrupt enable bits, as shown in Register 7-3.

**Note:** Bit PEIE of the INTCON register must be set to enable any peripheral interrupt.

## REGISTER 7-3: PIE2: PERIPHERAL INTERRUPT ENABLE REGISTER 2

| R/W-0/0 | R/W-0/0 | R/W-0/0 | R/W-0/0 | R/W-0/0 | R/W-0/0 | U-0 | R/W-0/0 |
|---------|---------|---------|---------|---------|---------|-----|---------|
| OSFIE   | C2IE    | C1IE    | EEIE    | BCLIE   | LCDIE   | _   | CCP2IE  |
| bit 7   |         |         |         |         |         |     | bit 0   |

| Legend:              |                      |   |
|----------------------|----------------------|---|
| R = Readable bit     | W = Writable bit     | U = Unimplemented bit, read as '0'                    |
| u = Bit is unchanged | x = Bit is unknown   | -n/n = Value at POR and BOR/Value at all other Resets |
| '1' = Bit is set     | '0' = Bit is cleared |   |

| bit 7 | OSFIE: Oscillator Fail Interrupt Enable bit   |
|-------|---|
|       | <ul><li>1 = Enables the Oscillator Fail interrupt</li><li>0 = Disables the Oscillator Fail interrupt</li></ul>                |
| bit 6 | C2IE: Comparator C2 Interrupt Enable bit  |
|       | <ul><li>1 = Enables the Comparator C2 interrupt</li><li>0 = Disables the Comparator C2 interrupt</li></ul>                    |
| bit 5 | C1IE: Comparator C1 Interrupt Enable bit  |
|       | <ul><li>1 = Enables the Comparator C1 interrupt</li><li>0 = Disables the Comparator C1 interrupt</li></ul>                    |
| bit 4 | <b>EEIE:</b> EEPROM Write Completion Interrupt Enable bit   |
|       | <ul><li>1 = Enables the EEPROM Write Completion interrupt</li><li>0 = Disables the EEPROM Write Completion interrup</li></ul> |
| bit 3 | BCLIE: MSSP Bus Collision Interrupt Enable bit  |
|       | <ul><li>1 = Enables the MSSP Bus Collision Interrupt</li><li>0 = Disables the MSSP Bus Collision Interrupt</li></ul>          |
| bit 2 | LCDIE: LCD Module Interrupt Enable bit  |
|       | <ul><li>1 = Enables the LCD module interrupt</li><li>0 = Disables the LCD module interrupt</li></ul>                          |
| bit 1 | Unimplemented: Read as '0'  |
| bit 0 | CCP2IE: CCP2 Interrupt Enable bit   |
|       | 1 = Enables the CCP2 interrupt  |
|       | 0 = Disables the CCP2 interrupt   |

## 7.6.4 PIE3 REGISTER

The PIE3 register contains the interrupt enable bits, as shown in Register 7-4.

**Note:** Bit PEIE of the INTCON register must be set to enable any peripheral interrupt.

## REGISTER 7-4: PIE3: PERIPHERAL INTERRUPT ENABLE REGISTER 3

| U-0   | R/W-0/0 | R/W-0/0 | R/W-0/0 | R/W-0/0 | U-0 | R/W-0/0 | U-0   |
|-------|---------|---------|---------|---------|-----|---------|-------|
| _     | CCP5IE  | CCP4IE  | CCP3IE  | TMR6IE  | _   | TMR4IE  | _     |
| bit 7 |         |         |         |         |     |         | bit 0 |

| Legend:              |                      |   |
|----------------------|----------------------|---|
| R = Readable bit     | W = Writable bit     | U = Unimplemented bit, read as '0'                    |
| u = Bit is unchanged | x = Bit is unknown   | -n/n = Value at POR and BOR/Value at all other Resets |
| '1' = Bit is set     | '0' = Bit is cleared |   |

| bit 7 | Unimplemented: Read as '0'                     |
|-------|--|
| bit 6 | CCP5IE: CCP5 Interrupt Enable bit              |
|       | 1 = Enables the CCP5 interrupt                 |
|       | 0 = Disables the CCP5 interrupt                |
| bit 5 | CCP4IE: CCP4 Interrupt Enable bit              |
|       | 1 = Enables the CCP4 interrupt                 |
|       | 0 = Disables the CCP4 interrupt                |
| bit 4 | CCP3IE: CCP3 Interrupt Enable bit              |
|       | 1 = Enables the CCP3 interrupt                 |
|       | 0 = Disables the CCP3 interrupt                |
| bit 3 | TMR6IE: TMR6 to PR6 Match Interrupt Enable bit |
|       | 1 = Enables the TMR6 to PR6 Match interrupt    |
|       | 0 = Disables the TMR6 to PR6 Match interrupt   |
| bit 2 | Unimplemented: Read as '0'                     |
| bit 1 | TMR4IE: TMR4 to PR4 Match Interrupt Enable bit |
|       | 1 = Enables the TMR4 to PR4 Match interrupt    |
|       | 0 = Disables the TMR4 to PR4 Match interrupt   |
| bit 0 | Unimplemented: Read as '0'                     |

### 7.6.5 PIR1 REGISTER

The PIR1 register contains the interrupt flag bits, as shown in Register 7-5.

Interrupt flag bits are set when an interrupt condition occurs, regardless of the state of its corresponding enable bit or the Global Enable bit, GIE, of the INTCON register. User software should ensure the appropriate interrupt flag bits are clear prior to enabling an interrupt.

## REGISTER 7-5: PIR1: PERIPHERAL INTERRUPT REQUEST REGISTER 1

| R/W-0/0 | R/W-0/0 | R-0/0 | R-0/0 | R/W-0/0 | R/W-0/0 | R/W-0/0 | R/W-0/0 |
|---------|---------|-------|-------|---------|---------|---------|---------|
| TMR1GIF | ADIF    | RCIF  | TXIF  | SSPIF   | CCP1IF  | TMR2IF  | TMR1IF  |
| bit 7   |         |       |       |         |         |         | bit 0   |

Note:

| Legend:              |                      |   |
|----------------------|----------------------|---|
| R = Readable bit     | W = Writable bit     | U = Unimplemented bit, read as '0'                    |
| u = Bit is unchanged | x = Bit is unknown   | -n/n = Value at POR and BOR/Value at all other Resets |
| '1' = Bit is set     | '0' = Bit is cleared |   |
|                      |                      |   |

| bit 7 | TMR1GIF: Timer1 Gate Interrupt Flag bit                         |
|-------|---|
|       | 1 = Interrupt is pending  |
|       | 0 = Interrupt is not pending                                    |
| bit 6 | ADIF: A/D Converter Interrupt Flag bit                          |
|       | 1 = Interrupt is pending  |
|       | 0 = Interrupt is not pending                                    |
| bit 5 | RCIF: USART Receive Interrupt Flag bit                          |
|       | 1 = Interrupt is pending  |
|       | 0 = Interrupt is not pending                                    |
| bit 4 | TXIF: USART Transmit Interrupt Flag bit                         |
|       | 1 = Interrupt is pending  |
|       | 0 = Interrupt is not pending                                    |
| bit 3 | <b>SSPIF:</b> Synchronous Serial Port (MSSP) Interrupt Flag bit |
|       | 1 = Interrupt is pending  |
|       | 0 = Interrupt is not pending                                    |
| bit 2 | CCP1IF: CCP1 Interrupt Flag bit                                 |
|       | 1 = Interrupt is pending  |
|       | 0 = Interrupt is not pending                                    |
| bit 1 | TMR2IF: Timer2 to PR2 Interrupt Flag bit                        |
|       | 1 = Interrupt is pending  |
|       | 0 = Interrupt is not pending                                    |
| bit 0 | TMR1IF: Timer1 Overflow Interrupt Flag bit                      |
|       | 1 = Interrupt is pending  |
|       | 0 = Interrupt is not pending                                    |
|       |   |

### 7.6.6 PIR2 REGISTER

Legend:

R = Readable bit

u = Bit is unchanged

The PIR2 register contains the interrupt flag bits, as shown in Register 7-6.

Interrupt flag bits are set when an interrupt condition occurs, regardless of the state of its corresponding enable bit or the Global Enable bit, GIE, of the INTCON register. User software should ensure the appropriate interrupt flag bits are clear prior to enabling an interrupt.

#### REGISTER 7-6: PIR2: PERIPHERAL INTERRUPT REQUEST REGISTER 2

W = Writable bit

x = Bit is unknown

| R/W-0/0 | R/W-0/0 | R/W-0/0 | R/W-0/0 | R/W-0/0 | R/W-0/0 | U-0 | R/W-0/0 |
|---------|---------|---------|---------|---------|---------|-----|---------|
| OSFIF   | C2IF    | C1IF    | EEIF    | BCLIF   | LCDIF   | _   | CCP2IF  |
| bit 7   |         |         |         |         |         |     | bit 0   |

Note:

U = Unimplemented bit, read as '0'

-n/n = Value at POR and BOR/Value at all other Resets

| '1' = Bit is set | '0' = Bit is cleared                                     |  |  |  |
|------------------|--|--|--|--|
|                  |  |  |  |  |
| bit 7            | OSFIF: Oscillator Fail Interrupt Flag                    |  |  |  |
|                  | 1 = Interrupt is pending                                 |  |  |  |
|                  | 0 = Interrupt is not pending                             |  |  |  |
| bit 6            | C2IF: Comparator C2 Interrupt Flag                       |  |  |  |
|                  | 1 = Interrupt is pending<br>0 = Interrupt is not pending |  |  |  |
| bit 5            | C1IF: Comparator C1 Interrupt Flag                       |  |  |  |
|                  | 1 = Interrupt is pending                                 |  |  |  |
|                  | 0 = Interrupt is not pending                             |  |  |  |
| bit 4            | <b>EEIF:</b> EEPROM Write Completion Interrupt Flag bit  |  |  |  |
|                  | 1 = Interrupt is pending                                 |  |  |  |
|                  | 0 = Interrupt is not pending                             |  |  |  |
| bit 3            | BCLIF: MSSP Bus Collision Interrupt Flag bit             |  |  |  |
|                  | 1 = Interrupt is pending                                 |  |  |  |
|                  | 0 = Interrupt is not pending                             |  |  |  |
| bit 2            | LCDIF: LCD Module Interrupt Flag bit                     |  |  |  |
|                  | 1 = Interrupt is pending                                 |  |  |  |
|                  | 0 = Interrupt is not pending                             |  |  |  |
| bit 1            | Unimplemented: Read as '0'                               |  |  |  |
| bit 0            | CCP2IF: CCP2 Interrupt Flag bit                          |  |  |  |
|                  | 1 = Interrupt is pending                                 |  |  |  |
|                  | 0 = Interrupt is not pending                             |  |  |  |

### 7.6.7 PIR3 REGISTER

The PIR3 register contains the interrupt flag bits, as shown in Register 7-7.

Interrupt flag bits are set when an interrupt condition occurs, regardless of the state of its corresponding enable bit or the Global Enable bit, GIE, of the INTCON register. User software should ensure the appropriate interrupt flag bits are clear prior to enabling an interrupt.

## REGISTER 7-7: PIR3: PERIPHERAL INTERRUPT REQUEST REGISTER 3

| R/W-0/0 |
|---------|---------|---------|---------|---------|---------|---------|---------|
| _       | CCP5IF  | CCP4IF  | CCP3IF  | TMR6IF  | _       | TMR4IF  | _       |
| bit 7   |         |         |         |         |         |         | bit 0   |

Note:

| Legend:              |                      |   |
|----------------------|----------------------|---|
| R = Readable bit     | W = Writable bit     | U = Unimplemented bit, read as '0'                    |
| u = Bit is unchanged | x = Bit is unknown   | -n/n = Value at POR and BOR/Value at all other Resets |
| '1' = Bit is set     | '0' = Bit is cleared |   |

| bit 7 | Unimplemented: Read as '0'                   |
|-------|--|
| bit 6 | CCP5IF: CCP5 Interrupt Flag bit              |
|       | 1 = Interrupt is pending                     |
|       | 0 = Interrupt is not pending                 |
| bit 5 | CCP4IF: CCP4 Interrupt Flag bit              |
|       | 1 = Interrupt is pending                     |
|       | 0 = Interrupt is not pending                 |
| bit 4 | CCP3IF: CCP3 Interrupt Flag bit              |
|       | 1 = Interrupt is pending                     |
|       | 0 = Interrupt is not pending                 |
| bit 3 | TMR6IF: TMR6 to PR6 Match Interrupt Flag bit |
|       | 1 = Interrupt is pending                     |
|       | 0 = Interrupt is not pending                 |
| bit 2 | Unimplemented: Read as '0'                   |
| bit 1 | TMR4IF: TMR4 to PR4 Match Interrupt Flag bit |
|       | 1 = Interrupt is pending                     |
|       | 0 = Interrupt is not pending                 |
| bit 0 | Unimplemented: Read as '0'                   |
|       |  |

TABLE 7-1: SUMMARY OF REGISTERS ASSOCIATED WITH INTERRUPTS

| Name       | Bit 7   | Bit 6  | Bit 5  | Bit 4  | Bit 3  | Bit 2   | Bit 1  | Bit 0  | Register on Page |
|------------|---------|--------|--------|--------|--------|---------|--------|--------|------------------|
| INTCON     | GIE     | PEIE   | TMR0IE | INTE   | IOCIE  | TMR0IF  | INTF   | IOCIF  | 98               |
| OPTION_REG | WPUEN   | INTEDG | TMROCS | TMROSE | PSA    | PS<2:0> |        |        | 193              |
| PIE1       | TMR1GIE | ADIE   | RCIE   | TXIE   | SSPIE  | CCP1IE  | TMR2IE | TMR1IE | 99               |
| PIE2       | OSFIE   | C2IE   | C1IE   | EEIE   | BCLIE  | LCDIE   | 1      | CCP2IE | 100              |
| PIE3       | -       | CCP5IE | CCP4IE | CCP3IE | TMR6IE | 1       | TMR4IE | _      | 101              |
| PIR1       | TMR1GIF | ADIF   | RCIF   | TXIF   | SSPIF  | CCP1IF  | TMR2IF | TMR1IF | 102              |
| PIR2       | OSFIF   | C2IF   | C1IF   | EEIF   | BCLIF  | LCDIF   |        | CCP2IF | 103              |
| PIR3       | _       | CCP5IF | CCP4IF | CCP3IF | TMR6IF | _       | TMR4IF | _      | 104              |

**Legend:** — = unimplemented location, read as '0'. Shaded cells are not used by Interrupts.

**NOTES:** 

## 8.0 LOW DROPOUT (LDO) VOLTAGE REGULATOR

The PIC16F1934/6/7 has an internal Low Dropout Regulator (LDO) which provides operation above 3.6V. The LDO regulates a voltage for the internal device logic while permitting the VDD and I/O pins to operate at a higher voltage. There is no user enable/disable control available for the LDO, it is always active. The PIC16(L)F1934/6/7 operates at a maximum VDD of 3.6V and does not incorporate an LDO.

A device I/O pin may be configured as the LDO voltage output, identified as the VCAP pin. Although not required, an external low-ESR capacitor may be connected to the VCAP pin for additional regulator stability.

The VCAPEN<1:0> bits of Configuration Word 2 determines which pin is assigned as the VCAP pin. Refer to Table 8-1.

TABLE 8-1: VCAPEN<1:0> SELECT BITS

| VCAPEN<1:0> | Pin     |
|-------------|---------|
| 00          | RA0     |
| 01          | RA5     |
| 10          | RA6     |
| 11          | No Vcap |

On power-up, the external capacitor will load the LDO voltage regulator. To prevent erroneous operation, the device is held in Reset while a constant current source charges the external capacitor. After the cap is fully charged, the device is released from Reset. For more information on recommended capacitor values and the constant current rate, refer to the LDO Regulator Characteristics Table in the applicable Electrical Specifications Chapter.

TABLE 8-2: SUMMARY OF CONFIGURATION WORD WITH LDO

| Name    | Bits | Bit -/7 | Bit -/6 | Bit 13/5               | Bit 12/4               | Bit 11/3 | Bit 10/2 | Bit 9/1 | Bit 8/0 | Register on Page |
|---------|------|---------|---------|------------------------|------------------------|----------|----------|---------|---------|------------------|
| CONFIG2 | 13:8 | I       | _       | LVP                    | DEBUG                  | 1        | BORV     | STVREN  | PLLEN   | 64               |
|         | 7:0  | _       | _       | VCAPEN1 <sup>(1)</sup> | VCAPEN0 <sup>(1)</sup> | _        | _        | WRT1    | WRT0    | 64               |

**Legend:** — = unimplemented locations read as '0'. Shaded cells are not used by LDO.

Note 1: PIC16F1934/6/7 only.

**NOTES:** 

#### 9.0 POWER-DOWN MODE (SLEEP)

The Power-down mode is entered by executing a SLEEP instruction.

Upon entering Sleep mode, the following conditions exist:

- WDT will be cleared but keeps running, if enabled for operation during Sleep.
- 2. PD bit of the STATUS register is cleared.
- 3. TO bit of the STATUS register is set.
- 4. CPU clock is disabled.
- 31 kHz LFINTOSC is unaffected and peripherals that operate from it may continue operation in Sleep
- Timer1 oscillator is unaffected and peripherals that operate from it may continue operation in Sleep.
- ADC is unaffected, if the dedicated FRC clock is selected.
- 8. Capacitive Sensing oscillator is unaffected.
- I/O ports maintain the status they had before SLEEP was executed (driving high, low or highimpedance).
- 10. Resets other than WDT are not affected by Sleep mode.

Refer to individual chapters for more details on peripheral operation during Sleep.

To minimize current consumption, the following conditions should be considered:

- · I/O pins should not be floating
- · External circuitry sinking current from I/O pins
- · Internal circuitry sourcing current from I/O pins
- · Current draw from pins with internal weak pull-ups
- Modules using 31 kHz LFINTOSC
- · Modules using Timer1 oscillator

I/O pins that are high-impedance inputs should be pulled to VDD or Vss externally to avoid switching currents caused by floating inputs.

Examples of internal circuitry that might be sourcing current include modules such as the DAC and FVR modules. See Section 17.0 "Digital-to-Analog Converter (DAC) Module" and Section 14.0 "Fixed Voltage Reference (FVR)" for more information on these modules.

#### 9.1 Wake-up from Sleep

The device can wake-up from Sleep through one of the following events:

- 1. External Reset input on MCLR pin, if enabled
- 2. BOR Reset, if enabled
- 3. POR Reset
- 4. Watchdog Timer, if enabled
- 5. Any external interrupt
- Interrupts by peripherals capable of running during Sleep (see individual peripheral for more information)

The first three events will cause a device Reset. The last three events are considered a continuation of program execution. To determine whether a device Reset or wake-up event occurred, refer to Section 6.10 "Determining the Cause of a Reset".

When the SLEEP instruction is being executed, the next instruction (PC + 1) is prefetched. For the device to wake-up through an interrupt event, the corresponding interrupt enable bit must be enabled. Wake-up will occur regardless of the state of the GIE bit. If the GIE bit is disabled, the device continues execution at the instruction after the SLEEP instruction. If the GIE bit is enabled, the device executes the instruction after the SLEEP instruction, the device will call the Interrupt Service Routine. In cases where the execution of the instruction following SLEEP is not desirable, the user should have a NOP after the SLEEP instruction.

The WDT is cleared when the device wakes up from Sleep, regardless of the source of wake-up.

#### 9.1.1 WAKE-UP USING INTERRUPTS


When global interrupts are disabled (GIE cleared) and any interrupt source has both its interrupt enable bit and interrupt flag bit set, one of the following will occur:

- If the interrupt occurs before the execution of a SLEEP instruction
  - SLEEP instruction will execute as a NOP.
  - WDT and WDT prescaler will not be cleared
  - TO bit of the STATUS register will not be set
  - PD bit of the STATUS register will not be cleared.

- If the interrupt occurs during or after the execution of a SLEEP instruction
  - SLEEP instruction will be completely executed
  - Device will immediately wake-up from Sleep
  - WDT and WDT prescaler will be cleared
  - TO bit of the STATUS register will be set
  - PD bit of the STATUS register will be cleared.

Even if the flag bits were checked before executing a SLEEP instruction, it may be possible for flag bits to become set before the SLEEP instruction completes. To determine whether a SLEEP instruction executed, test the  $\overline{PD}$  bit. If the  $\overline{PD}$  bit is set, the SLEEP instruction was executed as a NOP.





Note 1: XT, HS or LP Oscillator mode assumed.

2: CLKOUT is not available in XT, HS, or LP Oscillator modes, but shown here for timing reference.

3: Tost = 1024 Tosc (drawing not to scale). This delay applies only to XT, HS or LP Oscillator modes.

4: GIE = 1 assumed. In this case after wake-up, the processor calls the ISR at 0004h. If GIE = 0, execution will continue in-line.

TABLE 9-1: SUMMARY OF REGISTERS ASSOCIATED WITH POWER-DOWN MODE

| Name   | Bit 7   | Bit 6  | Bit 5  | Bit 4  | Bit 3      | Bit 2  | Bit 1  | Bit 0  | Register on<br>Page |
|--------|---------|--------|--------|--------|------------|--------|--------|--------|---------------------|
| INTCON | GIE     | PEIE   | TMR0IE | INTE   | IOCIE      | TMR0IF | INTF   | IOCIF  | 98                  |
| IOCBF  | IOCBF7  | IOCBF6 | IOCBF5 | IOCBF4 | IOCBF3     | IOCBF2 | IOCBF1 | IOCBF0 | 152                 |
| IOCBN  | IOCBN7  | IOCBN6 | IOCBN5 | IOCBN4 | IOCBN3     | IOCBN2 | IOCBN1 | IOCBN0 | 152                 |
| IOCBP  | IOCBP7  | IOCBP6 | IOCBP5 | IOCBP4 | IOCBP3     | IOCBP2 | IOCBP1 | IOCBP0 | 152                 |
| PIE1   | TMR1GIE | ADIE   | RCIE   | TXIE   | SSPIE      | CCP1IE | TMR2IE | TMR1IE | 99                  |
| PIE2   | OSFIE   | C2IE   | C1IE   | EEIE   | BCLIE      | LCDIE  | _      | CCP2IE | 100                 |
| PIE3   | -       | CCP5IE | CCP4IE | CCP3IE | TMR6IE     | _      | TMR4IE | _      | 101                 |
| PIR1   | TMR1GIF | ADIF   | RCIF   | TXIF   | SSPIF      | CCP1IF | TMR2IF | TMR1IF | 102                 |
| PIR2   | OSFIF   | C2IF   | C1IF   | EEIF   | BCLIF      | LCDIF  | _      | CCP2IF | 103                 |
| PIR3   | _       | CCP5IF | CCP4IF | CCP3IF | TMR6IF     | _      | TMR4IF | _      | 104                 |
| STATUS | _       | _      | _      | TO     | PD         | Z      | DC     | С      | 29                  |
| WDTCON | _       | _      |        |        | WDTPS<4:0> |        |        | SWDTEN | 113                 |

Legend: — = unimplemented location, read as '0'. Shaded cells are not used in Power-down mode.


#### 10.0 WATCHDOG TIMER

The Watchdog Timer is a system timer that generates a Reset if the firmware does not issue a CLRWDT instruction within the time-out period. The Watchdog Timer is typically used to recover the system from unexpected events.

The WDT has the following features:

- · Independent clock source
- · Multiple operating modes
  - WDT is always on
  - WDT is off when in Sleep
  - WDT is controlled by software
  - WDT is always off
- Configurable time-out period is from 1 ms to 256 seconds (typical)
- · Multiple Reset conditions
- · Operation during Sleep

#### FIGURE 10-1: WATCHDOG TIMER BLOCK DIAGRAM



#### 10.1 Independent Clock Source

The WDT derives its time base from the 31 kHz LFINTOSC internal oscillator. Time intervals in this chapter are based on a nominal interval of 1 ms. See the Electrical Specifications Chapters for the LFINTOSC tolerances.

#### 10.2 WDT Operating Modes

The Watchdog Timer module has four operating modes controlled by the WDTE<1:0> bits in Configuration Word 1. See Table 10-1.

#### 10.2.1 WDT IS ALWAYS ON

When the WDTE bits of Configuration Word 1 are set to '11', the WDT is always on.

WDT protection is active during Sleep.

#### 10.2.2 WDT IS OFF IN SLEEP

When the WDTE bits of Configuration Word 1 are set to '10', the WDT is on, except in Sleep.

WDT protection is not active during Sleep.

#### 10.2.3 WDT CONTROLLED BY SOFTWARE

When the WDTE bits of Configuration Word 1 are set to '01', the WDT is controlled by the SWDTEN bit of the WDTCON register.

WDT protection is unchanged by Sleep. See Table 10-1 for more details.

TABLE 10-1: WDT OPERATING MODES

| WDTE<1:0> | SWDTEN | Device<br>Mode | WDT<br>Mode |
|-----------|--------|----------------|-------------|
| 11        | Х      | Х              | Active      |
| 1.0       | 77     | Awake          | Active      |
| 10        | Х      | Sleep          | Disabled    |
| 01        | 1      | Х              | Active      |
| 01        | 0      | ^              | Disabled    |
| 00        | Х      | Х              | Disabled    |

#### 10.3 Time-Out Period

The WDTPS bits of the WDTCON register set the time-out period from 1 ms to 256 seconds (nominal). After a Reset, the default time-out period is 2 seconds.

#### 10.4 Clearing the WDT

The WDT is cleared when any of the following conditions occur:

- Any Reset
- CLRWDT instruction is executed
- · Device enters Sleep
- · Device wakes up from Sleep
- · Oscillator fail event
- · WDT is disabled
- · Oscillator Start-up TImer (OST) is running

See Table 10-2 for more information.

#### 10.5 Operation During Sleep

When the device enters Sleep, the WDT is cleared. If the WDT is enabled during Sleep, the WDT resumes counting.

When the device exits Sleep, the WDT is cleared again. The WDT remains clear until the OST, if enabled, completes. See Section 5.0 "Oscillator Module (With Fail-Safe Clock Monitor)" for more information on the OST.

When a WDT time-out occurs while the device is in Sleep, no Reset is generated. Instead, the device wakes up and resumes operation. The TO and PD bits in the STATUS register are changed to indicate the event. See Section 3.0 "Memory Organization" and STATUS register (Register 3-1) for more information.

TABLE 10-2: WDT CLEARING CONDITIONS

| Conditions   | WDT                          |  |  |  |
|--|------------------------------|--|--|--|
| WDTE<1:0> = 00   |                              |  |  |  |
| WDTE<1:0> = 01 and SWDTEN = 0                            |                              |  |  |  |
| WDTE<1:0> = 10 and enter Sleep                           | Cleared                      |  |  |  |
| CLRWDT Command   | Cleared                      |  |  |  |
| Oscillator Fail Detected                                 |                              |  |  |  |
| Exit Sleep + System Clock = T1OSC, EXTRC, INTOSC, EXTCLK |                              |  |  |  |
| Exit Sleep + System Clock = XT, HS, LP                   | Cleared until the end of OST |  |  |  |
| Change INTOSC divider (IRCF bits)                        | Unaffected                   |  |  |  |

#### 10.6 Watchdog Control Register

#### REGISTER 10-1: WDTCON: WATCHDOG TIMER CONTROL REGISTER

| U-0   | U-0 | R/W-0/0 | R/W-1/1 | R/W-0/0    | R/W-1/1 | R/W-1/1 | R/W-0/0 |
|-------|-----|---------|---------|------------|---------|---------|---------|
| _     | _   |         |         | WDTPS<4:0> | >       |         | SWDTEN  |
| bit 7 |     |         |         |            |         |         | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -m/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-6 Unimplemented: Read as '0' bit 5-1 WDTPS<4:0>: Watchdog Timer Period Select bits Bit Value = Prescale Rate 00000 = 1:32 (Interval 1 ms typ)00001 = 1:64 (Interval 2 ms typ)00010 = 1:128 (Interval 4 ms typ) 00011 = 1:256 (Interval 8 ms typ) 00100 = 1:512(Interval 16 ms typ) 00101 = 1:1024 (Interval 32 ms typ) 00110 = 1:2048 (Interval 64 ms typ) 00111 = 1:4096 (Interval 128 ms typ) 01000 = 1:8192 (Interval 256 ms typ) 01001 = 1:16384 (Interval 512 ms typ) 01010 = 1:32768 (Interval 1s typ) 01011 = 1:65536 (Interval 2s typ) (Reset value)  $01100 = 1:131072 (2^{17}) (Interval 4s typ)$ 01100 = 1.36072 (2) (interval 8s typ) 01110 = 1:524288 (2<sup>19</sup>) (Interval 16s typ)  $01111 = 1:1048576 (2^{20}) (Interval 32s typ)$  $10000 = 1:2097152 (2^{21}) (Interval 64s typ)$  $10001 = 1:4194304 (2^{22}) (Interval 128s typ)$  $10010 = 1:8388608 (2^{23}) (Interval 256s typ)$ 10011 = Reserved. Results in minimum interval (1:32) 11111 = Reserved. Results in minimum interval (1:32) bit 0 SWDTEN: Software Enable/Disable for Watchdog Timer bit If WDTE<1:0> = 00: This bit is ignored. If WDTE<1:0> = 01: 1 = WDT is turned on 0 = WDT is turned off If WDTE<1:0> = 1x:

© 2008-2011 Microchip Technology Inc.

This bit is ignored.

#### TABLE 10-3: SUMMARY OF REGISTERS ASSOCIATED WITH WATCHDOG TIMER

| Name   | Bit 7  | Bit 6 | Bit 5      | Bit 4 | Bit 3 | Bit 2 | Bit 1    | Bit 0  | Register on Page |
|--------|--------|-------|------------|-------|-------|-------|----------|--------|------------------|
| OSCCON | SPLLEN |       | IRCF<3:0>  |       |       |       | SCS<1:0> |        | 64               |
| STATUS | _      | _     | _          | TO    | PD    | Z     | DC       | С      | 29               |
| WDTCON | _      | _     | WDTPS<4:0> |       |       |       |          | SWDTEN | 113              |

**Legend:** x = unknown, u = unchanged, – = unimplemented locations read as '0'. Shaded cells are not used by Watchdog Timer.

#### TABLE 10-4: SUMMARY OF CONFIGURATION WORD WITH WATCHDOG TIMER

| Name    | Bits | Bit -/7 | Bit -/6 | Bit 13/5 | Bit 12/4 | Bit 11/3 | Bit 10/2   | Bit 9/1 | Bit 8/0 | Register on Page |
|---------|------|---------|---------|----------|----------|----------|------------|---------|---------|------------------|
| CONFIG1 | 13:8 | _       | _       | FCMEN    | IESO     | CLKOUTEN | BOREN<1:0> |         | CPD     | 60               |
| CONFIGI | 7:0  | CP      | MCLRE   | PWRTE    | WDTE     | E<1:0>   | FOSC<2:0>  |         |         | 62               |

**Legend:** — = unimplemented location, read as '0'. Shaded cells are not used by Watchdog Timer.

# 11.0 DATA EEPROM AND FLASH PROGRAM MEMORY CONTROL

The data EEPROM and Flash program memory are readable and writable during normal operation (full VDD range). These memories are not directly mapped in the register file space. Instead, they are indirectly addressed through the Special Function Registers (SFRs). There are six SFRs used to access these memories:

- EECON1
- EECON2
- EEDATL
- EEDATH
- EEADRL
- EEADRH

When interfacing the data memory block, EEDATL holds the 8-bit data for read/write, and EEADRL holds the address of the EEDATL location being accessed. These devices have 256 bytes of data EEPROM with an address range from 0h to 0FFh.

When accessing the program memory block, the EEDATH:EEDATL register pair forms a 2-byte word that holds the 14-bit data for read/write, and the EEADRL and EEADRH registers form a 2-byte word that holds the 15-bit address of the program memory location being read.

The EEPROM data memory allows byte read and write. An EEPROM byte write automatically erases the location and writes the new data (erase before write).

The write time is controlled by an on-chip timer. The write/erase voltages are generated by an on-chip charge pump rated to operate over the voltage range of the device for byte or word operations.

Depending on the setting of the Flash Program Memory Self Write Enable bits WRT<1:0> of the Configuration Word 2, the device may or may not be able to write certain blocks of the program memory. However, reads from the program memory are always allowed.

When the device is code-protected, the device programmer can no longer access data or program memory. When code-protected, the CPU may continue to read and write the data EEPROM memory and Flash program memory.

#### 11.1 EEADRL and EEADRH Registers

The EEADRH:EEADRL register pair can address up to a maximum of 256 bytes of data EEPROM or up to a maximum of 32K words of program memory.

When selecting a program address value, the MSB of the address is written to the EEADRH register and the LSB is written to the EEADRL register. When selecting a EEPROM address value, only the LSB of the address is written to the EEADRL register.

#### 11.1.1 EECON1 AND EECON2 REGISTERS

EECON1 is the control register for EE memory accesses.

Control bit EEPGD determines if the access will be a program or data memory access. When clear, any subsequent operations will operate on the EEPROM memory. When set, any subsequent operations will operate on the program memory. On Reset, EEPROM is selected by default.

Control bits RD and WR initiate read and write, respectively. These bits cannot be cleared, only set, in software. They are cleared in hardware at completion of the read or write operation. The inability to clear the WR bit in software prevents the accidental, premature termination of a write operation.

The WREN bit, when set, will allow a write operation to occur. On power-up, the WREN bit is clear. The WRERR bit is set when a write operation is interrupted by a Reset during normal operation. In these situations, following Reset, the user can check the WRERR bit and execute the appropriate error handling routine.

Interrupt flag bit EEIF of the PIR2 register is set when write is complete. It must be cleared in the software.

Reading EECON2 will read all '0's. The EECON2 register is used exclusively in the data EEPROM write sequence. To enable writes, a specific pattern must be written to EECON2.

#### 11.2 Using the Data EEPROM

The data EEPROM is a high-endurance, byte addressable array that has been optimized for the storage of frequently changing information (e.g., program variables or other data that are updated often). When variables in one section change frequently, while variables in another section do not change, it is possible to exceed the total number of write cycles to the EEPROM without exceeding the total number of write cycles to a single byte. Refer to the applicable Electrical Specifications Chapter. If this is the case, then a refresh of the array must be performed. For this reason, variables that change infrequently (such as constants, IDs, calibration, etc.) should be stored in Flash program memory.

# 11.2.1 READING THE DATA EEPROM MEMORY

To read a data memory location, the user must write the address to the EEADRL register, clear the EEPGD and CFGS control bits of the EECON1 register, and then set control bit RD. The data is available at the very next cycle, in the EEDATL register; therefore, it can be read in the next instruction. EEDATL will hold this value until another read or until it is written to by the user (during a write operation).

#### **EXAMPLE 11-1: DATA EEPROM READ**

```
BANKSEL EEADRL ;

MOVUW DATA_EE_ADDR;

MOVWF EEADRL ;Data Memory;Address to read

BCF EECON1, CFGS;Deselect Config space

BCF EECON1, EEPGD;Point to DATA memory

BSF EECON1, RD ;EE Read

MOVF EEDATL, W ;W = EEDATL
```

Note: Data EEPROM can be read regardless of the setting of the CPD bit.

# 11.2.2 WRITING TO THE DATA EEPROM MEMORY

To write an EEPROM data location, the user must first write the address to the EEADRL register and the data to the EEDATL register. Then the user must follow a specific sequence to initiate the write for each byte.

The write will not initiate if the above sequence is not followed exactly (write 55h to EECON2, write AAh to EECON2, then set the WR bit) for each byte. Interrupts should be disabled during this code segment.

Additionally, the WREN bit in EECON1 must be set to enable write. This mechanism prevents accidental writes to data EEPROM due to errant (unexpected) code execution (i.e., lost programs). The user should keep the WREN bit clear at all times, except when updating EEPROM. The WREN bit is not cleared by hardware.

After a write sequence has been initiated, clearing the WREN bit will not affect this write cycle. The WR bit will be inhibited from being set unless the WREN bit is set.

At the completion of the write cycle, the WR bit is cleared in hardware and the EE Write Complete Interrupt Flag bit (EEIF) is set. The user can either enable this interrupt or poll this bit. EEIF must be cleared by software.

### 11.2.3 PROTECTION AGAINST SPURIOUS WRITE

There are conditions when the user may not want to write to the data EEPROM memory. To protect against spurious EEPROM writes, various mechanisms have been built-in. On power-up, WREN is cleared. Also, the Power-up Timer (64 ms duration) prevents EEPROM write.

The write initiate sequence and the WREN bit together help prevent an accidental write during:

- · Brown-out
- · Power Glitch
- · Software Malfunction

# 11.2.4 DATA EEPROM OPERATION DURING CODE-PROTECT


Data memory can be code-protected by programming the  $\overline{\text{CPD}}$  bit in the Configuration Word 1 (Register 5-1) to '0'

When the data memory is code-protected, only the CPU is able to read and write data to the data EEPROM. It is recommended to code-protect the program memory when code-protecting data memory. This prevents anyone from replacing your program with a program that will access the contents of the data EEPROM.

#### **EXAMPLE 11-2: DATA EEPROM WRITE**

```
BANKSEL EEADRL
MOVLW
        DATA_EE_ADDR
                       ;
MOVWF
        EEADRL
                       ;Data Memory Address to write
MOVLW
        DATA_EE_DATA
MOVWF
        EEDATL
                       ;Data Memory Value to write
        EECON1, CFGS
BCF
                       ;Deselect Configuration space
BCF
        EECON1, EEPGD ; Point to DATA memory
        EECON1, WREN
                       ;Enable writes
BSF
BCF
        INTCON, GIE
                       ;Disable INTs.
MOVLW
        55h
MOVWF
        EECON2
                       ;Write 55h
MOVLW
        0AAh
MOVWF
        EECON2
                       ;Write AAh
BSF
        EECON1, WR
                       ;Set WR bit to begin write
        INTCON, GIE
BSF
                       ;Enable Interrupts
        EECON1, WREN
BCF
                       ;Disable writes
BTFSC
        EECON1, WR
                       ;Wait for write to complete
GOTO
                       ;Done
```

#### FIGURE 11-1: FLASH PROGRAM MEMORY READ CYCLE EXECUTION



#### 11.3 Flash Program Memory Overview

It is important to understand the Flash program memory structure for erase and programming operations. Flash Program memory is arranged in rows. A row consists of a fixed number of 14-bit program memory words. A row is the minimum block size that can be erased by user software.

Flash program memory may only be written or erased if the destination address is in a segment of memory that is not write-protected, as defined in bits WRT<1:0> of Configuration Word 2.

After a row has been erased, the user can reprogram all or a portion of this row. Data to be written into the program memory row is written to 14-bit wide data write latches. These write latches are not directly accessible to the user, but may be loaded via sequential writes to the EEDATH:EEDATL register pair.

**Note:** If the user wants to modify only a portion of a previously programmed row, then the contents of the entire row must be read and saved in RAM prior to the erase.

The number of data write latches may not be equivalent to the number of row locations. During programming, user software may need to fill the set of write latches and initiate a programming operation multiple times in order to fully reprogram an erased row. For example, a device with a row size of 32 words and eight write latches will need to load the write latches with data and initiate a programming operation four times.

The size of a program memory row and the number of program memory write latches may vary by device. See Table 11-1 for details.

TABLE 11-1: FLASH MEMORY ORGANIZATION BY DEVICE

| Device            | Erase Block<br>(Row) Size/<br>Boundary | Number of<br>Write<br>Latches/<br>Boundary |
|-------------------|--|--|
| PIC16(L)F1934/6/7 | 32 words,<br>EEADRL<4:0><br>= 00000    | 8 words,<br>EEADRL<2:0><br>= 000           |

# 11.3.1 READING THE FLASH PROGRAM MEMORY

To read a program memory location, the user must:

- Write the Least and Most Significant address bits to the EEADRH:EEADRL register pair.
- Clear the CFGS bit of the EECON1 register.
- Set the EEPGD control bit of the EECON1 register.
- 4. Then, set control bit RD of the EECON1 register.

Once the read control bit is set, the program memory Flash controller will use the second instruction cycle to read the data. This causes the second instruction immediately following the "BSF EECON1,RD" instruction to be ignored. The data is available in the very next cycle, in the EEDATH:EEDATL register pair; therefore, it can be read as two bytes in the following instructions.

EEDATH:EEDATL register pair will hold this value until another read or until it is written to by the user.

- Note 1: The two instructions following a program memory read are required to be NOPs. This prevents the user from executing a two-cycle instruction on the next instruction after the RD bit is set.
  - **2:** Flash program memory can be read regardless of the setting of the CP bit.

#### **EXAMPLE 11-3: FLASH PROGRAM MEMORY READ**

```
* This code block will read 1 word of program
* memory at the memory address:
   PROG_ADDR_HI: PROG_ADDR_LO
   data will be returned in the variables;
   PROG_DATA_HI, PROG_DATA_LO
   BANKSEL EEADRL ; Select Bank for EEPRO ; MOVLW PROG_ADDR_LO ; MOVWF EEADRL ; Store LSB of address MOVLW PROG_ADDR_HI ;
   BANKSEL EEADRL
                                 ; Select Bank for EEPROM registers
   MOVWL EEADRH
                               ; Store MSB of address
             EECON1,CFGS ; Do not select Configuration Space
EECON1,EEPGD ; Select Program Memory
   BCF
            EECON1, CFGS
   BSF
             INTCON,GIE ; Disable interrupts
   BCF
   BSF
              EECON1,RD
                                 ; Initiate read
   NOP
                                 ; Executed (Figure 11-1)
   NOP
                                 ; Ignored (Figure 11-1)
   BSF
             INTCON, GIE
                               ; Restore interrupts
             EEDATL,W
   MOVF
                               ; Get LSB of word
   MOVWF
             PROG_DATA_LO ; Store in user location
             EEDATH,W ; Get MSB of word
PROG_DATA_HI ; Store in user location
   MOVE
   MOVWF
```

### 11.3.2 ERASING FLASH PROGRAM MEMORY

While executing code, program memory can only be erased by rows. To erase a row:

- Load the EEADRH:EEADRL register pair with the address of new row to be erased.
- 2. Clear the CFGS bit of the EECON1 register.
- Set the EEPGD, FREE, and WREN bits of the EECON1 register.
- 4. Write 55h, then AAh, to EECON2 (Flash programming unlock sequence).
- Set control bit WR of the EECON1 register to begin the erase operation.
- Poll the FREE bit in the EECON1 register to determine when the row erase has completed.

#### See Example 11-4.

After the "BSF EECON1, WR" instruction, the processor requires two cycles to set up the erase operation. The user must place two NOP instructions after the WR bit is set. The processor will halt internal operations for the typical 2 ms erase time. This is not Sleep mode as the clocks and peripherals will continue to run. After the erase cycle, the processor will resume operation with the third instruction after the EECON1 write instruction.

### 11.3.3 WRITING TO FLASH PROGRAM MEMORY

Program memory is programmed using the following steps:

- Load the starting address of the word(s) to be programmed.
- 2. Load the write latches with data.
- 3. Initiate a programming operation.
- 4. Repeat steps 1 through 3 until all data is written.

Before writing to program memory, the word(s) to be written must be erased or previously unwritten. Program memory can only be erased one row at a time. No automatic erase occurs upon the initiation of the write.

Program memory can be written one or more words at a time. The maximum number of words written at one time is equal to the number of write latches. See Figure 11-2 (block writes to program memory with 8 write latches) for more details. The write latches are aligned to the address boundary defined by EEADRL as shown in Table 11-1. Write operations do not cross these boundaries. At the completion of a program memory write operation, the write latches are reset to contain 0x3FFF.

The following steps should be completed to load the write latches and program a block of program memory. These steps are divided into two parts. First, all write latches are loaded with data except for the last program memory location. Then, the last write latch is loaded and the programming sequence is initiated. A special unlock sequence is required to load a write latch with data or initiate a Flash programming operation. This unlock sequence should not be interrupted.

- Set the EEPGD and WREN bits of the EECON1 register.
- 2. Clear the CFGS bit of the EECON1 register.
- Set the LWLO bit of the EECON1 register. When the LWLO bit of the EECON1 register is '1', the write sequence will only load the write latches and will not initiate the write to Flash program memory.
- 4. Load the EEADRH:EEADRL register pair with the address of the location to be written.
- 5. Load the EEDATH:EEDATL register pair with the program memory data to be written.
- Write 55h, then AAh, to EECON2, then set the WR bit of the EECON1 register (Flash programming unlock sequence). The write latch is now loaded.
- Increment the EEADRH:EEADRL register pair to point to the next location.
- Repeat steps 5 through 7 until all but the last write latch has been loaded.
- Clear the LWLO bit of the EECON1 register. When the LWLO bit of the EECON1 register is '0', the write sequence will initiate the write to Flash program memory.
- 10. Load the EEDATH:EEDATL register pair with the program memory data to be written.
- 11. Write 55h, then AAh, to EECON2, then set the WR bit of the EECON1 register (Flash programming unlock sequence). The entire latch block is now written to Flash program memory.


It is not necessary to load the entire write latch block with user program data. However, the entire write latch block will be written to program memory.

An example of the complete write sequence for eight words is shown in Example 11-5. The initial address is loaded into the EEADRH:EEADRL register pair; the eight words of data are loaded using indirect addressing.

Note: The code sequence provided in Example 11-5 must be repeated multiple times to fully program an erased program memory row. After the "BSF EECON1, WR" instruction, the processor requires two cycles to set up the write operation. The user must place two NOP instructions after the WR bit is set. The processor will halt internal operations for the typical 2 ms, only during the cycle in which the write takes place (i.e., the last word of the block write). This is not Sleep mode as the clocks and peripherals will

continue to run. The processor does not stall when LWLO = 1, loading the write latches. After the write cycle, the processor will resume operation with the third instruction after the EECON1 write instruction.

FIGURE 11-2: BLOCK WRITES TO FLASH PROGRAM MEMORY WITH 8 WRITE LATCHES



#### **EXAMPLE 11-4: ERASING ONE ROW OF PROGRAM MEMORY -**

```
; This row erase routine assumes the following:
; 1. A valid address within the erase block is loaded in ADDRH:ADDRL
; 2. ADDRH and ADDRL are located in shared data memory 0x70 - 0x7F (common RAM)
       BCF
                  INTCON, GIE
                                 ; Disable ints so required sequences will execute properly
       BANKSEL
                  EEADRL
       MOVF
                  ADDRL,W
                                ; Load lower 8 bits of erase address boundary
       MOVWF
                  EEADRL
       MOVF
                  ADDRH,W
                                 ; Load upper 6 bits of erase address boundary
       MOVWF
                  EEADRH
                  EECON1, EEPGD
                                ; Point to program memory
       BSF
                  EECON1, CFGS
       BCF
                                 ; Not configuration space
       BSF
                  EECON1, FREE
                                 ; Specify an erase operation
       BSF
                  EECON1, WREN
                                 ; Enable writes
       MOVT.W
                  55h
                                 ; Start of required sequence to initiate erase
       MOVWF
                  EECON2
                                 ; Write 55h
      MOVLW
                  0AAh
       MOVWF
                  EECON2
                                 ; Write AAh
       BSF
                  EECON1,WR
                                 ; Set WR bit to begin erase
       NOP
                                  ; Any instructions here are ignored as processor
                                  ; halts to begin erase sequence
       NOP
                                  ; Processor will stop here and wait for erase complete.
                                  ; after erase processor continues with 3rd instruction
       BCF
                  EECON1, WREN
                                  ; Disable writes
       BSF
                  INTCON, GIE
                                  ; Enable interrupts
```

#### **EXAMPLE 11-5: WRITING TO FLASH PROGRAM MEMORY**

```
; This write routine assumes the following:
; 1. The 16 bytes of data are loaded, starting at the address in DATA_ADDR
; 2. Each word of data to be written is made up of two adjacent bytes in DATA_ADDR,
     stored in little endian format
; 3. A valid starting address (the least significant bits = 000) is loaded in ADDRH: ADDRL
; 4. ADDRH and ADDRL are located in shared data memory 0x70 - 0x7F (common RAM)
       BCF
                   INTCON, GIE
                                 ; Disable ints so required sequences will execute properly
       BANKSEL
                  EEADRH
                                 ; Bank 3
       MOVF
                  ADDRH,W
                                  ; Load initial address
       MOVWF
                   EEADRH
       MOVF
                   ADDRL, W
       MOVWF
                   EEADRL
                   LOW DATA_ADDR ; Load initial data address
       M.TVOM
       MOVWF
                  FSR0L
       MOVLW
                  HIGH DATA_ADDR ; Load initial data address
       MOVWF
                  FSR0H
       BSF
                  EECON1, EEPGD ; Point to program memory
       BCF
                   EECON1,CFGS ; Not configuration space
       BSF
                   EECON1, WREN
                                  ; Enable writes
                   EECON1,LWLO
                                  ; Only Load Write Latches
LOOP
                  FSR0++
                                  ; Load first data byte into lower
       MOVIW
       MOVWF
                  EEDATL
       MOVIW
                   FSR0++
                                  ; Load second data byte into upper
       MOVWF
                   EEDATH
       MOVF
                   EEADRL,W
                                  ; Check if lower bits of address are '000'
       XORLW
                   0x07
                                  ; Check if we're on the last of 8 addresses
       ANDLW
                   0 \times 07
       BTFSC
                   STATUS, Z
                                  ; Exit if last of eight words,
       GOTO
                   START_WRITE
       MOVLW
                   55h
                                  ; Start of required write sequence:
       MOVWF
                   EECON2
                                  ; Write 55h
  Required
Sequence
       MOVLW
                   0AAh
       MOVWF
                                  ; Write AAh
                   EECON2
       BSF
                   EECON1,WR
                                  ; Set WR bit to begin write
                                  ; Any instructions here are ignored as processor
       NOP
                                  ; halts to begin write sequence
       NOP
                                  ; Processor will stop here and wait for write to complete.
                                  ; After write processor continues with 3rd instruction.
       INCF
                   EEADRL,F
                                  ; Still loading latches Increment address
       GOTO
                   LOOP
                                  ; Write next latches
START_WRITE
                   EECON1,LWLO
                                  ; No more loading latches - Actually start Flash program
                                  ; memory write
       MOVLW
                   55h
                                  ; Start of required write sequence:
       MOVWF
                   EECON2
                                  ; Write 55h
  Required
Sequence
       MOVLW
                   0AAh
       MOVWF
                   EECON2
                                  ; Write AAh
       BSF
                   EECON1,WR
                                  ; Set WR bit to begin write
       NOP
                                  ; Any instructions here are ignored as processor
                                  ; halts to begin write sequence
       NOP
                                  ; Processor will stop here and wait for write complete.
                                  ; after write processor continues with 3rd instruction
       BCF
                   EECON1, WREN
                                  ; Disable writes
       BSF
                   INTCON, GIE
                                  ; Enable interrupts
```

#### 11.4 Modifying Flash Program Memory

When modifying existing data in a program memory row, and data within that row must be preserved, it must first be read and saved in a RAM image. Program memory is modified using the following steps:

- Load the starting address of the row to be modified
- Read the existing data from the row into a RAM image.
- Modify the RAM image to contain the new data to be written into program memory.
- Load the starting address of the row to be rewritten.
- 5. Erase the program memory row.
- Load the write latches with data from the RAM image.
- 7. Initiate a programming operation.
- 8. Repeat steps 6 and 7 as many times as required to reprogram the erased row.

# 11.5 User ID, Device ID and Configuration Word Access

Instead of accessing program memory or EEPROM data memory, the User ID's, Device ID/Revision ID and Configuration Words can be accessed when CFGS = 1 in the EECON1 register. This is the region that would be pointed to by PC<15> = 1, but not all addresses are accessible. Different access may exist for reads and writes. Refer to Table 11-2.

When read access is initiated on an address outside the parameters listed in Table 11-2, the EEDATH:EEDATL register pair is cleared.

TABLE 11-2: USER ID, DEVICE ID AND CONFIGURATION WORD ACCESS (CFGS = 1)

| Address     | Function                    | Read Access | Write Access |
|-------------|-----------------------------|-------------|--------------|
| 8000h-8003h | User IDs                    | Yes         | Yes          |
| 8006h       | Device ID/Revision ID       | Yes         | No           |
| 8007h-8008h | Configuration Words 1 and 2 | Yes         | No           |

#### **EXAMPLE 11-3: CONFIGURATION WORD AND DEVICE ID ACCESS**

```
This code block will read 1 word of program memory at the memory address:
  PROG_ADDR_LO (must be 00h-08h) data will be returned in the variables;
  PROG_DATA_HI, PROG_DATA_LO
  BANKSEL EEADRL
                           ; Select correct Bank
          PROG_ADDR_LO
 W-TV/OM
 MOVWF
          EEADRL
                          ; Store LSB of address
  CLRF
          EEADRH
                           ; Clear MSB of address
 BSF
          EECON1,CFGS
                          ; Select Configuration Space
          INTCON,GIE
  BCF
                           ; Disable interrupts
          EECON1,RD
                           ; Initiate read
  BSF
  NOP
                           ; Executed (See Figure 11-1)
  NOP
                           ; Ignored (See Figure 11-1)
          INTCON, GIE
  BSF
                           ; Restore interrupts
 MOVF
          EEDATL,W
                          ; Get LSB of word
                          ; Store in user location
  MOVWF
          PROG_DATA_LO
  MOVF
          EEDATH,W
                           ; Get MSB of word
  MOVWF
          PROG_DATA_HI
                           ; Store in user location
```

#### 11.6 Write Verify

Depending on the application, good programming practice may dictate that the value written to the data EEPROM or program memory should be verified (see Example 11-6) to the desired value to be written. Example 11-6 shows how to verify a write to EEPROM.

#### **EXAMPLE 11-6: EEPROM WRITE VERIFY**

```
BANKSEL EEDATL ;

MOVF EEDATL, W ; EEDATL not changed ; from previous write

BSF EECON1, RD ; YES, Read the ; value written

XORWF EEDATL, W ;

BTFSS STATUS, Z ; Is data the same GOTO WRITE_ERR ;No, handle error ; Yes, continue
```

#### REGISTER 11-1: EEDATL: EEPROM DATA LOW BYTE REGISTER

| R/W-x/u | R/W-x/u    | R/W-x/u | R/W-x/u | R/W-x/u | R/W-x/u | R/W-x/u | R/W-x/u |  |  |  |
|---------|------------|---------|---------|---------|---------|---------|---------|--|--|--|
|         | EEDAT<7:0> |         |         |         |         |         |         |  |  |  |
| bit 7   |            |         |         |         |         |         | bit 0   |  |  |  |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 **EEDAT<7:0>**: Read/write value for EEPROM data byte or Least Significant bits of program memory

#### REGISTER 11-2: EEDATH: EEPROM DATA HIGH BYTE REGISTER

| U-0   | U-0 | R/W-x/u | R/W-x/u | R/W-x/u           | R/W-x/u | R/W-x/u | R/W-x/u |
|-------|-----|---------|---------|-------------------|---------|---------|---------|
| _     | _   |         |         | EEDA <sup>-</sup> | T<13:8> |         |         |
| bit 7 |     |         |         |                   |         |         | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-6 **Unimplemented:** Read as '0'

bit 5-0 **EEDAT<13:8>**: Read/write value for Most Significant bits of program memory

#### REGISTER 11-3: EEADRL: EEPROM ADDRESS LOW BYTE REGISTER

| R/W-0/0 | R/W-0/0    | R/W-0/0 | R/W-0/0 | R/W-0/0 | R/W-0/0 | R/W-0/0 | R/W-0/0 |  |  |  |
|---------|------------|---------|---------|---------|---------|---------|---------|--|--|--|
|         | EEADR<7:0> |         |         |         |         |         |         |  |  |  |
| bit 7   |            |         |         |         |         |         | bit 0   |  |  |  |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 **EEADR<7:0>**: Specifies the Least Significant bits for program memory address or EEPROM address

#### REGISTER 11-4: EEADRH: EEPROM ADDRESS HIGH BYTE REGISTER

| U-1   | R/W-0/0 | R/W-0/0 | R/W-0/0 | R/W-0/0     | R/W-0/0 | R/W-0/0 | R/W-0/0 |
|-------|---------|---------|---------|-------------|---------|---------|---------|
| _     |         |         |         | EEADR<14:8> | >       |         |         |
| bit 7 |         |         |         |             |         |         | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7 **Unimplemented:** Read as '1'

bit 6-0 **EEADR<14:8>**: Specifies the Most Significant bits for program memory address or EEPROM address

#### REGISTER 11-5: EECON1: EEPROM CONTROL 1 REGISTER

| R/W-0/0 | R/W-0/0 | R/W-0/0 | R/W/HC-0/0 | R/W-x/q | R/W-0/0 | R/S/HC-0/0 | R/S/HC-0/0 |
|---------|---------|---------|------------|---------|---------|------------|------------|
| EEPGD   | CFGS    | LWLO    | FREE       | WRERR   | WREN    | WR         | RD         |
| bit 7   |         |         |            |         |         |            | bit 0      |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

S = Bit can only be set x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared HC = Bit is cleared by hardware

bit 7 **EEPGD:** Flash Program/Data EEPROM Memory Select bit

1 = Accesses program space Flash memory

0 = Accesses data EEPROM memory

bit 6 CFGS: Flash Program/Data EEPROM or Configuration Select bit

1 = Accesses Configuration, User ID and Device ID Registers

0 = Accesses Flash Program or data EEPROM Memory

bit 5 LWLO: Load Write Latches Only bit

If CFGS = 1 (Configuration space) OR CFGS = 0 and EEPGD = 1 (program Flash):

- 1 = The next WR command does not initiate a write; only the program memory latches are updated.
- 0 = The next WR command writes a value from EEDATH:EEDATL into program memory latches and initiates a write of all the data stored in the program memory latches.

#### <u>If CFGS = 0 and EEPGD = 0:</u> (Accessing data EEPROM)

LWLO is ignored. The next WR command initiates a write to the data EEPROM.

bit 4 FREE: Program Flash Erase Enable bit

If CFGS = 1 (Configuration space) OR CFGS = 0 and EEPGD = 1 (program Flash):

- 1 = Performs an erase operation on the next WR command (cleared by hardware after completion of erase).
- 0 = Performs a write operation on the next WR command.

#### If EEPGD = 0 and CFGS = 0: (Accessing data EEPROM)

FREE is ignored. The next WR command will initiate both a erase cycle and a write cycle.

- bit 3 WRERR: EEPROM Error Flag bit
  - 1 = Condition indicates an improper program or erase sequence attempt or termination (bit is set automatically on any set attempt (write '1') of the WR bit).
  - 0 = The program or erase operation completed normally.
- bit 2 WREN: Program/Erase Enable bit
  - 1 = Allows program/erase cycles
  - 0 = Inhibits programming/erasing of program Flash and data EEPROM
- bit 1 WR: Write Control bit
  - 1 = Initiates a program Flash or data EEPROM program/erase operation. The operation is self-timed and the bit is cleared by hardware once operation is complete. The WR bit can only be set (not cleared) in software.
  - 0 = Program/erase operation to the Flash or data EEPROM is complete and inactive.
- bit 0 RD: Read Control bit
  - 1 = Initiates an program Flash or data EEPROM read. Read takes one cycle. RD is cleared in hardware. The RD bit can only be set (not cleared) in software.
  - 0 = Does not initiate a program Flash or data EEPROM data read.

#### REGISTER 11-6: EECON2: EEPROM CONTROL 2 REGISTER

| W-0/0                     | W-0/0 | W-0/0 | W-0/0 | W-0/0 | W-0/0 | W-0/0 | W-0/0 |  |
|---------------------------|-------|-------|-------|-------|-------|-------|-------|--|
| EEPROM Control Register 2 |       |       |       |       |       |       |       |  |
| bit 7                     |       |       |       |       |       |       | bit 0 |  |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

S = Bit can only be set x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

#### bit 7-0 Data EEPROM Unlock Pattern bits

To unlock writes, a 55h must be written first, followed by an AAh, before setting the WR bit of the EECON1 register. The value written to this register is used to unlock the writes. There are specific timing requirements on these writes. Refer to **Section 11.2.2 "Writing to the Data EEPROM Memory"** for more information.

#### TABLE 11-3: SUMMARY OF REGISTERS ASSOCIATED WITH DATA EEPROM

| Name   | Bit 7 | Bit 6       | Bit 5                               | Bit 4         | Bit 3          | Bit 2           | Bit 1 | Bit 0  | Register on Page |  |  |
|--------|-------|-------------|-------------------------------------|---------------|----------------|-----------------|-------|--------|------------------|--|--|
| EECON1 | EEPGD | CFGS        | LWLO                                | FREE          | WRERR          | WREN            | WR    | RD     | 127              |  |  |
| EECON2 |       |             | EEPROM Co                           | ntrol Registe | r 2 (not a phy | sical register) |       |        | 115*             |  |  |
| EEADRL |       | EEADRL<7:0> |                                     |               |                |                 |       |        |                  |  |  |
| EEADRH | _     |             |                                     |               | EEADRH<6:0     | )               |       |        | 126              |  |  |
| EEDATL |       |             |                                     | EEDAT         | TL<7:0>        |                 |       |        | 126              |  |  |
| EEDATH | _     | _           |                                     |               | EEDAT          | H<5:0>          |       |        | 126              |  |  |
| INTCON | GIE   | PEIE        | TMR0IE                              | INTE          | IOCIE          | TMR0IF          | INTF  | IOCIF  | 98               |  |  |
| PIE2   | OSFIE | C2IE        | C2IE C1IE EEIE BCLIE LCDIE — CCP2IE |               |                |                 |       |        |                  |  |  |
| PIR2   | OSFIF | C2IF        | C1IF                                | EEIF          | BCLIF          | LCDIF           | _     | CCP2IF | 103              |  |  |

Legend: — = unimplemented location, read as '0'. Shaded cells are not used by the data EEPROM module.

<sup>\*</sup> Page provides register information.

#### 12.0 I/O PORTS

Depending on the device selected and peripherals enabled, there are up to five ports available. In general, when a peripheral is enabled on a port pin, that pin cannot be used as a general purpose output. However, the pin can still be read.

Each port has three standard registers for its operation. These registers are:

- TRISx registers (data direction)
- PORTx registers (reads the levels on the pins of the device)
- LATx registers (output latch)

Some ports may have one or more of the following additional registers. These registers are:

- · ANSELx (analog select)
- WPUx (weak pull-up)
- · INLVLx (input level control)

TABLE 12-1: PORT AVAILABILITY PER DEVICE


| Device        | PORTA | PORTB | PORTC | PORTD | PORTE |
|---------------|-------|-------|-------|-------|-------|
| PIC16(L)F1934 | •     | •     | •     | •     | •     |
| PIC16(L)F1936 | •     | •     | •     |       | •     |
| PIC16(L)F1937 | •     | •     | •     | •     | •     |

The Data Latch (LATx registers) is useful for read-modify-write operations on the value that the I/O pins are driving.

A write operation to the LATx register has the same effect as a write to the corresponding PORTx register. A read of the LATx register reads of the values held in the I/O PORT latches, while a read of the PORTx register reads the actual I/O pin value.

Ports that support analog inputs have an associated ANSELx register. When an ANSEL bit is set, the digital input buffer associated with that bit is disabled. Disabling the input buffer prevents analog signal levels on the pin between a logic high and low from causing excessive current in the logic input circuitry. A simplified model of a generic I/O port, without the interfaces to other peripherals, is shown in Figure 12-1.

FIGURE 12-1: GENERIC I/O PORT OPERATION



#### **EXAMPLE 12-1: INITIALIZING PORTA**

```
; This code example illustrates
; initializing the PORTA register. The
; other ports are initialized in the same
; manner.
BANKSEL PORTA
CLRF
        PORTA
                     ;Init PORTA
BANKSEL LATA
                     ;Data Latch
CLRF
        T.ATA
BANKSEL ANSELA
                     ;digital I/O
CLRF
        ANSELA
BANKSEL TRISA
MOVLW B'00111000'
                    ;Set RA<5:3> as inputs
MOVWE
                     ;and set RA<2:0> as
        TRISA
                     ;outputs
```

#### 12.1 Alternate Pin Function

The Alternate Pin Function Control (APFCON) register is used to steer specific peripheral input and output functions between different pins. The APFCON register is shown in Register 12-1. For this device family, the following functions can be moved between different pins.

- SS (Slave Select)
- · P2B output
- · CCP2/P2A output
- CCP3/P3A output
- · Timer1 Gate
- · SR Latch SRNQ output
- · Comparator C2 output

These bits have no effect on the values of any TRIS register. PORT and TRIS overrides will be routed to the correct pin. The unselected pin will be unaffected.

#### REGISTER 12-1: APFCON: ALTERNATE PIN FUNCTION CONTROL REGISTER

| U-0   | R/W-0/0 | R/W-0/0 | R/W-0/0 | R/W-0/0 | R/W-0/0  | R/W-0/0 | R/W-0/0 |
|-------|---------|---------|---------|---------|----------|---------|---------|
| _     | CCP3SEL | T1GSEL  | P2BSEL  | SRNQSEL | C2OUTSEL | SSSEL   | CCP2SEL |
| bit 7 |         |         |         |         |          |         | bit 0   |

Legend:R = Readable bitW = Writable bitU = Unimplemented bit, read as '0'u = bit is unchangedx = Bit is unknown-n/n = Value at POR and BOR/Value at all other Resets'1' = Bit is set'0' = Bit is cleared

bit 7 Unimplemented: Read as '0'.

bit 6 CCP3SEL: CCP3 Input/Output Pin Selection bit

For 28-Pin Devices (PIC16F1936):

0 = CCP3/P3A function is on RC6/TX/CK/CCP3/P3A/SEG9

1 = CCP3/P3A function is on RB5/AN13/CPS5/CCP3/P3A/T1G/COM1

For 40-Pin Devices (PIC16F1934/7):

0 = CCP3/P3A function is on RE0/AN5/CCP3/P3A/SEG21

1 = CCP3/P3A function is on RB5/AN13/CPS5/CCP3/P3A/T1G/COM1

bit 5 T1GSEL: Timer1 Gate Input Pin Selection bit

0 = T1G function is on RB5/AN13/CPS5/CCP3/P3A/T1G/COM1

1 = T1G function is on RC4/SDI/SDA/T1G/SEG11

bit 4 P2BSEL: CCP2 PWM B Output Pin Selection bit

For 28-Pin Devices (PIC16F1936):

0 = P2B function is on RC0/T1OSO/T1CKI/P2B

1 = P2B function is on RB5/AN13/P2B/CPS5/T1G/COM1

For 40-Pin Devices (PIC16F1934/7):

0 = P2B function is on RC0/T1OSO/T1CKI/P2B

1 = P2B function is on RD2/CPS10/P2B

bit 3 SRNQSEL: SR Latch nQ Output Pin Selection bit

0 = SRnQ function is on RA5/AN4/C2OUT/SRnQ/SS/CPS7/SEG5/VCAP 1 = SRnQ function is on RA0/AN0/C12IN0-/C2OUT/SRnQ/SS/SEG12/VCAP

bit 2 C2OUTSEL: Comparator C2 Output Pin Selection bit

0 = C2OUT function is on RA5/AN4/C2OUT/SRnQ/SS/CPS7/SEG5/VCAP

1 = C2OUT function is on RA0/AN0/C12IN0-/C2OUT/SRnQ/SS/SEG12/VCAP

bit 1 SSSEL: SS Input Pin Selection bit

0 = SS function is on RA5/AN4/C2OUT/SRNQ/SS/CPS7/SEG5/VCAP

1 = SS function is on RA0/AN0/C12IN0-/C2OUT/SRNQ/SS/SEG12/VCAP

bit 0 CCP2SEL: CCP2 Input/Output Pin Selection bit

0 = CCP2/P2A function is on RC1/T1OSI/CCP2/P2A

1 = CCP2/P2A function is on RB3/AN9/C12IN2-/CPS3/CCP2/P2A/VLCD3

#### 12.2 PORTA Registers

PORTA is a 8-bit wide, bidirectional port. The corresponding data direction register is TRISA (Register 12-3). Setting a TRISA bit (= 1) will make the corresponding PORTA pin an input (i.e., disable the output driver). Clearing a TRISA bit (= 0) will make the corresponding PORTA pin an output (i.e., enables output driver and puts the contents of the output latch on the selected pin). Example 12-1 shows how to initialize an I/O port.

Reading the PORTA register (Register 12-2) reads the status of the pins, whereas writing to it will write to the PORT latch. All write operations are read-modify-write operations. Therefore, a write to a port implies that the port pins are read, this value is modified and then written to the PORT data latch (LATA).

The TRISA register (Register 12-3) controls the PORTA pin output drivers, even when they are being used as analog inputs. The user should ensure the bits in the TRISA register are maintained set when using them as analog inputs. I/O pins configured as analog input always read '0'.

#### 12.2.1 ANSELA REGISTER

The ANSELA register (Register 12-5) is used to configure the Input mode of an I/O pin to analog. Setting the appropriate ANSELA bit high will cause all digital reads on the pin to be read as '0' and allow analog functions on the pin to operate correctly.

The state of the ANSELA bits has no effect on digital output functions. A pin with TRIS clear and ANSEL set will still operate as a digital output, but the Input mode will be analog. This can cause unexpected behavior when executing read-modify-write instructions on the affected port.

Note: The ANSELA bits default to the Analog mode after Reset. To use any pins as digital general purpose or peripheral inputs, the corresponding ANSEL bits must be initialized to '0' by user software.

# 12.2.2 PORTA FUNCTIONS AND OUTPUT PRIORITIES

Each PORTA pin is multiplexed with other functions. The pins, their combined functions and their output priorities are shown in Table 12-2.

When multiple outputs are enabled, the actual pin control goes to the peripheral with the highest priority.

Analog input functions, such as ADC, comparator and CapSense inputs, are not shown in the priority lists. These inputs are active when the I/O pin is set for Analog mode using the ANSELx registers. Digital output functions may control the pin when it is in Analog mode with the priority shown in Table 12-2.

TABLE 12-2: PORTA OUTPUT PRIORITY

| Pin Name | Function Priority <sup>(1)</sup>  |
|----------|---|
| RA0      | VCAP<br>SEG12 (LCD)<br>SRNQ (SR Latch)<br>C2OUT (Comparator)<br>RA0   |
| RA1      | SEG7 (LCD)<br>RA1   |
| RA2      | COM2 (LCD)<br>AN2 (DAC)<br>RA2  |
| RA3      | COM3 (LCD) 28-pin only<br>SEG15<br>RA3  |
| RA4      | SEG4 (LCD) SRQ (SR Latch) C1OUT (Comparator) CCP5, 28-pin only RA4  |
| RA5      | VCAP (enabled by Config. Word) SEG5 (LCD) SRNQ (SR Latch) C2OUT (Comparator) RA5                              |
| RA6      | VCAP (enabled by Config. Word) OSC2 (enabled by Config. Word) CLKOUT (enabled by Config. Word) SEG1 (LCD) RA6 |
| RA7      | OSC1/CLKIN (enabled by Config. Word)<br>SEG2 (LCD)<br>RA7   |

**Note 1:** Priority listed from highest to lowest.

#### **REGISTER 12-2: PORTA: PORTA REGISTER**

| R/W-x/u |
|---------|---------|---------|---------|---------|---------|---------|---------|
| RA7     | RA6     | RA5     | RA4     | RA3     | RA2     | RA1     | RA0     |
| bit 7   |         |         |         |         |         |         | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 RA<7:0>: PORTA I/O Value bits<sup>(1)</sup>

1 = Port pin is > VIH 0 = Port pin is < VIL

**Note 1:** Writes to PORTA are actually written to corresponding LATA register. Reads from PORTA register is return of actual I/O pin values.

#### **REGISTER 12-3: TRISA: PORTA TRI-STATE REGISTER**

| R/W-1/1 |
|---------|---------|---------|---------|---------|---------|---------|---------|
| TRISA7  | TRISA6  | TRISA5  | TRISA4  | TRISA3  | TRISA2  | TRISA1  | TRISA0  |
| bit 7   |         |         |         |         |         |         | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 TRISA<7:0>: PORTA Tri-State Control bit

1 = PORTA pin configured as an input (tri-stated)

0 = PORTA pin configured as an output

#### REGISTER 12-4: LATA: PORTA DATA LATCH REGISTER

| R/W-x/u |
|---------|---------|---------|---------|---------|---------|---------|---------|
| LATA7   | LATA6   | LATA5   | LATA4   | LATA3   | LATA2   | LATA1   | LATA0   |
| bit 7   |         |         |         |         |         |         | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 LATA<7:0>: PORTA Output Latch Value bits<sup>(1)</sup>

**Note 1:** Writes to PORTA are actually written to corresponding LATA register. Reads from PORTA register is return of actual I/O pin values.

#### REGISTER 12-5: ANSELA: PORTA ANALOG SELECT REGISTER

| U-0   | U-0 | R/W-1/1 | R/W-1/1 | R/W-1/1 | R/W-1/1 | R/W-1/1 | R/W-1/1 |
|-------|-----|---------|---------|---------|---------|---------|---------|
| _     | _   | ANSA5   | ANSA4   | ANSA3   | ANSA2   | ANSA1   | ANSA0   |
| bit 7 |     |         |         |         |         |         | bit 0   |

Legend:R = Readable bitW = Writable bitU = Unimplemented bit, read as '0'u = Bit is unchangedx = Bit is unknown-n/n = Value at POR and BOR/Value at all other Resets'1' = Bit is set'0' = Bit is cleared

bit 7-6 **Unimplemented:** Read as '0'

bit 5-0 ANSA<5:0>: Analog Select between Analog or Digital Function on pins RA<5:0>, respectively

0 = Digital I/O. Pin is assigned to port or digital special function.

1 = Analog input. Pin is assigned as analog input<sup>(1)</sup>. Digital input buffer disabled.

**Note 1:** When setting a pin to an analog input, the corresponding TRIS bit must be set to Input mode in order to allow external control of the voltage on the pin.

TABLE 12-3: SUMMARY OF REGISTERS ASSOCIATED WITH PORTA

| Name       | Bit 7  | Bit 6   | Bit 5      | Bit 4    | Bit 3                    | Bit 2    | Bit 1       | Bit 0   | Register<br>on Page |
|------------|--------|---------|------------|----------|--------------------------|----------|-------------|---------|---------------------|
| ADCON0     | _      |         |            | CHS<4:0> |                          |          | GO/DONE     | ADON    | 163                 |
| ADCON1     | ADFM   |         | ADCS<2:0>  |          | _                        | ADNREF   | ADPREF<1:0> |         | 164                 |
| ANSELA     | _      | _       | ANSA5      | ANSA4    | ANSA3                    | ANSA2    | ANSA1       | ANSA0   | 134                 |
| APFCON     | _      | CCP3SEL | T1GSEL     | P2BSEL   | SRNQSEL                  | C2OUTSEL | SSSEL       | CCP2SEL | 131                 |
| CM1CON0    | C10N   | C10UT   | C10E       | C1POL    | _                        | C1SP     | C1HYS       | C1SYNC  | 183                 |
| CM2CON0    | C2ON   | C2OUT   | C2OE       | C2POL    | _                        | C2SP     | C2HYS       | C2SYNC  | 183                 |
| CM1CON1    | C1NTP  | C1INTN  | C1PCI      | H<1:0>   | _                        | _        | C1NCI       | H<1:0>  | 184                 |
| CM2CON1    | C2NTP  | C2INTN  | C2PCI      | H<1:0>   | — — C2NCH<1:0>           |          |             |         | 184                 |
| CPSCON0    | CPSON  | _       | _          | _        | CPSRNG<1:0> CPSOUT T0XCS |          |             |         | 323                 |
| CPSCON1    | _      | _       | _          | _        |                          | CPSCI    | H<3:0>      |         | 324                 |
| DACCON0    | DACEN  | DACLPS  | DACOE      |          | DACPS                    | SS<1:0>  |             | DACNSS  | 176                 |
| LATA       | LATA7  | LATA6   | LATA5      | LATA4    | LATA3                    | LATA2    | LATA1       | LATA0   | 133                 |
| LCDCON     | LCDEN  | SLPEN   | WERR       | _        | CS<                      | 1:0>     | LMUX        | <1:0>   | 329                 |
| LCDSE0     | SE7    | SE6     | SE5        | SE4      | SE3                      | SE2      | SE1         | SE0     | 333                 |
| LCDSE1     | SE15   | SE14    | SE13       | SE12     | SE11                     | SE10     | SE9         | SE8     | 333                 |
| OPTION_REG | WPUEN  | INTEDG  | TMR0CS     | TMR0SE   | PSA                      |          | PS<2:0>     |         | 193                 |
| PORTA      | RA7    | RA6     | RA5        | RA4      | RA3                      | RA2      | RA1         | RA0     | 133                 |
| SRCON0     | SRLEN  | ;       | SRCLK<2:0> |          | SRQEN                    | SRNQEN   | SRPS        | SRPR    | 189                 |
| SSPCON1    | WCOL   | SSPOV   | SSPEN      | CKP      |                          | SSPM     | l<3:0>      |         | 287                 |
| TRISA      | TRISA7 | TRISA6  | TRISA5     | TRISA4   | TRISA3                   | TRISA2   | TRISA1      | TRISA0  | 133                 |

**Legend:** x = unknown, u = unchanged, – = unimplemented locations read as '0'. Shaded cells are not used by PORTA.

TABLE 12-4: SUMMARY OF CONFIGURATION WORD WITH PORTA

| Name    | Bits | Bit -/7 | Bit -/6 | Bit 13/5 | Bit 12/4              | Bit 11/3 | Bit 10/2 | Bit 9/1   | Bit 8/0 | Register on Page |
|---------|------|---------|---------|----------|-----------------------|----------|----------|-----------|---------|------------------|
| CONFICA | 13:8 | 1       | 1       | FCMEN    | IESO                  | CLKOUTEN | BORE     | N<1:0>    | CPD     | 60               |
| CONFIG1 | 7:0  | CP      | MCLRE   | PWRTE    | WDTE                  | E<1:0>   |          | FOSC<2:0> |         | 62               |
| CONFICE | 13:8 | _       | _       | LVP      | DEBUG                 | _        | BORV     | STVREN    | PLLEN   | 0.4              |
| CONFIG2 | 7:0  | _       | _       | VCAPEN   | V<1:0> <sup>(1)</sup> | _        | _        | WRT       | <1:0>   | 64               |

**Legend:** — = unimplemented location, read as '0'. Shaded cells are not used by PORTA.

Note 1: PIC16F1934/6/7 only.

#### 12.3 PORTB Registers

PORTB is an 8-bit wide, bidirectional port. The corresponding data direction register is TRISB (Register 12-7). Setting a TRISB bit (= 1) will make the corresponding PORTB pin an input (i.e., put the corresponding output driver in a High-Impedance mode). Clearing a TRISB bit (= 0) will make the corresponding PORTB pin an output (i.e., enable the output driver and put the contents of the output latch on the selected pin). Example 12-1 shows how to initialize an I/O port.

Reading the PORTB register (Register 12-6) reads the status of the pins, whereas writing to it will write to the PORT latch. All write operations are read-modify-write operations. Therefore, a write to a port implies that the port pins are read, this value is modified and then written to the PORT data latch (LATB).

The TRISB register (Register 12-7) controls the PORTB pin output drivers, even when they are being used as analog inputs. The user should ensure the bits in the TRISB register are maintained set when using them as analog inputs. I/O pins configured as analog input always read '0'.

#### 12.3.1 WEAK PULL-UPS

Each of the PORTB pins has an individually configurable internal weak pull-up. Control bits WPUB<7:0> enable or disable each pull-up (see Register 12-10). Each weak pull-up is automatically turned off when the port pin is configured as an output. All pull-ups are disabled on a Power-on Reset by the WPUEN bit of the OPTION\_REG register.

#### 12.3.2 INTERRUPT-ON-CHANGE

All of the PORTB pins are individually configurable as an interrupt-on-change pin. Control bits IOCB<7:0> enable or disable the interrupt function for each pin. The interrupt-on-change feature is disabled on a Power-on Reset.

Reference
Section 13.0
"Interrupt-On-Change" for more information.

#### 12.3.3 ANSELB REGISTER

The ANSELB register (Register 12-9) is used to configure the Input mode of an I/O pin to analog. Setting the appropriate ANSELB bit high will cause all digital reads on the pin to be read as '0' and allow analog functions on the pin to operate correctly.

The state of the ANSELB bits has no effect on digital output functions. A pin with TRIS clear and ANSELB set will still operate as a digital output, but the Input mode will be analog. This can cause unexpected behavior when executing read-modify-write instructions on the affected port.

Note:

The ANSELB bits default to the Analog mode after Reset. To use any pins as digital general purpose or peripheral inputs, the corresponding ANSEL bits must be initialized to '0' by user software.

# 12.3.4 PORTB FUNCTIONS AND OUTPUT PRIORITIES

Each PORTB pin is multiplexed with other functions. The pins, their combined functions and their output priorities are shown in Table 12-5.

When multiple outputs are enabled, the actual pin control goes to the peripheral with the highest priority.

Analog input and some digital input functions are not included in the list below. These input functions can remain active when the pin is configured as an output. Certain digital input functions override other port functions and are included in Table 12-5.

**TABLE 12-5: PORTB OUTPUT PRIORITY** 

| Pin Name | Function Priority <sup>(1)</sup>                                       |
|----------|--|
| RB0      | SEG0 (LCD)<br>CCP4, 28-pin only<br>RB0                                 |
| RB1      | P1C (ECCP1), 28-pin only<br>RB1  |
| RB2      | P1B (ECCP1), 28-pin only<br>RB2  |
| RB3      | CCP2/P2A<br>RB3  |
| RB4      | COM0<br>P1D, 28-pin only<br>RB4  |
| RB5      | COM1<br>P2B, 28-pin only<br>CCP3/P3A<br>RB5                            |
| RB6      | ICSPCLK (Programming) ICDCLK (enabled by Config. Word) SEG14 (LCD) RB6 |
| RB7      | ICSPDAT (Programming) ICDDAT (enabled by Config. Word) SEG13 (LCD) RB7 |

Note 1: Priority listed from highest to lowest.

#### REGISTER 12-6: PORTB: PORTB REGISTER

| R/W-x/u |
|---------|---------|---------|---------|---------|---------|---------|---------|
| RB7     | RB6     | RB5     | RB4     | RB3     | RB2     | RB1     | RB0     |
| bit 7   |         |         |         |         |         |         | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 **RB<7:0>**: PORTB I/O Pin bit

1 = Port pin is > VIH 0 = Port pin is < VIL

#### REGISTER 12-7: TRISB: PORTB TRI-STATE REGISTER

| R/W-1/1 |
|---------|---------|---------|---------|---------|---------|---------|---------|
| TRISB7  | TRISB6  | TRISB5  | TRISB4  | TRISB3  | TRISB2  | TRISB1  | TRISB0  |
| bit 7   |         |         |         |         |         |         | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 TRISB<7:0>: PORTB Tri-State Control bit

1 = PORTB pin configured as an input (tri-stated)

0 = PORTB pin configured as an output

#### REGISTER 12-8: LATB: PORTB DATA LATCH REGISTER

| R/W-x/u |
|---------|---------|---------|---------|---------|---------|---------|---------|
| LATB7   | LATB6   | LATB5   | LATB4   | LATB3   | LATB2   | LATB1   | LATB0   |
| bit 7   |         |         |         |         |         |         | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 LATB<7:0>: PORTB Output Latch Value bits<sup>(1)</sup>

**Note 1:** Writes to PORTB are actually written to corresponding LATB register. Reads from PORTB register is return of actual I/O pin values.

#### REGISTER 12-9: ANSELB: PORTB ANALOG SELECT REGISTER

| U-0   | U-0 | R/W-1/1 | R/W-1/1 | R/W-1/1 | R/W-1/1 | R/W-1/1 | R/W-1/1 |
|-------|-----|---------|---------|---------|---------|---------|---------|
| _     | _   | ANSB5   | ANSB4   | ANSB3   | ANSB2   | ANSB1   | ANSB0   |
| bit 7 |     |         |         |         |         |         | bit 0   |

| Legend:              |                      |   |
|----------------------|----------------------|---|
| R = Readable bit     | W = Writable bit     | U = Unimplemented bit, read as '0'                    |
| u = Bit is unchanged | x = Bit is unknown   | -n/n = Value at POR and BOR/Value at all other Resets |
| '1' = Bit is set     | '0' = Bit is cleared |   |

bit 7-6 **Unimplemented:** Read as '0'

bit 5-0 ANSB<5:0>: Analog Select between Analog or Digital Function on Pins RB<5:0>, respectively

0 = Digital I/O. Pin is assigned to port or digital special function.

1 = Analog input. Pin is assigned as analog input<sup>(1)</sup>. Digital input buffer disabled.

**Note 1:** When setting a pin to an analog input, the corresponding TRIS bit must be set to Input mode in order to allow external control of the voltage on the pin.

#### REGISTER 12-10: WPUB: WEAK PULL-UP PORTB REGISTER

| R/W-1/1 |
|---------|---------|---------|---------|---------|---------|---------|---------|
| WPUB7   | WPUB6   | WPUB5   | WPUB4   | WPUB3   | WPUB2   | WPUB1   | WPUB0   |
| bit 7   |         |         |         |         |         |         | bit 0   |

| Legend:              |                      |   |
|----------------------|----------------------|---|
| R = Readable bit     | W = Writable bit     | U = Unimplemented bit, read as '0'                    |
| u = Bit is unchanged | x = Bit is unknown   | -n/n = Value at POR and BOR/Value at all other Resets |
| '1' = Bit is set     | '0' = Bit is cleared |   |

bit 7-0 WPUB<7:0>: Weak Pull-up Register bits

1 = Pull-up enabled0 = Pull-up disabled

**Note 1:** Global WPUEN bit of the OPTION\_REG register must be cleared for individual pull-ups to be enabled.

2: The weak pull-up device is automatically disabled if the pin is in configured as an output.

TABLE 12-6: SUMMARY OF REGISTERS ASSOCIATED WITH PORTB

| Name       | Bit 7  | Bit 6   | Bit 5  | Bit 4   | Bit 3      | Bit 2    | Bit 1   | Bit 0   | Register on Page |
|------------|--------|---------|--------|---------|------------|----------|---------|---------|------------------|
| ADCON0     | _      |         |        | CHS<4:0 | >          |          | GO/DONE | ADON    | 163              |
| ANSELB     | _      | _       | ANSB5  | ANSB4   | ANSB3      | ANSB2    | ANSB1   | ANSB0   | 139              |
| APFCON     | _      | CCP3SEL | T1GSEL | P2BSEL  | SRNQSEL    | C2OUTSEL | SSSEL   | CCP2SEL | 131              |
| CCPxCON    | PxM<   | <1:0>   | DCxB   | <1:0>   |            | CCPxM<   | 3:0>    |         | 234              |
| CPSCON0    | CPSON  | _       | _      | _       | CPSRNG     | <1:0>    | CPSOUT  | T0XCS   | 323              |
| CPSCON1    | _      | _       | _      | _       |            | CPSCH-   | <3:>    |         | 324              |
| INTCON     | GIE    | PEIE    | TMR0IE | INTE    | IOCIE      | TMR0IF   | INTF    | IOCIF   | 98               |
| IOCBP      | IOCBP7 | IOCBP6  | IOCBP5 | IOCBP4  | IOCBP3     | IOCBP2   | IOCBP1  | IOCBP0  | 152              |
| IOCBN      | IOCBN7 | IOCBN6  | IOCBN5 | IOCBN4  | IOCBN3     | IOCBN2   | IOCBN1  | IOCBN0  | 152              |
| IOCBF      | IOCBF7 | IOCBF6  | IOCBF5 | IOCBF4  | IOCBF3     | IOCBF2   | IOCBF1  | IOCBF0  | 152              |
| LATB       | LATB7  | LATB6   | LATB5  | LATB4   | LATB3      | LATB2    | LATB1   | LATB0   | 138              |
| LCDCON     | LCDEN  | SLPEN   | WERR   | _       | CS<1:      | 0>       | LMUX    | <1:0>   | 329              |
| LCDSE0     | SE7    | SE6     | SE5    | SE4     | SE3        | SE2      | SE1     | SE0     | 333              |
| LCDSE1     | SE15   | SE14    | SE13   | SE12    | SE11       | SE10     | SE9     | SE8     | 333              |
| OPTION_REG | WPUEN  | INTEDG  | TMR0CS | TMR0SE  | PSA        |          | PS<2:0> |         | 193              |
| PORTB      | RB7    | RB6     | RB5    | RB4     | RB3        | RB2      | RB1     | RB0     | 138              |
| T1GCON     | TMR1GE | T1GPOL  | T1GTM  | T1GSPM  | T1GGO/DONE | T1GVAL   | T1GS    | S<1:0>  | 204              |
| TRISB      | TRISB7 | TRISB6  | TRISB5 | TRISB4  | TRISB3     | TRISB2   | TRISB1  | TRISB0  | 138              |
| WPUB       | WPUB7  | WPUB6   | WPUB5  | WPUB4   | WPUB3      | WPUB2    | WPUB1   | WPUB0   | 139              |

**Legend:** x = unknown, u = unchanged, - = unimplemented locations read as '0'. Shaded cells are not used by PORTB.

#### 12.4 PORTC Registers

PORTC is a 8-bit wide, bidirectional port. The corresponding data direction register is TRISC (Register 12-12). Setting a TRISC bit (= 1) will make the corresponding PORTC pin an input (i.e., put the corresponding output driver in a High-Impedance mode). Clearing a TRISC bit (= 0) will make the corresponding PORTC pin an output (i.e., enable the output driver and put the contents of the output latch on the selected pin). Example 12-1 shows how to initialize an I/O port.

Reading the PORTC register (Register 12-11) reads the status of the pins, whereas writing to it will write to the PORT latch. All write operations are read-modify-write operations. Therefore, a write to a port implies that the port pins are read, this value is modified and then written to the PORT data latch (LATC).

The TRISC register (Register 12-12) controls the PORTC pin output drivers, even when they are being used as analog inputs. The user should ensure the bits in the TRISC register are maintained set when using them as analog inputs. I/O pins configured as analog input always read '0'.

# 12.4.1 PORTC FUNCTIONS AND OUTPUT PRIORITIES

Each PORTC pin is multiplexed with other functions. The pins, their combined functions and their output priorities are shown in Table 12-7.

When multiple outputs are enabled, the actual pin control goes to the peripheral with the highest priority.

Analog input and some digital input functions are not included in the list below. These input functions can remain active when the pin is configured as an output. Certain digital input functions override other port functions and are included in Table 12-7.

TABLE 12-7: PORTC OUTPUT PRIORITY

| Pin Name | Function Priority <sup>(1)</sup>                              |
|----------|---|
| RC0      | T1OSO (Timer1 Oscillator)<br>CCP2/P2B<br>RC0                  |
| RC1      | T1OSI (Timer1 Oscillator)<br>CCP2/P2A<br>RC1                  |
| RC2      | SEG3 (LCD)<br>CCP1/P1A<br>RC2                                 |
| RC3      | SEG6 (LCD)<br>SCL (MSSP)<br>SCK (MSSP)<br>RC3                 |
| RC4      | SEG11 (LCD)<br>SDA (MSSP)<br>RC4                              |
| RC5      | SEG10 (LCD)<br>SDO (MSSP)<br>RC5                              |
| RC6      | ISEG9 (LCD) TX (EUSART) CK (EUSART) CCP3/P3A, 28-pin only RC6 |
| RC7      | SEG8 (LCD)<br>DT (EUSART)<br>CCP3/P3B, 28 pin only<br>RC7     |

**Note 1:** Priority listed from highest to lowest.

#### REGISTER 12-11: PORTC: PORTC REGISTER

| R/W-x/u |
|---------|---------|---------|---------|---------|---------|---------|---------|
| RC7     | RC6     | RC5     | RC4     | RC3     | RC2     | RC1     | RC0     |
| bit 7   |         |         |         |         |         |         | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 RC<7:0>: PORTC General Purpose I/O Pin bits

1 = Port pin is > VIH 0 = Port pin is < VIL

#### REGISTER 12-12: TRISC: PORTC TRI-STATE REGISTER

| R/W-1/1 |
|---------|---------|---------|---------|---------|---------|---------|---------|
| TRISC7  | TRISC6  | TRISC5  | TRISC4  | TRISC3  | TRISC2  | TRISC1  | TRISC0  |
| bit 7   |         |         |         |         |         |         | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 TRISC<7:0>: PORTC Tri-State Control bits

1 = PORTC pin configured as an input (tri-stated)

0 = PORTC pin configured as an output

#### REGISTER 12-13: LATC: PORTC DATA LATCH REGISTER

| R/W-x/u |
|---------|---------|---------|---------|---------|---------|---------|---------|
| LATC7   | LATC6   | LATC5   | LATC4   | LATC3   | LATC2   | LATC1   | LATC0   |
| bit 7   |         |         |         |         |         |         | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 LATC<7:0>: PORTC Output Latch Value bits<sup>(1)</sup>

Note 1: Writes to PORTC are actually written to corresponding LATC register. Reads from PORTC register is

return of actual I/O pin values.

TABLE 12-8: SUMMARY OF REGISTERS ASSOCIATED WITH PORTC

| Name    | Bit 7       | Bit 6   | Bit 5       | Bit 4  | Bit 3      | Bit 2    | Bit 1        | Bit 0   | Register<br>on Page |
|---------|-------------|---------|-------------|--------|------------|----------|--------------|---------|---------------------|
| APFCON  | _           | CCP3SEL | T1GSEL      | P2BSEL | SRNQSEL    | C2OUTSEL | SSSEL        | CCP2SEL | 131                 |
| CCPxCON | PxM<1:0>    |         | DCxB<1:0>   |        | CCPxM<3:0> |          |              |         | 234                 |
| LATC    | LATC7       | LATC6   | LATC5       | LATC4  | LATC3      | LATC2    | LATC1        | LATC0   | 142                 |
| LCDCON  | LCDEN       | SLPEN   | WERR        | _      | CS<        | 1:0>     | 0> LMUX<1:0> |         | 329                 |
| LCDSE0  | SE7         | SE6     | SE5         | SE4    | SE3        | SE2      | SE1          | SE0     | 333                 |
| LCDSE1  | SE15        | SE14    | SE13        | SE12   | SE11       | SE10     | SE9          | SE8     | 333                 |
| PORTC   | RC7         | RC6     | RC5         | RC4    | RC3        | RC2      | RC1          | RC0     | 142                 |
| RCSTA   | SPEN        | RX9     | SREN        | CREN   | ADDEN      | FERR     | OERR         | RX9D    | 301                 |
| SSPCON1 | WCOL        | SSPOV   | SSPEN       | CKP    | SSPM<3:0>  |          |              | 287     |                     |
| SSPSTAT | SMP         | CKE     | D/A         | Р      | S          | R/W      | UA           | BF      | 286                 |
| T1CON   | TMR1CS<1:0> |         | T1CKPS<1:0> |        | T10SCEN    | T1SYNC   | _            | TMR10N  | 203                 |
| TXSTA   | CSRC        | TX9     | TXEN        | SYNC   | _          | BRGH     | TRMT         | TX9D    | 300                 |
| TRISC   | TRISC7      | TRISC6  | TRISC5      | TRISC4 | TRISC3     | TRISC2   | TRISC1       | TRISC0  | 142                 |

**Legend:** x = unknown, u = unchanged, - = unimplemented locations read as '0'. Shaded cells are not used by PORTC.

#### 12.5 PORTD Registers

PORTD is a 8-bit wide, bidirectional port. The corresponding data direction register is TRISD (Register 12-14). Setting a TRISD bit (= 1) will make the corresponding PORTD pin an input (i.e., put the corresponding output driver in a High-Impedance mode). Clearing a TRISD bit (= 0) will make the corresponding PORTD pin an output (i.e., enable the output driver and put the contents of the output latch on the selected pin). Example 12-1 shows how to initialize an I/O port.

Reading the PORTD register (Register 12-14) reads the status of the pins, whereas writing to it will write to the PORT latch. All write operations are read-modify-write operations. Therefore, a write to a port implies that the port pins are read, this value is modified and then written to the PORT data latch (LATD).

**Note:** PORTD is available on PIC16(L)F1934 and PIC16(L)F1937 only.

The TRISD register (Register 12-15) controls the PORTD pin output drivers, even when they are being used as analog inputs. The user should ensure the bits in the TRISD register are maintained set when using them as analog inputs. I/O pins configured as analog input always read '0'.

#### 12.5.1 ANSELD REGISTER

The ANSELD register (Register 12-17) is used to configure the Input mode of an I/O pin to analog. Setting the appropriate ANSELD bit high will cause all digital reads on the pin to be read as '0' and allow analog functions on the pin to operate correctly.

The state of the ANSELD bits has no effect on digital output functions. A pin with TRIS clear and ANSEL set will still operate as a digital output, but the Input mode will be analog. This can cause unexpected behavior when executing read-modify-write instructions on the affected port.

Note: The ANSELD bits default to the Analog mode after Reset. To use any pins as digital general purpose or peripheral inputs, the corresponding ANSEL bits must be initialized to '0' by user software.

# 12.5.2 PORTD FUNCTIONS AND OUTPUT PRIORITIES

Each PORTD pin is multiplexed with other functions. The pins, their combined functions and their output priorities are shown in Table 12-9.

When multiple outputs are enabled, the actual pin control goes to the peripheral with the highest priority.

Analog input and some digital input functions are not included in the list below. These input functions can remain active when the pin is configured as an output. Certain digital input functions override other port functions and are included in Table 12-9.

TABLE 12-9: PORTD OUTPUT PRIORITY

| Pin Name | Function Priority <sup>(1)</sup> |  |  |  |
|----------|----------------------------------|--|--|--|
| RD0      | COM3 (LCD)<br>RD0                |  |  |  |
| RD1      | CCP4 (CCP)<br>RD1                |  |  |  |
| RD2      | P2B (CCP)<br>RD2                 |  |  |  |
| RD3      | SEG16 (LCD)<br>P2C (CCP)<br>RD3  |  |  |  |
| RD4      | SEG17 (LCD)<br>P2D (CCP)<br>RD4  |  |  |  |
| RD5      | SEG18 (LCD)<br>P1B (CCP)<br>RD5  |  |  |  |
| RD6      | SEG19 (LCD)<br>P1C (CCP)<br>RD6  |  |  |  |
| RD7      | SEG20 (LCD)<br>P1D (CCP)<br>RD7  |  |  |  |

**Note 1:** Priority listed from highest to lowest.

# REGISTER 12-14: PORTD: PORTD REGISTER<sup>(1)</sup>

| R/W-x/u |
|---------|---------|---------|---------|---------|---------|---------|---------|
| RD7     | RD6     | RD5     | RD4     | RD3     | RD2     | RD1     | RD0     |
| bit 7   |         |         |         |         |         |         | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 RD<7:0>: PORTD General Purpose I/O Pin bits

1 = Port pin is > VIH 0 = Port pin is < VIL

Note 1: PORTD is not implemented on PIC16(L)F1936 devices, read as '0'.

# REGISTER 12-15: TRISD: PORTD TRI-STATE REGISTER<sup>(1)</sup>

| R/W-1/1 |
|---------|---------|---------|---------|---------|---------|---------|---------|
| TRISD7  | TRISD6  | TRISD5  | TRISD4  | TRISD3  | TRISD2  | TRISD1  | TRISD0  |
| bit 7   |         |         |         |         |         |         | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 TRISD<7:0>: PORTD Tri-State Control bits

1 = PORTD pin configured as an input (tri-stated)

0 = PORTD pin configured as an output

Note 1: TRISD is not implemented on PIC16(L)F1936 devices, read as '0'.

2: PORTD implemented on PIC16(L)F1934/7 devices only.

### REGISTER 12-16: LATD: PORTD DATA LATCH REGISTER

| R/W-x/u |
|---------|---------|---------|---------|---------|---------|---------|---------|
| LATD7   | LATD6   | LATD5   | LATD4   | LATD3   | LATD2   | LATD1   | LATD0   |
| bit 7   |         |         |         |         |         |         | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 LATD<7:0>: PORTD Output Latch Value bits(1,2)

**Note 1:** Writes to PORTD are actually written to corresponding LATD register. Reads from PORTD register is return of actual I/O pin values.

2: PORTD implemented on PIC16(L)F1934/7 devices only.

# REGISTER 12-17: ANSELD: PORTD ANALOG SELECT REGISTER<sup>(2)</sup>

| R/W-1/1 |
|---------|---------|---------|---------|---------|---------|---------|---------|
| ANSD7   | ANSD6   | ANSD5   | ANSD4   | ANSD3   | ANSD2   | ANSD1   | ANSD0   |
| bit 7   |         |         |         |         |         |         | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets '1' = Bit is set '0' = Bit is cleared

1 - Dit is set 0 - Dit is cleared

bit 7-0 ANSD<7:0>: Analog Select between Analog or Digital Function on Pins RD<7:0>, respectively

0 = Digital I/O. Pin is assigned to port or digital special function.

1 = Analog input. Pin is assigned as analog input<sup>(1)</sup>. Digital input buffer disabled.

**Note 1:** When setting a pin to an analog input, the corresponding TRIS bit must be set to Input mode in order to allow external control of the voltage on the pin.

2: ANSELD register is not implemented on the PIC16(L)F1936. Read as '0'.

3: PORTD implemented on PIC16(L)F1934/7 devices only.

# TABLE 12-10: SUMMARY OF REGISTERS ASSOCIATED WITH PORTD<sup>(1)</sup>

| Name    | Bit 7  | Bit 6  | Bit 5  | Bit 4     | Bit 3             | Bit 2      | Bit 1  | Bit 0  | Register on Page |  |
|---------|--------|--------|--------|-----------|-------------------|------------|--------|--------|------------------|--|
| ANSELD  | ANSD7  | ANSD6  | ANSD5  | ANSD4     | ANSD3             | ANSD2      | ANSD1  | ANSD0  | 146              |  |
| CCPxCON | PxM<   | <1:0>  | DCxB   | DCxB<1:0> |                   | CCPxM<3:0> |        |        |                  |  |
| CPSCON0 | CPSON  | _      | _      | _         | CPSRNG<1:0> CPSOL |            | CPSOUT | T0XCS  | 323              |  |
| CPSCON1 | _      | _      | _      | _         |                   | 324        |        |        |                  |  |
| LATD    | LATD7  | LATD6  | LATD5  | LATD4     | LATD3             | LATD2      | LATD1  | LATD0  | 145              |  |
| LCDCON  | LCDEN  | SLPEN  | WERR   | _         | CS<               | 1:0>       | LMUX   | <1:0>  | 329              |  |
| LCDSE2  | SE23   | SE22   | SE21   | SE20      | SE19              | SE18       | SE17   | SE16   | 333              |  |
| PORTD   | RD7    | RD6    | RD5    | RD4       | RD3               | RD2        | RD1    | RD0    | 145              |  |
| TRISD   | TRISD7 | TRISD6 | TRISD5 | TRISD4    | TRISD3            | TRISD2     | TRISD1 | TRISD0 | 145              |  |

**Legend:** x = unknown, u = unchanged, - = unimplemented locations read as '0'. Shaded cells are not used by PORTD.

Note 1: These registers are not implemented on the PIC16(L)F1936 devices, read as '0'.

### 12.6 PORTE Registers

PORTE is a 4-bit wide, bidirectional port. The corresponding data direction register is TRISE. Setting a TRISE bit (= 1) will make the corresponding PORTE pin an input (i.e., put the corresponding output driver in a High-Impedance mode). Clearing a TRISE bit (= 0) will make the corresponding PORTE pin an output (i.e., enable the output driver and put the contents of the output latch on the selected pin). The exception is RE3, which is input only and its TRIS bit will always read as '1'. Example 12-1 shows how to initialize an I/O port.

Reading the PORTE register (Register 12-18) reads the status of the pins, whereas writing to it will write to the PORT latch. All write operations are read-modify-write operations. Therefore, a write to a port implies that the port pins are read, this value is modified and then written to the PORT data latch (LATE). RE3 reads '0' when MCLRE = 1.

| Note: | RE<2:0>   | and  | TRISE<2:0>    | pins | are |
|-------|-----------|------|---------------|------|-----|
|       | available | on   | PIC16(L)F1934 |      | and |
|       | PIC16(L)F | 1937 | only.         |      |     |

#### 12.6.1 ANSELE REGISTER

The ANSELE register (Register 12-21) is used to configure the Input mode of an I/O pin to analog. Setting the appropriate ANSELE bit high will cause all digital reads on the pin to be read as '0' and allow analog functions on the pin to operate correctly.

The state of the ANSELE bits has no effect on digital output functions. A pin with TRIS clear and ANSEL set will still operate as a digital output, but the Input mode will be analog. This can cause unexpected behavior when executing read-modify-write instructions on the affected port.

The TRISE register (Register 12-19) controls the PORTE pin output drivers, even when they are being used as analog inputs. The user should ensure the bits in the TRISE register are maintained set when using them as analog inputs. I/O pins configured as analog input always read '0'.

| Note: | The ANSELE bits default to the Analog        |
|-------|--|
|       | mode after Reset. To use any pins as         |
|       | digital general purpose or peripheral        |
|       | inputs, the corresponding ANSEL bits         |
|       | must be initialized to '0' by user software. |

# 12.6.2 PORTE FUNCTIONS AND OUTPUT PRIORITIES

Each PORTD pin is multiplexed with other functions. The pins, their combined functions and their output priorities are shown in Table 12-11.

When multiple outputs are enabled, the actual pin control goes to the peripheral with the highest priority.

Analog input and some digital input functions are not included in the list below. These input functions can remain active when the pin is configured as an output. Certain digital input functions override other port functions and are included in Table 12-11.

**TABLE 12-11: PORTE OUTPUT PRIORITY** 

| Pin Name | Function Priority <sup>(1)</sup>     |
|----------|--------------------------------------|
| RE0      | SEG21 (LCD)<br>CCP3/P3A (CCP)<br>RE0 |
| RE1      | SEG22 (LCD)<br>P3B (CCP)<br>RE1      |
| RE2      | SEG23 (LCD)<br>CCP5 (CCP)<br>RE2     |

**Note 1:** Priority listed from highest to lowest.

### **REGISTER 12-18: PORTE: PORTE REGISTER**

| U-0   | U-0 | U-0 | U-0 | R-x/u | R/W-x/u            | R/W-x/u            | R/W-x/u            |
|-------|-----|-----|-----|-------|--------------------|--------------------|--------------------|
| _     | _   | _   |     | RE3   | RE2 <sup>(1)</sup> | RE1 <sup>(1)</sup> | RE0 <sup>(1)</sup> |
| bit 7 |     |     |     |       |                    |                    | bit 0              |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-4 **Unimplemented**: Read as '0' bit 3-0 **RE<3:0>**: PORTE I/O Pin bits<sup>(1)</sup>

1 = Port pin is > VIH 0 = Port pin is < VIL

Note 1: RE<2:0> are not implemented on the PIC16(L)F1936. Read as '0'.

### **REGISTER 12-19: TRISE: PORTE TRI-STATE REGISTER**

| U-0   | U-0 | U-0 | U-0 | U-1 <sup>(2)</sup> | R/W-1                 | R/W-1                 | R/W-1                 |
|-------|-----|-----|-----|--------------------|-----------------------|-----------------------|-----------------------|
| _     | _   | _   | _   | _                  | TRISE2 <sup>(1)</sup> | TRISE1 <sup>(1)</sup> | TRISE0 <sup>(1)</sup> |
| bit 7 |     |     |     |                    |                       |                       | bit 0                 |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets '1' = Bit is set '0' = Bit is cleared

bit 7-4 **Unimplemented**: Read as '0' bit 3 **Unimplemented**: Read as '1'

bit 2-0 TRISE<2:0>: RE<2:0> Tri-State Control bits<sup>(1)</sup>

1 = PORTE pin configured as an input (tri-stated)

0 = PORTE pin configured as an output

Note 1: TRISE<2:0> are not implemented on the PIC16(L)F1936. Read as '0'.

2: Unimplemented, read as '1'.

### **REGISTER 12-20: LATE: PORTE DATA LATCH REGISTER**

| U-0   | U-0 | U-0 | U-0 | U-0 | R/W-x/u | R/W-x/u | R/W-x/u |
|-------|-----|-----|-----|-----|---------|---------|---------|
| _     | _   | _   | _   | _   | LATE2   | LATE1   | LATE0   |
| bit 7 |     |     |     |     |         |         | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-3 **Unimplemented**: Read as '0'

bit 2-0 LATE<2:0>: PORTE Output Latch Value bits<sup>(1)</sup>

**Note 1:** Writes to PORTE are actually written to corresponding LATE register. Reads from PORTE register is return of actual I/O pin values.

### REGISTER 12-21: ANSELE: PORTE ANALOG SELECT REGISTER

| U-0   | U-0 | U-0 | U-0 | U-0 | R/W-1                | R/W-1                | R/W-1                |
|-------|-----|-----|-----|-----|----------------------|----------------------|----------------------|
| _     | _   | _   | _   | _   | ANSE2 <sup>(2)</sup> | ANSE1 <sup>(2)</sup> | ANSE0 <sup>(2)</sup> |
| bit 7 |     |     |     |     |                      |                      | bit 0                |

| Legend:              |                      |   |
|----------------------|----------------------|---|
| R = Readable bit     | W = Writable bit     | U = Unimplemented bit, read as '0'                    |
| u = bit is unchanged | x = Bit is unknown   | -n/n = Value at POR and BOR/Value at all other Resets |
| '1' = Bit is set     | '0' = Bit is cleared |   |

bit 7-3 **Unimplemented:** Read as '0'

bit 2-0 ANSE<2:0>: Analog Select between Analog or Digital Function on Pins RE<2:0>, respectively

0 = Digital I/O. Pin is assigned to port or digital special function.

1 = Analog input. Pin is assigned as analog input<sup>(1)</sup>. Digital input buffer disabled.

**Note 1:** When setting a pin to an analog input, the corresponding TRIS bit must be set to Input mode in order to allow external control of the voltage on the pin.

2: ANSELE register is not implemented on the PIC16(L)F1936. Read as '0'

### REGISTER 12-22: WPUE: WEAK PULL-UP PORTE REGISTER

| U-0   | U-0 | U-0 | U-0 | R/W-1/1 | U-0 | U-0 | U-0   |
|-------|-----|-----|-----|---------|-----|-----|-------|
| _     | _   | _   | _   | WPUE3   | _   | _   | _     |
| bit 7 |     |     |     |         |     |     | bit 0 |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-4 **Unimplemented:** Read as '0' bit 3 **WPUE:** Weak Pull-up Register bit

1 = Pull-up enabled0 = Pull-up disabled

bit 2-0 Unimplemented: Read as '0'

Note 1: Global WPUEN bit of the OPTION\_REG register must be cleared for individual pull-ups to be enabled.

2: The weak pull-up device is automatically disabled if the pin is in configured as an output.

#### TABLE 12-12: SUMMARY OF REGISTERS ASSOCIATED WITH PORTE

| Name    | Bit 7 | Bit 6 | Bit 5        | Bit 4 | Bit 3   | Bit 2                 | Bit 1                 | Bit 0                 | Register<br>on Page |
|---------|-------|-------|--------------|-------|---------|-----------------------|-----------------------|-----------------------|---------------------|
| ADCON0  | _     |       | CHS<4:0> GO. |       |         |                       |                       | ADON                  | 163                 |
| ANSELE  | _     | _     | _            | _     | _       | ANSE2 <sup>(1)</sup>  | ANSE1 <sup>(1)</sup>  | ANSE0 <sup>(1)</sup>  | 149                 |
| CCPxCON | PxM<  | <1:0> | 0> DCxB<1:0> |       |         | CCPxM<3:0>            |                       |                       |                     |
| LATE    | _     | 1     | -            | _     | _       | LATE2 <sup>(1)</sup>  | LATE1 <sup>(1)</sup>  | LATE0 <sup>(1)</sup>  | 149                 |
| LCDCON  | LCDEN | SLPEN | WERR         | _     | CS<1:0> |                       | LMUX<1:0>             |                       | 329                 |
| LCDSE2  | SE23  | SE22  | SE21         | SE20  | SE19    | SE18                  | SE17                  | SE16                  | 333                 |
| PORTE   | _     | _     | _            | _     | RE3     | RE2 <sup>(1)</sup>    | RE1 <sup>(1)</sup>    | RE0 <sup>(1)</sup>    | 148                 |
| TRISE   | _     | _     | _            | _     | (2)     | TRISE2 <sup>(1)</sup> | TRISE1 <sup>(1)</sup> | TRISE0 <sup>(1)</sup> | 148                 |
| WPUE    | _     | _     | _            | _     | WPUE3   | _                     | _                     | _                     | 150                 |

**Legend:** x = unknown, u = unchanged, - = unimplemented locations read as '0'. Shaded cells are not used by PORTE.

Note 1: These bits are not implemented on the PIC16(L)F1936 devices, read as '0'.

2: Unimplemented, read as '1'.

3: These registers/bits are not implemented on PIC16(L)F1936 devices, read as '0'.

### 13.0 INTERRUPT-ON-CHANGE

The PORTB pins can be configured to operate as Interrupt-On-Change (IOC) pins. An interrupt can be generated by detecting a signal that has either a rising edge or a falling edge. Any individual PORT IOC pin, or combination of PORT IOC pins, can be configured to generate an interrupt. The interrupt-on-change module has the following features:

- Interrupt-on-Change enable (Master Switch)
- · Individual pin configuration
- · Rising and falling edge detection
- · Individual pin interrupt flags

Figure 13-1 is a block diagram of the IOC module.

# 13.1 Enabling the Module

To allow individual PORTB pins to generate an interrupt, the IOCIE bit of the INTCON register must be set. If the IOCIE bit is disabled, the edge detection on the pin will still occur, but an interrupt will not be generated.

### 13.2 Individual Pin Configuration

For each PORTB pin, a rising edge detector and a falling edge detector are present. To enable a pin to detect a rising edge, the associated IOCBPx bit of the IOCBP register is set. To enable a pin to detect a falling edge, the associated IOCBNx bit of the IOCBN register is set.

A pin can be configured to detect rising and falling edges simultaneously by setting both the IOCBPx bit and the IOCBNx bit of the IOCBP and IOCBN registers, respectively.

### 13.3 Interrupt Flags

The IOCBFx bits located in the IOCBF register are status flags that correspond to the interrupt-on-change pins of PORTB. If an expected edge is detected on an appropriately enabled pin, then the status flag for that pin will be set, and an interrupt will be generated if the IOCIE bit is set. The IOCIF bit of the INTCON register reflects the status of all IOCBFx bits.

## 13.4 Clearing Interrupt Flags

The individual status flags, (IOCBFx bits), can be cleared by resetting them to zero. If another edge is detected during this clearing operation, the associated status flag will be set at the end of the sequence, regardless of the value actually being written.

In order to ensure that no detected edge is lost while clearing flags, only AND operations masking out known changed bits should be performed. The following sequence is an example of what should be performed.

#### **EXAMPLE 13-1:**


| MOTITUE | 066    |   |
|---------|--------|---|
| MOVLW   | UXII   |   |
| XORWF   | IOCBF, | W |
| ANDWF   | IOCBF, | F |

# 13.5 Operation in Sleep

The interrupt-on-change interrupt sequence will wake the device from Sleep mode, if the IOCIE bit is set.

If an edge is detected while in Sleep mode, the IOCBF register will be updated prior to the first instruction executed out of Sleep.

FIGURE 13-1: INTERRUPT-ON-CHANGE BLOCK DIAGRAM



## 13.6 Interrupt-On-Change Registers

### REGISTER 13-1: IOCBP: INTERRUPT-ON-CHANGE POSITIVE EDGE REGISTER

| R/W-0/0 |
|---------|---------|---------|---------|---------|---------|---------|---------|
| IOCBP7  | IOCBP6  | IOCBP5  | IOCBP4  | IOCBP3  | IOCBP2  | IOCBP1  | IOCBP0  |
| bit 7   |         |         |         |         |         |         | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 **IOCBP<7:0>:** Interrupt-on-Change Positive Edge Enable bits

1 = Interrupt-on-Change enabled on the pin for a positive going edge. Associated Status bit and interrupt flag will be set upon detecting an edge.

0 = Interrupt-on-Change disabled for the associated pin.

#### REGISTER 13-2: IOCBN: INTERRUPT-ON-CHANGE NEGATIVE EDGE REGISTER

| R/W-0/0 |
|---------|---------|---------|---------|---------|---------|---------|---------|
| IOCBN7  | IOCBN6  | IOCBN5  | IOCBN4  | IOCBN3  | IOCBN2  | IOCBN1  | IOCBN0  |
| bit 7   |         |         |         |         |         |         | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 **IOCBN<7:0>:** Interrupt-on-Change Negative Edge Enable bits

1 = Interrupt-on-Change enabled on the pin for a negative going edge. Associated Status bit and interrupt flag will be set upon detecting an edge.

0 = Interrupt-on-Change disabled for the associated pin.

### REGISTER 13-3: IOCBF: INTERRUPT-ON-CHANGE FLAG REGISTER

| R/W/HS-0/0 |
|------------|------------|------------|------------|------------|------------|------------|------------|
| IOCBF7     | IOCBF6     | IOCBF5     | IOCBF4     | IOCBF3     | IOCBF2     | IOCBF1     | IOCBF0     |
| bit 7      |            |            |            |            |            |            | bit 0      |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared HS - Bit is set in hardware

bit 7-0 **IOCBF<7:0>:** Interrupt-on-Change Flag bits

1 = An enabled change was detected on the associated pin. Set when IOCBPx = 1 and a rising edge was detected on RBx, or when IOCBNx = 1 and a falling edge was detected on RBx.

0 = No change was detected, or the user cleared the detected change.

TABLE 13-1: SUMMARY OF REGISTERS ASSOCIATED WITH INTERRUPT-ON-CHANGE

| Name   | Bit 7  | Bit 6  | Bit 5  | Bit 4  | Bit 3  | Bit 2  | Bit 1  | Bit 0  | Register on Page |
|--------|--------|--------|--------|--------|--------|--------|--------|--------|------------------|
| ANSELB | _      | _      | ANSB5  | ANSB4  | ANSB3  | ANSB2  | ANSB1  | ANSB0  | 139              |
| INTCON | GIE    | PEIE   | TMR0IE | INTE   | IOCIE  | TMR0IF | INTF   | IOCIF  | 98               |
| IOCBF  | IOCBF7 | IOCBF6 | IOCBF5 | IOCBF4 | IOCBF3 | IOCBF2 | IOCBF1 | IOCBF0 | 152              |
| IOCBN  | IOCBN7 | IOCBN6 | IOCBN5 | IOCBN4 | IOCBN3 | IOCBN2 | IOCBN1 | IOCBN0 | 152              |
| IOCBP  | IOCBP7 | IOCBP6 | IOCBP5 | IOCBP4 | IOCBP3 | IOCBP2 | IOCBP1 | IOCBP0 | 152              |
| TRISB  | TRISB7 | TRISB6 | TRISB5 | TRISB4 | TRISB3 | TRISB2 | TRISB1 | TRISB0 | 138              |

**Legend:** — = unimplemented location, read as '0'. Shaded cells are not used by Interrupt-on-Change.

NOTES:

# 14.0 FIXED VOLTAGE REFERENCE (FVR)

The Fixed Voltage Reference, or FVR, is a stable voltage reference, independent of VDD, with 1.024V, 2.048V or 4.096V selectable output levels. The output of the FVR can be configured to supply a reference voltage to the following:

- · ADC input channel
- · ADC positive reference
- · Comparator positive input
- Digital-to-Analog Converter (DAC)
- · Capacitive Sensing (CPS) module
- · LCD bias generator

The FVR can be enabled by setting the FVREN bit of the FVRCON register.

## 14.1 Independent Gain Amplifiers

The output of the FVR supplied to the ADC, Comparators, DAC and CPS is routed through two independent programmable gain amplifiers. Each

amplifier can be configured to amplify the reference voltage by 1x, 2x or 4x, to produce the three possible voltage levels.


The ADFVR<1:0> bits of the FVRCON register are used to enable and configure the gain amplifier settings for the reference supplied to the ADC module. Reference Section 15.0 "Analog-to-Digital Converter (ADC) Module" for additional information.

The CDAFVR<1:0> bits of the FVRCON register are used to enable and configure the gain amplifier settings for the reference supplied to the DAC, CPS and comparator module. Reference Section 17.0 "Digital-to-Analog Converter (DAC) Module", Section 18.0 "Comparator Module" and Section 26.0 "Capacitive Sensing (CPS) Module" for additional information.

### 14.2 FVR Stabilization Period

When the Fixed Voltage Reference module is enabled, it requires time for the reference and amplifier circuits to stabilize. Once the circuits stabilize and are ready for use, the FVRRDY bit of the FVRCON register will be set. See in the applicable Electrical Specifications Chapter for the minimum delay requirement.

FIGURE 14-1: VOLTAGE REFERENCE BLOCK DIAGRAM



### 14.3 FVR Control Registers

#### REGISTER 14-1: FVRCON: FIXED VOLTAGE REFERENCE CONTROL REGISTER

| R/W-0/0 | R-q/q                 | R/W-0/0 | R/W-0/0 | R/W-0/0 | R/W-0/0 | R/W-0/0 | R/W-0/0 |
|---------|-----------------------|---------|---------|---------|---------|---------|---------|
| FVREN   | FVRRDY <sup>(1)</sup> | TSEN    | TSRNG   | CDAF    | /R<1:0> | ADFV    | R<1:0>  |
| bit 7   |                       |         |         |         |         |         | bit 0   |

Legend:R = Readable bitW = Writable bitU = Unimplemented bit, read as '0'u = Bit is unchangedx = Bit is unknown-n/n = Value at POR and BOR/Value at all other Resets'1' = Bit is set'0' = Bit is clearedq = Value depends on condition

bit 7

FVREN: Fixed Voltage Reference Enable bit
0 = Fixed Voltage Reference is disabled
1 = Fixed Voltage Reference is enabled

bit 6

FVRRDY: Fixed Voltage Reference Ready Flag bit(1)
0 = Fixed Voltage Reference output is not ready or not enabled
1 = Fixed Voltage Reference output is ready for use

bit 5

TSEN: Temperature Indicator Enable bit(3)
0 = Temperature Indicator is disabled
1 = Temperature Indicator is enabled

bit 4

TSRNG: Temperature Indicator Range Selection bit(3)
0 = VOUT = VDD - 2VT (Low Range)

1 = Vout = VDD - 4VT (High Range)
 bit 3-2
 CDAFVR<1:0>: Comparator and DAC Fixed Voltage Reference Selection bit

00 = Comparator and DAC Fixed Voltage Reference Peripheral output is off.

01 = Comparator and DAC Fixed Voltage Reference Peripheral output is 1x (1.024V) 10 = Comparator and DAC Fixed Voltage Reference Peripheral output is 2x (2.048V)<sup>(2)</sup> 11 = Comparator and DAC Fixed Voltage Reference Peripheral output is 4x (4.096V)<sup>(2)</sup>

bit 1-0 ADFVR<1:0>: ADC Fixed Voltage Reference Selection bit

00 = ADC Fixed Voltage Reference Peripheral output is off.01 = ADC Fixed Voltage Reference Peripheral output is 1x (1.024V)

10 = ADC Fixed Voltage Reference Peripheral output is 1x (1.024V) 10 = ADC Fixed Voltage Reference Peripheral output is 2x (2.048V)<sup>(2)</sup>

11 = ADC Fixed Voltage Reference Peripheral output is 4x (4.096V)(2)

Note 1: FVRRDY is always '1' on devices with LDO (PIC16F1934/6/7).

2: Fixed Voltage Reference output cannot exceed VDD.

3: See Section 16.0 "Temperature Indicator Module" for additional information.

### TABLE 14-1: SUMMARY OF REGISTERS ASSOCIATED WITH FIXED VOLTAGE REFERENCE

| Name   | Bit 7 | Bit 6  | Bit 5 | Bit 4 | Bit 3 | Bit 2  | Bit 1 | Bit 0  | Register on page |
|--------|-------|--------|-------|-------|-------|--------|-------|--------|------------------|
| FVRCON | FVREN | FVRRDY | TSEN  | TSRNG | CDAFV | R<1:0> | ADFVI | R<1:0> | 156              |

Legend: Shaded cells are not used with the Fixed Voltage Reference.


# 15.0 ANALOG-TO-DIGITAL CONVERTER (ADC) MODULE

The Analog-to-Digital Converter (ADC) allows conversion of an analog input signal to a 10-bit binary representation of that signal. This device uses analog inputs, which are multiplexed into a single sample and hold circuit. The output of the sample and hold is connected to the input of the converter. The converter generates a 10-bit binary result via successive approximation and stores the conversion result into the ADC result registers (ADRESH:ADRESL register pair). Figure 15-1 shows the block diagram of the ADC.

The ADC voltage reference is software selectable to be either internally generated or externally supplied.

The ADC can generate an interrupt upon completion of a conversion. This interrupt can be used to wake-up the device from Sleep.

### FIGURE 15-1: ADC BLOCK DIAGRAM



### 15.1 ADC Configuration

When configuring and using the ADC the following functions must be considered:

- · Port configuration
- · Channel selection
- · ADC voltage reference selection
- · ADC conversion clock source
- · Interrupt control
- · Result formatting

# 15.1.1 PORT CONFIGURATION

The ADC can be used to convert both analog and digital signals. When converting analog signals, the I/O pin should be configured for analog by setting the associated TRIS and ANSEL bits. Refer to Section 12.0 "I/O Ports" for more information.

Note: A

Analog voltages on any pin that is defined as a digital input may cause the input buffer to conduct excess current.

### 15.1.2 CHANNEL SELECTION

There are 17 channel selections available:

- AN<13:0> pins
- · Temperature Indicator
- DAC Output
- · FVR (Fixed Voltage Reference) Output

Refer to Section 16.0 "Temperature Indicator Module", Section 17.0 "Digital-to-Analog Converter (DAC) Module" and Section 14.0 "Fixed Voltage Reference (FVR)" for more information on these channel selections.

The CHS bits of the ADCON0 register determine which channel is connected to the sample and hold circuit.

When changing channels, a delay is required before starting the next conversion. Refer to **Section 15.2** "**ADC Operation**" for more information.

# 15.1.3 ADC VOLTAGE REFERENCE

The ADPREF bits of the ADCON1 register provides control of the positive voltage reference. The positive voltage reference can be:

- VREF+ pin
- VDD
- FVR 2.048V
- FVR 4.096V (Not available on LF devices)

The ADNREF bits of the ADCON1 register provides control of the negative voltage reference. The negative voltage reference can be:

- VREF- pin
- Vss

See Section 14.0 "Fixed Voltage Reference (FVR)" for more details on the fixed voltage reference.

#### 15.1.4 CONVERSION CLOCK

The source of the conversion clock is software selectable via the ADCS bits of the ADCON1 register. There are seven possible clock options:

- Fosc/2
- Fosc/4
- Fosc/8
- Fosc/16
- Fosc/32
- Fosc/64
- · FRC (dedicated internal oscillator)

The time to complete one bit conversion is defined as TAD. One full 10-bit conversion requires 11.5 TAD periods as shown in Figure 15-2.

For correct conversion, the appropriate TAD specification must be met. Refer to the A/D conversion requirements in the applicable Electrical Specifications Chapter for more information. Table 15-1 gives examples of appropriate ADC clock selections.

Note:

Unless using the FRC, any changes in the system clock frequency will change the ADC clock frequency, which may adversely affect the ADC result.


TABLE 15-1: ADC CLOCK PERIOD (TAD) Vs. DEVICE OPERATING FREQUENCIES

| ADC Clock P         | eriod (TAD) |                             |                             | •                           | uency (Fosc)<br>uency (Fosc) |                             |                             |  |
|---------------------|-------------|-----------------------------|-----------------------------|-----------------------------|------------------------------|-----------------------------|-----------------------------|--|
| ADC<br>Clock Source | ADCS<2:0>   | 32 MHz                      | 20 MHz                      | 16 MHz                      | 8 MHz                        | 4 MHz                       | 1 MHz                       |  |
| Fosc/2              | 000         | 62.5ns <sup>(2)</sup>       | 100 ns <sup>(2)</sup>       | 125 ns <sup>(2)</sup>       | 250 ns <sup>(2)</sup>        | 500 ns <sup>(2)</sup>       | 2.0 μs                      |  |
| Fosc/4              | 100         | 125 ns <sup>(2)</sup>       | 200 ns <sup>(2)</sup>       | 250 ns <sup>(2)</sup>       | 500 ns <sup>(2)</sup>        | 1.0 μs                      | 4.0 μs                      |  |
| Fosc/8              | 001         | 0.5 μs <sup>(2)</sup>       | 400 ns <sup>(2)</sup>       | 0.5 μs <sup>(2)</sup>       | 1.0 μs                       | 2.0 μs                      | 8.0 μs <sup>(3)</sup>       |  |
| Fosc/16             | 101         | 800 ns                      | 800 ns                      | 1.0 μs                      | 2.0 μs                       | 4.0 μs                      | 16.0 μs <sup>(3)</sup>      |  |
| Fosc/32             | 010         | 1.0 μs                      | 1.6 μs                      | 2.0 μs                      | 4.0 μs                       | 8.0 μs <sup>(3)</sup>       | 32.0 μs <sup>(3)</sup>      |  |
| Fosc/64             | 110         | 2.0 μs                      | 3.2 μs                      | 4.0 μs                      | 8.0 μs <sup>(3)</sup>        | 16.0 μs <sup>(3)</sup>      | 64.0 μs <sup>(3)</sup>      |  |
| FRC                 | x11         | 1.0-6.0 μs <sup>(1,4)</sup> | 1.0-6.0 μs <sup>(1,4)</sup> | 1.0-6.0 μs <sup>(1,4)</sup> | 1.0-6.0 μs <sup>(1,4)</sup>  | 1.0-6.0 μs <sup>(1,4)</sup> | 1.0-6.0 μs <sup>(1,4)</sup> |  |

**Legend:** Shaded cells are outside of recommended range.

- Note 1: The FRC source has a typical TAD time of 1.6  $\mu s$  for VDD.
  - 2: These values violate the minimum required TAD time.
  - 3: For faster conversion times, the selection of another clock source is recommended.
  - 4: The ADC clock period (TAD) and total ADC conversion time can be minimized when the ADC clock is derived from the system clock Fosc. However, the FRC clock source must be used when conversions are to be performed with the device in Sleep mode.

### FIGURE 15-2: ANALOG-TO-DIGITAL CONVERSION TAD CYCLES



#### 15.1.5 INTERRUPTS

The ADC module allows for the ability to generate an interrupt upon completion of an Analog-to-Digital conversion. The ADC Interrupt Flag is the ADIF bit in the PIR1 register. The ADC Interrupt Enable is the ADIE bit in the PIE1 register. The ADIF bit must be cleared in software.

- **Note 1:** The ADIF bit is set at the completion of every conversion, regardless of whether or not the ADC interrupt is enabled.
  - **2:** The ADC operates during Sleep only when the FRC oscillator is selected.

This interrupt can be generated while the device is operating or while in Sleep. If the device is in Sleep, the interrupt will wake-up the device. Upon waking from Sleep, the next instruction following the SLEEP instruction is always executed. If the user is attempting to wake-up from Sleep and resume in-line code execution, the GIE and PEIE bits of the INTCON register must be disabled. If the GIE and PEIE bits of the INTCON register are enabled, execution will switch to the Interrupt Service Routine.


Please refer to **Section 15.1.5 "Interrupts"** for more information.

#### 15.1.6 RESULT FORMATTING

The 10-bit A/D conversion result can be supplied in two formats, left justified or right justified. The ADFM bit of the ADCON1 register controls the output format.

Figure 15-3 shows the two output formats.

### FIGURE 15-3: 10-BIT A/D CONVERSION RESULT FORMAT



### 15.2 ADC Operation

### 15.2.1 STARTING A CONVERSION

To enable the ADC module, the ADON bit of the ADCON0 register must be set to a '1'. Setting the GO/DONE bit of the ADCON0 register to a '1' will start the Analog-to-Digital conversion.

Note: The GO/DONE bit should not be set in the same instruction that turns on the ADC. Refer to Section 15.2.6 "A/D Conversion Procedure".

#### 15.2.2 COMPLETION OF A CONVERSION

When the conversion is complete, the ADC module will:

- Clear the GO/DONE bit
- · Set the ADIF Interrupt Flag bit
- Update the ADRESH and ADRESL registers with new conversion result

#### 15.2.3 TERMINATING A CONVERSION

If a conversion must be terminated before completion, the GO/DONE bit can be cleared in software. The ADRESH and ADRESL registers will be updated with the partially complete Analog-to-Digital conversion sample. Incomplete bits will match the last bit converted.

Note: A device Reset forces all registers to their Reset state. Thus, the ADC module is turned off and any pending conversion is terminated.

#### 15.2.4 ADC OPERATION DURING SLEEP

The ADC module can operate during Sleep. This requires the ADC clock source to be set to the FRC option. When the FRC clock source is selected, the ADC waits one additional instruction before starting the conversion. This allows the SLEEP instruction to be executed, which can reduce system noise during the conversion. If the ADC interrupt is enabled, the device will wake-up from Sleep when the conversion completes. If the ADC interrupt is disabled, the ADC module is turned off after the conversion completes, although the ADON bit remains set.

When the ADC clock source is something other than FRC, a SLEEP instruction causes the present conversion to be aborted and the ADC module is turned off, although the ADON bit remains set.

### 15.2.5 SPECIAL EVENT TRIGGER

The Special Event Trigger of the CCPx/ECCPX module allows periodic ADC measurements without software intervention. When this trigger occurs, the GO/DONE bit is set by hardware and the Timer1 counter resets to zero.

TABLE 15-2: SPECIAL EVENT TRIGGER

| Device            | CCPx/ECCPx |
|-------------------|------------|
| PIC16(L)F1934/6/7 | CCP5       |

Using the Special Event Trigger does not assure proper ADC timing. It is the user's responsibility to ensure that the ADC timing requirements are met.

Refer to Section 23.0 "Capture/Compare/PWM Modules" for more information.

#### 15.2.6 A/D CONVERSION PROCEDURE

This is an example procedure for using the ADC to perform an Analog-to-Digital conversion:

- 1. Configure Port:
  - Disable pin output driver (Refer to the TRIS register)
  - Configure pin as analog (Refer to the ANSEL register)
- 2. Configure the ADC module:
  - · Select ADC conversion clock
  - · Configure voltage reference
  - · Select ADC input channel
  - · Turn on ADC module
- 3. Configure ADC interrupt (optional):
  - · Clear ADC interrupt flag
  - · Enable ADC interrupt
  - · Enable peripheral interrupt
  - Enable global interrupt<sup>(1)</sup>
- 4. Wait the required acquisition time<sup>(2)</sup>.
- 5. Start conversion by setting the GO/DONE bit.
- Wait for ADC conversion to complete by one of the following:
  - Polling the GO/DONE bit
  - Waiting for the ADC interrupt (interrupts enabled)
- 7. Read ADC Result.
- 8. Clear the ADC interrupt flag (required if interrupt is enabled).
  - **Note 1:** The global interrupt can be disabled if the user is attempting to wake-up from Sleep and resume in-line code execution.
    - 2: Refer to Section 15.3 "A/D Acquisition Requirements".

### **EXAMPLE 15-1: A/D CONVERSION**

```
; This code block configures the ADC
; for polling, Vdd and Vss references, Frc
; clock and ANO input.
;Conversion start & polling for completion
; are included.
BANKSEL ADCON1
        B'11110000' ;Right justify, Frc
MOVLW
                    ;clock
MOVWF
        ADCON1
                   ;Vdd and Vss Vref
BANKSEL TRISA
BSF
        TRISA,0 ;Set RAO to input
BANKSEL ANSEL
BSF
        ANSEL,0 ;Set RAO to analog
BANKSEL
        ADCON0
         B'00000001' ;Select channel AN0
MOVLW
MOVWE
                    ;Turn ADC On
         ADCON0
         SampleTime ;Acquisiton delay
CALL
         ADCON0, ADGO ; Start conversion
BSF
BTFSC
        ADCON0, ADGO ; Is conversion done?
GOTO
         $-1
                   ;No, test again
        ADRESH
BANKSEL
         ADRESH,W ;Read upper 2 bits
MOVF
MOVWF
         RESULTHI
                    ;store in GPR space
BANKSEL
         ADRESL
         ADRESL,W
MOVF
                    ;Read lower 8 bits
MOVWF
         RESULTIO
                    ;Store in GPR space
```

#### 15.2.7 ADC REGISTER DEFINITIONS

The following registers are used to control the operation of the ADC.

#### REGISTER 15-1: ADCON0: A/D CONTROL REGISTER 0

| U-0   | R/W-0/0 | R/W-0/0 | R/W-0/0  | R/W-0/0 | R/W-0/0 | R/W-0/0 | R/W-0/0 |
|-------|---------|---------|----------|---------|---------|---------|---------|
| _     |         |         | CHS<4:0> |         |         | GO/DONE | ADON    |
| bit 7 |         |         |          |         |         |         | bit 0   |

| Legend:              |                      |   |
|----------------------|----------------------|---|
| R = Readable bit     | W = Writable bit     | U = Unimplemented bit, read as '0'                    |
| u = Bit is unchanged | x = Bit is unknown   | -n/n = Value at POR and BOR/Value at all other Resets |
| '1' = Bit is set     | '0' = Bit is cleared |   |

bit 7 Unimplemented: Read as '0' CHS<4:0>: Analog Channel Select bits bit 6-2 00000 = AN000001 = AN1 00010 = AN200011 = AN3 00100 = AN4 00101 = AN5<sup>(4)</sup> 00110 = AN6<sup>(4)</sup>  $00111 = AN7^{(4)}$ 01000 = AN8 01001 = AN9 01010 **= AN10** 01011 = AN11 01100 = AN1201101 **= AN13** 01110 = Reserved. No channel connected. 11100 = Reserved. No channel connected. 11101 = Temperature Indicator<sup>(3)</sup> 11110 = DAC output<sup>(1)</sup> 11111 = FVR (Fixed Voltage Reference) Buffer 1 Output(2) GO/DONE: A/D Conversion Status bit bit 1 1 = A/D conversion cycle in progress. Setting this bit starts an A/D conversion cycle. This bit is automatically cleared by hardware when the A/D conversion has completed. 0 = A/D conversion completed/not in progress bit 0 ADON: ADC Enable bit 1 = ADC is enabled 0 = ADC is disabled and consumes no operating current Note 1: See Section 17.0 "Digital-to-Analog Converter (DAC) Module" for more information.

- 2: See Section 14.0 "Fixed Voltage Reference (FVR)" for more information.
- 3: See Section 16.0 "Temperature Indicator Module" for more information.
- 4: Not available on the PIC16(L)F1936.

### REGISTER 15-2: ADCON1: A/D CONTROL REGISTER 1

| R/W-0/0 | R/W-0/0   | R/W-0/0 | R/W-0/0 | U-0 | R/W-0/0 | R/W-0/0 | R/W-0/0 |
|---------|-----------|---------|---------|-----|---------|---------|---------|
| ADFM    | ADCS<2:0> |         |         | _   | ADNREF  | ADPRE   | F<1:0>  |
| bit 7   |           |         |         |     |         |         | bit 0   |

| Legend:              |                      |   |
|----------------------|----------------------|---|
| R = Readable bit     | W = Writable bit     | U = Unimplemented bit, read as '0'                    |
| u = Bit is unchanged | x = Bit is unknown   | -n/n = Value at POR and BOR/Value at all other Resets |
| '1' = Bit is set     | '0' = Bit is cleared |   |

bit 7 ADFM: A/D Result Format Select bit

1 = Right justified. Six Most Significant bits of ADRESH are set to '0' when the conversion result is loaded.

0 = Left justified. Six Least Significant bits of ADRESL are set to '0' when the conversion result is loaded.

bit 6-4 ADCS<2:0>: A/D Conversion Clock Select bits

000 = Fosc/2

001 = Fosc/8

010 = Fosc/32

011 = FRC (clock supplied from a dedicated RC oscillator)

100 = Fosc/4

101 = Fosc/16

110 = Fosc/64

111 = FRC (clock supplied from a dedicated RC oscillator)

bit 3 **Unimplemented:** Read as '0'

bit 2 ADNREF: A/D Negative Voltage Reference Configuration bit

0 = VREF- is connected to Vss

1 = VREF- is connected to external VREF- pin<sup>(1)</sup>

bit 1-0 ADPREF<1:0>: A/D Positive Voltage Reference Configuration bits

00 = VREF+ is connected to VDD

01 = Reserved

10 = VREF+ is connected to external VREF+ pin<sup>(1)</sup>

11 = VREF+ is connected to internal Fixed Voltage Reference (FVR) module<sup>(1)</sup>

**Note 1:** When selecting the FVR or the VREF+ pin as the source of the positive reference, be aware that a minimum voltage specification exists. See the applicable Electrical Specifications Chapter for details.

### REGISTER 15-3: ADRESH: ADC RESULT REGISTER HIGH (ADRESH) ADFM = 0

| R/W-x/u    | R/W-x/u | R/W-x/u | R/W-x/u | R/W-x/u | R/W-x/u | R/W-x/u | R/W-x/u |
|------------|---------|---------|---------|---------|---------|---------|---------|
| ADRES<9:2> |         |         |         |         |         |         |         |
| bit 7      |         |         |         |         |         |         | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

bit 7-0 **ADRES<9:2>**: ADC Result Register bits Upper 8 bits of 10-bit conversion result

# REGISTER 15-4: ADRESL: ADC RESULT REGISTER LOW (ADRESL) ADFM = 0

| R/W-x/u |
|---------|---------|---------|---------|---------|---------|---------|---------|
| ADRES   | 6<1:0>  | _       | _       | _       | _       | _       | _       |
| bit 7   |         |         |         |         |         |         | bit 0   |

Legend:R = Readable bitW = Writable bitU = Unimplemented bit, read as '0'u = Bit is unchangedx = Bit is unknown-n/n = Value at POR and BOR/Value at all other Resets'1' = Bit is set'0' = Bit is cleared

bit 7-6 ADRES<1:0>: ADC Result Register bits

Lower 2 bits of 10-bit conversion result

bit 5-0 **Reserved**: Do not use.

# REGISTER 15-5: ADRESH: ADC RESULT REGISTER HIGH (ADRESH) ADFM = 1

| R/W-x/u    | R/W-x/u |
|---------|---------|---------|---------|---------|---------|------------|---------|
| _       | _       | _       | _       | _       | _       | ADRES<9:8> |         |
| bit 7   |         |         |         |         |         |            | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets '1' = Bit is set '0' = Bit is cleared

bit 7-2 **Reserved**: Do not use.

bit 1-0 **ADRES<9:8>**: ADC Result Register bits Upper 2 bits of 10-bit conversion result

### REGISTER 15-6: ADRESL: ADC RESULT REGISTER LOW (ADRESL) ADFM = 1

| R/W-x/u    | R/W-x/u | R/W-x/u | R/W-x/u | R/W-x/u | R/W-x/u | R/W-x/u | R/W-x/u |  |
|------------|---------|---------|---------|---------|---------|---------|---------|--|
| ADRES<7:0> |         |         |         |         |         |         |         |  |
| bit 7      |         |         |         |         |         |         | bit 0   |  |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 ADRES<7:0>: ADC Result Register bits

Lower 8 bits of 10-bit conversion result

### 15.3 A/D Acquisition Requirements

For the ADC to meet its specified accuracy, the charge holding capacitor (Chold) must be allowed to fully charge to the input channel voltage level. The Analog Input model is shown in Figure 15-4. The source impedance (Rs) and the internal sampling switch (Rss) impedance directly affect the time required to charge the capacitor Chold. The sampling switch (Rss) impedance varies over the device voltage (VDD), refer to Figure 15-4. The maximum recommended impedance for analog sources is  $10~\mathrm{k}\Omega$ . As the

source impedance is decreased, the acquisition time may be decreased. After the analog input channel is selected (or changed), an A/D acquisition must be done before the conversion can be started. To calculate the minimum acquisition time, Equation 15-1 may be used. This equation assumes that 1/2 LSb error is used (1,024 steps for the ADC). The 1/2 LSb error is the maximum error allowed for the ADC to meet its specified resolution.

#### **EQUATION 15-1: ACQUISITION TIME EXAMPLE**

Assumptions: Temperature =  $50^{\circ}$ C and external impedance of  $10k\Omega 5.0V VDD$ 

$$TACQ = Amplifier Settling Time + Hold Capacitor Charging Time + Temperature Coefficient$$
  
=  $TAMP + TC + TCOFF$   
=  $2\mu s + TC + [(Temperature - 25°C)(0.05\mu s/°C)]$ 

The value for TC can be approximated with the following equations:

$$V_{APPLIED}\left(1 - \frac{1}{(2^{n+1}) - 1}\right) = V_{CHOLD}$$
 ;[1] VCHOLD charged to within 1/2 lsb

$$V_{APPLIED}\left(1-e^{\frac{-Tc}{RC}}\right) = V_{CHOLD}$$
 ;[2] VCHOLD charge response to VAPPLIED

$$V_{APPLIED}\left(1-e^{\frac{-Tc}{RC}}\right) = V_{APPLIED}\left(1-\frac{1}{(2^{n+1})-1}\right)$$
 ; combining [1] and [2]

*Note:* Where n = number of bits of the ADC.

Solving for TC:

$$TC = -C_{HOLD}(RIC + RSS + RS) \ln(1/511)$$

$$= -10pF(1k\Omega + 7k\Omega + 10k\Omega) \ln(0.001957)$$


$$= 1.12\mu s$$

Therefore:

$$TACQ = 2\mu s + 1.12\mu s + [(50^{\circ}C - 25^{\circ}C)(0.05\mu s/^{\circ}C)]$$
  
= 4.42\mu s

- Note 1: The reference voltage (VREF) has no effect on the equation, since it cancels itself out.
  - 2: The charge holding capacitor (CHOLD) is not discharged after each conversion.
  - **3:** The maximum recommended impedance for analog sources is 10 kΩ. This is required to meet the pin leakage specification.

FIGURE 15-4: ANALOG INPUT MODEL



# FIGURE 15-5: ADC TRANSFER FUNCTION




TABLE 15-3: SUMMARY OF REGISTERS ASSOCIATED WITH ADC

| Name    | Bit 7        | Bit 6               | Bit 5          | Bit 4    | Bit 3       | Bit 2                 | Bit 1                 | Bit 0                 | Register on Page |
|---------|--------------|---------------------|----------------|----------|-------------|-----------------------|-----------------------|-----------------------|------------------|
| ADCON0  | _            |                     |                | CHS<4:0> |             |                       | GO/DONE               | ADON                  | 163              |
| ADCON1  | ADFM         |                     | ADCS<2:0>      |          | _           | ADNREF                | ADPRE                 | F<1:0>                | 164              |
| ADRESH  | A/D Result I | esult Register High |                |          |             |                       |                       |                       | 165              |
| ADRESL  | A/D Result I | Register Low        |                |          |             |                       |                       |                       | 165              |
| ANSELA  | _            | _                   | ANSA5          | ANSA4    | ANSA3       | ANSA2                 | ANSA1                 | ANSA0                 | 134              |
| ANSELB  | _            | _                   | ANSB5          | ANSB4    | ANSB3       | ANSB2                 | ANSB1                 | ANSB0                 | 139              |
| ANSELE  | _            | _                   | _              | _        | _           | ANSE2                 | ANSE1                 | ANSE0                 | 149              |
| CCP1CON | P1M          | <1:0>               | 1:0> DC1B<1:0> |          |             | CCP1M<3:0>            |                       |                       |                  |
| INTCON  | GIE          | PEIE                | TMR0IE         | INTE     | IOCIE       | TMR0IF                | INTF                  | IOCIF                 | 98               |
| PIE1    | TMR1GIE      | ADIE                | RCIE           | TXIE     | SSPIE       | CCP1IE                | TMR2IE                | TMR1IE                | 99               |
| PIR1    | TMR1GIF      | ADIF                | RCIF           | TXIF     | SSPIF       | CCP1IF                | TMR2IF                | TMR1IF                | 102              |
| TRISA   | TRISA7       | TRISA6              | TRISA5         | TRISA4   | TRISA3      | TRISA2                | TRISA1                | TRISA0                | 133              |
| TRISB   | TRISB7       | TRISB6              | TRISB5         | TRISB4   | TRISB3      | TRISB2                | TRISB1                | TRISB0                | 138              |
| TRISE   | _            | _                   | _              | _        | (1)         | TRISE2 <sup>(2)</sup> | TRISE1 <sup>(2)</sup> | TRISE0 <sup>(2)</sup> | 148              |
| FVRCON  | FVREN        | FVRRDY              | TSEN           | TSRNG    | CDAF        | /R<1:0>               | ADFVR<1:0>            |                       | 156              |
| DACCON0 | DACEN        | DACLPS              | DACOE          | _        | DACPSS<1:0> |                       | _                     | DACNSS                | 176              |
| DACCON1 | _            | _                   | _              |          |             | DACR<4:0>             |                       |                       | 176              |

**Legend:** x = unknown, u = unchanged, - = unimplemented read as '0', q = value depends on condition. Shaded cells are not used for ADC module.

Note 1: Unimplemented, read as '1'.

2: These registers/bits are not implemented on PIC16(L)F1936 devices, read as '0'.

NOTES:

# 16.0 TEMPERATURE INDICATOR MODULE

This family of devices is equipped with a temperature circuit designed to measure the operating temperature of the silicon die. The circuit's range of operating temperature falls between -40°C and +85°C. The output is a voltage that is proportional to the device temperature. The output of the temperature indicator is internally connected to the device ADC.

The circuit may be used as a temperature threshold detector or a more accurate temperature indicator, depending on the level of calibration performed. A one-point calibration allows the circuit to indicate a temperature closely surrounding that point. A two-point calibration allows the circuit to sense the entire range of temperature more accurately. Reference Application Note AN1333, "Use and Calibration of the Internal Temperature Indicator" (DS01333) for more details regarding the calibration process.

# 16.1 Circuit Operation

Figure 16-1 shows a simplified block diagram of the temperature circuit. The proportional voltage output is achieved by measuring the forward voltage drop across multiple silicon junctions.

Equation 16-1 describes the output characteristics of the temperature indicator.

### **EQUATION 16-1: VOUT RANGES**

High Range: VOUT = VDD - 4VT

Low Range: VOUT = VDD - 2VT


The temperature sense circuit is integrated with the Fixed Voltage Reference (FVR) module. See Section 14.0 "Fixed Voltage Reference (FVR)" for more information.

The circuit is enabled by setting the TSEN bit of the FVRCON register. When disabled, the circuit draws no current.

The circuit operates in either high or low range. The high range, selected by setting the TSRNG bit of the FVRCON register, provides a wider output voltage. This provides more resolution over the temperature range, but may be less consistent from part to part. This range requires a higher bias voltage to operate and thus, a higher VDD is needed.

The low range is selected by clearing the TSRNG bit of the FVRCON register. The low range generates a lower voltage drop and thus, a lower bias voltage is needed to operate the circuit. The low range is provided for low voltage operation.

FIGURE 16-1: TEMPERATURE CIRCUIT DIAGRAM



# 16.2 Minimum Operating VDD vs. Minimum Sensing Temperature

When the temperature circuit is operated in low range, the device may be operated at any operating voltage that is within specifications.

When the temperature circuit is operated in high range, the device operating voltage, VDD, must be high enough to ensure that the temperature circuit is correctly biased.

Table 16-1 shows the recommended minimum VDD vs. range setting.

TABLE 16-1: RECOMMENDED VDD VS. RANGE

| Min. VDD, TSRNG = 1 | Min. VDD, TSRNG = 0 |
|---------------------|---------------------|
| 3.6V                | 1.8V                |

### 16.3 Temperature Output

The output of the circuit is measured using the internal Analog-to-Digital Converter. A channel is reserved for the temperature circuit output. Refer to **Section 16.0** "Analog-to-Digital Converter (ADC) Module" for detailed information.

### 16.4 ADC Acquisition Time

To ensure accurate temperature measurements, the user must wait at least 200  $\mu s$  after the ADC input multiplexer is connected to the temperature indicator output before the conversion is performed. In addition, the user must wait 200  $\mu s$  between sequential conversions of the temperature indicator output.

NOTES:

# 17.0 DIGITAL-TO-ANALOG CONVERTER (DAC) MODULE

The Digital-to-Analog Converter supplies a variable voltage reference, ratiometric with the input source, with 32 selectable output levels.

The input of the DAC can be connected to:

- · External VREF pins
- VDD supply voltage
- · FVR (Fixed Voltage Reference)

The output of the DAC can be configured to supply a reference voltage to the following:

- · Comparator positive input
- · ADC input channel
- DACOUT pin
- · Capacitive Sensing module (CSM)

The Digital-to-Analog Converter (DAC) can be enabled by setting the DACEN bit of the DACCON0 register.

# 17.1 Output Voltage Selection

The DAC has 32 voltage level ranges. The 32 levels are set with the DACR<4:0> bits of the DACCON1 register.

The DAC output voltage is determined by the following equations:

#### **EQUATION 17-1: DAC OUTPUT VOLTAGE**

### IF DACEN = 1

$$VOUT = \left( (VSOURCE + - VSOURCE -) \times \frac{DACR[4:0]}{2^5} \right) + VSOURCE - VSOUR$$

#### IF DACEN = 0 & DACLPS = 1 & DACR[4:0] = 11111

VOUT = VSOURCE +

#### IF DACEN = 0 & DACLPS = 0 & DACR[4:0] = 00000

VOUT = VSOURCE -

VSOURCE+ = VDD, VREF, or FVR BUFFER 2

VSOURCE-=VSS

### 17.2 Ratiometric Output Level

The DAC output value is derived using a resistor ladder with each end of the ladder tied to a positive and negative voltage reference input source. If the voltage of either input source fluctuates, a similar fluctuation will result in the DAC output value.


The value of the individual resistors within the ladder can be found in the applicable Electrical Specifications chapter.

# 17.3 DAC Voltage Reference Output


The DAC can be output to the DACOUT pin by setting the DACOE bit of the DACCON0 register to '1'. Selecting the DAC reference voltage for output on the DACOUT pin automatically overrides the digital output buffer and digital input threshold detector functions of that pin. Reading the DACOUT pin when it has been configured for DAC reference voltage output will always return a '0'.

Due to the limited current drive capability, a buffer must be used on the DAC voltage reference output for external connections to DACOUT. Figure 17-2 shows an example buffering technique.

FIGURE 17-1: DIGITAL-TO-ANALOG CONVERTER BLOCK DIAGRAM



# FIGURE 17-2: VOLTAGE REFERENCE OUTPUT BUFFER EXAMPLE



### 17.4 Low-Power Voltage State

In order for the DAC module to consume the least amount of power, one of the two voltage reference input sources to the resistor ladder must be disconnected. Either the positive voltage source, (VSOURCE+), or the negative voltage source, (VSOURCE-) can be disabled.

The negative voltage source is disabled by setting the DACLPS bit in the DACCON0 register. Clearing the DACLPS bit in the DACCON0 register disables the positive voltage source.

# 17.4.1 OUTPUT CLAMPED TO POSITIVE VOLTAGE SOURCE

The DAC output voltage can be set to VSOURCE+ with the least amount of power consumption by performing the following:

- · Clearing the DACEN bit in the DACCON0 register.
- Setting the DACLPS bit in the DACCON0 register.
- Configuring the DACPSS bits to the proper positive source.
- Configuring the DACR<4:0> bits to '11111' in the DACCON1 register.

This is also the method used to output the voltage level from the FVR to an output pin. See **Section 17.5** "Operation During Sleep" for more information.

Reference Figure 17-3 for output clamping examples.

# 17.4.2 OUTPUT CLAMPED TO NEGATIVE VOLTAGE SOURCE


The DAC output voltage can be set to VSOURCE- with the least amount of power consumption by performing the following:

- · Clearing the DACEN bit in the DACCON0 register.
- Clearing the DACLPS bit in the DACCON0 register.
- Configuring the DACNSS bits to the proper negative source.
- Configuring the DACR<4:0> bits to '00000' in the DACCON1 register.

This allows the comparator to detect a zero-crossing while not consuming additional current through the DAC module.

Reference Figure 17-3 for output clamping examples.

### FIGURE 17-3: OUTPUT VOLTAGE CLAMPING EXAMPLES



# 17.5 Operation During Sleep

When the device wakes up from Sleep through an interrupt or a Watchdog Timer time-out, the contents of the DACCON0 register are not affected. To minimize current consumption in Sleep mode, the voltage reference should be disabled.

### 17.6 Effects of a Reset

A device Reset affects the following:

- · DAC is disabled.
- DAC output voltage is removed from the DACOUT pin.
- The DACR<4:0> range select bits are cleared.

#### REGISTER 17-1: DACCON0: VOLTAGE REFERENCE CONTROL REGISTER 0

| R/W-0/0 | R/W-0/0 | R/W-0/0 | U-0 | R/W-0/0 | R/W-0/0 | U-0 | R/W-0/0 |
|---------|---------|---------|-----|---------|---------|-----|---------|
| DACEN   | DACLPS  | DACOE   | _   | DACP    | SS<1:0> | _   | DACNSS  |
| bit 7   |         |         |     |         |         |     | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7 DACEN: DAC Enable bit

1 = DAC is enabled

0 = DAC is disabled

bit 6 DACLPS: DAC Low-Power Voltage State Select bit

1 = DAC Positive reference source selected0 = DAC Negative reference source selected

bit 5 DACOE: DAC Voltage Output Enable bit

1 = DAC voltage level is also an output on the DACOUT pin
 0 = DAC voltage level is disconnected from the DACOUT pin

bit 4 Unimplemented: Read as '0'

bit 3-2 DACPSS<1:0>: DAC Positive Source Select bits

00 = VDD 01 = VREF+ pin 10 = FVR Buffer2 output 11 = Reserved, do not use

bit 1 **Unimplemented:** Read as '0'

bit 0 DACNSS: DAC Negative Source Select bits

1 = VREF-0 = VSS

### REGISTER 17-2: DACCON1: VOLTAGE REFERENCE CONTROL REGISTER 1

| U-0   | U-0 | U-0 | R/W-0/0 | R/W-0/0 | R/W-0/0   | R/W-0/0 | R/W-0/0 |
|-------|-----|-----|---------|---------|-----------|---------|---------|
| _     | _   | _   |         |         | DACR<4:0> |         |         |
| bit 7 |     |     |         |         |           |         | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-5 Unimplemented: Read as '0'

bit 4-0 DACR<4:0>: DAC Voltage Output Select bits

### TABLE 17-1: SUMMARY OF REGISTERS ASSOCIATED WITH THE DAC MODULE

| Name    | Bit 7 | Bit 6  | Bit 5 | Bit 4     | Bit 3 | Bit 2   | Bit 1 | Bit 0  | Register on page |
|---------|-------|--------|-------|-----------|-------|---------|-------|--------|------------------|
| FVRCON  | FVREN | FVRRDY | TSEN  | TSRNG     | CDAFV | /R<1:0> | ADFVF | R<1:0> | 156              |
| DACCON0 | DACEN | DACLPS | DACOE | _         | DACPS | SS<1:0> | _     | DACNSS | 176              |
| DACCON1 | _     | _      | -     | DACR<4:0> |       |         |       | 176    |                  |

**Legend:** — = Unimplemented location, read as '0'. Shaded cells are not used with the DAC Module.

### 18.0 COMPARATOR MODULE


Comparators are used to interface analog circuits to a digital circuit by comparing two analog voltages and providing a digital indication of their relative magnitudes. Comparators are very useful mixed signal building blocks because they provide analog functionality independent of program execution. The analog comparator module includes the following features:

- · Independent comparator control
- · Programmable input selection
- · Comparator output is available internally/externally
- · Programmable output polarity
- · Interrupt-on-change
- · Wake-up from Sleep
- Programmable Speed/Power optimization
- · PWM shutdown
- · Programmable and fixed voltage reference

### 18.1 Comparator Overview

A single comparator is shown in Figure 18-1 along with the relationship between the analog input levels and the digital output. When the analog voltage at VIN+ is less than the analog voltage at VIN-, the output of the comparator is a digital low level. When the analog voltage at VIN+ is greater than the analog voltage at VIN-, the output of the comparator is a digital high level.

### FIGURE 18-1: SINGLE COMPARATOR



**Note:** The black areas of the output of the comparator represents the uncertainty due to input offsets and response time.




FIGURE 18-2: COMPARATOR MODULE SIMPLIFIED BLOCK DIAGRAM

### 18.2 Comparator Control

Each comparator has 2 control registers: CMxCON0 and CMxCON1.

The CMxCON0 registers (see Register 18-1) contain Control and Status bits for the following:

- Fnable
- · Output selection
- · Output polarity
- · Speed/Power selection
- · Hysteresis enable
- · Output synchronization

The CMxCON1 registers (see Register 18-2) contain Control bits for the following:

- · Interrupt enable
- · Interrupt edge polarity
- · Positive input channel selection
- · Negative input channel selection

### 18.2.1 COMPARATOR ENABLE

Setting the CxON bit of the CMxCON0 register enables the comparator for operation. Clearing the CxON bit disables the comparator resulting in minimum current consumption.

# 18.2.2 COMPARATOR OUTPUT SELECTION

The output of the comparator can be monitored by reading either the CxOUT bit of the CMxCON0 register or the MCxOUT bit of the CMOUT register. In order to make the output available for an external connection, the following conditions must be true:

- CxOE bit of the CMxCON0 register must be set
- · Corresponding TRIS bit must be cleared
- CxON bit of the CMxCON0 register must be set
  - Note 1: The CxOE bit of the CMxCON0 register overrides the PORT data latch. Setting the CxON bit of the CMxCON0 register has no impact on the port override.
    - 2: The internal output of the comparator is latched with each instruction cycle. Unless otherwise specified, external outputs are not latched.

#### 18.2.3 COMPARATOR OUTPUT POLARITY

Inverting the output of the comparator is functionally equivalent to swapping the comparator inputs. The polarity of the comparator output can be inverted by setting the CxPOL bit of the CMxCON0 register. Clearing the CxPOL bit results in a non-inverted output.

Table 18-1 shows the output state versus input conditions, including polarity control.

TABLE 18-1: COMPARATOR OUTPUT STATE VS. INPUT CONDITIONS

| Input Condition | CxPOL | CxOUT |
|-----------------|-------|-------|
| CxVn > CxVp     | 0     | 0     |
| CxVn < CxVp     | 0     | 1     |
| CxVn > CxVp     | 1     | 1     |
| CxVn < CxVp     | 1     | 0     |

# 18.2.4 COMPARATOR SPEED/POWER SELECTION

The trade-off between speed or power can be optimized during program execution with the CxSP control bit. The default state for this bit is '1' which selects the normal speed mode. Device power consumption can be optimized at the cost of slower comparator propagation delay by clearing the CxSP bit to '0'.

### 18.3 Comparator Hysteresis

A selectable amount of separation voltage can be added to the input pins of each comparator to provide a hysteresis function to the overall operation. Hysteresis is enabled by setting the CxHYS bit of the CMxCON0 register.

See the applicable Electrical Specifications Chapter for more information.

### 18.4 Timer1 Gate Operation

The output resulting from a comparator operation can be used as a source for gate control of Timer1. See **Section 21.6 "Timer1 Gate"** for more information. This feature is useful for timing the duration or interval of an analog event.

It is recommended that the comparator output be synchronized to Timer1. This ensures that Timer1 does not increment while a change in the comparator is occurring.

# 18.4.1 COMPARATOR OUTPUT SYNCHRONIZATION

The output from either comparator, C1 or C2, can be synchronized with Timer1 by setting the CxSYNC bit of the CMxCON0 register.

Once enabled, the comparator output is latched on the falling edge of the Timer1 source clock. If a prescaler is used with Timer1, the comparator output is latched after the prescaling function. To prevent a race condition, the comparator output is latched on the falling edge of the Timer1 clock source and Timer1 increments on the rising edge of its clock source. See the Comparator Block Diagram (Figure 18-2) and the Timer1 Block Diagram (Figure 22-1) for more information.

## 18.5 Comparator Interrupt

An interrupt can be generated upon a change in the output value of the comparator for each comparator, a rising edge detector and a falling edge detector are present.

When either edge detector is triggered and its associated enable bit is set (CxINTP and/or CxINTN bits of the CMxCON1 register), the Corresponding Interrupt Flag bit (CxIF bit of the PIR2 register) will be set.

To enable the interrupt, you must set the following bits:

- CxON, CxPOL and CxSP bits of the CMxCON0 register
- CxIE bit of the PIE2 register
- CxINTP bit of the CMxCON1 register (for a rising edge detection)
- CxINTN bit of the CMxCON1 register (for a falling edge detection)
- · PEIE and GIE bits of the INTCON register

The associated interrupt flag bit, CxIF bit of the PIR2 register, must be cleared in software. If another edge is detected while this flag is being cleared, the flag will still be set at the end of the sequence.

Note:

Although a comparator is disabled, an interrupt can be generated by changing the output polarity with the CxPOL bit of the CMxCON0 register, or by switching the comparator on or off with the CxON bit of the CMxCON0 register.

# 18.6 Comparator Positive Input Selection

Configuring the CxPCH<1:0> bits of the CMxCON1 register directs an internal voltage reference or an analog pin to the non-inverting input of the comparator:

- CxIN+ analog pin
- DAC
- FVR (Fixed Voltage Reference)
- · Vss (Ground)

See Section 14.0 "Fixed Voltage Reference (FVR)" for more information on the Fixed Voltage Reference module.

See Section 17.0 "Digital-to-Analog Converter (DAC) Module" for more information on the DAC input signal.

Any time the comparator is disabled (CxON = 0), all comparator inputs are disabled.

# 18.7 Comparator Negative Input Selection

The CxNCH<1:0> bits of the CMxCON0 register direct one of four analog pins to the comparator inverting input.

Note:

To use CxIN+ and CxINx- pins as analog input, the appropriate bits must be set in the ANSEL register and the corresponding TRIS bits must also be set to disable the output drivers.

#### 18.8 Comparator Response Time

The comparator output is indeterminate for a period of time after the change of an input source or the selection of a new reference voltage. This period is referred to as the response time. The response time of the comparator differs from the settling time of the voltage reference. Therefore, both of these times must be considered when determining the total response time to a comparator input change. See the Comparator and Voltage Reference Specifications in the applicable Electrical Specifications Chapter for more details.

### 18.9 Interaction with ECCP Logic

The C1 and C2 comparators can be used as general purpose comparators. Their outputs can be brought out to the C1OUT and C2OUT pins. When the ECCP Auto-Shutdown is active it can use one or both comparator signals. If auto-restart is also enabled, the comparators can be configured as a closed loop analog feedback to the ECCP, thereby, creating an analog controlled PWM.

Note:

When the comparator module is first initialized the output state is unknown. Upon initialization, the user should verify the output state of the comparator prior to relying on the result, primarily when using the result in connection with other peripheral features, such as the ECCP Auto-Shutdown mode.


# 18.10 Analog Input Connection Considerations

A simplified circuit for an analog input is shown in Figure 18-3. Since the analog input pins share their connection with a digital input, they have reverse biased ESD protection diodes to VDD and Vss. The analog input, therefore, must be between Vss and VDD. If the input voltage deviates from this range by more than 0.6V in either direction, one of the diodes is forward biased and a latch-up may occur.

A maximum source impedance of 10 k $\Omega$  is recommended for the analog sources. Also, any external component connected to an analog input pin, such as a capacitor or a Zener diode, should have very little leakage current to minimize inaccuracies introduced.

- Note 1: When reading a PORT register, all pins configured as analog inputs will read as a '0'. Pins configured as digital inputs will convert as an analog input, according to the input specification.
  - **2:** Analog levels on any pin defined as a digital input, may cause the input buffer to consume more current than is specified.

### FIGURE 18-3: ANALOG INPUT MODEL



### REGISTER 18-1: CMxCON0: COMPARATOR X CONTROL REGISTER 0

| R/W-0/0 | R-0/0 | R/W-0/0 | R/W-0/0 | U-0 | R/W-1/1 | R/W-0/0 | R/W-0/0 |
|---------|-------|---------|---------|-----|---------|---------|---------|
| CxON    | CxOUT | CxOE    | CxPOL   | _   | CxSP    | CxHYS   | CxSYNC  |
| bit 7   |       |         |         |     |         |         | bit 0   |

Legend:R = Readable bitW = Writable bitU = Unimplemented bit, read as '0'u = Bit is unchangedx = Bit is unknown-n/n = Value at POR and BOR/Value at all other Resets'1' = Bit is set'0' = Bit is cleared

bit 7 **CxON:** Comparator Enable bit

1 = Comparator is enabled and consumes no active power

0 = Comparator is disabled

bit 6 **CxOUT:** Comparator Output bit

If CxPOL = 1 (inverted polarity):

1 = CxVP < CxVN 0 = CxVP > CxVN

If CxPOL = 0 (non-inverted polarity):

1 = CxVP > CxVN 0 = CxVP < CxVN

bit 5 **CxOE:** Comparator Output Enable bit

1 = CxOUT is present on the CxOUT pin. Requires that the associated TRIS bit be cleared to actually drive the pin. Not affected by CxON.

0 = CxOUT is internal only

bit 4 **CxPOL:** Comparator Output Polarity Select bit

1 = Comparator output is inverted0 = Comparator output is not inverted

bit 3 Unimplemented: Read as '0'

bit 2 CxSP: Comparator Speed/Power Select bit

1 = Comparator operates in normal power, higher speed mode 0 = Comparator operates in low-power, low-speed mode

bit 1 CxHYS: Comparator Hysteresis Enable bit

1 = Comparator hysteresis enabled0 = Comparator hysteresis disabled

bit 0 **CxSYNC:** Comparator Output Synchronous Mode bit

1 = Comparator output to Timer1 and I/O pin is synchronous to changes on Timer1 clock source. Output updated on the falling edge of Timer1 clock source.

0 = Comparator output to Timer1 and I/O pin is asynchronous.

#### REGISTER 18-2: CMxCON1: COMPARATOR CX CONTROL REGISTER 1

| R/W-0/0 | R/W-0/0 | R/W-0/0    | R/W-0/0 | U-0 | U-0 | R/W-0/0    | R/W-0/0 |
|---------|---------|------------|---------|-----|-----|------------|---------|
| CxINTP  | CxINTN  | CxPCH<1:0> |         | _   | _   | CxNCH<1:0> |         |
| bit 7   |         |            |         | •   |     |            | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7 CXINTP: Comparator Interrupt on Positive Going Edge Enable bits

1 = The CxIF interrupt flag will be set upon a positive going edge of the CxOUT bit

0 = No interrupt flag will be set on a positive going edge of the CxOUT bit

bit 6 CXINTN: Comparator Interrupt on Negative Going Edge Enable bits

1 = The CxIF interrupt flag will be set upon a negative going edge of the CxOUT bit

0 = No interrupt flag will be set on a negative going edge of the CxOUT bit

bit 5-4 **CxPCH<1:0>:** Comparator Positive Input Channel Select bits

00 = CxVP connects to CxIN+ pin

01 = CxVP connects to DAC Voltage Reference

10 = CxVP connects to FVR Voltage Reference

11 = CxVP connects to Vss

bit 3-2 **Unimplemented:** Read as '0'

bit 1-0 CxNCH<1:0>: Comparator Negative Input Channel Select bits

00 = CxVN connects to C12IN0- pin 01 = CxVN connects to C12IN1- pin

10 = CxVN connects to C12IN2- pin

11 = CxVN connects to C12IN3- pin

### **REGISTER 18-3: CMOUT: COMPARATOR OUTPUT REGISTER**

| U-0   | U-0 | U-0 | U-0 | U-0 | U-0 | R-0/0  | R-0/0  |
|-------|-----|-----|-----|-----|-----|--------|--------|
| _     | _   | -   | _   | -   | _   | MC2OUT | MC1OUT |
| bit 7 |     |     |     |     |     |        | bit 0  |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-2 **Unimplemented:** Read as '0'

bit 1 MC2OUT: Mirror Copy of C2OUT bit bit 0 MC1OUT: Mirror Copy of C1OUT bit

TABLE 18-2: SUMMARY OF REGISTERS ASSOCIATED WITH COMPARATOR MODULE

| Name    | Bit 7  | Bit 6  | Bit 5  | Bit 4  | Bit 3  | Bit 2     | Bit 1  | Bit 0  | Register on Page |
|---------|--------|--------|--------|--------|--------|-----------|--------|--------|------------------|
| CM1CON0 | C10N   | C1OUT  | C10E   | C1POL  |        | C1SP      | C1HYS  | C1SYNC | 183              |
| CM2CON0 | C2ON   | C2OUT  | C2OE   | C2POL  | _      | C2SP      | C2HYS  | C2SYNC | 183              |
| CM1CON1 | C1NTP  | C1INTN | C1PCI  | H<1:0> | _      | _         | C1NCI  | H<1:0> | 184              |
| CM2CON1 | C2NTP  | C2INTN | C2PCI  | H<1:0> | _      | _         | C2NCI  | H<1:0> | 184              |
| CMOUT   | _      | _      | _      | _      | _      | _         | MC2OUT | MC1OUT | 184              |
| FVRCON  | FVREN  | FVRRDY | TSEN   | TSRNG  | CDAFV  | 'R<1:0>   | ADFVI  | R<1:0> | 156              |
| DACCON0 | DACEN  | DACLPS | DACOE  | _      | DACPS  | S<1:0>    | _      | DACNSS | 176              |
| DACCON1 | _      | _      | _      |        |        | DACR<4:0> |        |        | 176              |
| INTCON  | GIE    | PEIE   | TMR0IE | INTE   | IOCIE  | TMR0IF    | INTF   | IOCIF  | 98               |
| PIE2    | OSFIE  | C2IE   | C1IE   | EEIE   | BCLIE  | LCDIE     | _      | CCP2IE | 100              |
| PIR2    | OSFIF  | C2IF   | C1IF   | EEIF   | BCLIF  | LCDIF     | _      | CCP2IF | 103              |
| TRISA   | TRISA7 | TRISA6 | TRISA5 | TRISA4 | TRISA3 | TRISA2    | TRISA1 | TRISA0 | 133              |
| TRISB   | TRISB7 | TRISB6 | TRISB5 | TRISB4 | TRISB3 | TRISB2    | TRISB1 | TRISB0 | 138              |
| ANSELA  | _      | _      | ANSA5  | ANSA4  | ANSA3  | ANSA2     | ANSA1  | ANSA0  | 134              |
| ANSELB  | _      | _      | ANSB5  | ANSB4  | ANSB3  | ANSB2     | ANSB1  | ANSB0  | 139              |

**Legend:** — = unimplemented location, read as '0'. Shaded cells are unused by the comparator module.

**NOTES:** 

#### 19.0 SR LATCH

The module consists of a single SR Latch with multiple Set and Reset inputs as well as separate latch outputs. The SR Latch module includes the following features:

- · Programmable input selection
- SR Latch output is available externally
- Separate Q and Q outputs
- · Firmware Set and Reset

The SR Latch can be used in a variety of analog applications, including oscillator circuits, one-shot circuit, hysteretic controllers, and analog timing applications.

## 19.1 Latch Operation

The latch is a Set-Reset Latch that does not depend on a clock source. Each of the Set and Reset inputs are active-high. The latch can be set or reset by:

- Software control (SRPS and SRPR bits)
- Comparator C1 output (SYNCC1OUT)
- Comparator C2 output (SYNCC2OUT)
- SRI pin
- Programmable clock (SRCLK)

The SRPS and the SRPR bits of the SRCON0 register may be used to set or reset the SR Latch, respectively. The latch is Reset-dominant. Therefore, if both Set and Reset inputs are high, the latch will go to the Reset state. Both the SRPS and SRPR bits are self resetting which means that a single write to either of the bits is all that is necessary to complete a latch Set or Reset operation.

The output from Comparator C1 or C2 can be used as the Set or Reset inputs of the SR Latch. The output of either Comparator can be synchronized to the Timer1 clock source. See Section 18.0 "Comparator Module" and Section 21.0 "Timer1 Module with Gate Control" for more information.

An external source on the SRI pin can be used as the Set or Reset inputs of the SR Latch.

An internal clock source is available that can periodically set or reset the SR Latch. The SRCLK<2:0> bits in the SRCON0 register are used to select the clock source period. The SRSCKE and SRRCKE bits of the SRCON1 register enable the clock source to set or reset the SR Latch, respectively.

Note:

Enabling both the Set and Reset inputs from any one source at the same time may result in indeterminate operation, as the Reset dominance cannot be assured.

### 19.2 Latch Output

The SRQEN and SRNQEN bits of the SRCON0 register control the Q and  $\overline{Q}$  latch outputs. Both of the SR Latch outputs may be directly output to an I/O pin at the same time. The  $\overline{Q}$  latch output pin function can be moved to an alternate pin using the SRNQSEL bit of the APFCON register.

The applicable TRIS bit of the corresponding port must be cleared to enable the port pin output driver.

#### 19.3 Effects of a Reset

Upon any device Reset, the SR Latch output is not initialized to a known state. The user's firmware is responsible for initializing the latch output before enabling the output pins.




TABLE 19-1: SRCLK FREQUENCY TABLE

| SRCLK | Divider | Fosc = 32 MHz | Fosc = 20 MHz | Fosc = 16 MHz | Fosc = 4 MHz | Fosc = 1 MHz |
|-------|---------|---------------|---------------|---------------|--------------|--------------|
| 111   | 512     | 62.5 kHz      | 39.0 kHz      | 31.3 kHz      | 7.81 kHz     | 1.95 kHz     |
| 110   | 256     | 125 kHz       | 78.1 kHz      | 62.5 kHz      | 15.6 kHz     | 3.90 kHz     |
| 101   | 128     | 250 kHz       | 156 kHz       | 125 kHz       | 31.25 kHz    | 7.81 kHz     |
| 100   | 64      | 500 kHz       | 313 kHz       | 250 kHz       | 62.5 kHz     | 15.6 kHz     |
| 011   | 32      | 1 MHz         | 625 kHz       | 500 kHz       | 125 kHz      | 31.3 kHz     |
| 010   | 16      | 2 MHz         | 1.25 MHz      | 1 MHz         | 250 kHz      | 62.5 kHz     |
| 001   | 8       | 4 MHz         | 2.5 MHz       | 2 MHz         | 500 kHz      | 125 kHz      |
| 000   | 4       | 8 MHz         | 5 MHz         | 4 MHz         | 1 MHz        | 250 kHz      |

#### REGISTER 19-1: SRCON0: SR LATCH CONTROL 0 REGISTER

| R/W-0/0 | R/W-0/0 | R/W-0/0    | R/W-0/0 | R/W-0/0 | R/W-0/0 | R/S-0/0 | R/S-0/0 |
|---------|---------|------------|---------|---------|---------|---------|---------|
| SRLEN   |         | SRCLK<2:0> |         | SRQEN   | SRNQEN  | SRPS    | SRPR    |
| bit 7   |         |            |         |         |         |         | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared S = Bit is set only

bit 7 SRLEN: SR Latch Enable bit

1 = SR Latch is enabled

0 = SR Latch is disabled

bit 6-4 SRCLK<2:0>: SR Latch Clock Divider bits

000 = Generates a 1 Fosc wide pulse every 4th Fosc cycle clock

001 = Generates a 1 Fosc wide pulse every 8th Fosc cycle clock

010 = Generates a 1 Fosc wide pulse every 16th Fosc cycle clock

011 = Generates a 1 Fosc wide pulse every 32nd Fosc cycle clock

100 = Generates a 1 Fosc wide pulse every 64th Fosc cycle clock

101 = Generates a 1 Fosc wide pulse every 128th Fosc cycle clock

110 = Generates a 1 Fosc wide pulse every 256th Fosc cycle clock

111 = Generates a 1 Fosc wide pulse every 512th Fosc cycle clock

bit 3 SRQEN: SR Latch Q Output Enable bit

If SRLEN = 1:

1 = Q is present on the SRQ pin

0 = External Q output is disabled

If SRLEN = 0:

SR Latch is disabled

bit 2 SRNQEN: SR Latch  $\overline{Q}$  Output Enable bit

If SRLEN = 1:

 $1 = \overline{Q}$  is present on the SRnQ pin

 $0 = \text{External } \overline{Q} \text{ output is disabled}$ 

If SRLEN = 0:

SR Latch is disabled

bit 1 SRPS: Pulse Set Input of the SR Latch bit (1)

1 = Pulse set input for 1 Q-clock period

0 = No effect on set input.

bit 0 SRPR: Pulse Reset Input of the SR Latch bit (1)

1 = Pulse Reset input for 1 Q-clock period

0 = No effect on Reset input.

Note 1: Set only, always reads back '0'.

#### REGISTER 19-2: SRCON1: SR LATCH CONTROL 1 REGISTER

| R/W-0/0 |
|---------|---------|---------|---------|---------|---------|---------|---------|
| SRSPE   | SRSCKE  | SRSC2E  | SRSC1E  | SRRPE   | SRRCKE  | SRRC2E  | SRRC1E  |
| bit 7   |         |         |         |         |         |         | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7 SRSPE: SR Latch Peripheral Set Enable bit

1 = SR Latch is set when the SRI pin is high.

0 = SRI pin has no effect on the set input of the SR Latch

bit 6 SRSCKE: SR Latch Set Clock Enable bit

1 = Set input of SR Latch is pulsed with SRCLK

0 = SRCLK has no effect on the set input of the SR Latch

bit 5 SRSC2E: SR Latch C2 Set Enable bit

1 = SR Latch is set when the C2 Comparator output is high

0 = C2 Comparator output has no effect on the set input of the SR Latch

bit 4 SRSC1E: SR Latch C1 Set Enable bit

1 = SR Latch is set when the C1 Comparator output is high

0 = C1 Comparator output has no effect on the set input of the SR Latch

bit 3 SRRPE: SR Latch Peripheral Reset Enable bit

1 = SR Latch is reset when the SRI pin is high.

0 = SRI pin has no effect on the reset input of the SR Latch

bit 2 SRRCKE: SR Latch Reset Clock Enable bit

1 = Reset input of SR Latch is pulsed with SRCLK

0 = SRCLK has no effect on the reset input of the SR Latch

bit 1 SRRC2E: SR Latch C2 Reset Enable bit

1 = SR Latch is reset when the C2 Comparator output is high

0 = C2 Comparator output has no effect on the reset input of the SR Latch

bit 0 SRRC1E: SR Latch C1 Reset Enable bit

1 = SR Latch is reset when the C1 Comparator output is high

0 = C1 Comparator output has no effect on the reset input of the SR Latch

#### TABLE 19-2: SUMMARY OF REGISTERS ASSOCIATED WITH SR LATCH MODULE

| Name   | Bit 7  | Bit 6  | Bit 5      | Bit 4  | Bit 3  | Bit 2  | Bit 1  | Bit 0  | Register on Page |
|--------|--------|--------|------------|--------|--------|--------|--------|--------|------------------|
| ANSELA | _      | _      | ANSA5      | ANSA4  | ANSA3  | ANSA2  | ANSA1  | ANSA0  | 134              |
| SRCON0 | SRLEN  | S      | SRCLK<2:0> |        |        | SRNQEN | SRPS   | SRPR   | 189              |
| SRCON1 | SRSPE  | SRSCKE | SRSC2E     | SRSC1E | SRRPE  | SRRCKE | SRRC2E | SRRC1E | 190              |
| TRISA  | TRISA7 | TRISA6 | TRISA5     | TRISA4 | TRISA3 | TRISA2 | TRISA1 | TRISA0 | 133              |

Legend: — = unimplemented location, read as '0'. Shaded cells are unused by the SR Latch module.

### 20.0 TIMERO MODULE

The Timer0 module is an 8-bit timer/counter with the following features:

- 8-bit timer/counter register (TMR0)
- 8-bit prescaler (independent of Watchdog Timer)
- · Programmable internal or external clock source
- · Programmable external clock edge selection
- · Interrupt on overflow
- · TMR0 can be used to gate Timer1

Figure 20-1 is a block diagram of the Timer0 module.

## 20.1 Timer0 Operation

The Timer0 module can be used as either an 8-bit timer or an 8-bit counter.

#### 20.1.1 8-BIT TIMER MODE

The Timer0 module will increment every instruction cycle, if used without a prescaler. 8-it Timer mode is selected by clearing the TMR0CS bit of the OPTION\_REG register.

When TMR0 is written, the increment is inhibited for two instruction cycles immediately following the write.

te: The value written to the TMR0 register can be adjusted, in order to account for the two instruction cycle delay when TMR0 is written.

#### 20.1.2 8-BIT COUNTER MODE


In 8-Bit Counter mode, the Timer0 module will increment on every rising or falling edge of the T0CKI pin or the Capacitive Sensing Oscillator (CPSCLK) signal.

8-Bit Counter mode using the T0CKI pin is selected by setting the TMR0CS bit in the OPTION\_REG register to '1' and resetting the T0XCS bit in the CPSCON0 register to '0'.

8-Bit Counter mode using the Capacitive Sensing Oscillator (CPSCLK) signal is selected by setting the TMR0CS bit in the OPTION\_REG register to '1' and setting the T0XCS bit in the CPSCON0 register to '1'.

The rising or falling transition of the incrementing edge for either input source is determined by the TMR0SE bit in the OPTION\_REG register.

#### FIGURE 20-1: BLOCK DIAGRAM OF THE TIMER0



# 20.1.3 SOFTWARE PROGRAMMABLE PRESCALER

A software programmable prescaler is available for exclusive use with Timer0. The prescaler is enabled by clearing the PSA bit of the OPTION\_REG register.

**Note:** The Watchdog Timer (WDT) uses its own independent prescaler.

There are 8 prescaler options for the Timer0 module ranging from 1:2 to 1:256. The prescale values are selectable via the PS<2:0> bits of the OPTION\_REG register. In order to have a 1:1 prescaler value for the Timer0 module, the prescaler must be disabled by setting the PSA bit of the OPTION REG register.

The prescaler is not readable or writable. All instructions writing to the TMR0 register will clear the prescaler.

#### 20.1.4 TIMER0 INTERRUPT

Timer0 will generate an interrupt when the TMR0 register overflows from FFh to 00h. The TMR0IF interrupt flag bit of the INTCON register is set every time the TMR0 register overflows, regardless of whether or not the Timer0 interrupt is enabled. The TMR0IF bit can only be cleared in software. The Timer0 interrupt enable is the TMR0IE bit of the INTCON register.

| Note: | The Timer0 interrupt cannot wake the    |
|-------|---|
|       | processor from Sleep since the timer is |
|       | frozen during Sleep.                    |

# 20.1.5 8-BIT COUNTER MODE SYNCHRONIZATION

When in 8-Bit Counter mode, the incrementing edge on the T0CKI pin must be synchronized to the instruction clock. Synchronization can be accomplished by sampling the prescaler output on the Q2 and Q4 cycles of the instruction clock. The high and low periods of the external clocking source must meet the timing requirements as shown in the applicable Electrical Specifications Chapter.

#### 20.1.6 OPERATION DURING SLEEP

Timer0 cannot operate while the processor is in Sleep mode. The contents of the TMR0 register will remain unchanged while the processor is in Sleep mode.

## 20.2 Option and Timer0 Control Register

#### REGISTER 20-1: OPTION\_REG: OPTION REGISTER

| R/W-1/1 |
|---------|---------|---------|---------|---------|---------|---------|---------|
| WPUEN   | INTEDG  | TMR0CS  | TMR0SE  | PSA     |         | PS<2:0> |         |
| bit 7   |         |         |         |         |         |         | bit 0   |

Legend:R = Readable bitW = Writable bitU = Unimplemented bit, read as '0'u = Bit is unchangedx = Bit is unknown-n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7 WPUEN: Weak Pull-up Enable bit

1 = All weak pull-ups are disabled (except MCLR, if it is enabled) 0 = Weak pull-ups are enabled by individual WPUx latch values

bit 6 INTEDG: Interrupt Edge Select bit

1 = Interrupt on rising edge of INT pin0 = Interrupt on falling edge of INT pin

bit 5 TMR0CS: Timer0 Clock Source Select bit

1 = Transition on T0CKI pin

0 = Internal instruction cycle clock (Fosc/4)

bit 4 TMR0SE: Timer0 Source Edge Select bit

1 = Increment on high-to-low transition on T0CKI pin 0 = Increment on low-to-high transition on T0CKI pin

bit 3 **PSA:** Prescaler Assignment bit

1 = Prescaler is not assigned to the Timer0 module0 = Prescaler is assigned to the Timer0 module

bit 2-0 **PS<2:0>:** Prescaler Rate Select bits

Bit Value Timer<sub>0</sub> Rate 1:2 000 1:4 001 010 1:8 011 1:16 1:32 100 101 1:64 110 1:128 111 1:256

#### TABLE 20-1: SUMMARY OF REGISTERS ASSOCIATED WITH TIMERO

| Name                        | Bit 7  | Bit 6  | Bit 5  | Bit 4  | Bit 3  | Bit 2  | Bit 1  | Bit 0  | Register on Page |
|-----------------------------|--------|--------|--------|--------|--------|--------|--------|--------|------------------|
| CPSCON0                     | CPSON  | _      | _      | _      | CPSRN  | G<1:0> | CPSOUT | T0XCS  | 323              |
| INTCON                      | GIE    | PEIE   | TMR0IE | INTE   | IOCIE  | TMR0IF | INTF   | IOCIF  | 98               |
| OPTION_REG                  | WPUEN  | INTEDG | TMR0CS | TMR0SE | PSA    |        | -      | 193    |                  |
| TMR0 Timer0 Module Register |        |        |        |        |        |        |        | 191*   |                  |
| TRISA                       | TRISA7 | TRISA6 | TRISA5 | TRISA4 | TRISA3 | TRISA2 | TRISA1 | TRISA0 | 133              |

**Legend:** — = Unimplemented location, read as '0'. Shaded cells are not used by the Timer0 module.

Page provides register information.

**NOTES:** 

# 21.0 TIMER1 MODULE WITH GATE CONTROL


The Timer1 module is a 16-bit timer/counter with the following features:

- 16-bit timer/counter register pair (TMR1H:TMR1L)
- · Programmable internal or external clock source
- · 2-bit prescaler
- · Dedicated 32 kHz oscillator circuit
- · Optionally synchronized comparator out
- Multiple Timer1 gate (count enable) sources
- · Interrupt on overflow
- Wake-up on overflow (external clock, Asynchronous mode only)
- Time base for the Capture/Compare function
- Special Event Trigger (with CCP/ECCP)
- · Selectable Gate Source Polarity

- · Gate Toggle Mode
- · Gate Single-pulse Mode
- · Gate Value Status
- · Gate Event Interrupt

Figure 21-1 is a block diagram of the Timer1 module.

## FIGURE 21-1: TIMER1 BLOCK DIAGRAM



### 21.1 Timer1 Operation

The Timer1 module is a 16-bit incrementing counter which is accessed through the TMR1H:TMR1L register pair. Writes to TMR1H or TMR1L directly update the counter.

When used with an internal clock source, the module is a timer and increments on every instruction cycle. When used with an external clock source, the module can be used as either a timer or counter and increments on every selected edge of the external source.

Timer1 is enabled by configuring the TMR1ON and TMR1GE bits in the T1CON and T1GCON registers, respectively. Table 21-1 displays the Timer1 enable selections.

TABLE 21-1: TIMER1 ENABLE SELECTIONS

| TMR10N | TMR1GE | Timer1<br>Operation |
|--------|--------|---------------------|
| 0      | 0      | Off                 |
| 0      | 1      | Off                 |
| 1      | 0      | Always On           |
| 1      | 1      | Count Enabled       |

#### 21.2 Clock Source Selection

The TMR1CS<1:0> and T1OSCEN bits of the T1CON register are used to select the clock source for Timer1. Table 21-2 displays the clock source selections.

#### 21.2.1 INTERNAL CLOCK SOURCE

When the internal clock source is selected the TMR1H:TMR1L register pair will increment on multiples of Fosc as determined by the Timer1 prescaler.

When the Fosc internal clock source is selected, the Timer1 register value will increment by four counts every instruction clock cycle. Due to this condition, a 2 LSB error in resolution will occur when reading the Timer1 value. To utilize the full resolution of Timer1, an asynchronous input signal must be used to gate the Timer1 clock input.

The following asynchronous sources may be used:

- Asynchronous event on the T1G pin to Timer1 gate
- · C1 or C2 comparator input to Timer1 gate

#### 21.2.2 EXTERNAL CLOCK SOURCE

When the external clock source is selected, the Timer1 module may work as a timer or a counter.

When enabled to count, Timer1 is incremented on the rising edge of the external clock input T1CKI or the capacitive sensing oscillator signal. Either of these external clock sources can be synchronized to the microcontroller system clock or they can run asynchronously.

When used as a timer with a clock oscillator, an external 32.768 kHz crystal can be used in conjunction with the dedicated internal oscillator circuit.

Note:

In Counter mode, a falling edge must be registered by the counter prior to the first incrementing rising edge after any one or more of the following conditions:

- · Timer1 enabled after POR
- Write to TMR1H or TMR1L
- · Timer1 is disabled
- Timer1 is disabled (TMR1ON = 0) when T1CKI is high then Timer1 is enabled (TMR1ON=1) when T1CKI is low

TABLE 21-2: CLOCK SOURCE SELECTIONS

| TMR1CS1 | TMR1CS0 | T10SCEN | Clock Source                   |
|---------|---------|---------|--------------------------------|
| 0       | 0       | x       | Instruction Clock (Fosc/4)     |
| 0       | 1       | x       | System Clock (Fosc)            |
| 1       | 0       | 0       | External Clocking on T1CKI Pin |
| 1       | 0       | 0       | External Clocking on T1CKI Pin |
| 1       | 1       | х       | Capacitive Sensing Oscillator  |

#### 21.3 Timer1 Prescaler

Timer1 has four prescaler options allowing 1, 2, 4 or 8 divisions of the clock input. The T1CKPS bits of the T1CON register control the prescale counter. The prescale counter is not directly readable or writable; however, the prescaler counter is cleared upon a write to TMR1H or TMR1L.

#### 21.4 Timer1 Oscillator

A dedicated low-power 32.768 kHz oscillator circuit is built-in between pins T1OSI (input) and T1OSO (amplifier output). This internal circuit is to be used in conjunction with an external 32.768 kHz crystal.

The oscillator circuit is enabled by setting the T1OSCEN bit of the T1CON register. The oscillator will continue to run during Sleep.

Note:

The oscillator requires a start-up and stabilization time before use. Thus, T1OSCEN should be set and a suitable delay observed prior to using Timer1. A suitable delay similar to the OST delay can be implemented in software by clearing the TMR1IF bit then presetting the TMR1H:TMR1L register pair to FC00h. The TMR1IF flag will be set when 1024 clock cycles have elapsed, thereby indicating that the oscillator is running and reasonably stable.

# 21.5 Timer1 Operation in Asynchronous Counter Mode

If control bit T1SYNC of the T1CON register is set, the external clock input is not synchronized. The timer increments asynchronously to the internal phase clocks. If the external clock source is selected then the timer will continue to run during Sleep and can generate an interrupt on overflow, which will wake-up the processor. However, special precautions in software are needed to read/write the timer (see Section 21.5.1 "Reading and Writing Timer1 in Asynchronous Counter Mode").

Note:

When switching from synchronous to asynchronous operation, it is possible to skip an increment. When switching from asynchronous to synchronous operation, it is possible to produce an additional increment.

# 21.5.1 READING AND WRITING TIMER1 IN ASYNCHRONOUS COUNTER MODE

Reading TMR1H or TMR1L while the timer is running from an external asynchronous clock will ensure a valid read (taken care of in hardware). However, the user should keep in mind that reading the 16-bit timer in two 8-bit values itself, poses certain problems, since the timer may overflow between the reads.

For writes, it is recommended that the user simply stop the timer and write the desired values. A write contention may occur by writing to the timer registers, while the register is incrementing. This may produce an unpredictable value in the TMR1H:TMR1L register pair.

#### 21.6 Timer1 Gate

Timer1 can be configured to count freely or the count can be enabled and disabled using Timer1 gate circuitry. This is also referred to as Timer1 Gate Enable.

Timer1 gate can also be driven by multiple selectable sources.

#### 21.6.1 TIMER1 GATE ENABLE

The Timer1 Gate Enable mode is enabled by setting the TMR1GE bit of the T1GCON register. The polarity of the Timer1 Gate Enable mode is configured using the T1GPOL bit of the T1GCON register.

When Timer1 Gate Enable mode is enabled, Timer1 will increment on the rising edge of the Timer1 clock source. When Timer1 Gate Enable mode is disabled, no incrementing will occur and Timer1 will hold the current count. See Figure 21-3 for timing details.

TABLE 21-3: TIMER1 GATE ENABLE SELECTIONS

| T1CLK    | T1GPOL | T1G | Timer1 Operation |
|----------|--------|-----|------------------|
| <b>↑</b> | 0      | 0   | Counts           |
| <b>↑</b> | 0      | 1   | Holds Count      |
| <b>↑</b> | 1      | 0   | Holds Count      |
| <b>↑</b> | 1      | 1   | Counts           |

# 21.6.2 TIMER1 GATE SOURCE SELECTION

The Timer1 gate source can be selected from one of four different sources. Source selection is controlled by the T1GSS bits of the T1GCON register. The polarity for each available source is also selectable. Polarity selection is controlled by the T1GPOL bit of the T1GCON register.

TABLE 21-4: TIMER1 GATE SOURCES

| T1GSS | Timer1 Gate Source  |
|-------|---|
| 00    | Timer1 Gate Pin   |
| 01    | Overflow of Timer0 (TMR0 increments from FFh to 00h)                  |
| 10    | Comparator 1 Output SYNCC1OUT (optionally Timer1 synchronized output) |
| 11    | Comparator 2 Output SYNCC2OUT (optionally Timer1 synchronized output) |

#### 21.6.2.1 T1G Pin Gate Operation

The T1G pin is one source for Timer1 gate control. It can be used to supply an external source to the Timer1 gate circuitry.

### 21.6.2.2 Timer0 Overflow Gate Operation

When Timer0 increments from FFh to 00h, a low-to-high pulse will automatically be generated and internally supplied to the Timer1 gate circuitry.

#### 21.6.2.3 Comparator C1 Gate Operation

The output resulting from a Comparator 1 operation can be selected as a source for Timer1 gate control. The Comparator 1 output (SYNCC1OUT) can be synchronized to the Timer1 clock or left asynchronous. For more information see Section 18.4.1 "Comparator Output Synchronization".

### 21.6.2.4 Comparator C2 Gate Operation

The output resulting from a Comparator 2 operation can be selected as a source for Timer1 gate control. The Comparator 2 output (SYNCC2OUT) can be synchronized to the Timer1 clock or left asynchronous. For more information see Section 18.4.1 "Comparator Output Synchronization".

#### 21.6.3 TIMER1 GATE TOGGLE MODE

When Timer1 Gate Toggle mode is enabled, it is possible to measure the full-cycle length of a Timer1 gate signal, as opposed to the duration of a single level pulse.

The Timer1 gate source is routed through a flip-flop that changes state on every incrementing edge of the signal. See Figure 21-4 for timing details.

Timer1 Gate Toggle mode is enabled by setting the T1GTM bit of the T1GCON register. When the T1GTM bit is cleared, the flip-flop is cleared and held clear. This is necessary in order to control which edge is measured.

| Note: | Enabling Toggle mode at the same time       |  |  |  |  |  |
|-------|---|--|--|--|--|--|
|       | as changing the gate polarity may result in |  |  |  |  |  |
|       | indeterminate operation.                    |  |  |  |  |  |

# 21.6.4 TIMER1 GATE SINGLE-PULSE MODE

When Timer1 Gate Single-Pulse mode is enabled, it is possible to capture a single pulse gate event. Timer1 Gate Single-Pulse mode is first enabled by setting the T1GSPM bit in the T1GCON register. Next, the T1GGO/DONE bit in the T1GCON register must be set. The Timer1 will be fully enabled on the next incrementing edge. On the next trailing edge of the pulse, the T1GGO/DONE bit will automatically be cleared. No other gate events will be allowed to increment Timer1 until the T1GGO/DONE bit is once again set in software. See Figure 21-5 for timing details.

If the Single Pulse Gate mode is disabled by clearing the T1GSPM bit in the T1GCON register, the T1GGO/DONE bit should also be cleared.

Enabling the Toggle mode and the Single-Pulse mode simultaneously will permit both sections to work together. This allows the cycle times on the Timer1 gate source to be measured. See Figure 21-6 for timing details.

#### 21.6.5 TIMER1 GATE VALUE STATUS

When Timer1 Gate Value Status is utilized, it is possible to read the most current level of the gate control value. The value is stored in the T1GVAL bit in the T1GCON register. The T1GVAL bit is valid even when the Timer1 gate is not enabled (TMR1GE bit is cleared).

#### 21.6.6 TIMER1 GATE EVENT INTERRUPT

When Timer1 Gate Event Interrupt is enabled, it is possible to generate an interrupt upon the completion of a gate event. When the falling edge of T1GVAL occurs, the TMR1GIF flag bit in the PIR1 register will be set. If the TMR1GIE bit in the PIE1 register is set, then an interrupt will be recognized.

The TMR1GIF flag bit operates even when the Timer1 gate is not enabled (TMR1GE bit is cleared).

## 21.7 Timer1 Interrupt

The Timer1 register pair (TMR1H:TMR1L) increments to FFFFh and rolls over to 0000h. When Timer1 rolls over, the Timer1 interrupt flag bit of the PIR1 register is set. To enable the interrupt on rollover, you must set these bits:

- · TMR1ON bit of the T1CON register
- TMR1IE bit of the PIE1 register
- · PEIE bit of the INTCON register
- · GIE bit of the INTCON register

The interrupt is cleared by clearing the TMR1IF bit in the Interrupt Service Routine.

**Note:** The TMR1H:TMR1L register pair and the TMR1IF bit should be cleared before enabling interrupts.

## 21.8 Timer1 Operation During Sleep

Timer1 can only operate during Sleep when setup in Asynchronous Counter mode. In this mode, an external crystal or clock source can be used to increment the counter. To set up the timer to wake the device:

- TMR1ON bit of the T1CON register must be set
- TMR1IE bit of the PIE1 register must be set
- · PEIE bit of the INTCON register must be set
- T1SYNC bit of the T1CON register must be set
- TMR1CS bits of the T1CON register must be configured
- T10SCEN bit of the T1CON register must be configured

The device will wake-up on an overflow and execute the next instructions. If the GIE bit of the INTCON register is set, the device will call the Interrupt Service Routine.

Timer1 oscillator will continue to operate in Sleep regardless of the T1SYNC bit setting.

# 21.9 ECCP/CCP Capture/Compare Time Base

The CCP modules use the TMR1H:TMR1L register pair as the time base when operating in Capture or Compare mode.

In Capture mode, the value in the TMR1H:TMR1L register pair is copied into the CCPR1H:CCPR1L register pair on a configured event.

In Compare mode, an event is triggered when the value CCPR1H:CCPR1L register pair matches the value in the TMR1H:TMR1L register pair. This event can be a Special Event Trigger.

For more information, see Section 12.0 "I/O Ports".

## 21.10 ECCP/CCP Special Event Trigger

When any of the CCP's are configured to trigger a special event, the trigger will clear the TMR1H:TMR1L register pair. This special event does not cause a Timer1 interrupt. The CCP module may still be configured to generate a CCP interrupt.


In this mode of operation, the CCPR1H:CCPR1L register pair becomes the period register for Timer1.

Timer1 should be synchronized and Fosc/4 should be selected as the clock source in order to utilize the Special Event Trigger. Asynchronous operation of Timer1 can cause a Special Event Trigger to be missed.

In the event that a write to TMR1H or TMR1L coincides with a Special Event Trigger from the CCP, the write will take precedence.

For more information, see **Section 15.2.5** "**Special Event Trigger**".

### FIGURE 21-2: TIMER1 INCREMENTING EDGE



Note 1: Arrows indicate counter increments.

2: In Counter mode, a falling edge must be registered by the counter prior to the first incrementing rising edge of the clock.

FIGURE 21-3: TIMER1 GATE ENABLE MODE







FIGURE 21-4: TIMER1 GATE TOGGLE MODE







## 21.11 Timer1 Control Register

The Timer1 Control register (T1CON), shown in Register 21-1, is used to control Timer1 and select the various features of the Timer1 module.

### REGISTER 21-1: T1CON: TIMER1 CONTROL REGISTER

| R/W-0/u     | R/W-0/u | R/W-0/u     | R/W-0/u | R/W-0/u | R/W-0/u | U-0 | R/W-0/u |
|-------------|---------|-------------|---------|---------|---------|-----|---------|
| TMR1CS<1:0> |         | T1CKPS<1:0> |         | T10SCEN | T1SYNC  | _   | TMR10N  |
| bit 7       |         |             |         |         |         |     | bit 0   |

| Legend:              |                      |   |
|----------------------|----------------------|---|
| R = Readable bit     | W = Writable bit     | U = Unimplemented bit, read as '0'                    |
| u = Bit is unchanged | x = Bit is unknown   | -n/n = Value at POR and BOR/Value at all other Resets |
| '1' = Bit is set     | '0' = Bit is cleared |   |

bit 7-6 TMR1CS<1:0>: Timer1 Clock Source Select bits

11 = Timer1 clock source is Capacitive Sensing Oscillator (CAPOSC)

10 = Timer1 clock source is pin or oscillator:

If T1OSCEN = 0:

External clock from T1CKI pin (on the rising edge)

<u>If T1OSCEN = 1</u>:

Crystal oscillator on T1OSI/T1OSO pins

01 = Timer1 clock source is system clock (Fosc)

00 = Timer1 clock source is instruction clock (Fosc/4)

bit 5-4 T1CKPS<1:0>: Timer1 Input Clock Prescale Select bits

11 = 1:8 Prescale value

10 = 1:4 Prescale value

01 = 1:2 Prescale value

00 = 1:1 Prescale value

bit 3 T10SCEN: LP Oscillator Enable Control bit

1 = Dedicated Timer1 oscillator circuit enabled

0 = Dedicated Timer1 oscillator circuit disabled

bit 2 T1SYNC: Timer1 External Clock Input Synchronization Control bit

TMR1CS<1:0> = 1X

1 = Do not synchronize external clock input

0 = Synchronize external clock input with system clock (Fosc)

TMR1CS<1:0> = 0X

This bit is ignored. Timer1 uses the internal clock when TMR1CS<1:0> = 1x.

bit 1 **Unimplemented:** Read as '0'

bit 0 TMR1ON: Timer1 On bit

1 = Enables Timer1

0 = Stops Timer1

Clears Timer1 gate flip-flop

# 21.12 Timer1 Gate Control Register

The Timer1 Gate Control register (T1GCON), shown in Register 21-2, is used to control Timer1 gate.

#### REGISTER 21-2: T1GCON: TIMER1 GATE CONTROL REGISTER

| R/W-0/u | R/W-0/u | R/W-0/u | R/W-0/u | R/W/HC-0/u     | R-x/x  | R/W-0/u    | R/W-0/u |
|---------|---------|---------|---------|----------------|--------|------------|---------|
| TMR1GE  | T1GPOL  | T1GTM   | T1GSPM  | T1GGO/<br>DONE | T1GVAL | T1GSS<1:0> |         |
| bit 7   |         |         |         |                |        |            | bit 0   |

| Legend:              |                      |   |
|----------------------|----------------------|---|
| R = Readable bit     | W = Writable bit     | U = Unimplemented bit, read as '0'                    |
| u = Bit is unchanged | x = Bit is unknown   | -n/n = Value at POR and BOR/Value at all other Resets |
| '1' = Bit is set     | '0' = Bit is cleared | HC = Bit is cleared by hardware                       |

bit 7 TMR1GE: Timer1 Gate Enable bit

 $\frac{\text{If TMR1ON} = 0}{\text{This bit is ignored}}$  If TMR1ON = 1

1 = Timer1 counting is controlled by the Timer1 gate function

0 = Timer1 counts regardless of Timer1 gate function

bit 6 T1GPOL: Timer1 Gate Polarity bit

1 = Timer1 gate is active-high (Timer1 counts when gate is high)0 = Timer1 gate is active-low (Timer1 counts when gate is low)

bit 5 T1GTM: Timer1 Gate Toggle Mode bit

1 = Timer1 Gate Toggle mode is enabled

0 = Timer1 Gate Toggle mode is disabled and toggle flip flop is cleared

Timer1 gate flip-flop toggles on every rising edge.

bit 4 T1GSPM: Timer1 Gate Single-Pulse Mode bit

1 = Timer1 gate Single-Pulse mode is enabled and is controlling Timer1 gate

0 = Timer1 gate Single-Pulse mode is disabled

bit 3 T1GGO/DONE: Timer1 Gate Single-Pulse Acquisition Status bit

1 = Timer1 gate single-pulse acquisition is ready, waiting for an edge

0 = Timer1 gate single-pulse acquisition has completed or has not been started

bit 2 T1GVAL: Timer1 Gate Current State bit

Indicates the current state of the Timer1 gate that could be provided to TMR1H:TMR1L.

Unaffected by Timer1 Gate Enable (TMR1GE).

bit 1-0 T1GSS<1:0>: Timer1 Gate Source Select bits

00 = Timer1 gate pin

01 = Timer0 overflow output

10 = Comparator 1 optionally synchronized output (SYNCC1OUT)

11 = Comparator 2 optionally synchronized output (SYNCC2OUT)

TABLE 21-5: SUMMARY OF REGISTERS ASSOCIATED WITH TIMER1

| Name    | Bit 7        | Bit 6           | Bit 5          | Bit 4          | Bit 3          | Bit 2    | Bit 1  | Bit 0  | Register on Page |
|---------|--------------|-----------------|----------------|----------------|----------------|----------|--------|--------|------------------|
| ANSELB  | _            | -               | ANSB5          | ANSB4          | ANSB3          | ANSB2    | ANSB1  | ANSB0  | 139              |
| CCP1CON | P1M          | <1:0>           | DC1B           | S<1:0>         |                | CCP1M    | 1<3:0> |        | 234              |
| CCP2CON | P2M          | <1:0>           | DC2B           | I<1:0>         |                | CCP2N    | 1<3:0> |        | 234              |
| INTCON  | GIE          | PEIE            | TMR0IE         | INTE           | IOCIE          | TMR0IF   | INTF   | IOCIF  | 98               |
| PIE1    | TMR1GIE      | ADIE            | RCIE           | TXIE           | SSPIE          | CCP1IE   | TMR2IE | TMR1IE | 99               |
| PIR1    | TMR1GIF      | ADIF            | RCIF           | TXIF           | SSPIF          | CCP1IF   | TMR2IF | TMR1IF | 102              |
| TMR1H   | Holding Regi | ster for the Mo | ost Significan | t Byte of the  | 16-bit TMR1 F  | Register |        |        | 199*             |
| TMR1L   | Holding Regi | ster for the Le | ast Significa  | nt Byte of the | 16-bit TMR1    | Register |        |        | 199*             |
| TRISB   | TRISB7       | TRISB6          | TRISB5         | TRISB4         | TRISB3         | TRISB2   | TRISB1 | TRISB0 | 138              |
| TRISC   | TRISC7       | TRISC6          | TRISC5         | TRISC4         | TRISC3         | TRISC2   | TRISC1 | TRISC0 | 142              |
| T1CON   | TMR1C        | S<1:0>          | T1CKP          | S<1:0>         | T10SCEN        | T1SYNC   | _      | TMR10N | 203              |
| T1GCON  | TMR1GE       | T1GPOL          | T1GTM          | T1GSPM         | T1GGO/<br>DONE | T1GVAL   | T1GS   | 204    |                  |

**Legend:** — = unimplemented location, read as '0'. Shaded cells are not used by the Timer1 module.

<sup>\*</sup> Page provides register information.

**NOTES:** 

### 22.0 TIMER2/4/6 MODULES

There are up to three identical Timer2-type modules available. To maintain pre-existing naming conventions, the Timers are called Timer2, Timer4 and Timer6 (also Timer2/4/6).


Note: The 'x' variable used in this section is used to designate Timer2, Timer4, or Timer6. For example, TxCON references T2CON, T4CON, or T6CON. PRx references PR2, PR4, or PR6.

The Timer2/4/6 modules incorporate the following features:

- 8-bit Timer and Period registers (TMRx and PRx, respectively)
- Readable and writable (both registers)
- Software programmable prescaler (1:1, 1:4, 1:16, and 1:64)
- Software programmable postscaler (1:1 to 1:16)
- Interrupt on TMRx match with PRx, respectively
- Optional use as the shift clock for the MSSP modules (Timer2 only)

See Figure 22-1 for a block diagram of Timer2/4/6.

### FIGURE 22-1: TIMER2/4/6 BLOCK DIAGRAM



### 22.1 Timer2/4/6 Operation

The clock input to the Timer2/4/6 modules is the system instruction clock (Fosc/4).

TMRx increments from 00h on each clock edge.

A 4-bit counter/prescaler on the clock input allows direct input, divide-by-4 and divide-by-16 prescale options. These options are selected by the prescaler control bits, TxCKPS<1:0> of the TxCON register. The value of TMRx is compared to that of the Period register, PRx, on each clock cycle. When the two values match, the comparator generates a match signal as the timer output. This signal also resets the value of TMRx to 00h on the next cycle and drives the output counter/postscaler (see Section 22.2 "Timer2/4/6 Interrupt").

The TMRx and PRx registers are both directly readable and writable. The TMRx register is cleared on any device Reset, whereas the PRx register initializes to FFh. Both the prescaler and postscaler counters are cleared on the following events:

- · a write to the TMRx register
- · a write to the TxCON register
- Power-on Reset (POR)
- · Brown-out Reset (BOR)
- MCLR Reset
- · Watchdog Timer (WDT) Reset
- · Stack Overflow Reset
- · Stack Underflow Reset
- RESET Instruction

**Note:** TMRx is not cleared when TxCON is written.

### 22.2 Timer2/4/6 Interrupt

Timer2/4/6 can also generate an optional device interrupt. The Timer2/4/6 output signal (TMRx-to-PRx match) provides the input for the 4-bit counter/postscaler. This counter generates the TMRx match interrupt flag which is latched in TMRxIF of the PIRx register. The interrupt is enabled by setting the TMRx Match Interrupt Enable bit, TMRxIE, of the PIEx register.

A range of 16 postscale options (from 1:1 through 1:16 inclusive) can be selected with the postscaler control bits, TxOUTPS<3:0>, of the TxCON register.

### 22.3 Timer2/4/6 Output

The unscaled output of TMRx is available primarily to the CCP modules, where it is used as a time base for operations in PWM mode.

Timer2 can be optionally used as the shift clock source for the MSSP module operating in SPI mode. Additional information is provided in Section 24.0 "Master Synchronous Serial Port Module"

## 22.4 Timer2/4/6 Operation During Sleep

The Timer2/4/6 timers cannot be operated while the processor is in Sleep mode. The contents of the TMRx and PRx registers will remain unchanged while the processor is in Sleep mode.

# 22.5 Timer2/4/6 Control Register

#### REGISTER 22-1: TXCON: TIMER2/TIMER4/TIMER6 CONTROL REGISTER

| U-0   | R/W-0/0 |
|-------|---------|---------|---------|---------|---------|---------|---------|
| _     |         | TOUTP   | S<3:0>  | TMRxON  | TxCKP   | S<1:0>  |         |
| bit 7 |         |         |         |         |         |         | bit 0   |

| Legend:              |                      |   |
|----------------------|----------------------|---|
| R = Readable bit     | W = Writable bit     | U = Unimplemented bit, read as '0'                    |
| u = Bit is unchanged | x = Bit is unknown   | -n/n = Value at POR and BOR/Value at all other Resets |
| '1' = Bit is set     | '0' = Bit is cleared |   |

bit 7 Unimplemented: Read as '0' bit 6-3 TOUTPS<3:0>: Timer Output Postscaler Select bits 0000 = 1:1 Postscaler 0001 = 1:2 Postscaler 0010 = 1:3 Postscaler 0011 = 1:4 Postscaler 0100 = 1:5 Postscaler 0101 = 1:6 Postscaler 0110 = 1:7 Postscaler 0111 = 1:8 Postscaler 1000 = 1:9 Postscaler 1001 = 1:10 Postscaler 1010 = 1:11 Postscaler 1011 = 1:12 Postscaler 1100 = 1:13 Postscaler 1101 = 1:14 Postscaler 1110 = 1:15 Postscaler 1111 = 1:16 Postscaler bit 2 TMRxON: Timerx On bit 1 = Timerx is on 0 = Timerx is off bit 1-0 TxCKPS<1:0>: Timer2-type Clock Prescale Select bits 00 = Prescaler is 1 01 = Prescaler is 4 10 = Prescaler is 16 11 = Prescaler is 64

TABLE 22-1: SUMMARY OF REGISTERS ASSOCIATED WITH TIMER2/4/6

| Name    | Bit 7  | Bit 6                            | Bit 5        | Bit 4                     | Bit 3  | Bit 2  | Bit 1  | Bit 0  | Register on Page |
|---------|--|----------------------------------|--------------|---------------------------|--------|--------|--------|--------|------------------|
| CCP2CON | P2M  | <1:0>                            | DC2B         | <1:0>                     |        | CCP2N  | Л<3:0> |        | 234              |
| INTCON  | GIE  | PEIE                             | TMR0IE       | INTE                      | IOCIE  | TMR0IF | INTF   | IOCIF  | 98               |
| PIE1    | TMR1GIE                                      | ADIE                             | RCIE         | TXIE                      | SSPIE  | CCP1IE | TMR2IE | TMR1IE | 99               |
| PIE3    | _  | CCP5IE                           | CCP4IE       | CCP3IE                    | TMR6IE | _      | TMR4IE | _      | 101              |
| PIR1    | TMR1GIF                                      | ADIF                             | RCIF         | TXIF                      | SSPIF  | CCP1IF | TMR2IF | TMR1IF | 102              |
| PIR3    | _  | CCP5IF                           | CCP4IF       | CCP3IF                    | TMR6IF | _      | TMR4IF | _      | 104              |
| PR2     | Timer2 Mo                                    | dule Period                      | Register     |                           |        |        |        |        | 207*             |
| PR4     | Timer4 Mo                                    | dule Period                      | Register     |                           |        |        |        |        | 207*             |
| PR6     | Timer6 Mo                                    | dule Period                      | Register     |                           |        |        |        |        | 207*             |
| T2CON   | _  |                                  | TOUTP        | 'S<3:0>                   |        | TMR2ON | T2CKP  | S<1:0> | 209              |
| T4CON   | _  |                                  | TOUTP        | 'S<3:0>                   |        | TMR40N | T4CKP  | S<1:0> | 209              |
| T6CON   | _  | — TOUTPS<3:0> TMR2ON T6CKPS<1:0> |              |                           |        |        |        | 209    |                  |
| TMR2    | Holding Register for the 8-bit TMR2 Register |                                  |              |                           |        |        |        |        | 207*             |
| TMR4    | Holding Re                                   | gister for the                   | e 8-bit TMR4 | 4 Register <sup>(1)</sup> | )      |        |        |        | 207*             |
| TMR6    | Holding Re                                   | gister for the                   | e 8-bit TMR6 | Register <sup>(1)</sup>   |        |        |        |        | 207*             |

**Legend:** — = unimplemented location, read as '0'. Shaded cells are not used for Timer2 module.

<sup>\*</sup> Page provides register information.

# 23.0 CAPTURE/COMPARE/PWM MODULES

The Capture/Compare/PWM module is a peripheral which allows the user to time and control different events, and to generate Pulse-Width Modulation (PWM) signals. In Capture mode, the peripheral allows the timing of the duration of an event. The Compare mode allows the user to trigger an external event when a predetermined amount of time has expired. The PWM mode can generate Pulse-Width Modulated signals of varying frequency and duty cycle.

This family of devices contains three Enhanced Capture/Compare/PWM modules (ECCP1, ECCP2, and ECCP3) and two standard Capture/Compare/PWM modules (CCP4 and CCP5).

The Capture and Compare functions are identical for all five CCP modules (ECCP1, ECCP2, ECCP3, CCP4, and CCP5). The only differences between CCP modules are in the Pulse-Width Modulation (PWM) function. The standard PWM function is identical in modules, CCP4 and CCP5. In CCP modules ECCP1, ECCP2, and ECCP3, the Enhanced PWM function has slight variations from one another. Full-Bridge ECCP modules have four available I/O pins while Half-Bridge ECCP modules only have two available I/O pins. See Table 23-1 for more information.

- Note 1: In devices with more than one CCP module, it is very important to pay close attention to the register names used. A number placed after the module acronym is used to distinguish between separate modules. For example, the CCP1CON and CCP2CON control the same operational aspects of two completely different CCP modules.
  - 2: Throughout this section, generic references to a CCP module in any of its operating modes may be interpreted as being equally applicable to ECCP1, ECCP2, ECCP3, CCP4 and CCP5. Register names, module signals, I/O pins, and bit names may use the generic designator 'x' to indicate the use of a numeral to distinguish a particular module, when required.

TABLE 23-1: PWM RESOURCES

| Device Name     | ECCP1                       | CP1 ECCP2 ECCP3             |                             | CCP4         | CCP5         |  |
|-----------------|-----------------------------|-----------------------------|-----------------------------|--------------|--------------|--|
| PIC16(L)F1936   | Enhanced PWM<br>Full-Bridge | Enhanced PWM<br>Half-Bridge | Enhanced PWM<br>Half-Bridge | Standard PWM | Standard PWM |  |
| PIC16(L)F1934/7 | Enhanced PWM<br>Full-Bridge | Enhanced PWM<br>Full-Bridge | Enhanced PWM<br>Half-Bridge | Standard PWM |              |  |

### 23.1 Capture Mode

The Capture mode function described in this section is available and identical for CCP modules ECCP1, ECCP2, ECCP3, CCP4 and CCP5.

Capture mode makes use of the 16-bit Timer1 resource. When an event occurs on the CCPx pin, the 16-bit CCPRxH:CCPRxL register pair captures and stores the 16-bit value of the TMR1H:TMR1L register pair, respectively. An event is defined as one of the following and is configured by the CCPxM<3:0> bits of the CCPxCON register:

- · Every falling edge
- · Every rising edge
- · Every 4th rising edge
- · Every 16th rising edge

When a capture is made, the Interrupt Request Flag bit CCPxIF of the PIRx register is set. The interrupt flag must be cleared in software. If another capture occurs before the value in the CCPRxH, CCPRxL register pair is read, the old captured value is overwritten by the new captured value.

Figure 23-1 shows a simplified diagram of the Capture operation.

#### 23.1.1 CCP PIN CONFIGURATION


In Capture mode, the CCPx pin should be configured as an input by setting the associated TRIS control bit.

Also, the CCPx pin function can be moved to alternative pins using the APFCON register. Refer to **Section 12.1 "Alternate Pin Function"** for more details.

**Note:** If the CCPx pin is configured as an output, a write to the port can cause a capture

condition.

# FIGURE 23-1: CAPTURE MODE OPERATION BLOCK DIAGRAM



#### 23.1.2 TIMER1 MODE RESOURCE

Timer1 must be running in Timer mode or Synchronized Counter mode for the CCP module to use the capture feature. In Asynchronous Counter mode, the capture operation may not work.

See Section 21.0 "Timer1 Module with Gate Control" for more information on configuring Timer1.

#### 23.1.3 SOFTWARE INTERRUPT MODE

When the Capture mode is changed, a false capture interrupt may be generated. The user should keep the CCPxIE interrupt enable bit of the PIEx register clear to avoid false interrupts. Additionally, the user should clear the CCPxIF interrupt flag bit of the PIRx register following any change in Operating mode.

Note: Clocking Timer1 from the system clock (Fosc) should not be used in Capture mode. In order for Capture mode to recognize the trigger event on the CCPx pin, Timer1 must be clocked from the instruction clock (Fosc/4) or from an external clock source.

#### 23.1.4 CCP PRESCALER

There are four prescaler settings specified by the CCPxM<3:0> bits of the CCPxCON register. Whenever the CCP module is turned off, or the CCP module is not in Capture mode, the prescaler counter is cleared. Any Reset will clear the prescaler counter.

Switching from one capture prescaler to another does not clear the prescaler and may generate a false interrupt. To avoid this unexpected operation, turn the module off by clearing the CCPxCON register before changing the prescaler. Example 23-1 demonstrates the code to perform this function.

# EXAMPLE 23-1: CHANGING BETWEEN CAPTURE PRESCALERS

| BANKSEL | CCPxCON     | ;Set Bank bits to point |
|---------|-------------|-------------------------|
|         |             | ; to CCPxCON            |
| CLRF    | CCPxCON     | ;Turn CCP module off    |
| MOVLW   | NEW_CAPT_PS | ;Load the W reg with    |
|         |             | ;the new prescaler      |
|         |             | ;move value and CCP ON  |
| MOVWF   | CCPxCON     | ;Load CCPxCON with this |
|         |             | ;value                  |
|         |             |                         |

#### 23.1.5 CAPTURE DURING SLEEP

Capture mode depends upon the Timer1 module for proper operation. There are two options for driving the Timer1 module in Capture mode. It can be driven by the instruction clock (Fosc/4), or by an external clock source.

When Timer1 is clocked by Fosc/4, Timer1 will not increment during Sleep. When the device wakes from Sleep, Timer1 will continue from its previous state.

Capture mode will operate during Sleep when Timer1 is clocked by an external clock source.

### 23.1.6 ALTERNATE PIN LOCATIONS

This module incorporates I/O pins that can be moved to other locations with the use of the alternate pin function register, APFCON. To determine which pins can be moved and what their default locations are upon a Reset, see Section 12.1 "Alternate Pin Function" for more information.

TABLE 23-2: SUMMARY OF REGISTERS ASSOCIATED WITH CAPTURE

| Name                 | Bit 7   | Bit 6     | Bit 5        | Bit 4        | Bit 3   | Bit 2                 | Bit 1                 | Bit 0                 | Register<br>on Page |
|----------------------|---|-----------|--------------|--------------|---------|-----------------------|-----------------------|-----------------------|---------------------|
| APFCON               | _   | CCP3SEL   | T1GSEL       | P2BSEL       | SRNQSEL | C2OUTSEL              | SSSEL                 | CCP2SEL               | 131                 |
| CCPxCON              | PxM<1:0> <sup>(1)</sup> DCxB<1:0>   |           |              |              | CCPxM<  | 3:0>                  |                       | 234                   |                     |
| CCPRxL               | Capture/Compare/PWM Register x Low Byte (LSB)                               |           |              |              |         |                       |                       |                       | 212                 |
| CCPRxH               | Capture/Co  | mpare/PWM | Register x I | High Byte (M | SB)     |                       |                       |                       | 212                 |
| INTCON               | GIE   | PEIE      | TMR0IE       | INTE         | IOCIE   | TMR0IF                | INTF                  | IOCIF                 | 98                  |
| PIE1                 | TMR1GIE   | ADIE      | RCIE         | TXIE         | SSPIE   | CCP1IE                | TMR2IE                | TMR1IE                | 99                  |
| PIE2                 | OSFIE   | C2IE      | C1IE         | EEIE         | BCLIE   | LCDIE                 | _                     | CCP2IE                | 100                 |
| PIE3                 | _   | CCP5IE    | CCP4IE       | CCP3IE       | TMR6IE  | -                     | TMR4IE                | _                     | 101                 |
| PIR1                 | TMR1GIF   | ADIF      | RCIF         | TXIF         | SSPIF   | CCP1IF                | TMR2IF                | TMR1IF                | 102                 |
| PIR2                 | OSFIF   | C2IF      | C1IF         | EEIF         | BCLIF   | LCDIF                 | _                     | CCP2IF                | 103                 |
| PIR3                 | _   | CCP5IF    | CCP4IF       | CCP3IF       | TMR6IF  | _                     | TMR4IF                | _                     | 104                 |
| T1CON                | TMR1CS<1:0> T1CKPS<1:0> T1OSCEN T1SYNC — TMR1ON                             |           |              |              |         |                       |                       | 203                   |                     |
| T1GCON               | TMR1GE T1GPOL T1GTM T1GSPM T1GGO/DONE T1GVAL T1GSS<1:0>                     |           |              |              |         |                       | 204                   |                       |                     |
| TMR1L                | Holding Register for the Least Significant Byte of the 16-bit TMR1 Register |           |              |              |         |                       |                       |                       | 199                 |
| TMR1H                | Holding Register for the Most Significant Byte of the 16-bit TMR1 Register  |           |              |              |         |                       |                       |                       | 199                 |
| TRISA                | TRISA7  | TRISA6    | TRISA5       | TRISA4       | TRISA3  | TRISA2                | TRISA1                | TRISA0                | 133                 |
| TRISB                | TRISB7  | TRISB6    | TRISB5       | TRISB4       | TRISB3  | TRISB2                | TRISB1                | TRISB0                | 138                 |
| TRISC                | TRISC7  | TRISC6    | TRISC5       | TRISC4       | TRISC3  | TRISC2                | TRISC1                | TRISC0                | 142                 |
| TRISD <sup>(2)</sup> | TRISD7  | TRISD6    | TRISD5       | TRISD4       | TRISD3  | TRISD2                | TRISD1                | TRISD0                | 145                 |
| TRISE                | _   |           | _            | _            | (3)     | TRISE2 <sup>(2)</sup> | TRISE1 <sup>(2)</sup> | TRISE0 <sup>(2)</sup> | 148                 |

Legend: — = Unimplemented location, read as '0'. Shaded cells are not used by Capture mode.

- Note 1: Applies to ECCP modules only.
  - 2: These registers/bits are not implemented on PIC16(L)F1936 devices, read as '0'.
  - 3: Unimplemented, read as '1'.

### 23.2 Compare Mode

The Compare mode function described in this section is available and identical for CCP modules ECCP1, ECCP2, ECCP3, CCP4 and CCP5.

Compare mode makes use of the 16-bit Timer1 resource. The 16-bit value of the CCPRxH:CCPRxL register pair is constantly compared against the 16-bit value of the TMR1H:TMR1L register pair. When a match occurs, one of the following events can occur:


- Toggle the CCPx output
- · Set the CCPx output
- · Clear the CCPx output
- · Generate a Special Event Trigger
- · Generate a Software Interrupt

The action on the pin is based on the value of the CCPxM<3:0> control bits of the CCPxCON register. At the same time, the interrupt flag CCPxIF bit is set.

All Compare modes can generate an interrupt.

Figure 23-2 shows a simplified diagram of the Compare operation.

FIGURE 23-2: COMPARE MODE OPERATION BLOCK DIAGRAM



#### 23.2.1 CCP PIN CONFIGURATION

The user must configure the CCPx pin as an output by clearing the associated TRIS bit.

Also, the CCPx pin function can be moved to alternative pins using the APFCON register. Refer to **Section 12.1 "Alternate Pin Function"** for more details.

Note: Clearing the CCPxCON register will force the CCPx compare output latch to the default low level. This is not the PORT I/O data latch.

#### 23.2.2 TIMER1 MODE RESOURCE

In Compare mode, Timer1 must be running in either Timer mode or Synchronized Counter mode. The compare operation may not work in Asynchronous Counter mode.

See Section 21.0 "Timer1 Module with Gate Control" for more information on configuring Timer1.

Clocking Timer1 from the system clock (Fosc) should not be used in Compare mode. In order for Compare mode to recognize the trigger event on the CCPx pin, Tlmer1 must be clocked from the instruction clock (Fosc/4) or from an external clock source.

#### 23.2.3 SOFTWARE INTERRUPT MODE

When Generate Software Interrupt mode is chosen (CCPxM<3:0> = 1010), the CCPx module does not assert control of the CCPx pin (see the CCPxCON register).

#### 23.2.4 SPECIAL EVENT TRIGGER

When Special Event Trigger mode is chosen (CCPxM<3:0> = 1011), the CCPx module does the following:

· Resets Timer1

Note:

· Starts an ADC conversion if ADC is enabled

The CCPx module does not assert control of the CCPx pin in this mode.

The Special Event Trigger output of the CCP occurs immediately upon a match between the TMR1H, TMR1L register pair and the CCPRxH, CCPRxL register pair. The TMR1H, TMR1L register pair is not reset until the next rising edge of the Timer1 clock. The Special Event Trigger output starts an A/D conversion (if the A/D module is enabled). This allows the CCPRxH, CCPRxL register pair to effectively provide a 16-bit programmable period register for Timer1.

**TABLE 23-3: SPECIAL EVENT TRIGGER** 

| Device            | CCPx/ECCPx |  |  |  |  |
|-------------------|------------|--|--|--|--|
| PIC16(L)F1934/6/7 | CCP5       |  |  |  |  |

Refer to Section 15.2.5 "Special Event Trigger"for more information.

Note 1: The Special Event Trigger from the CCP module does not set interrupt flag bit TMR1IF of the PIR1 register.

2: Removing the match condition by changing the contents of the CCPRxH and CCPRxL register pair, between the clock edge that generates the Special Event Trigger and the clock edge that generates the Timer1 Reset, will preclude the Reset from occurring.

# 23.2.5 COMPARE DURING SLEEP

The Compare mode is dependent upon the system clock (Fosc) for proper operation. Since Fosc is shut down during Sleep mode, the Compare mode will not function properly during Sleep.

#### 23.2.6 ALTERNATE PIN LOCATIONS

This module incorporates I/O pins that can be moved to other locations with the use of the alternate pin function register, APFCON. To determine which pins can be moved and what their default locations are upon a Reset, see Section 12.1 "Alternate Pin Function" for more information.

TABLE 23-4: SUMMARY OF REGISTERS ASSOCIATED WITH COMPARE

| Name                 | Bit 7   | Bit 6     | Bit 5        | Bit 4        | Bit 3   | Bit 2                 | Bit 1                 | Bit 0                 | Register on Page |
|----------------------|---|-----------|--------------|--------------|---------|-----------------------|-----------------------|-----------------------|------------------|
| APFCON               | _   | CCP3SEL   | T1GSEL       | P2BSEL       | SRNQSEL | C2OUTSEL              | SSSEL                 | CCP2SEL               | 131              |
| CCPxCON              | PxM<1:0> <sup>(1)</sup> DCxB<1:0>   |           |              |              | CCPxM<  | 3:0>                  |                       | 234                   |                  |
| CCPRxL               | Capture/Compare/PWM Register x Low Byte (LSB)                               |           |              |              |         |                       |                       |                       | 212              |
| CCPRxH               | Capture/Co  | mpare/PWM | Register x I | High Byte (M | ISB)    |                       |                       |                       | 212              |
| INTCON               | GIE   | PEIE      | TMR0IE       | INTE         | IOCIE   | TMR0IF                | INTF                  | IOCIF                 | 98               |
| PIE1                 | TMR1GIE   | ADIE      | RCIE         | TXIE         | SSPIE   | CCP1IE                | TMR2IE                | TMR1IE                | 99               |
| PIE2                 | OSFIE   | C2IE      | C1IE         | EEIE         | BCLIE   | LCDIE                 | _                     | CCP2IE                | 100              |
| PIE3                 | _   | CCP5IE    | CCP4IE       | CCP3IE       | TMR6IE  | -                     | TMR4IE                | _                     | 101              |
| PIR1                 | TMR1GIF   | ADIF      | RCIF         | TXIF         | SSPIF   | CCP1IF                | TMR2IF                | TMR1IF                | 102              |
| PIR2                 | OSFIF   | C2IF      | C1IF         | EEIF         | BCLIF   | LCDIF                 | _                     | CCP2IF                | 103              |
| PIR3                 | _   | CCP5IF    | CCP4IF       | CCP3IF       | TMR6IF  | _                     | TMR4IF                | _                     | 104              |
| T1CON                | TMR1CS<1:0> T1CKPS<1:0> T1OSCEN T1SYNC — TMR1ON                             |           |              |              |         |                       |                       | 203                   |                  |
| T1GCON               | TMR1GE T1GPOL T1GTM T1GSPM T1GGO/DONE T1GVAL T1GSS<1:0>                     |           |              |              |         |                       | 204                   |                       |                  |
| TMR1L                | Holding Register for the Least Significant Byte of the 16-bit TMR1 Register |           |              |              |         |                       |                       |                       | 199              |
| TMR1H                | Holding Register for the Most Significant Byte of the 16-bit TMR1 Register  |           |              |              |         |                       |                       |                       | 199              |
| TRISA                | TRISA7  | TRISA6    | TRISA5       | TRISA4       | TRISA3  | TRISA2                | TRISA1                | TRISA0                | 133              |
| TRISB                | TRISB7  | TRISB6    | TRISB5       | TRISB4       | TRISB3  | TRISB2                | TRISB1                | TRISB0                | 138              |
| TRISC                | TRISC7  | TRISC6    | TRISC5       | TRISC4       | TRISC3  | TRISC2                | TRISC1                | TRISC0                | 142              |
| TRISD <sup>(2)</sup> | TRISD7  | TRISD6    | TRISD5       | TRISD4       | TRISD3  | TRISD2                | TRISD1                | TRISD0                | 145              |
| TRISE                |   | _         | _            | _            | (3)     | TRISE2 <sup>(2)</sup> | TRISE1 <sup>(2)</sup> | TRISE0 <sup>(2)</sup> | 148              |

**Legend:** — = Unimplemented location, read as '0'. Shaded cells are not used by Compare mode.

Note 1: Applies to ECCP modules only.

- 2: These bits are not implemented on PIC16(L)F1936 devices, read as '0'.
- 3: Unimplemented, read as '1'.

#### 23.3 PWM Overview

Pulse-Width Modulation (PWM) is a scheme that provides power to a load by switching quickly between fully on and fully off states. The PWM signal resembles a square wave where the high portion of the signal is considered the on state and the low portion of the signal is considered the off state. The high portion, also known as the pulse width, can vary in time and is defined in steps. A larger number of steps applied, which lengthens the pulse width, also supplies more power to the load. Lowering the number of steps applied, which shortens the pulse width, supplies less power. The PWM period is defined as the duration of one complete cycle or the total amount of on and off time combined.

PWM resolution defines the maximum number of steps that can be present in a single PWM period. A higher resolution allows for more precise control of the pulse width time and in turn the power that is applied to the load.

The term duty cycle describes the proportion of the on time to the off time and is expressed in percentages, where 0% is fully off and 100% is fully on. A lower duty cycle corresponds to less power applied and a higher duty cycle corresponds to more power applied.

Figure 23-3 shows a typical waveform of the PWM signal.

#### 23.3.1 STANDARD PWM OPERATION

The standard PWM function described in this section is available and identical for CCP modules ECCP1, ECCP2, ECCP3, CCP4 and CCP5.


The standard PWM mode generates a Pulse-Width modulation (PWM) signal on the CCPx pin with up to 10 bits of resolution. The period, duty cycle, and resolution are controlled by the following registers:

- PRx registers
- TxCON registers
- · CCPRxL registers
- · CCPxCON registers


Figure 23-4 shows a simplified block diagram of PWM operation.

- Note 1: The corresponding TRIS bit must be cleared to enable the PWM output on the CCPx pin.
  - **2:** Clearing the CCPxCON register will relinquish control of the CCPx pin.

#### FIGURE 23-3: CCP PWM OUTPUT SIGNAL



# FIGURE 23-4: SIMPLIFIED PWM BLOCK DIAGRAM



- Note 1: The 8-bit timer TMRx register is concatenated with the 2-bit internal system clock (Fosc), or 2 bits of the prescaler, to create the 10-bit time
  - 2: In PWM mode, CCPRxH is a read-only register.

#### 23.3.2 SETUP FOR PWM OPERATION

The following steps should be taken when configuring the CCP module for standard PWM operation:

- 1. Disable the CCPx pin output driver by setting the associated TRIS bit.
- Load the PRx register with the PWM period value.
- 3. Configure the CCP module for the PWM mode by loading the CCPxCON register with the appropriate values.
- Load the CCPRxL register and the DCxBx bits of the CCPxCON register, with the PWM duty cycle value.
- 5. Configure and start Timer2/4/6:
  - Select the Timer2/4/6 resource to be used for PWM generation by setting the CxTSEL<1:0> bits in the CCPTMRSx register.
  - Clear the TMRxIF interrupt flag bit of the PIRx register. See Note below.
  - Configure the TxCKPS bits of the TxCON register with the Timer prescale value.
  - Enable the Timer by setting the TMRxON bit of the TxCON register.
- 6. Enable PWM output pin:
  - Wait until the Timer overflows and the TMRxIF bit of the PIRx register is set. See Note below.
  - Enable the CCPx pin output driver by clearing the associated TRIS bit.

Note: In order to send a complete duty cycle and period on the first PWM output, the above steps must be included in the setup sequence. If it is not critical to start with a complete PWM signal on the first output, then step 6 may be ignored.

#### 23.3.3 TIMER2/4/6 TIMER RESOURCE

The PWM standard mode makes use of one of the 8-bit Timer2/4/6 timer resources to specify the PWM period.

Configuring the CxTSEL<1:0> bits in the CCPTMRSx register selects which Timer2/4/6 timer is used.

### 23.3.4 PWM PERIOD

The PWM period is specified by the PRx register of Timer2/4/6. The PWM period can be calculated using the formula of Equation 23-1.

### **EQUATION 23-1: PWM PERIOD**

$$PWM \ Period = [(PRx) + 1] \bullet 4 \bullet TOSC \bullet$$
 $(TMRx \ Prescale \ Value)$ 

Note 1: Tosc = 1/Fosc

When TMRx is equal to PRx, the following three events occur on the next increment cycle:

- · TMRx is cleared
- The CCPx pin is set. (Exception: If the PWM duty cycle = 0%, the pin will not be set.)
- The PWM duty cycle is latched from CCPRxL into CCPRxH.

Note: The Timer postscaler (see Section 22.1 "Timer2/4/6 Operation") is not used in the determination of the PWM frequency.

### 23.3.5 PWM DUTY CYCLE

The PWM duty cycle is specified by writing a 10-bit value to multiple registers: CCPRxL register and DCxB<1:0> bits of the CCPxCON register. The CCPRxL contains the eight MSbs and the DCxB<1:0> bits of the CCPxCON register contain the two LSbs. CCPRxL and DCxB<1:0> bits of the CCPxCON register can be written to at any time. The duty cycle value is not latched into CCPRxH until after the period completes (i.e., a match between PRx and TMRx registers occurs). While using the PWM, the CCPRxH register is read-only.

Equation 23-2 is used to calculate the PWM pulse width.

Equation 23-3 is used to calculate the PWM duty cycle ratio.

#### **EQUATION 23-2: PULSE WIDTH**

 $\label{eq:pulse Width of CCPRxL:CCPxCON<5:4>} \bullet \\ TOSC \bullet (TMRx\ Prescale\ Value)$ 

### **EQUATION 23-3: DUTY CYCLE RATIO**

 $Duty\ Cycle\ Ratio\ =\ \frac{(CCPRxL:CCPxCON<5:4>)}{4(PRx+I)}$ 

The CCPRxH register and a 2-bit internal latch are used to double buffer the PWM duty cycle. This double buffering is essential for glitchless PWM operation.

The 8-bit timer TMRx register is concatenated with either the 2-bit internal system clock (Fosc), or 2 bits of the prescaler, to create the 10-bit time base. The system clock is used if the Timer2/4/6 prescaler is set to 1:1.

When the 10-bit time base matches the CCPRxH and 2-bit latch, then the CCPx pin is cleared (see Figure 23-4).

### 23.3.6 PWM RESOLUTION

The resolution determines the number of available duty cycles for a given period. For example, a 10-bit resolution will result in 1024 discrete duty cycles, whereas an 8-bit resolution will result in 256 discrete duty cycles.

The maximum PWM resolution is 10 bits when PRx is 255. The resolution is a function of the PRx register value as shown by Equation 23-4.

## **EQUATION 23-4: PWM RESOLUTION**

Resolution = 
$$\frac{log[4(PRx+1)]}{log(2)}$$
 bits

Note: If the pulse width value is greater than the period the assigned PWM pin(s) will remain unchanged.

## TABLE 23-5: EXAMPLE PWM FREQUENCIES AND RESOLUTIONS (Fosc = 32 MHz)

| PWM Frequency             | 1.95 kHz | 7.81 kHz | 31.25 kHz | 125 kHz | 250 kHz | 333.3 kHz |
|---------------------------|----------|----------|-----------|---------|---------|-----------|
| Timer Prescale (1, 4, 16) | 16       | 4        | 1         | 1       | 1       | 1         |
| PRx Value                 | 0xFF     | 0xFF     | 0xFF      | 0x3F    | 0x1F    | 0x17      |
| Maximum Resolution (bits) | 10       | 10       | 10        | 8       | 7       | 6.6       |

### TABLE 23-6: EXAMPLE PWM FREQUENCIES AND RESOLUTIONS (Fosc = 20 MHz)

| PWM Frequency             | 1.22 kHz | 4.88 kHz | 19.53 kHz | 78.12 kHz | 156.3 kHz | 208.3 kHz |
|---------------------------|----------|----------|-----------|-----------|-----------|-----------|
| Timer Prescale (1, 4, 16) | 16       | 4        | 1         | 1         | 1         | 1         |
| PRx Value                 | 0xFF     | 0xFF     | 0xFF      | 0x3F      | 0x1F      | 0x17      |
| Maximum Resolution (bits) | 10       | 10       | 10        | 8         | 7         | 6.6       |

### TABLE 23-7: EXAMPLE PWM FREQUENCIES AND RESOLUTIONS (Fosc = 8 MHz)

| PWM Frequency             | 1.22 kHz | 4.90 kHz | 19.61 kHz | 76.92 kHz | 153.85 kHz | 200.0 kHz |
|---------------------------|----------|----------|-----------|-----------|------------|-----------|
| Timer Prescale (1, 4, 16) | 16       | 4        | 1         | 1         | 1          | 1         |
| PRx Value                 | 0x65     | 0x65     | 0x65      | 0x19      | 0x0C       | 0x09      |
| Maximum Resolution (bits) | 8        | 8        | 8         | 6         | 5          | 5         |

#### 23.3.7 OPERATION IN SLEEP MODE

In Sleep mode, the TMRx register will not increment and the state of the module will not change. If the CCPx pin is driving a value, it will continue to drive that value. When the device wakes up, TMRx will continue from its previous state.

## 23.3.8 CHANGES IN SYSTEM CLOCK FREQUENCY

The PWM frequency is derived from the system clock frequency. Any changes in the system clock frequency will result in changes to the PWM frequency. See Section 5.0 "Oscillator Module (With Fail-Safe Clock Monitor)" for additional details.

### 23.3.9 EFFECTS OF RESET

Any Reset will force all ports to Input mode and the CCP registers to their Reset states.

#### 23.3.10 ALTERNATE PIN LOCATIONS

This module incorporates I/O pins that can be moved to other locations with the use of the alternate pin function register, APFCON. To determine which pins can be moved and what their default locations are upon a Reset, see **Section 12.1 "Alternate Pin Function"** for more information.

TABLE 23-8: SUMMARY OF REGISTERS ASSOCIATED WITH STANDARD PWM

| Name                 | Bit 7        | Bit 6               | Bit 5  | Bit 4   | Bit 3   | Bit 2                 | Bit 1                 | Bit 0                 | Register on Page |
|----------------------|--------------|---------------------|--------|---------|---------|-----------------------|-----------------------|-----------------------|------------------|
| APFCON               | _            | CCP3SEL             | T1GSEL | P2BSEL  | SRNQSEL | C2OUTSEL              | SSSEL                 | CCP2SEL               | 131              |
| CCPxCON              | PxM<         | 1:0> <sup>(1)</sup> | DCxB   | <1:0>   |         | CCPxN                 | /l<3:0>               |                       | 234              |
| CCPTMRS0             | C4TSE        | L<1:0>              | C3TSE  | L<1:0>  | C2TSE   | :L<1:0>               | C1TSE                 | L<1:0>                | 235              |
| CCPTMRS1             | _            | _                   | _      | _       | _       | _                     | C5TSE                 | L<1:0>                | 235              |
| INTCON               | GIE          | PEIE                | TMR0IE | INTE    | IOCIE   | TMR0IF                | INTF                  | IOCIF                 | 98               |
| PIE1                 | TMR1GIE      | ADIE                | RCIE   | TXIE    | SSPIE   | CCP1IE                | TMR2IE                | TMR1IE                | 99               |
| PIE2                 | OSFIE        | C2IE                | C1IE   | EEIE    | BCLIE   | LCDIE                 | _                     | CCP2IE                | 100              |
| PIE3                 | _            | CCP5IE              | CCP4IE | CCP3IE  | TMR6IE  | _                     | TMR4IE                | _                     | 101              |
| PIR1                 | TMR1GIF      | ADIF                | RCIF   | TXIF    | SSPIF   | CCP1IF                | TMR2IF                | TMR1IF                | 102              |
| PIR2                 | OSFIF        | C2IF                | C1IF   | EEIF    | BCLIF   | LCDIF                 | _                     | CCP2IF                | 103              |
| PIR3                 | _            | CCP5IF              | CCP4IF | CCP3IF  | TMR6IF  | _                     | TMR4IF                | _                     | 104              |
| PRx                  | Timer2/4/6 P | eriod Registe       | er     |         |         |                       |                       |                       | 207*             |
| TxCON                | _            |                     | TxOUTF | PS<3:0> |         | TMRxON                | TxCKP                 | S<:0>1                | 209              |
| TMRx                 | Timer2/4/6 N | lodule Regist       | er     |         |         |                       |                       |                       | 207              |
| TRISA                | TRISA7       | TRISA6              | TRISA5 | TRISA4  | TRISA3  | TRISA2                | TRISA1                | TRISA0                | 133              |
| TRISB                | TRISB7       | TRISB6              | TRISB5 | TRISB4  | TRISB3  | TRISB2                | TRISB1                | TRISB0                | 138              |
| TRISC                | TRISC7       | TRISC6              | TRISC5 | TRISC4  | TRISC3  | TRISC2                | TRISC1                | TRISC0                | 142              |
| TRISD <sup>(2)</sup> | TRISD7       | TRISD6              | TRISD5 | TRISD4  | TRISD3  | TRISD2                | TRISD1                | TRISD0                | 145              |
| TRISE                | _            | _                   | _      | _       | (3)     | TRISE2 <sup>(2)</sup> | TRISE1 <sup>(2)</sup> | TRISE0 <sup>(2)</sup> | 148              |

**Legend:** — = Unimplemented location, read as '0'. Shaded cells are not used by the PWM.

Note 1: Applies to ECCP modules only.

2: These registers/bits are not implemented on PIC16(L)F1936 devices, read as '0'.

3: Unimplemented, read as '1'.

Page provides register information.

## 23.4 PWM (Enhanced Mode)

The enhanced PWM function described in this section is available for CCP modules ECCP1, ECCP2 and ECCP3, with any differences between modules noted.

The enhanced PWM mode generates a Pulse-Width Modulation (PWM) signal on up to four different output pins with up to 10 bits of resolution. The period, duty cycle, and resolution are controlled by the following registers:

- PRx registers
- · TxCON registers
- · CCPRxL registers
- CCPxCON registers

The ECCP modules have the following additional PWM registers which control Auto-shutdown, Auto-restart, Dead-band Delay and PWM Steering modes:

- · CCPxAS registers
- · PSTRxCON registers
- · PWMxCON registers

The enhanced PWM module can generate the following five PWM Output modes:

- · Single PWM
- · Half-Bridge PWM
- · Full-Bridge PWM, Forward Mode
- Full-Bridge PWM, Reverse Mode
- · Single PWM with PWM Steering Mode

To select an Enhanced PWM Output mode, the PxM bits of the CCPxCON register must be configured appropriately.


The PWM outputs are multiplexed with I/O pins and are designated PxA, PxB, PxC and PxD. The polarity of the PWM pins is configurable and is selected by setting the CCPxM bits in the CCPxCON register appropriately.

Figure 23-5 shows an example of a simplified block diagram of the Enhanced PWM module.

Table 23-9 shows the pin assignments for various Enhanced PWM modes.

- **Note 1:** The corresponding TRIS bit must be cleared to enable the PWM output on the CCPx pin.
  - **2:** Clearing the CCPxCON register will relinquish control of the CCPx pin.
  - **3:** Any pin not used in the enhanced PWM mode is available for alternate pin functions, if applicable.
  - 4: To prevent the generation of an incomplete waveform when the PWM is first enabled, the ECCP module waits until the start of a new PWM period before generating a PWM signal.

## FIGURE 23-5: EXAMPLE SIMPLIFIED BLOCK DIAGRAM OF THE ENHANCED PWM MODE




Note 1: The 8-bit timer TMRx register is concatenated with the 2-bit internal Q clock, or 2 bits of the prescaler to create the 10-bit time base.

**TABLE 23-9: EXAMPLE PIN ASSIGNMENTS FOR VARIOUS PWM ENHANCED MODES** 


| ECCP Mode            | PxM<1:0> | CCPx/PxA           | PxB                | PxC                | PxD                |
|----------------------|----------|--------------------|--------------------|--------------------|--------------------|
| Single               | 0.0      | Yes <sup>(1)</sup> | Yes <sup>(1)</sup> | Yes <sup>(1)</sup> | Yes <sup>(1)</sup> |
| Half-Bridge          | 10       | Yes                | Yes                | No                 | No                 |
| Full-Bridge, Forward | 01       | Yes                | Yes                | Yes                | Yes                |
| Full-Bridge, Reverse | 11       | Yes                | Yes                | Yes                | Yes                |

Note 1: PWM Steering enables outputs in Single mode.

**EXAMPLE PWM (ENHANCED MODE) OUTPUT RELATIONSHIPS (ACTIVE-HIGH FIGURE 23-6:** 



Delay = 4 \* Tosc \* (PWMxCON<6:0>)




#### 23.4.1 HALF-BRIDGE MODE

In Half-Bridge mode, two pins are used as outputs to drive push-pull loads. The PWM output signal is output on the CCPx/PxA pin, while the complementary PWM output signal is output on the PxB pin (see Figure 23-9). This mode can be used for Half-Bridge applications, as shown in Figure 23-9, or for Full-Bridge applications, where four power switches are being modulated with two PWM signals.

In Half-Bridge mode, the programmable dead-band delay can be used to prevent shoot-through current in Half-Bridge power devices. The value of the PDC<6:0> bits of the PWMxCON register sets the number of instruction cycles before the output is driven active. If the value is greater than the duty cycle, the corresponding output remains inactive during the entire cycle. See Section 23.4.5 "Programmable Dead-Band Delay Mode" for more details of the dead-band delay operations.

Since the PxA and PxB outputs are multiplexed with the PORT data latches, the associated TRIS bits must be cleared to configure PxA and PxB as outputs.


FIGURE 23-8: EXAMPLE OF HALF-BRIDGE PWM OUTPUT



Note 1: At this time, the TMRx register is equal to the PRx register.

2: Output signals are shown as active-high.

FIGURE 23-9: EXAMPLE OF HALF-BRIDGE APPLICATIONS



### 23.4.2 FULL-BRIDGE MODE

In Full-Bridge mode, all four pins are used as outputs. An example of Full-Bridge application is shown in Figure 23-10.

In the Forward mode, pin CCPx/PxA is driven to its active state, pin PxD is modulated, while PxB and PxC will be driven to their inactive state as shown in Figure 23-11.

In the Reverse mode, PxC is driven to its active state, pin PxB is modulated, while PxA and PxD will be driven to their inactive state as shown Figure 23-11.

PxA, PxB, PxC and PxD outputs are multiplexed with the PORT data latches. The associated TRIS bits must be cleared to configure the PxA, PxB, PxC and PxD pins as outputs.

FIGURE 23-10: EXAMPLE OF FULL-BRIDGE APPLICATION






FIGURE 23-11: EXAMPLE OF FULL-BRIDGE PWM OUTPUT



### **Reverse Mode**



Note 1: At this time, the TMRx register is equal to the PRx register.

2: Output signal is shown as active-high.

## 23.4.2.1 Direction Change in Full-Bridge Mode

In the Full-Bridge mode, the PxM1 bit in the CCPxCON register allows users to control the forward/reverse direction. When the application firmware changes this direction control bit, the module will change to the new direction on the next PWM cycle.

A direction change is initiated in software by changing the PxM1 bit of the CCPxCON register. The following sequence occurs four Timer cycles prior to the end of the current PWM period:

- The modulated outputs (PxB and PxD) are placed in their inactive state.
- The associated unmodulated outputs (PxA and PxC) are switched to drive in the opposite direction.
- PWM modulation resumes at the beginning of the next period.

See Figure 23-12 for an illustration of this sequence.

The Full-Bridge mode does not provide dead-band delay. As one output is modulated at a time, dead-band delay is generally not required. There is a situation where dead-band delay is required. This situation occurs when both of the following conditions are true:

- The direction of the PWM output changes when the duty cycle of the output is at or near 100%.
- The turn off time of the power switch, including the power device and driver circuit, is greater than the turn on time.


Figure 23-13 shows an example of the PWM direction changing from forward to reverse, at a near 100% duty cycle. In this example, at time t1, the output PxA and PxD become inactive, while output PxC becomes active. Since the turn off time of the power devices is longer than the turn on time, a shoot-through current will flow through power devices QC and QD (see Figure 23-10) for the duration of 't'. The same phenomenon will occur to power devices QA and QB for PWM direction change from reverse to forward.

If changing PWM direction at high duty cycle is required for an application, two possible solutions for eliminating the shoot-through current are:


- Reduce PWM duty cycle for one PWM period before changing directions.
- 2. Use switch drivers that can drive the switches off faster than they can drive them on.

Other options to prevent shoot-through current may exist.

#### FIGURE 23-12: EXAMPLE OF PWM DIRECTION CHANGE



- Note 1: The direction bit PxM1 of the CCPxCON register is written any time during the PWM cycle.
  - 2: When changing directions, the PxA and PxC signals switch before the end of the current PWM cycle. The modulated PxB and PxD signals are inactive at this time. The length of this time is four Timer counts.



## 23.4.3 ENHANCED PWM AUTO-SHUTDOWN MODE

The PWM mode supports an Auto-Shutdown mode that will disable the PWM outputs when an external shutdown event occurs. Auto-Shutdown mode places the PWM output pins into a predetermined state. This mode is used to help prevent the PWM from damaging the application.

The auto-shutdown sources are selected using the CCPxAS<2:0> bits of the CCPxAS register. A shutdown event may be generated by:

- A logic '0' on the INT pin
- A logic '1' on a Comparator (Cx) output

A shutdown condition is indicated by the CCPxASE (Auto-Shutdown Event Status) bit of the CCPxAS register. If the bit is a '0', the PWM pins are operating normally. If the bit is a '1', the PWM outputs are in the shutdown state.

When a shutdown event occurs, two things happen:


The CCPxASE bit is set to '1'. The CCPxASE will remain set until cleared in firmware or an auto-restart occurs (see Section 23.4.4 "Auto-Restart Mode").

The enabled PWM pins are asynchronously placed in their shutdown states. The PWM output pins are grouped into pairs [PxA/PxC] and [PxB/PxD]. The state of each pin pair is determined by the PSSxAC and PSSxBD bits of the CCPxAS register. Each pin pair may be placed into one of three states:

- Drive logic '1'
- · Drive logic '0'
- Tri-state (high-impedance)

- Note 1: The auto-shutdown condition is a level-based signal, not an edge-based signal. As long as the level is present, the auto-shutdown will persist.
  - 2: Writing to the CCPxASE bit is disabled while an auto-shutdown condition persists.
  - **3:** Once the auto-shutdown condition has been removed and the PWM restarted (either through firmware or auto-restart) the PWM signal will always restart at the beginning of the next PWM period.
  - 4: Prior to an auto-shutdown event caused by a comparator output or INT pin event, a software shutdown can be triggered in firmware by setting the CCPxASE bit of the CCPxAS register to '1'. The Auto-Restart feature tracks the active status of a shutdown caused by a comparator output or INT pin event only. If it is enabled at this time, it will immediately clear this bit and restart the ECCP module at the beginning of the next PWM period.

FIGURE 23-14: PWM AUTO-SHUTDOWN WITH FIRMWARE RESTART (PXRSEN = 0)




### 23.4.4 AUTO-RESTART MODE

The Enhanced PWM can be configured to automatically restart the PWM signal once the auto-shutdown condition has been removed. Auto-restart is enabled by setting the PxRSEN bit in the PWMxCON register.

If auto-restart is enabled, the CCPxASE bit will remain set as long as the auto-shutdown condition is active. When the auto-shutdown condition is removed, the CCPxASE bit will be cleared via hardware and normal operation will resume.

FIGURE 23-15: PWM AUTO-SHUTDOWN WITH AUTO-RESTART (PXRSEN = 1)




## 23.4.5 PROGRAMMABLE DEAD-BAND DELAY MODE

In Half-Bridge applications where all power switches are modulated at the PWM frequency, the power switches normally require more time to turn off than to turn on. If both the upper and lower power switches are switched at the same time (one turned on, and the other turned off), both switches may be on for a short period of time until one switch completely turns off. During this brief interval, a very high current (shoot-through current) will flow through both power switches, shorting the bridge supply. To avoid this potentially destructive shoot-through current from flowing during switching, turning on either of the power switches is normally delayed to allow the other switch to completely turn off.


In Half-Bridge mode, a digitally programmable dead-band delay is available to avoid shoot-through current from destroying the bridge power switches. The delay occurs at the signal transition from the non-active state to the active state. See Figure 23-16 for illustration. The lower seven bits of the associated PWMxCON register (Register 23-5) sets the delay period in terms of microcontroller instruction cycles (Tcy or 4 Tosc).

# FIGURE 23-16: EXAMPLE OF HALF-BRIDGE PWM OUTPUT



- Note 1: At this time, the TMRx register is equal to the PRx register.
  - 2: Output signals are shown as active-high.

#### FIGURE 23-17: EXAMPLE OF HALF-BRIDGE APPLICATIONS



#### 23.4.6 PWM STEERING MODE

In Single Output mode, PWM steering allows any of the PWM pins to be the modulated signal. Additionally, the same PWM signal can be simultaneously available on multiple pins.


Once the Single Output mode is selected (CCPxM<3:2> = 11 and PxM<1:0> = 00 of the CCPxCON register), the user firmware can bring out the same PWM signal to one, two, three or four output pins by setting the appropriate STRx<D:A> bits of the PSTRxCON register, as shown in Table 23-9.

**Note:** The associated TRIS bits must be set to output ('0') to enable the pin output driver in order to see the PWM signal on the pin.

While the PWM Steering mode is active, CCPxM<1:0> bits of the CCPxCON register select the PWM output polarity for the Px<D:A> pins.

The PWM auto-shutdown operation also applies to PWM Steering mode as described in **Section 23.4.3 "Enhanced PWM Auto-shutdown mode"**. An auto-shutdown event will only affect pins that have PWM outputs enabled.

FIGURE 23-18: SIMPLIFIED STEERING BLOCK DIAGRAM



Note 1: Port outputs are configured as shown when the CCPxCON register bits PxM<1:0> = 00 and CCPxM<3:2> = 11.

2: Single PWM output requires setting at least one of the STRx bits.

### 23.4.6.1 Steering Synchronization

The STRxSYNC bit of the PSTRxCON register gives the user two selections of when the steering event will happen. When the STRxSYNC bit is '0', the steering event will happen at the end of the instruction that writes to the PSTRxCON register. In this case, the output signal at the Px<D:A> pins may be an incomplete PWM waveform. This operation is useful when the user firmware needs to immediately remove a PWM signal from the pin.

When the STRxSYNC bit is '1', the effective steering update will happen at the beginning of the next PWM period. In this case, steering on/off the PWM output will always produce a complete PWM waveform.

Figures 23-19 and 23-20 illustrate the timing diagrams of the PWM steering depending on the STRxSYNC setting.

#### 23.4.7 START-UP CONSIDERATIONS

When any PWM mode is used, the application hardware must use the proper external pull-up and/or pull-down resistors on the PWM output pins.

The CCPxM<1:0> bits of the CCPxCON register allow the user to choose whether the PWM output signals are active-high or active-low for each pair of PWM output pins (PxA/PxC and PxB/PxD). The PWM output polarities must be selected before the PWM pin output

drivers are enabled. Changing the polarity configuration while the PWM pin output drivers are enable is not recommended since it may result in damage to the application circuits.

The PxA, PxB, PxC and PxD output latches may not be in the proper states when the PWM module is initialized. Enabling the PWM pin output drivers at the same time as the Enhanced PWM modes may cause damage to the application circuit. The Enhanced PWM modes must be enabled in the proper Output mode and complete a full PWM cycle before enabling the PWM pin output drivers. The completion of a full PWM cycle is indicated by the TMRxIF bit of the PIRx register being set as the second PWM period begins.

Note: When the microcontroller is released from Reset, all of the I/O pins are in the high-impedance state. The external circuits must keep the power switch devices

cuits must keep the power switch devices in the Off state until the microcontroller drives the I/O pins with the proper signal levels or activates the PWM output(s).

FIGURE 23-19: EXAMPLE OF STEERING EVENT AT END OF INSTRUCTION (STRXSYNC = 0)




FIGURE 23-20: EXAMPLE OF STEERING EVENT AT BEGINNING OF INSTRUCTION (STRxSYNC = 1)




TABLE 23-10: SUMMARY OF REGISTERS ASSOCIATED WITH ENHANCED PWM

| Name                 | Bit 7        | Bit 6                         | Bit 5      | Bit 4    | Bit 3     | Bit 2                 | Bit 1                 | Bit 0                 | Register on Page |
|----------------------|--------------|-------------------------------|------------|----------|-----------|-----------------------|-----------------------|-----------------------|------------------|
| CCPxCON              | PxM<         | 1:0> <sup>(1)</sup> DCxB<1:0> |            |          |           |                       | 234                   |                       |                  |
| CCPxAS               | CCPxASE      | (                             | CCPxAS<2:0 | >        | PSSxA     | C<1:0>                | PSSxB                 | D<1:0>                | 236              |
| CCPTMRS0             | C4TSE        | L<1:0>                        | C3TSE      | L<1:0>   | C2TSE     | :L<1:0>               | C1TSE                 | L<1:0>                | 235              |
| CCPTMRS1             | _            | _                             | _          | _        | _         | _                     | C5TSE                 | L<1:0>                | 235              |
| INTCON               | GIE          | PEIE                          | TMR0IE     | INTE     | IOCIE     | TMR0IF                | INTF                  | IOCIF                 | 98               |
| PIE1                 | TMR1GIE      | ADIE                          | RCIE       | TXIE     | SSPIE     | CCP1IE                | TMR2IE                | TMR1IE                | 99               |
| PIE2                 | OSFIE        | C2IE                          | C1IE       | EEIE     | BCLIE     | LCDIE                 | _                     | CCP2IE                | 100              |
| PIE3                 | _            | CCP5IE                        | CCP4IE     | CCP3IE   | TMR6IE    | _                     | TMR4IE                | _                     | 101              |
| PIR1                 | TMR1GIF      | ADIF                          | RCIF       | TXIF     | SSPIF     | CCP1IF                | TMR2IF                | TMR1IF                | 102              |
| PIR2                 | OSFIF        | C2IF                          | C1IF       | EEIF     | BCLIF     | LCDIF                 | _                     | CCP2IF                | 103              |
| PIR3                 | _            | CCP5IF                        | CCP4IF     | CCP3IF   | TMR6IF    | _                     | TMR4IF                | _                     | 104              |
| PRx                  | Timer2/4/6 P | eriod Registe                 | er         |          |           |                       |                       |                       | 207*             |
| PSTRxCON             | _            | _                             | _          | STRxSYNC | STRxD     | STRxC                 | STRxB                 | STRxA                 | 238              |
| PWMxCON              | PxRSEN       |                               |            |          | PxDC<6:0> |                       |                       |                       | 237              |
| TxCON                | _            |                               | TxOUTF     | PS<3:0>  |           | TMRxON                | TxCKP                 | S<:0>1                | 209              |
| TMRx                 | Timer2/4/6 M | lodule Regist                 | er         |          |           |                       |                       |                       | 207              |
| TRISA                | TRISA7       | TRISA6                        | TRISA5     | TRISA4   | TRISA3    | TRISA2                | TRISA1                | TRISA0                | 133              |
| TRISB                | TRISB7       | TRISB6                        | TRISB5     | TRISB4   | TRISB3    | TRISB2                | TRISB1                | TRISB0                | 138              |
| TRISC                | TRISC7       | TRISC6                        | TRISC5     | TRISC4   | TRISC3    | TRISC2                | TRISC1                | TRISC0                | 142              |
| TRISD <sup>(2)</sup> | TRISD7       | TRISD6                        | TRISD5     | TRISD4   | TRISD3    | TRISD2                | TRISD1                | TRISD0                | 145              |
| TRISE                | _            | _                             | _          | _        | (3)       | TRISE2 <sup>(2)</sup> | TRISE1 <sup>(2)</sup> | TRISE0 <sup>(2)</sup> | 148              |

**Legend:** — = Unimplemented location, read as '0'. Shaded cells are not used by the PWM.

Note 1: Applies to ECCP modules only.

<sup>2:</sup> These registers/bits are not implemented on PIC16(L)F1936 devices, read as '0'.

<sup>3:</sup> Unimplemented, read as '1'.

<sup>\*</sup> Page provides register information.

## 23.5 CCP Control Register

## REGISTER 23-1: CCPxCON: CCPx CONTROL REGISTER

| R/W-00 | R/W-0/0             | R/W-0/0 | R/W-0/0 | R/W-0/0 | R/W-0/0 | R/W-0/0 | R/W-0/0 |
|--------|---------------------|---------|---------|---------|---------|---------|---------|
| PxM<   | 1:0> <sup>(1)</sup> | DCxE    | 3<1:0>  |         | CCPxI   | M<3:0>  |         |
| bit 7  |                     |         |         |         |         |         | bit 0   |

Legend:R = Readable bitW = Writable bitU = Unimplemented bit, read as '0'u = Bit is unchangedx = Bit is unknown-n/n = Value at POR and BOR/Value at all other Reset

'1' = Bit is set '0' = Bit is cleared

bit 7-6 PxM<1:0>: Enhanced PWM Output Configuration bits<sup>(1)</sup>

Capture mode:

Unused

Compare mode:

Unused

If CCPxM<3:2> = 00, 01, 10:

xx = PxA assigned as Capture/Compare input; PxB, PxC, PxD assigned as port pins

<u>If CCPxM<3:2> = 11:</u>

00 = Single output; PxA modulated; PxB, PxC, PxD assigned as port pins

01 = Full-Bridge output forward; PxD modulated; PxA active; PxB, PxC inactive

10 = Half-Bridge output; PxA, PxB modulated with dead-band control; PxC, PxD assigned as port pins

11 = Full-Bridge output reverse; PxB modulated; PxC active; PxA, PxD inactive

bit 5-4 DCxB<1:0>: PWM Duty Cycle Least Significant bits

Capture mode:

Unused

Compare mode:

Unused

PWM mode:

These bits are the two LSbs of the PWM duty cycle. The eight MSbs are found in CCPRxL.

bit 3-0 CCPxM<3:0>: ECCPx Mode Select bits

0000 = Capture/Compare/PWM off (resets ECCPx module)

0001 = Reserved

0010 = Compare mode: toggle output on match

0011 = Reserved

0100 = Capture mode: every falling edge

0101 = Capture mode: every rising edge

0110 = Capture mode: every 4th rising edge

0111 = Capture mode: every 16th rising edge

1000 = Compare mode: initialize ECCPx pin low; set output on compare match (set CCPxIF)

1001 = Compare mode: initialize ECCPx pin high; clear output on compare match (set CCPxIF)

1010 = Compare mode: generate software interrupt only; ECCPx pin reverts to I/O state

1011 = Compare mode: Special Event Trigger (ECCPx resets Timer, sets CCPxIF bit starts A/D conversion if A/D module is enabled)<sup>(1)</sup>

### CCP4/CCP5 only:

11xx = PWM mode

## ECCP1/ECCP2/ECCP3 only:

1100 = PWM mode: PxA, PxC active-high; PxB, PxD active-high

1101 = PWM mode: PxA, PxC active-high; PxB, PxD active-low

1110 = PWM mode: PxA, PxC active-low; PxB, PxD active-high

1111 = PWM mode: PxA, PxC active-low; PxB, PxD active-low

Note 1: These bits are not implemented on CCP4 and CCP5.

## REGISTER 23-2: CCPTMRS0: PWM TIMER SELECTION CONTROL REGISTER 0

| R/W-0/0 |
|---------|---------|---------|---------|---------|---------|---------|---------|
| C4TSE   | L<1:0>  | C3TSE   | L<1:0>  | C2TSE   | L<1:0>  | C1TSE   | L<1:0>  |
| bit 7   |         |         |         |         |         |         | bit 0   |

| Legend:              |                      |   |
|----------------------|----------------------|---|
| R = Readable bit     | W = Writable bit     | U = Unimplemented bit, read as '0'                    |
| u = Bit is unchanged | x = Bit is unknown   | -n/n = Value at POR and BOR/Value at all other Resets |
| '1' = Bit is set     | '0' = Bit is cleared |   |

| 1:170   | 047071 4.0 00047 0 1 1 1   |
|---------|--|
| bit 7-6 | C4TSEL<1:0>: CCP4 Timer Selection bits  00 = CCP4 is based off Timer2 in PWM mode  01 = CCP4 is based off Timer4 in PWM mode  10 = CCP4 is based off Timer6 in PWM mode  11 = Reserved |
| bit 5-4 | C3TSEL<1:0>: CCP3 Timer Selection bits  00 = CCP3 is based off Timer2 in PWM mode  01 = CCP3 is based off Timer4 in PWM mode  10 = CCP3 is based off Timer6 in PWM mode  11 = Reserved |
| bit 3-2 | C2TSEL<1:0>: CCP2 Timer Selection bits  00 = CCP2 is based off Timer2 in PWM mode  01 = CCP2 is based off Timer4 in PWM mode  10 = CCP2 is based off Timer6 in PWM mode  11 = Reserved |
| bit 1-0 | C1TSEL<1:0>: CCP1 Timer Selection bits  00 = CCP1 is based off Timer2 in PWM mode  01 = CCP1 is based off Timer4 in PWM mode  10 = CCP1 is based off Timer6 in PWM mode  11 = Reserved |
|         |  |

## REGISTER 23-3: CCPTMRS1: PWM TIMER SELECTION CONTROL REGISTER 1

| U-0   | U-0 | U-0 | U-0 | U-0 | U-0 | R/W-0/0 | R/W-0/0 |
|-------|-----|-----|-----|-----|-----|---------|---------|
| _     | _   | _   | _   | _   | _   | C5TSE   | L<1:0>  |
| bit 7 |     |     |     |     |     |         | bit 0   |

| Legend:              |                      |   |
|----------------------|----------------------|---|
| R = Readable bit     | W = Writable bit     | U = Unimplemented bit, read as '0'                    |
| u = Bit is unchanged | x = Bit is unknown   | -n/n = Value at POR and BOR/Value at all other Resets |
| '1' = Bit is set     | '0' = Bit is cleared |   |

bit 7-2 **Unimplemented:** Read as '0'

bit 1-0 **C5TSEL<1:0>:** CCP5 Timer Selection bits

00 = CCP5 is based off Timer2 in PWM mode

01 = CCP5 is based off Timer4 in PWM mode

10 = CCP5 is based off Timer6 in PWM mode

11 = Reserved

## REGISTER 23-4: CCPxAS: CCPX AUTO-SHUTDOWN CONTROL REGISTER

| R/W-0/0 | R/W-0/0     | R/W-0/0 | R/W-0/0 | R/W-0/0     | R/W-0/0 | R/W-0/0     | R/W-0/0 |
|---------|-------------|---------|---------|-------------|---------|-------------|---------|
| CCPxASE | CCPxAS<2:0> |         |         | PSSxAC<1:0> |         | PSSxBD<1:0> |         |
| bit 7   |             |         |         |             |         |             | bit 0   |

Legend:R = Readable bitW = Writable bitU = Unimplemented bit, read as '0'u = Bit is unchangedx = Bit is unknown-n/n = Value at POR and BOR/Value at all other Resets'1' = Bit is set'0' = Bit is cleared

001 = Comparator C1 output high<sup>(1)</sup>
010 = Comparator C2 output high<sup>(1)</sup>
011 = Either Comparator C1 or C2 high<sup>(1)</sup>
100 = VIL on INT pin

101 = VIL on INT pin or Comparator C1 high<sup>(1)</sup> 110 = VIL on INT pin or Comparator C2 high<sup>(1)</sup>

111 = VIL on INT pin or Comparator C1 or Comparator C2 high(1)

bit 3-2 **PSSxAC<1:0>:** Pins PxA and PxC Shutdown State Control bits

00 = Drive pins PxA and PxC to '0' 01 = Drive pins PxA and PxC to '1' 1x = Pins PxA and PxC tri-state

bit 1-0 PSSxBD<1:0>: Pins PxB and PxD Shutdown State Control bits

00 = Drive pins PxB and PxD to '0' 01 = Drive pins PxB and PxD to '1' 1x = Pins PxB and PxD tri-state

**Note 1:** If CxSYNC is enabled, the shutdown will be delayed by Timer1.

## REGISTER 23-5: PWMxCON: ENHANCED PWM CONTROL REGISTER

| R/W-0/0 | R/W-0/0 | R/W-0/0 | R/W-0/0 | R/W-0/0   | R/W-0/0 | R/W-0/0 | R/W-0/0 |
|---------|---------|---------|---------|-----------|---------|---------|---------|
| PxRSEN  |         |         |         | PxDC<6:0> |         |         |         |
| bit 7   |         |         |         |           |         |         | bit 0   |

| Legend:              |                      |   |
|----------------------|----------------------|---|
| R = Readable bit     | W = Writable bit     | U = Unimplemented bit, read as '0'                    |
| u = Bit is unchanged | x = Bit is unknown   | -n/n = Value at POR and BOR/Value at all other Resets |
| '1' = Bit is set     | '0' = Bit is cleared |   |

bit 7 PxRSEN: PWM Restart Enable bit

1 = Upon auto-shutdown, the CCPxASE bit clears automatically once the shutdown event goes away; the PWM restarts automatically

0 = Upon auto-shutdown, CCPxASE must be cleared in software to restart the PWM

bit 6-0 PxDC<6:0>: PWM Delay Count bits

PxDCx = Number of Fosc/4 (4 \* Tosc) cycles between the scheduled time when a PWM signal **should** transition active and the **actual** time it transitions active

Note 1: Bit resets to '0' with Two-Speed Start-up and LP, XT or HS selected as the Oscillator mode or Fail-Safe mode is enabled.

## REGISTER 23-6: PSTRxCON: PWM STEERING CONTROL REGISTER<sup>(1)</sup>

| U-0   | U-0         | U-0 | R/W-0/0  | R/W-0/0 | R/W-0/0 | R/W-0/0 | R/W-1/1 |
|-------|-------------|-----|----------|---------|---------|---------|---------|
| _     |             |     | STRxSYNC | STRxD   | STRxC   | STRxB   | STRxA   |
| bit 7 | pit 7 bit ( |     |          |         |         |         | bit 0   |

| Legend:              |                      |   |
|----------------------|----------------------|---|
| R = Readable bit     | W = Writable bit     | U = Unimplemented bit, read as '0'                    |
| u = Bit is unchanged | x = Bit is unknown   | -n/n = Value at POR and BOR/Value at all other Resets |
| '1' = Bit is set     | '0' = Bit is cleared |   |

| bit 7-5 | Unimplemented: Read as '0'   |
|---------|--|
| bit 4   | STRxSYNC: Steering Sync bit  |
|         | 1 = Output steering update occurs on next PWM period                                 |
|         | 0 = Output steering update occurs at the beginning of the instruction cycle boundary |
| bit 3   | STRxD: Steering Enable bit D   |
|         | 1 = PxD pin has the PWM waveform with polarity control from CCPxM<1:0>               |
|         | 0 = PxD pin is assigned to port pin  |
| bit 2   | STRxC: Steering Enable bit C   |
|         | 1 = PxC pin has the PWM waveform with polarity control from CCPxM<1:0>               |
|         | 0 = PxC pin is assigned to port pin  |
| bit 1   | STRxB: Steering Enable bit B   |
|         | 1 = PxB pin has the PWM waveform with polarity control from CCPxM<1:0>               |
|         | 0 = PxB pin is assigned to port pin  |
| bit 0   | STRxA: Steering Enable bit A   |
|         | 1 = PxA pin has the PWM waveform with polarity control from CCPxM<1:0>               |
|         | 0 = PxA pin is assigned to port pin  |

**Note 1:** The PWM Steering mode is available only when the CCPxCON register bits CCPxM<3:2> = 11 and PxM<1:0> = 00.

## 24.0 MASTER SYNCHRONOUS SERIAL PORT MODULE

## 24.1 Master SSP (MSSP) Module Overview

The Master Synchronous Serial Port (MSSP) module is a serial interface useful for communicating with other peripheral or microcontroller devices. These peripheral devices may be serial EEPROMs, shift registers, display drivers, A/D converters, etc. The MSSP module can operate in one of two modes:


- · Serial Peripheral Interface (SPI)
- Inter-Integrated Circuit (I<sup>2</sup>C<sup>™</sup>)

The SPI interface supports the following modes and features:

- · Master mode
- · Slave mode
- · Clock Parity
- · Slave Select Synchronization (Slave mode only)
- · Daisy-chain connection of slave devices

Figure 24-1 is a block diagram of the SPI interface module.

FIGURE 24-1: MSSP BLOCK DIAGRAM (SPI MODE)





The I<sup>2</sup>C interface supports the following modes and features:

- · Master mode
- · Slave mode
- · Byte NACKing (Slave mode)
- · Limited Multi-master support
- · 7-bit and 10-bit addressing
- · Start and Stop interrupts
- · Interrupt masking
- · Clock stretching
- · Bus collision detection
- · General call address matching
- · Address masking
- · Address Hold and Data Hold modes
- Selectable SDA hold times

Figure 24-2 is a block diagram of the I<sup>2</sup>C interface module in Master mode. Figure 24-3 is a diagram of the I<sup>2</sup>C interface module in Slave mode.

FIGURE 24-2: MSSP BLOCK DIAGRAM (I<sup>2</sup>C™ MASTER MODE)





### 24.2 SPI Mode Overview

The Serial Peripheral Interface (SPI) bus is a synchronous serial data communication bus that operates in Full-Duplex mode. Devices communicate in a master/slave environment where the master device initiates the communication. A slave device is controlled through a Chip Select known as Slave Select.

The SPI bus specifies four signal connections:

- · Serial Clock (SCK)
- Serial Data Out (SDO)
- · Serial Data In (SDI)
- Slave Select (SS)

Figure 24-1 shows the block diagram of the MSSP module when operating in SPI Mode.

The SPI bus operates with a single master device and one or more slave devices. When multiple slave devices are used, an independent Slave Select connection is required from the master device to each slave device.

Figure 24-4 shows a typical connection between a master device and multiple slave devices.

The master selects only one slave at a time. Most slave devices have tri-state outputs so their output signal appears disconnected from the bus when they are not selected.

Transmissions involve two shift registers, eight bits in size, one in the master and one in the slave. With either the master or the slave device, data is always shifted out one bit at a time, with the Most Significant bit (MSb) shifted out first. At the same time, a new Least Significant bit (LSb) is shifted into the same register.

Figure 24-5 shows a typical connection between two processors configured as master and slave devices.

Data is shifted out of both shift registers on the programmed clock edge and latched on the opposite edge of the clock

The master device transmits information out on its SDO output pin which is connected to, and received by, the slave's SDI input pin. The slave device transmits information out on its SDO output pin, which is connected to, and received by, the master's SDI input pin.

To begin communication, the master device first sends out the clock signal. Both the master and the slave devices should be configured for the same clock polarity.

The master device starts a transmission by sending out the MSb from its shift register. The slave device reads this bit from that same line and saves it into the LSb position of its shift register.

During each SPI clock cycle, a full-duplex data transmission occurs. This means that while the master device is sending out the MSb from its shift register (on

its SDO pin) and the slave device is reading this bit and saving it as the LSb of its shift register, that the slave device is also sending out the MSb from its shift register (on its SDO pin) and the master device is reading this bit and saving it as the LSb of its shift register.

After 8 bits have been shifted out, the master and slave have exchanged register values.

If there is more data to exchange, the shift registers are loaded with new data and the process repeats itself.

Whether the data is meaningful or not (dummy data), depends on the application software. This leads to three scenarios for data transmission:

- Master sends useful data and slave sends dummy data.
- Master sends useful data and slave sends useful data.
- Master sends dummy data and slave sends useful data.

Transmissions may involve any number of clock cycles. When there is no more data to be transmitted, the master stops sending the clock signal and it deselects the slave.

Every slave device connected to the bus that has not been selected through its slave select line must disregard the clock and transmission signals and must not transmit out any data of its own.




FIGURE 24-4: SPI MASTER AND MULTIPLE SLAVE CONNECTION

### 24.2.1 SPI MODE REGISTERS

The MSSP module has five registers for SPI mode operation. These are:

- MSSP STATUS register (SSPSTAT)
- MSSP Control Register 1 (SSPCON1)
- MSSP Control Register 3 (SSPCON3)
- MSSP Data Buffer register (SSPBUF)
- MSSP Address register (SSPADD)
- MSSP Shift register (SSPSR) (Not directly accessible)

SSPCON1 and SSPSTAT are the control and STATUS registers in SPI mode operation. The SSPCON1 register is readable and writable. The lower 6 bits of the SSPSTAT are read-only. The upper two bits of the SSPSTAT are read/write.

In one SPI master mode, SSPADD can be loaded with a value used in the Baud Rate Generator. More information on the Baud Rate Generator is available in **Section 24.7 "Baud Rate Generator"**.

SSPSR is the shift register used for shifting data in and out. SSPBUF provides indirect access to the SSPSR register. SSPBUF is the buffer register to which data bytes are written, and from which data bytes are read.

In receive operations, SSPSR and SSPBUF together create a buffered receiver. When SSPSR receives a complete byte, it is transferred to SSPBUF and the SSPIF interrupt is set.

During transmission, the SSPBUF is not buffered. A write to SSPBUF will write to both SSPBUF and SSPSR.

#### 24.2.2 SPI MODE OPERATION

When initializing the SPI, several options need to be specified. This is done by programming the appropriate control bits (SSPCON1<5:0> and SSPSTAT<7:6>). These control bits allow the following to be specified:

- Master mode (SCK is the clock output)
- · Slave mode (SCK is the clock input)
- Clock Polarity (Idle state of SCK)
- Data Input Sample Phase (middle or end of data output time)
- Clock Edge (output data on rising/falling edge of SCK)
- Clock Rate (Master mode only)
- · Slave Select mode (Slave mode only)

To enable the serial port, SSP Enable bit, SSPEN of the SSPCON1 register, must be set. To reset or reconfigure SPI mode, clear the SSPEN bit, re-initialize the SSPCONx registers and then set the SSPEN bit. This configures the SDI, SDO, SCK and SS pins as serial port pins. For the pins to behave as the serial port function, some must have their data direction bits (in the TRIS register) appropriately programmed as follows:

- · SDI must have corresponding TRIS bit set
- · SDO must have corresponding TRIS bit cleared
- SCK (Master mode) must have corresponding TRIS bit cleared
- SCK (Slave mode) must have corresponding TRIS bit set
- SS must have corresponding TRIS bit set


Any serial port function that is not desired may be overridden by programming the corresponding data direction (TRIS) register to the opposite value.

The MSSP consists of a transmit/receive shift register (SSPSR) and a buffer register (SSPBUF). The SSPSR shifts the data in and out of the device, MSb first. The SSPBUF holds the data that was written to the SSPSR until the received data is ready. Once the 8 bits of data have been received, that byte is moved to the SSPBUF register. Then, the Buffer Full Detect bit, BF of the SSPSTAT register, and the interrupt flag bit, SSPIF, are set. This double-buffering of the received data (SSPBUF) allows the next byte to start reception before reading the data that was just received. Any write to the SSPBUF register during transmission/reception of data will be ignored and the write collision detect bit WCOL of the SSPCON1 register, will be set. User software must clear the WCOL bit to allow the following write(s) to the SSPBUF register to complete successfully.

When the application software is expecting to receive valid data, the SSPBUF should be read before the next byte of data to transfer is written to the SSPBUF. The Buffer Full bit, BF of the SSPSTAT register, indicates when SSPBUF has been loaded with the received data (transmission is complete). When the SSPBUF is read, the BF bit is cleared. This data may be irrelevant if the SPI is only a transmitter. Generally, the MSSP interrupt is used to determine when the transmission/reception has completed. If the interrupt method is not going to be used, then software polling can be done to ensure that a write collision does not occur.

The SSPSR is not directly readable or writable and can only be accessed by addressing the SSPBUF register. Additionally, the SSPSTAT register indicates the various status conditions.

FIGURE 24-5: SPI MASTER/SLAVE CONNECTION



#### 24.2.3 SPI MASTER MODE

The master can initiate the data transfer at any time because it controls the SCK line. The master determines when the slave (Processor 2, Figure 24-5) is to broadcast data by the software protocol.

In Master mode, the data is transmitted/received as soon as the SSPBUF register is written to. If the SPI is only going to receive, the SDO output could be disabled (programmed as an input). The SSPSR register will continue to shift in the signal present on the SDI pin at the programmed clock rate. As each byte is received, it will be loaded into the SSPBUF register as if a normal received byte (interrupts and Status bits appropriately set).


The clock polarity is selected by appropriately programming the CKP bit of the SSPCON1 register and the CKE bit of the SSPSTAT register. This then, would give waveforms for SPI communication as shown in Figure 24-6, Figure 24-8 and Figure 24-9, where the MSB is transmitted first. In Master mode, the SPI clock rate (bit rate) is user programmable to be one of the following:

- Fosc/4 (or Tcy)
- Fosc/16 (or 4 \* Tcy)
- Fosc/64 (or 16 \* Tcy)
- Timer2 output/2
- Fosc/(4 \* (SSPADD + 1))

Figure 24-6 shows the waveforms for Master mode.

When the CKE bit is set, the SDO data is valid before there is a clock edge on SCK. The change of the input sample is shown based on the state of the SMP bit. The time when the SSPBUF is loaded with the received data is shown.

FIGURE 24-6: SPI MODE WAVEFORM (MASTER MODE)



## 24.2.4 SPI SLAVE MODE

In Slave mode, the data is transmitted and received as external clock pulses appear on SCK. When the last bit is latched, the SSPIF interrupt flag bit is set.

Before enabling the module in SPI Slave mode, the clock line must match the proper Idle state. The clock line can be observed by reading the SCK pin. The Idle state is determined by the CKP bit of the SSPCON1 register.

While in Slave mode, the external clock is supplied by the external clock source on the SCK pin. This external clock must meet the minimum high and low times as specified in the electrical specifications.

While in Sleep mode, the slave can transmit/receive data. The shift register is clocked from the SCK pin input and when a byte is received, the device will generate an interrupt. If enabled, the device will wake-up from Sleep.

### 24.2.4.1 Daisy-Chain Configuration

The SPI bus can sometimes be connected in a daisy-chain configuration. The first slave output is connected to the second slave input, the second slave output is connected to the third slave input, and so on. The final slave output is connected to the master input. Each slave sends out, during a second group of clock pulses, an exact copy of what was received during the first group of clock pulses. The whole chain acts as one large communication shift register. The daisy-chain feature only requires a single Slave Select line from the master device.

Figure 24-7 shows the block diagram of a typical daisy-chain connection when operating in SPI Mode.

In a daisy-chain configuration, only the most recent byte on the bus is required by the slave. Setting the BOEN bit of the SSPCON3 register will enable writes to the SSPBUF register, even if the previous byte has not been read. This allows the software to ignore data that may not apply to it.

## 24.2.5 SLAVE SELECT SYNCHRONIZATION

The Slave Select can also be used to synchronize communication. The Slave Select line is held high until the master device is ready to communicate. When the Slave Select line is pulled low, the slave knows that a new transmission is starting.

If the slave fails to receive the communication properly, it will be reset at the end of the transmission, when the Slave Select line returns to a high state. The slave is then ready to receive a new transmission when the Slave Select line is pulled low again. If the Slave Select line is not used, there is a risk that the slave will eventually become out of sync with the master. If the slave misses a bit, it will always be one bit off in future transmissions. Use of the Slave Select line allows the slave and master to align themselves at the beginning of each transmission.

The  $\overline{SS}$  pin allows a Synchronous Slave mode. The SPI must be in Slave mode with  $\overline{SS}$  pin control enabled (SSPCON1<3:0> = 0100).


When the  $\overline{SS}$  pin is low, transmission and reception are enabled and the SDO pin is driven.

When the SS pin goes high, the SDO pin is no longer driven, even if in the middle of a transmitted byte and becomes a floating output. External pull-up/pull-down resistors may be desirable depending on the application.


- Note 1: When the SPI is in Slave mode with \$\overline{SS}\$ pin control enabled (SSPCON1<3:0> = 0100), the SPI module will reset if the \$\overline{SS}\$ pin is set to VDD.
  - 2: When the SPI is used in Slave mode with CKE set; the user must enable SS pin control.
  - **3:** While operated in SPI Slave mode the SMP bit of the SSPSTAT register must remain clear.

When the SPI module resets, the bit counter is forced to '0'. This can be done by either forcing the  $\overline{SS}$  pin to a high level or clearing the SSPEN bit.

FIGURE 24-7: SPI DAISY-CHAIN CONNECTION













FIGURE 24-10: SPI MODE WAVEFORM (SLAVE MODE WITH CKE = 1)



#### 24.2.6 SPI OPERATION IN SLEEP MODE

In SPI Master mode, module clocks may be operating at a different speed than when in Full Power mode; in the case of the Sleep mode, all clocks are halted.

Special care must be taken by the user when the MSSP clock is much faster than the system clock.

In Slave mode, when MSSP interrupts are enabled, after the master completes sending data, an MSSP interrupt will wake the controller from Sleep.

If an exit from Sleep mode is not desired, MSSP interrupts should be disabled.

In SPI Master mode, when the Sleep mode is selected, all module clocks are halted and the transmission/reception will remain in that state until the device wakes. After the device returns to Run mode, the module will resume transmitting and receiving data.

In SPI Slave mode, the SPI Transmit/Receive Shift register operates asynchronously to the device. This allows the device to be placed in Sleep mode and data to be shifted into the SPI Transmit/Receive Shift register. When all 8 bits have been received, the MSSP interrupt flag bit will be set and if enabled, will wake the device.

TABLE 24-1: SUMMARY OF REGISTERS ASSOCIATED WITH SPI OPERATION

| Name    | Bit 7  | Bit 6   | Bit 5           | Bit 4  | Bit 3   | Bit 2    | Bit 1  | Bit 0   | Register on Page |
|---------|--|---------|-----------------|--------|---------|----------|--------|---------|------------------|
| ANSELA  | _  | _       | ANSA5           | ANSA4  | ANSA3   | ANSA2    | ANSA1  | ANSA0   | 134              |
| APFCON  | _  | CCP3SEL | T1GSEL          | P2BSEL | SRNQSEL | C2OUTSEL | SSSEL  | CCP2SEL | 131              |
| INTCON  | GIE  | PEIE    | TMR0IE          | INTE   | IOCIE   | TMR0IF   | INTF   | IOCIF   | 98               |
| PIE1    | TMR1GIE  | ADIE    | RCIE            | TXIE   | SSP1IE  | CCP1IE   | TMR2IE | TMR1IE  | 99               |
| PIR1    | TMR1GIF  | ADIF    | RCIF            | TXIF   | SSP1IF  | CCP1IF   | TMR2IF | TMR1IF  | 102              |
| SSPBUF  | Synchronous Serial Port Receive Buffer/Transmit Register |         |                 |        |         |          | 243*   |         |                  |
| SSPCON1 | WCOL   | SSPOV   | SSPEN           | CKP    |         | SSPM<    | <3:0>  |         | 287              |
| SSPCON3 | ACKTIM   | PCIE    | SCIE            | BOEN   | SDAHT   | SBCDE    | AHEN   | DHEN    | 289              |
| SSPSTAT | SMP  | CKE     | D/ <del>A</del> | Р      | S       | R/W      | UA     | BF      | 286              |
| TRISA   | TRISA7   | TRISA6  | TRISA5          | TRISA4 | TRISA3  | TRISA2   | TRISA1 | TRISA0  | 133              |
| TRISC   | TRISC7   | TRISC6  | TRISC5          | TRISC4 | TRISC3  | TRISB2   | TRISC1 | TRISC0  | 142              |

Legend: — = Unimplemented location, read as '0'. Shaded cells are not used by the MSSP in SPI mode.

<sup>\*</sup> Page provides register information.

### 24.3 I<sup>2</sup>C Mode Overview

The Inter-Integrated Circuit Bus (I<sup>2</sup>C) is a multi-master serial data communication bus. Devices communicate in a master/slave environment where the master devices initiate the communication. A Slave device is controlled through addressing.

The I<sup>2</sup>C bus specifies two signal connections:

- · Serial Clock (SCL)
- · Serial Data (SDA)

Figure 24-11 shows the block diagram of the MSSP module when operating in I<sup>2</sup>C Mode.

Both the SCL and SDA connections are bidirectional open-drain lines, each requiring pull-up resistors for the supply voltage. Pulling the line to ground is considered a logical zero and letting the line float is considered a logical one.

Figure 24-11 shows a typical connection between two processors configured as master and slave devices.

The I<sup>2</sup>C bus can operate with one or more master devices and one or more slave devices.

There are four potential modes of operation for a given device:


- Master Transmit mode (master is transmitting data to a slave)
- Master Receive mode (master is receiving data from a slave)
- Slave Transmit mode (slave is transmitting data to a master)
- Slave Receive mode (slave is receiving data from the master)

To begin communication, a master device starts out in Master Transmit mode. The master device sends out a Start bit followed by the address byte of the slave it intends to communicate with. This is followed by a single Read/Write bit, which determines whether the master intends to transmit to or receive data from the slave device.

If the requested slave exists on the bus, it will respond with an Acknowledge bit, otherwise known as an ACK. The master then continues in either Transmit mode or Receive mode and the slave continues in the complement, either in Receive mode or Transmit mode, respectively.

A Start bit is indicated by a high-to-low transition of the SDA line while the SCL line is held high. Address and data bytes are sent out, Most Significant bit (MSb) first. The Read/Write bit is sent out as a logical one when the master intends to read data from the slave, and is sent out as a logical zero when it intends to write data to the slave.

## FIGURE 24-11: I<sup>2</sup>C MASTER/ SLAVE CONNECTION



The Acknowledge bit  $(\overline{ACK})$  is an active-low signal, which holds the SDA line low to indicate to the transmitter that the slave device has received the transmitted data and is ready to receive more.

The transition of a data bit is always performed while the SCL line is held low. Transitions that occur while the SCL line is held high are used to indicate Start and Stop bits.

If the master intends to write to the slave, then it repeatedly sends out a byte of data, with the slave responding after each byte with an  $\overline{ACK}$  bit. In this example, the master device is in Master Transmit mode and the slave is in Slave Receive mode.

If the master intends to read from the slave, then it repeatedly receives a byte of data from the slave, and responds after each byte with an  $\overline{ACK}$  bit. In this example, the master device is in Master Receive mode and the slave is Slave Transmit mode.

On the last byte of data communicated, the master device may end the transmission by sending a Stop bit. If the master device is in Receive mode, it sends the Stop bit in place of the last  $\overline{ACK}$  bit. A Stop bit is indicated by a low-to-high transition of the SDA line while the SCL line is held high.

In some cases, the master may want to maintain control of the bus and re-initiate another transmission. If so, the master device may send another Start bit in place of the Stop bit or last ACK bit when it is in receive mode.

The I<sup>2</sup>C bus specifies three message protocols;

- Single message where a master writes data to a slave.
- Single message where a master reads data from a slave.
- Combined message where a master initiates a minimum of two writes, or two reads, or a combination of writes and reads, to one or more slaves.

When one device is transmitting a logical one, or letting the line float, and a second device is transmitting a logical zero, or holding the line low, the first device can detect that the line is not a logical one. This detection, when used on the SCL line, is called clock stretching. Clock stretching gives slave devices a mechanism to control the flow of data. When this detection is used on the SDA line, it is called arbitration. Arbitration ensures that there is only one master device communicating at any single time.

### 24.3.1 CLOCK STRETCHING

When a slave device has not completed processing data, it can delay the transfer of more data through the process of clock stretching. An addressed slave device may hold the SCL clock line low after receiving or sending a bit, indicating that it is not yet ready to continue. The master that is communicating with the slave will attempt to raise the SCL line in order to transfer the next bit, but will detect that the clock line has not yet been released. Because the SCL connection is open-drain, the slave has the ability to hold that line low until it is ready to continue communicating.

Clock stretching allows receivers that cannot keep up with a transmitter to control the flow of incoming data.

#### 24.3.2 ARBITRATION

Each master device must monitor the bus for Start and Stop bits. If the device detects that the bus is busy, it cannot begin a new message until the bus returns to an Idle state.

However, two master devices may try to initiate a transmission on or about the same time. When this occurs, the process of arbitration begins. Each transmitter checks the level of the SDA data line and compares it to the level that it expects to find. The first transmitter to observe that the two levels do not match, loses arbitration, and must stop transmitting on the SDA line.

For example, if one transmitter holds the SDA line to a logical one (lets it float) and a second transmitter holds it to a logical zero (pulls it low), the result is that the SDA line will be low. The first transmitter then observes that the level of the line is different than expected and concludes that another transmitter is communicating.

The first transmitter to notice this difference is the one that loses arbitration and must stop driving the SDA line. If this transmitter is also a master device, it also must stop driving the SCL line. It then can monitor the lines for a Stop condition before trying to reissue its transmission. In the meantime, the other device that has not noticed any difference between the expected and actual levels on the SDA line continues with its original transmission. It can do so without any complications, because so far, the transmission appears exactly as expected with no other transmitter disturbing the message.

Slave Transmit mode can also be arbitrated, when a master addresses multiple slaves, but this is less common

If two master devices are sending a message to two different slave devices at the address stage, the master sending the lower slave address always wins arbitration. When two master devices send messages to the same slave address, and addresses can sometimes refer to multiple slaves, the arbitration process must continue into the data stage.

Arbitration usually occurs very rarely, but it is a necessary process for proper multi-master support.

## 24.4 I<sup>2</sup>C<sup>™</sup> Mode Operation

All MSSP I<sup>2</sup>C communication is byte oriented and shifted out MSb first. Six SFR registers and 2 interrupt flags interface the module with the PIC<sup>®</sup> microcontroller and user software. Two pins, SDA and SCL, are exercised by the module to communicate with other external I<sup>2</sup>C devices.

### 24.4.1 BYTE FORMAT

All communication in  $I^2C$  is done in 9-bit segments. A byte is sent from a Master to a Slave or vice-versa, followed by an Acknowledge bit sent back. After the 8th falling edge of the SCL line, the device outputting data on the SDA changes that pin to an input and reads in an Acknowledge value on the next clock pulse.

The clock signal, SCL, is provided by the master. Data is valid to change while the SCL signal is low, and sampled on the rising edge of the clock. Changes on the SDA line while the SCL line is high define special conditions on the bus, explained below.

## 24.4.2 DEFINITION OF I<sup>2</sup>C TERMINOLOGY

There is language and terminology in the description of  $I^2C$  communication that have definitions specific to  $I^2C$ . That word usage is defined below and may be used in the rest of this document without explanation. This table was adapted from the Philips  $I^2C$  specification.

## 24.4.3 SDA AND SCL PINS

Selection of any I<sup>2</sup>C mode with the SSPEN bit set, forces the SCL and SDA pins to be open-drain. These pins should be set by the user to inputs by setting the appropriate TRIS bits.

**Note:** Data is tied to output zero when an I<sup>2</sup>C mode is enabled.

## 24.4.4 SDA HOLD TIME

The hold time of the SDA pin is selected by the SDAHT bit of the SSPCON3 register. Hold time is the time SDA is held valid after the falling edge of SCL. Setting the SDAHT bit selects a longer 300 ns minimum hold time and may help on buses with large capacitance.

### TABLE 24-2: I<sup>2</sup>C BUS TERMS

| TERM                | Description   |
|---------------------|---|
| Transmitter         | The device which shifts data out onto the bus.  |
| Receiver            | The device which shifts data in from the bus.   |
| Master              | The device that initiates a transfer, generates clock signals and terminates a transfer.  |
| Slave               | The device addressed by the master.   |
| Multi-master        | A bus with more than one device that can initiate data transfers.   |
| Arbitration         | Procedure to ensure that only one master at a time controls the bus. Winning arbitration ensures that the message is not corrupted.   |
| Synchronization     | Procedure to synchronize the clocks of two or more devices on the bus.  |
| Idle                | No master is controlling the bus, and both SDA and SCL lines are high.  |
| Active              | Any time one or more master devices are controlling the bus.  |
| Addressed<br>Slave  | Slave device that has received a matching address and is actively being clocked by a master.  |
| Matching<br>Address | Address byte that is clocked into a slave that matches the value stored in SSPADD.  |
| Write Request       | Slave receives a matching address with R/W bit clear, and is ready to clock in data.  |
| Read Request        | Master sends an address byte with the R/W bit set, indicating that it wishes to clock data out of the Slave. This data is the next and all following bytes until a Restart or Stop. |
| Clock Stretching    | When a device on the bus hold SCL low to stall communication.   |
| Bus Collision       | Any time the SDA line is sampled low by the module while it is outputting and expected high state.  |

#### 24.4.5 START CONDITION

The I<sup>2</sup>C specification defines a Start condition as a transition of SDA from a high to a low state while SCL line is high. A Start condition is always generated by the master and signifies the transition of the bus from an Idle to an Active state. Figure 24-10 shows wave forms for Start and Stop conditions.

A bus collision can occur on a Start condition if the module samples the SDA line low before asserting it low. This does not conform to the I<sup>2</sup>C specification that states no bus collision can occur on a Start.

#### 24.4.6 STOP CONDITION

A Stop condition is a transition of the SDA line from low-to-high state while the SCL line is high.

**Note:** At least one SCL low time must appear before a Stop is valid, therefore, if the SDA line goes low then high again while the SCL line stays high, only the Start condition is detected.

#### 24.4.7 RESTART CONDITION

A Restart is valid any time that a Stop would be valid. A master can issue a Restart if it wishes to hold the bus after terminating the current transfer. A Restart has the same effect on the slave that a Start would, resetting all slave logic and preparing it to clock in an address. The master may want to address the same or another slave.

In 10-bit Addressing Slave mode a Restart is required for the master to clock data out of the addressed slave. Once a slave has been fully addressed, matching both high and low address bytes, the master can issue a Restart and the high address byte with the  $R/\overline{W}$  bit set. The slave logic will then hold the clock and prepare to clock out data.

After a full match with  $R/\overline{W}$  clear in 10-bit mode, a prior match flag is set and maintained. Until a Stop condition, a high address with  $R/\overline{W}$  clear, or high address match fails.

## 24.4.8 START/STOP CONDITION INTERRUPT MASKING

The SCIE and PCIE bits of the SSPCON3 register can enable the generation of an interrupt in Slave modes that do not typically support this function. Slave modes where interrupt on Start and Stop detect are already enabled, these bits will have no effect.

FIGURE 24-12: I<sup>2</sup>C START AND STOP CONDITIONS





FIGURE 24-13: I<sup>2</sup>C RESTART CONDITION



#### 24.4.9 ACKNOWLEDGE SEQUENCE

The 9th SCL pulse for any transferred byte in  $I^2C$  is dedicated as an Acknowledge. It allows receiving devices to respond back to the transmitter by pulling the SDA line low. The transmitter must release control of the line during this time to shift in the response. The Acknowledge ( $\overline{ACK}$ ) is an active-low signal, pulling the SDA line low indicated to the transmitter that the device has received the transmitted data and is ready to receive more.

The result of an  $\overline{ACK}$  is placed in the ACKSTAT bit of the SSPCON2 register.

Slave software, when the AHEN and DHEN bits are set, allow the user to set the  $\overline{ACK}$  value sent back to the transmitter. The ACKDT bit of the SSPCON2 register is set/cleared to determine the response.

Slave hardware will generate an  $\overline{\mathsf{ACK}}$  response if the AHEN and DHEN bits of the SSPCON3 register are clear.

There are certain conditions where an  $\overline{ACK}$  will not be sent by the slave. If the BF bit of the SSPSTAT register or the SSPOV bit of the SSPCON1 register are set when a byte is received.

When the module is addressed, after the 8th falling edge of SCL on the bus, the ACKTIM bit of the SSPCON3 register is set. The ACKTIM bit indicates the acknowledge time of the active bus. The ACKTIM Status bit is only active when the AHEN bit or DHEN bit is enabled.

### 24.5 I<sup>2</sup>C Slave Mode Operation

The MSSP Slave mode operates in one of four modes selected in the SSPM bits of SSPCON1 register. The modes can be divided into 7-bit and 10-bit Addressing mode. 10-bit Addressing modes operate the same as 7-bit with some additional overhead for handling the larger addresses.

Modes with Start and Stop bit interrupts operated the same as the other modes with SSPIF additionally getting set upon detection of a Start, Restart, or Stop condition.

#### 24.5.1 SLAVE MODE ADDRESSES

The SSPADD register (Register 24-6) contains the Slave mode address. The first byte received after a Start or Restart condition is compared against the value stored in this register. If the byte matches, the value is loaded into the SSPBUF register and an interrupt is generated. If the value does not match, the module goes Idle and no indication is given to the software that anything happened.

The SSP Mask register (Register 24-5) affects the address matching process. See **Section 24.5.9** "**SSP Mask Register**" for more information.

### 24.5.1.1 I<sup>2</sup>C Slave 7-bit Addressing Mode

In 7-bit Addressing mode, the LSb of the received data byte is ignored when determining if there is an address match.

### 24.5.1.2 I<sup>2</sup>C Slave 10-bit Addressing Mode

In 10-bit Addressing mode, the first received byte is compared to the binary value of '1 1 1 1 0 A9 A8 0'. A9 and A8 are the two MSb of the 10-bit address and stored in bits 2 and 1 of the SSPADD register.

After the acknowledge of the high byte the UA bit is set and SCL is held low until the user updates SSPADD with the low address. The low address byte is clocked in and all 8 bits are compared to the low address value in SSPADD. Even if there is not an address match; SSPIF and UA are set, and SCL is held low until SSPADD is updated to receive a high byte again. When SSPADD is updated the UA bit is cleared. This ensures the module is ready to receive the high address byte on the next communication.

A high and low address match as a write request is required at the start of all 10-bit addressing communication. A transmission can be initiated by issuing a Restart once the slave is addressed, and clocking in the high address with the R/W bit set. The slave hardware will then acknowledge the read request and prepare to clock out data. This is only valid for a slave after it has received a complete high and low address byte match.

#### 24.5.2 SLAVE RECEPTION

When the  $R/\overline{W}$  bit of a matching received address byte is clear, the  $R/\overline{W}$  bit of the SSPSTAT register is cleared. The received address is loaded into the SSPBUF register and acknowledged.

When the overflow condition exists for a received address, then not Acknowledge is given. An overflow condition is defined as either bit BF bit of the SSPSTAT register is set, or bit SSPOV bit of the SSPCON1 register is set. The BOEN bit of the SSPCON3 register modifies this operation. For more information see Register 24-4.

An MSSP interrupt is generated for each transferred data byte. Flag bit, SSPIF, must be cleared by software.

When the SEN bit of the SSPCON2 register is set, SCL will be held low (clock stretch) following each received byte. The clock must be released by setting the CKP bit of the SSPCON1 register, except sometimes in 10-bit mode. See Section 24.2.3 "SPI Master Mode" for more detail.

#### 24.5.2.1 7-bit Addressing Reception

This section describes a standard sequence of events for the MSSP module configured as an I<sup>2</sup>C Slave in 7-bit Addressing mode. All decisions made by hardware or software and their effect on reception. Figure 24-13 and Figure 24-14 is used as a visual reference for this description.

This is a step by step process of what typically must be done to accomplish I<sup>2</sup>C communication.

- 1. Start bit detected.
- S bit of SSPSTAT is set; SSPIF is set if interrupt on Start detect is enabled.
- 3. Matching address with R/W bit clear is received.
- 4. The slave pulls SDA low sending an ACK to the master, and sets SSPIF bit.
- 5. Software clears the SSPIF bit.
- Software reads received address from SSPBUF clearing the BF flag.
- 7. If SEN = 1; Slave software sets CKP bit to release the SCL line.
- 8. The master clocks out a data byte.
- Slave drives SDA low sending an ACK to the master, and sets SSPIF bit.
- 10. Software clears SSPIF.
- Software reads the received byte from SSPBUF clearing BF.
- 12. Steps 8-12 are repeated for all received bytes from the Master.
- Master sends Stop condition, setting P bit of SSPSTAT, and the bus goes Idle.

### 24.5.2.2 7-bit Reception with AHEN and DHEN


Slave device reception with AHEN and DHEN set operate the same as without these options with extra interrupts and clock stretching added after the 8th falling edge of SCL. These additional interrupts allow the slave software to decide whether it wants to  $\overline{ACK}$  the receive address or data byte, rather than the hardware. This functionality adds support for PMBus™ that was not present on previous versions of this module.


This list describes the steps that need to be taken by slave software to use these options for I<sup>2</sup>C communication. Figure 24-15 displays a module using both address and data holding. Figure 24-16 includes the operation with the SEN bit of the SSPCON2 register set


- S bit of SSPSTAT is set; SSPIF is set if interrupt on Start detect is enabled.
- 2. Matching address with R/W bit clear is clocked in. SSPIF is set and CKP cleared after the 8th falling edge of SCL.
- 3. Slave clears the SSPIF.
- Slave can look at the ACKTIM bit of the SSPCON3 register to <u>determine</u> if the SSPIF was after or before the ACK.
- Slave reads the address value from SSPBUF, clearing the BF flag.
- 6. Slave sets ACK value clocked out to the master by setting ACKDT.
- 7. Slave releases the clock by setting CKP.
- 8. SSPIF is set after an ACK, not after a NACK.
- 9. If SEN = 1 the slave hardware will stretch the clock after the ACK.
- 10. Slave clears SSPIF.


Note: SSPIF is still set after the 9th falling edge of SCL even if there is no clock stretching and BF has been cleared. Only if NACK is sent to Master is SSPIF not set

- 11. SSPIF set and CKP cleared after 8th falling edge of SCL for a received data byte.
- 12. Slave looks at ACKTIM bit of SSPCON3 to determine the source of the interrupt.
- 13. Slave reads the received data from SSPBUF clearing BF.
- 14. Steps 7-14 are the same for each received data byte.
- 15. Communication is ended by either the slave sending an ACK = 1, or the master sending a Stop condition. If a Stop is sent and Interrupt on Stop Detect is disabled, the slave will only know by polling the P bit of the SSTSTAT register.









#### 24.5.3 SLAVE TRANSMISSION

When the  $R/\overline{W}$  bit of the incoming address byte is set and an address match occurs, the  $R/\overline{W}$  bit of the SSPSTAT register is set. The received address is loaded into the SSPBUF register, and an  $\overline{ACK}$  pulse is sent by the slave on the ninth bit.

Following the ACK, slave hardware clears the CKP bit and the SCL pin is held low (see **Section 24.5.6** "Clock Stretching" for more detail). By stretching the clock, the master will be unable to assert another clock pulse until the slave is done preparing the transmit data.

The transmit data must be loaded into the SSPBUF register which also loads the SSPSR register. Then the SCL pin should be released by setting the CKP bit of the SSPCON1 register. The eight data bits are shifted out on the falling edge of the SCL input. This ensures that the SDA signal is valid during the SCL high time.

The ACK pulse from the master-receiver is latched on the rising edge of the ninth SCL input pulse. This  $\overline{ACK}$  value is copied to the ACKSTAT bit of the SSPCON2 register. If ACKSTAT is set (not  $\overline{ACK}$ ), then the data transfer is complete. In this case, when the not  $\overline{ACK}$  is latched by the slave, the slave goes Idle and waits for another occurrence of the Start bit. If the SDA line was low ( $\overline{ACK}$ ), the next transmit data must be loaded into the SSPBUF register. Again, the SCL pin must be released by setting bit CKP.

An MSSP interrupt is generated for each data transfer byte. The SSPIF bit must be cleared by software and the SSPSTAT register is used to determine the status of the byte. The SSPIF bit is set on the falling edge of the ninth clock pulse.


#### 24.5.3.1 Slave Mode Bus Collision

A slave receives a Read request and begins shifting data out on the SDA line. If a bus collision is detected and the SBCDE bit of the SSPCON3 register is set, the BCLIF bit of the PIR register is set. Once a bus collision is detected, the slave goes Idle and waits to be addressed again. User software can use the BCLIF bit to handle a slave bus collision.

### 24.5.3.2 7-bit Transmission

A master device can transmit a read request to a slave, and then clock data out of the slave. The list below outlines what software for a slave will need to do to accomplish a standard transmission. Figure 24-17 can be used as a reference to this list.

- Master sends a Start condition on SDA and SCI.
- 2. S bit of SSPSTAT is set; SSPIF is set if interrupt on Start detect is enabled.
- Matching address with R/W bit set is received by the Slave setting SSPIF bit.
- Slave hardware generates an ACK and sets SSPIF.
- 5. SSPIF bit is cleared by user.
- 6. Software reads the received address from SSPBUF, clearing BF.
- R/W is set so CKP was automatically cleared after the ACK.
- The slave software loads the transmit data into SSPBUF.
- 9. CKP bit is set releasing SCL, allowing the master to clock the data out of the slave.
- 10. SSPIF is set after the ACK response from the master is loaded into the ACKSTAT register.
- 11. SSPIF bit is cleared.
- 12. The slave software checks the ACKSTAT bit to see if the master wants to clock out more data.
  - **Note 1:** If the master  $\overline{\mathsf{ACK}}$ s the clock will be stretched.
    - 2: ACKSTAT is the only bit updated on the rising edge of SCL (9th) rather than the falling.
- 13. Steps 9-13 are repeated for each transmitted byte.
- 14. If the master sends a not ACK; the clock is not held, but SSPIF is still set.
- 15. The master sends a Restart condition or a Stop.
- 16. The slave is no longer addressed.



### 24.5.3.3 7-bit Transmission with Address Hold Enabled

Setting the AHEN bit of the SSPCON3 register enables additional clock stretching and interrupt generation after the 8th falling edge of a received matching address. Once a matching address has been clocked in, CKP is cleared and the SSPIF interrupt is set.


Figure 24-18 displays a standard waveform of a 7-bit Address Slave Transmission with AHEN enabled.

- 1. Bus starts Idle.
- Master sends Start condition; the S bit of SSPSTAT is set; SSPIF is set if interrupt on Start detect is enabled.
- Master sends matching address with R/W bit set. After the 8th falling edge of the SCL line the CKP bit is cleared and SSPIF interrupt is generated.
- 4. Slave software clears SSPIF.
- Slave software <u>reads ACKTIM</u> bit of SSPCON3 register, and R/W and D/A of the SSPSTAT register to determine the source of the interrupt.
- 6. Slave reads the address value from the SSPBUF register clearing the BF bit.
- Slave software decides from this information if it wishes to ACK or not ACK and sets ACKDT bit of the SSPCON2 register accordingly.
- 8. Slave sets the CKP bit releasing SCL.
- 9. Master clocks in the ACK value from the slave.
- Slave hardware automatically clears the CKP bit and sets SSPIF after the ACK if the R/W bit is set.
- 11. Slave software clears SSPIF.
- 12. Slave loads value to transmit to the master into SSPBUF setting the BF bit.

Note:  $\frac{\text{SSPBUF}}{\text{ACK}}$  cannot be loaded until after the

- 13. Slave sets CKP bit releasing the clock.
- 14. Master clocks out the data from the slave and sends an  $\overline{ACK}$  value on the 9th SCL pulse.
- 15. Slave hardware copies the  $\overline{ACK}$  value into the ACKSTAT bit of the SSPCON2 register.
- 16. Steps 10-15 are repeated for each byte transmitted to the master from the slave.
- 17. If the master sends a not  $\overline{ACK}$  the slave releases the bus allowing the master to send a Stop and end the communication.

Note: Master must send a not ACK on the last byte to ensure that the slave releases the SCL line to receive a Stop.



### 24.5.4 SLAVE MODE 10-BIT ADDRESS RECEPTION

This section describes a standard sequence of events for the MSSP module configured as an I<sup>2</sup>C Slave in 10-bit Addressing mode.

Figure 24-19 is used as a visual reference for this description.

This is a step by step process of what must be done by slave software to accomplish I<sup>2</sup>C communication.

- Bus starts Idle.
- Master sends Start condition; S bit of SSPSTAT is set; SSPIF is set if interrupt on Start detect is enabled.
- Master sends matching high address with R/W bit clear; UA bit of the SSPSTAT register is set.
- 4. Slave sends ACK and SSPIF is set.
- 5. Software clears the SSPIF bit.
- Software reads received address from SSPBUF clearing the BF flag.
- Slave loads low address into SSPADD, releasing SCL.
- Master sends matching low address byte to the Slave; UA bit is set.

**Note:** Updates to the SSPADD register are not allowed until after the ACK sequence.

9. Slave sends ACK and SSPIF is set.


**Note:** If the low address does not match, SSPIF and UA are still set so that the slave software can set SSPADD back to the high address. BF is not set because there is no match. CKP is unaffected.


- 10. Slave clears SSPIF.
- 11. Slave reads the received matching address from SSPBUF clearing BF.
- 12. Slave loads high address into SSPADD.
- Master clocks a data byte to the slave and clocks out the slaves ACK on the 9th SCL pulse; SSPIF is set.
- 14. If SEN bit of SSPCON2 is set, CKP is cleared by hardware and the clock is stretched.
- 15. Slave clears SSPIF.
- Slave reads the received byte from SSPBUF clearing BF.
- If SEN is set the slave sets CKP to release the SCL.
- 18. Steps 13-17 repeat for each received byte.
- 19. Master sends Stop to end the transmission.


### 24.5.5 10-BIT ADDRESSING WITH ADDRESS OR DATA HOLD

Reception using 10-bit addressing with AHEN or DHEN set is the same as with 7-bit modes. The only difference is the need to update the SSPADD register using the UA bit. All functionality, specifically when the CKP bit is cleared and SCL line is held low are the same. Figure 24-20 can be used as a reference of a slave in 10-bit addressing with AHEN set.

Figure 24-21 shows a standard waveform for a slave transmitter in 10-bit Addressing mode.







#### 24.5.6 CLOCK STRETCHING

Clock stretching occurs when a device on the bus holds the SCL line low, effectively pausing communication. The slave may stretch the clock to allow more time to handle data or prepare a response for the master device. A master device is not concerned with stretching as anytime it is active on the bus and not transferring data it is stretching. Any stretching done by a slave is invisible to the master software and handled by the hardware that generates SCL.

The CKP bit of the SSPCON1 register is used to control stretching in software. Any time the CKP bit is cleared, the module will wait for the SCL line to go low and then hold it. Setting CKP will release SCL and allow more communication.

#### 24.5.6.1 Normal Clock Stretching

Following an  $\overline{ACK}$  if the R/W bit of SSPSTAT is set, a read request, the slave hardware will clear CKP. This allows the slave time to update SSPBUF with data to transfer to the master. If the SEN bit of SSPCON2 is set, the slave hardware will always stretch the clock after the  $\overline{ACK}$  sequence. Once the slave is ready, CKP is set by software and communication resumes.

- Note 1: The BF bit has no effect on whether the clock will be stretched or not. This is different than previous versions of the module that would not stretch the clock, clear CKP, if SSPBUF was read before the 9th falling edge of SCL.
  - 2: Previous versions of the module did not stretch the clock for a transmission if SSPBUF was loaded before the 9th falling edge of SCL. It is now always cleared for read requests.

#### 24.5.6.2 10-bit Addressing Mode

In 10-bit Addressing mode, when the UA bit is set, the clock is always stretched. This is the only time the SCL is stretched without CKP being cleared. SCL is released immediately after a write to SSPADD.

**Note:** Previous versions of the module did not stretch the clock if the second address byte did not match.

#### 24.5.6.3 Byte NACKing


When the AHEN bit of SSPCON3 is set; CKP is cleared by hardware after the 8th falling edge of SCL for a received matching address byte. When the DHEN bit of SSPCON3 is set; CKP is cleared after the 8th falling edge of SCL for received data.

Stretching after the 8th falling edge of SCL allows the slave to look at the received address or data and decide if it wants to ACK the received data.

## 24.5.7 CLOCK SYNCHRONIZATION AND THE CKP BIT

Any time the CKP bit is cleared, the module will wait for the SCL line to go low and then hold it. However, clearing the CKP bit will not assert the SCL output low until the SCL output is already sampled low. Therefore, the CKP bit will not assert the SCL line until an external I<sup>2</sup>C master device has already asserted the SCL line. The SCL output will remain low until the CKP bit is set and all other devices on the I<sup>2</sup>C bus have released SCL. This ensures that a write to the CKP bit will not violate the minimum high time requirement for SCL (see Figure 24-22).

#### FIGURE 24-23: CLOCK SYNCHRONIZATION TIMING



### 24.5.8 GENERAL CALL ADDRESS SUPPORT


The addressing procedure for the I<sup>2</sup>C bus is such that the first byte after the Start condition usually determines which device will be the slave addressed by the master device. The exception is the general call address which can address all devices. When this address is used, all devices should, in theory, respond with an Acknowledge.

The general call address is a reserved address in the I<sup>2</sup>C protocol, defined as address 0x00. When the GCEN bit of the SSPCON2 register is set, the slave module will automatically ACK the reception of this address regardless of the value stored in SSPADD. After the slave clocks in an address of all zeros with the R/W bit clear, an interrupt is generated and slave software can read SSPBUF and respond. shows a general Figure 24-23 call reception sequence.

In 10-bit Address mode, the UA bit will not be set on the reception of the general call address. The slave will prepare to receive the second byte as data, just as it would in 7-bit mode.

If the AHEN bit of the SSPCON3 register is set, just as with any other address reception, the slave hardware will stretch the clock after the 8th falling edge of SCL. The slave must then set its ACKDT value and release the clock with communication progressing as it would normally.





#### 24.5.9 SSP MASK REGISTER

An SSP Mask (SSPMSK) register (Register 24-5) is available in I<sup>2</sup>C Slave mode as a mask for the value held in the SSPSR register during an address comparison operation. A zero ('0') bit in the SSPMSK register has the effect of making the corresponding bit of the received address a "don't care".

This register is reset to all '1's upon any Reset condition and, therefore, has no effect on standard SSP operation until written with a mask value.

The SSP Mask register is active during:

- 7-bit Address mode: address compare of A<7:1>.
- 10-bit Address mode: address compare of A<7:0>
   only. The SSP mask has no effect during the
   reception of the first (high) byte of the address.

#### 24.6 I<sup>2</sup>C Master Mode

Master mode is enabled by setting and clearing the appropriate SSPM bits in the SSPCON1 register and by setting the SSPEN bit. In Master mode, the SDA and SCK pins must be configured as inputs. The MSSP peripheral hardware will override the output driver TRIS controls when necessary to drive the pins low.

Master mode of operation is supported by interrupt generation on the detection of the Start and Stop conditions. The Stop (P) and Start (S) bits are cleared from a Reset or when the MSSP module is disabled. Control of the I<sup>2</sup>C bus may be taken when the P bit is set, or the bus is Idle.

In Firmware Controlled Master mode, user code conducts all I<sup>2</sup>C bus operations based on Start and Stop bit condition detection. Start and Stop condition detection is the only active circuitry in this mode. All other communication is done by the user software directly manipulating the SDA and SCL lines.

The following events will cause the SSP Interrupt Flag bit, SSPIF, to be set (SSP interrupt, if enabled):

- · Start condition detected
- · Stop condition detected
- · Data transfer byte transmitted/received
- · Acknowledge transmitted/received
- · Repeated Start generated
  - Note 1: The MSSP module, when configured in I<sup>2</sup>C Master mode, does not allow queueing of events. For instance, the user is not allowed to initiate a Start condition and immediately write the SSPBUF register to initiate transmission before the Start condition is complete. In this case, the SSPBUF will not be written to and the WCOL bit will be set, indicating that a write to the SSPBUF did not occur
    - 2: When in Master mode, Start/Stop detection is masked and an interrupt is generated when the SEN/PEN bit is cleared and the generation is complete.

#### 24.6.1 I<sup>2</sup>C MASTER MODE OPERATION

The master device generates all of the serial clock pulses and the Start and Stop conditions. A transfer is ended with a Stop condition or with a Repeated Start condition. Since the Repeated Start condition is also the beginning of the next serial transfer, the I<sup>2</sup>C bus will not be released.

In Master Transmitter mode, serial data is output through SDA, while SCL outputs the serial clock. The first byte transmitted contains the slave address of the receiving device (7 bits) and the Read/Write (R/W) bit. In this case, the R/W bit will be logic '0'. Serial data is transmitted 8 bits at a time. After each byte is transmitted, an Acknowledge bit is received. Start and Stop conditions are output to indicate the beginning and the end of a serial transfer.


In Master Receive mode, the first byte transmitted contains the slave address of the transmitting device (7 bits) and the R/W bit. In this case, the R/W bit will be logic '1'. Thus, the first byte transmitted is a 7-bit slave address followed by a '1' to indicate the receive bit. Serial data is received via SDA, while SCL outputs the serial clock. Serial data is received 8 bits at a time. After each byte is received, an Acknowledge bit is transmitted. Start and Stop conditions indicate the beginning and end of transmission.

A Baud Rate Generator is used to set the clock frequency output on SCL. See Section 24.7 "Baud Rate Generator" for more detail.

#### 24.6.2 CLOCK ARBITRATION

Clock arbitration occurs when the master, during any receive, transmit or Repeated Start/Stop condition, releases the SCL pin (SCL allowed to float high). When the SCL pin is allowed to float high, the Baud Rate Generator (BRG) is suspended from counting until the SCL pin is actually sampled high. When the SCL pin is sampled high, the Baud Rate Generator is reloaded with the contents of SSPADD<7:0> and begins counting. This ensures that the SCL high time will always be at least one BRG rollover count in the event that the clock is held low by an external device (Figure 24-25).

FIGURE 24-25: BAUD RATE GENERATOR TIMING WITH CLOCK ARBITRATION



#### 24.6.3 WCOL STATUS FLAG

If the user writes the SSPBUF when a Start, Restart, Stop, Receive or Transmit sequence is in progress, the WCOL is set and the contents of the buffer are unchanged (the write does not occur). Any time the WCOL bit is set it indicates that an action on SSPBUF was attempted while the module was not Idle.

Note: Because queueing of events is not allowed, writing to the lower 5 bits of SSPCON2 is disabled until the Start condition is complete.

### 24.6.4 I<sup>2</sup>C MASTER MODE START CONDITION TIMING


To initiate a Start condition, the user sets the Start Enable bit, SEN bit of the SSPCON2 register. If the SDA and SCL pins are sampled high, the Baud Rate Generator is reloaded with the contents of SSPADD<7:0> and starts its count. If SCL and SDA are both sampled high when the Baud Rate Generator times out (TBRG), the SDA pin is driven low. The action of the SDA being driven low while SCL is high is the Start condition and causes the S bit of the SSPSTAT1 register to be set. Following this, the Baud Rate Generator is reloaded with the contents of SSPADD<7:0> and resumes its count. When the Baud Rate Generator times out (TBRG), the SEN bit of the SSPCON2 reg-

ister will be automatically cleared by hardware; the Baud Rate Generator is suspended, leaving the SDA line held low and the Start condition is complete.

Note 1: If at the beginning of the Start condition, the SDA and SCL pins are already sampled low, or if during the Start condition, the SCL line is sampled low before the SDA line is driven low, a bus collision occurs, the Bus Collision Interrupt Flag, BCLIF, is set, the Start condition is aborted and the I<sup>2</sup>C module is reset into its Idle state.

**2:** The Philips I<sup>2</sup>C specification states that a bus collision cannot occur on a Start.

FIGURE 24-26: FIRST START BIT TIMING




## 24.6.5 I<sup>2</sup>C MASTER MODE REPEATED START CONDITION TIMING

A Repeated Start condition occurs when the RSEN bit of the SSPCON2 register is programmed high and the Master state machine is no longer active. When the RSEN bit is set, the SCL pin is asserted low. When the SCL pin is sampled low, the Baud Rate Generator is loaded and begins counting. The SDA pin is released (brought high) for one Baud Rate Generator count (TBRG). When the Baud Rate Generator times out, if SDA is sampled high, the SCL pin will be deasserted (brought high). When SCL is sampled high, the Baud Rate Generator is reloaded and begins counting. SDA and SCL must be sampled high for one TBRG. This action is then followed by assertion of the SDA pin (SDA = 0) for one TBRG while SCL is high. SCL is asserted low. Following this, the RSEN bit of the

SSPCON2 register will be automatically cleared and the Baud Rate Generator will not be reloaded, leaving the SDA pin held low. As soon as a Start condition is detected on the SDA and SCL pins, the S bit of the SSPSTAT register will be set. The SSPIF bit will not be set until the Baud Rate Generator has timed out.

- **Note 1:** If RSEN is programmed while any other event is in progress, it will not take effect.
  - **2:** A bus collision during the Repeated Start condition occurs if:
    - SDA is sampled low when SCL goes from low-to-high.
    - SCL goes low before SDA is asserted low. This may indicate that another master is attempting to transmit a data '1'.

FIGURE 24-27: REPEAT START CONDITION WAVEFORM



### 24.6.6 I<sup>2</sup>C MASTER MODE TRANSMISSION

Transmission of a data byte, a 7-bit address or the other half of a 10-bit address is accomplished by simply writing a value to the SSPBUF register. This action will set the Buffer Full (BF) flag bit, and allow the Baud Rate Generator to begin counting and start the next transmission. Each bit of address/data will be shifted out onto the SDA pin after the falling edge of SCL is asserted. SCL is held low for one Baud Rate Generator rollover count (TBRG). Data should be valid before SCL is released high. When the SCL pin is released high, it is held that way for TBRG. The data on the SDA pin must remain stable for that duration and some hold time after the next falling edge of SCL. After the eighth bit is shifted out (the falling edge of the eighth clock), the BF flag is cleared and the master releases SDA. This allows the slave device being addressed to respond with an ACK bit during the ninth bit time if an address match occurred, or if data was received properly. The status of ACK is written into the ACKSTAT bit on the rising edge of the ninth clock. If the master receives an Acknowledge, the Acknowledge Status bit, ACKSTAT, is cleared. If not, the bit is set. After the ninth clock, the SSPIF bit is set and the master clock (Baud Rate Generator) is suspended until the next data byte is loaded into the SSPBUF, leaving SCL low and SDA unchanged (Figure 24-27).

After the write to the SSPBUF, each bit of the address will be shifted out on the falling edge of SCL until all seven address bits and the R/W bit are completed. On the falling edge of the eighth clock, the master will release the SDA pin, allowing the slave to respond with an Acknowledge. On the falling edge of the ninth clock, the master will sample the SDA pin to see if the address was recognized by a slave. The status of the ACK bit is loaded into the ACKSTAT Status bit of the SSPCON2 register. Following the falling edge of the ninth clock transmission of the address, the SSPIF is set, the BF flag is cleared and the Baud Rate Generator is turned off until another write to the SSPBUF takes place, holding SCL low and allowing SDA to float.

#### 24.6.6.1 BF Status Flag

In Transmit mode, the BF bit of the SSPSTAT register is set when the CPU writes to SSPBUF and is cleared when all 8 bits are shifted out.

#### 24.6.6.2 WCOL Status Flag

If the user writes the SSPBUF when a transmit is already in progress (i.e., SSPSR is still shifting out a data byte), the WCOL is set and the contents of the buffer are unchanged (the write does not occur).


WCOL must be cleared by software before the next transmission.

#### 24.6.6.3 ACKSTAT Status Flag

In Transmit mode, the ACKSTAT bit of the SSPCON2 register is cleared when the slave has sent an Acknowledge ( $\overline{ACK}$  = 0) and is set when the slave does not Acknowledge ( $\overline{ACK}$  = 1). A slave sends an Acknowledge when it has recognized its address (including a general call), or when the slave has properly received its data.

#### 24.6.6.4 Typical transmit sequence:

- The user generates a Start condition by setting the SEN bit of the SSPCON2 register.
- SSPIF is set by hardware on completion of the Start.
- 3. SSPIF is cleared by software.
- 4. The MSSP module will wait the required start time before any other operation takes place.
- The user loads the SSPBUF with the slave address to transmit.
- Address is shifted out the SDA pin until all 8 bits are transmitted. Transmission begins as soon as SSPBUF is written to.
- 7. The MSSP module shifts in the ACK bit from the slave device and writes its value into the ACKSTAT bit of the SSPCON2 register.
- The MSSP module generates an interrupt at the end of the ninth clock cycle by setting the SSPIF bit.
- The user loads the SSPBUF with eight bits of data.
- Data is shifted out the SDA pin until all 8 bits are transmitted.
- 11. The MSSP module shifts in the ACK bit from the slave device and writes its value into the ACKSTAT bit of the SSPCON2 register.
- Steps 8-11 are repeated for all transmitted data bytes.
- 13. The user generates a Stop or Restart condition by setting the PEN or RSEN bits of the SSPCON2 register. Interrupt is generated once the Stop/Restart condition is complete.



### 24.6.7 I<sup>2</sup>C MASTER MODE RECEPTION

Master mode reception is enabled by programming the Receive Enable bit, RCEN bit of the SSPCON2 register.

**Note:** The MSSP module must be in an Idle state before the RCEN bit is set or the RCEN bit will be disregarded.

The Baud Rate Generator begins counting and on each rollover, the state of the SCL pin changes (high-to-low/low-to-high) and data is shifted into the SSPSR. After the falling edge of the eighth clock, the receive enable flag is automatically cleared, the contents of the SSPSR are loaded into the SSPBUF, the BF flag bit is set, the SSPIF flag bit is set and the Baud Rate Generator is suspended from counting, holding SCL low. The MSSP is now in Idle state awaiting the next command. When the buffer is read by the CPU, the BF flag bit is automatically cleared. The user can then send an Acknowledge bit at the end of reception by setting the Acknowledge Sequence Enable, ACKEN bit of the SSPCON2 register.

#### 24.6.7.1 BF Status Flag

In receive operation, the BF bit is set when an address or data byte is loaded into SSPBUF from SSPSR. It is cleared when the SSPBUF register is read.

#### 24.6.7.2 SSPOV Status Flag


In receive operation, the SSPOV bit is set when 8 bits are received into the SSPSR and the BF flag bit is already set from a previous reception.

### 24.6.7.3 WCOL Status Flag

If the user writes the SSPBUF when a receive is already in progress (i.e., SSPSR is still shifting in a data byte), the WCOL bit is set and the contents of the buffer are unchanged (the write does not occur).

#### 24.6.7.4 Typical Receive Sequence:

- The user generates a Start condition by setting the SEN bit of the SSPCON2 register.
- SSPIF is set by hardware on completion of the Start.
- 3. SSPIF is cleared by software.
- 4. User writes SSPBUF with the slave address to transmit and the R/W bit set.
- 5. Address is shifted out the SDA pin until all 8 bits are transmitted. Transmission begins as soon as SSPBUF is written to.
- 6. The MSSP module shifts in the ACK bit from the slave device and writes its value into the ACKSTAT bit of the SSPCON2 register.
- The MSSP module generates an interrupt at the end of the ninth clock cycle by setting the SSPIF bit.
- 8. User sets the RCEN bit of the SSPCON2 register and the Master clocks in a byte from the slave.
- After the 8th falling edge of SCL, SSPIF and BF are set.
- Master clears SSPIF and reads the received byte from SSPBUF, clears BF.
- 11. Master sets ACK value sent to slave in ACKDT bit of the SSPCON2 register and initiates the ACK by setting the ACKEN bit.
- Masters ACK is clocked out to the Slave and SSPIF is set.
- 13. User clears SSPIF.
- Steps 8-13 are repeated for each received byte from the slave.
- 15. Master sends a not ACK or Stop to end communication.



### 24.6.8 ACKNOWLEDGE SEQUENCE TIMING

An Acknowledge sequence is enabled by setting the Acknowledge Sequence Enable bit, ACKEN bit of the SSPCON2 register. When this bit is set, the SCL pin is pulled low and the contents of the Acknowledge data bit are presented on the SDA pin. If the user wishes to generate an Acknowledge, then the ACKDT bit should be cleared. If not, the user should set the ACKDT bit before starting an Acknowledge sequence. The Baud Rate Generator then counts for one rollover period (TBRG) and the SCL pin is deasserted (pulled high). When the SCL pin is sampled high (clock arbitration), the Baud Rate Generator counts for TBRG. The SCL pin is then pulled low. Following this, the ACKEN bit is automatically cleared, the Baud Rate Generator is turned off and the MSSP module then goes into Idle mode (Figure 24-29).

#### 24.6.8.1 WCOL Status Flag

If the user writes the SSPBUF when an Acknowledge sequence is in progress, then WCOL is set and the contents of the buffer are unchanged (the write does not occur).


#### 24.6.9 STOP CONDITION TIMING

A Stop bit is asserted on the SDA pin at the end of a receive/transmit by setting the Stop Sequence Enable bit, PEN bit of the SSPCON2 register. At the end of a receive/transmit, the SCL line is held low after the falling edge of the ninth clock. When the PEN bit is set, the master will assert the SDA line low. When the SDA line is sampled low, the Baud Rate Generator is reloaded and counts down to '0'. When the Baud Rate Generator times out, the SCL pin will be brought high and one TBRG (Baud Rate Generator rollover count) later, the SDA pin will be deasserted. When the SDA pin is sampled high while SCL is high, the P bit of the SSPSTAT register is set. A TBRG later, the PEN bit is cleared and the SSPIF bit is set (Figure 24-30).


#### 24.6.9.1 WCOL Status Flag

If the user writes the SSPBUF when a Stop sequence is in progress, then the WCOL bit is set and the contents of the buffer are unchanged (the write does not occur).

#### FIGURE 24-30: ACKNOWLEDGE SEQUENCE WAVEFORM



#### FIGURE 24-31: STOP CONDITION RECEIVE OR TRANSMIT MODE



#### 24.6.10 SLEEP OPERATION

While in Sleep mode, the I<sup>2</sup>C slave module can receive addresses or data and when an address match or complete byte transfer occurs, wake the processor from Sleep (if the MSSP interrupt is enabled).

#### **EFFECTS OF A RESET** 24.6.11

A Reset disables the MSSP module and terminates the current transfer.

#### 24.6.12 **MULTI-MASTER MODE**

In Multi-Master mode, the interrupt generation on the detection of the Start and Stop conditions allows the determination of when the bus is free. The Stop (P) and Start (S) bits are cleared from a Reset or when the MSSP module is disabled. Control of the I<sup>2</sup>C bus may be taken when the P bit of the SSPSTAT register is set. or the bus is Idle, with both the S and P bits clear. When the bus is busy, enabling the SSP interrupt will generate the interrupt when the Stop condition occurs.

In multi-master operation, the SDA line must be monitored for arbitration to see if the signal level is the expected output level. This check is performed by hardware with the result placed in the BCLIF bit.

The states where arbitration can be lost are:

- · Address Transfer
- · Data Transfer
- A Start Condition
- · A Repeated Start Condition
- · An Acknowledge Condition

#### 24.6.13 MULTI -MASTER COMMUNICATION, **BUS COLLISION AND BUS ARBITRATION**

Multi-Master mode support is achieved by bus arbitration. When the master outputs address/data bits onto the SDA pin, arbitration takes place when the master outputs a '1' on SDA, by letting SDA float high and another master asserts a '0'. When the SCL pin floats high, data should be stable. If the expected data on SDA is a '1' and the data sampled on the SDA pin is '0', then a bus collision has taken place. The master will set the Bus Collision Interrupt Flag, BCLIF, and reset the I<sup>2</sup>C port to its Idle state (Figure 24-31).

If a transmit was in progress when the bus collision occurred, the transmission is halted, the BF flag is cleared, the SDA and SCL lines are deasserted and the SSPBUF can be written to. When the user services the bus collision Interrupt Service Routine and if the I<sup>2</sup>C bus is free, the user can resume communication by asserting a Start condition.


If a Start, Repeated Start, Stop or Acknowledge condition was in progress when the bus collision occurred, the condition is aborted, the SDA and SCL lines are deasserted and the respective control bits in the SSPCON2 register are cleared. When the user services the bus collision Interrupt Service Routine and if the I<sup>2</sup>C bus is free. the user can resume communication by asserting a Start condition.

The master will continue to monitor the SDA and SCL pins. If a Stop condition occurs, the SSPIF bit will be set.

A write to the SSPBUF will start the transmission of data at the first data bit, regardless of where the transmitter left off when the bus collision occurred.

In Multi-Master mode, the interrupt generation on the detection of Start and Stop conditions allows the determination of when the bus is free. Control of the I<sup>2</sup>C bus can be taken when the P bit is set in the SSPSTAT register, or the bus is Idle and the S and P bits are cleared.





### 24.6.13.1 Bus Collision During a Start Condition

During a Start condition, a bus collision occurs if:

- a) SDA or SCL are sampled low at the beginning of the Start condition (Figure 24-32).
- b) SCL is sampled low before SDA is asserted low (Figure 24-33).

During a Start condition, both the SDA and the SCL pins are monitored.

If the SDA pin is already low, or the SCL pin is already low, then all of the following occur:

- · the Start condition is aborted,
- · the BCLIF flag is set and
- the MSSP module is reset to its Idle state (Figure 24-32).

The Start condition begins with the SDA and SCL pins deasserted. When the SDA pin is sampled high, the Baud Rate Generator is loaded and counts down. If the SCL pin is sampled low while SDA is high, a bus collision occurs because it is assumed that another master is attempting to drive a data '1' during the Start condition.

If the SDA pin is sampled low during this count, the BRG is reset and the SDA line is asserted early (Figure 24-34). If, however, a '1' is sampled on the SDA pin, the SDA pin is asserted low at the end of the BRG count. The Baud Rate Generator is then reloaded and counts down to zero; if the SCL pin is sampled as '0' during this time, a bus collision does not occur. At the end of the BRG count, the SCL pin is asserted low.

The reason that bus collision is not a factor during a Start condition is that no two bus masters can assert a Start condition at the exact same time. Therefore, one master will always assert SDA before the other. This condition does not cause a bus collision because the two masters must be allowed to arbitrate the first address following the Start condition. If the address is the same, arbitration must be allowed to continue into the data portion, Repeated Start or Stop conditions.






FIGURE 24-34: BUS COLLISION DURING START CONDITION (SCL = 0)





FIGURE 24-35: BRG RESET DUE TO SDA ARBITRATION DURING START CONDITION



### 24.6.13.2 Bus Collision During a Repeated Start Condition

During a Repeated Start condition, a bus collision occurs if:

- A low level is sampled on SDA when SCL goes from low level to high level.
- SCL goes low before SDA is asserted low, indicating that another master is attempting to transmit a data '1'.

When the user releases SDA and the pin is allowed to float high, the BRG is loaded with SSPADD and counts down to zero. The SCL pin is then deasserted and when sampled high, the SDA pin is sampled.

If SDA is low, a bus collision has occurred (i.e., another master is attempting to transmit a data '0', Figure 24-35). If SDA is sampled high, the BRG is reloaded and begins counting. If SDA goes from high-to-low before the BRG times out, no bus collision occurs because no two masters can assert SDA at exactly the same time.

If SCL goes from high-to-low before the BRG times out and SDA has not already been asserted, a bus collision occurs. In this case, another master is attempting to transmit a data '1' during the Repeated Start condition, see Figure 24-36.

If, at the end of the BRG time-out, both SCL and SDA are still high, the SDA pin is driven low and the BRG is reloaded and begins counting. At the end of the count, regardless of the status of the SCL pin, the SCL pin is driven low and the Repeated Start condition is complete.

FIGURE 24-36: BUS COLLISION DURING A REPEATED START CONDITION (CASE 1)





FIGURE 24-37: BUS COLLISION DURING REPEATED START CONDITION (CASE 2)




### 24.6.13.3 Bus Collision During a Stop Condition

Bus collision occurs during a Stop condition if:

- After the SDA pin has been deasserted and allowed to float high, SDA is sampled low after the BRG has timed out.
- After the SCL pin is deasserted, SCL is sampled low before SDA goes high.

The Stop condition begins with SDA asserted low. When SDA is sampled low, the SCL pin is allowed to float. When the pin is sampled high (clock arbitration), the Baud Rate Generator is loaded with SSPADD and counts down to 0. After the BRG times out, SDA is sampled. If SDA is sampled low, a bus collision has occurred. This is due to another master attempting to drive a data '0' (Figure 24-37). If the SCL pin is sampled low before SDA is allowed to float high, a bus collision occurs. This is another case of another master attempting to drive a data '0' (Figure 24-38).

FIGURE 24-38: BUS COLLISION DURING A STOP CONDITION (CASE 1)








TABLE 24-3: SUMMARY OF REGISTERS ASSOCIATED WITH I<sup>2</sup>C™ OPERATION

| Name    | Bit 7                                 | Bit 6   | Bit 5           | Bit 4  | Bit 3  | Bit 2  | Bit 1  | Bit 0                 | Reset<br>Values on<br>Page: |
|---------|---------------------------------------|---------|-----------------|--------|--------|--------|--------|-----------------------|-----------------------------|
| INTCON  | GIE                                   | PEIE    | TMR0IE          | INTE   | IOCIE  | TMR0IF | INTF   | IOCIF                 | 98                          |
| PIE1    | TMR1GIE                               | ADIE    | RCIE            | TXIE   | SSPIE  | CCP1IE | TMR2IE | TMR1IE                | 99                          |
| PIE2    | OSFIE                                 | C2IE    | C1IE            | EEIE   | BCLIE  | _      | _      | CCP2IE <sup>(1)</sup> | 100                         |
| PIR1    | TMR1GIF                               | ADIF    | RCIF            | TXIF   | SSPIF  | CCP1IF | TMR2IF | TMR1IF                | 102                         |
| PIR2    | OSFIF                                 | C2IF    | C1IF            | EEIF   | BCLIF  | _      | _      | CCP2IF <sup>(1)</sup> | 103                         |
| TRISC   | TRISC7                                | TRISC6  | TRISC5          | TRISC4 | TRISC3 | TRISC2 | TRISC1 | TRISC0                | 142                         |
| SSPADD  | ADD<7:0>                              |         |                 |        |        |        |        |                       |                             |
| SSPBUF  | MSSP Receive Buffer/Transmit Register |         |                 |        |        |        |        |                       | 243*                        |
| SSPCON1 | WCOL                                  | SSPOV   | SSPEN           | CKP    |        | 287    |        |                       |                             |
| SSPCON2 | GCEN                                  | ACKSTAT | ACKDT           | ACKEN  | RCEN   | PEN    | RSEN   | SEN                   | 288                         |
| SSPCON3 | ACKTIM                                | PCIE    | SCIE            | BOEN   | SDAHT  | SBCDE  | AHEN   | DHEN                  | 289                         |
| SSPMSK  | MSK<7:0>                              |         |                 |        |        |        |        |                       |                             |
| SSPSTAT | SMP                                   | CKE     | D/ <del>A</del> | Р      | S      | R/W    | UA     | BF                    | 286                         |

**Legend:** — = unimplemented location, read as '0'. Shaded cells are not used by the MSSP module in  $I^2C^{TM}$  mode.

\* Page provides register information.

**Note 1:** PIC16F1934 only.

#### 24.7 Baud Rate Generator

The MSSP module has a Baud Rate Generator available for clock generation in both  $I^2C$  and SPI Master modes. The Baud Rate Generator (BRG) reload value is placed in the SSPADD register (Register 24-6). When a write occurs to SSPBUF, the Baud Rate Generator will automatically begin counting down.

Once the given operation is complete, the internal clock will automatically stop counting and the clock pin will remain in its last state.

An internal signal "Reload" in Figure 24-39 triggers the value from SSPADD to be loaded into the BRG counter. This occurs twice for each oscillation of the module


clock line. The logic dictating when the reload signal is asserted depends on the mode the MSSP is being operated in.

Table 24-4 demonstrates clock rates based on instruction cycles and the BRG value loaded into SSPADD.

#### **EQUATION 24-1:**

$$FCLOCK = \frac{FOSC}{(SSPxADD + 1)(4)}$$

FIGURE 24-40: BAUD RATE GENERATOR BLOCK DIAGRAM



**Note:** Values of 0x00, 0x01 and 0x02 are not valid for SSPADD when used as a Baud Rate Generator for I<sup>2</sup>C. This is an implementation limitation.

TABLE 24-4: MSSP CLOCK RATE W/BRG

| Fosc   | Fcy   | BRG Value | FCLOCK<br>(2 Rollovers of BRG) |  |
|--------|-------|-----------|--------------------------------|--|
| 32 MHz | 8 MHz | 13h       | 400 kHz <sup>(1)</sup>         |  |
| 32 MHz | 8 MHz | 19h       | 308 kHz                        |  |
| 32 MHz | 8 MHz | 4Fh       | 100 kHz                        |  |
| 16 MHz | 4 MHz | 09h       | 400 kHz <sup>(1)</sup>         |  |
| 16 MHz | 4 MHz | 0Ch       | 308 kHz                        |  |
| 16 MHz | 4 MHz | 27h       | 100 kHz                        |  |
| 4 MHz  | 1 MHz | 09h       | 100 kHz                        |  |

**Note 1:** The I<sup>2</sup>C interface does not conform to the 400 kHz I<sup>2</sup>C specification (which applies to rates greater than 100 kHz) in all details, but may be used with care where higher rates are required by the application.

#### REGISTER 24-1: SSPSTAT: SSP STATUS REGISTER

| R/W-0/0 | R/W-0/0 | R-0/0           | R-0/0 | R-0/0 | R-0/0 | R-0/0 | R-0/0 |
|---------|---------|-----------------|-------|-------|-------|-------|-------|
| SMP     | CKE     | D/ <del>A</del> | Р     | S     | R/W   | UA    | BF    |
| bit 7   |         |                 |       |       |       |       | bit 0 |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n/n = Value at POR and BOR/Value at all other Resets u = Bit is unchanged x = Bit is unknown

'1' = Bit is set '0' = Bit is cleared

bit 7 SMP: SPI Data Input Sample bit

1 = Input data sampled at end of data output time

0 = Input data sampled at middle of data output time

SPI Slave mode:

SMP must be cleared when SPI is used in Slave mode

In I<sup>2</sup>C Master or Slave mode:

1 = Slew rate control disabled for standard speed mode (100 kHz and 1 MHz)

0 = Slew rate control enabled for high speed mode (400 kHz)

bit 6 CKE: SPI Clock Edge Select bit (SPI mode only)

In SPI Master or Slave mode:

1 = Transmit occurs on transition from active to Idle clock state

0 = Transmit occurs on transition from Idle to active clock state

In I<sup>2</sup>C™ mode only:

1 = Enable input logic so that thresholds are compliant with SMBus specification

0 = Disable SMBus specific inputs

bit 5 **D/A**: Data/Address bit (I<sup>2</sup>C mode only)

1 = Indicates that the last byte received or transmitted was data

0 = Indicates that the last byte received or transmitted was address

bit 4 P: Stop bit

(I<sup>2</sup>C mode only. This bit is cleared when the MSSP module is disabled, SSPEN is cleared.)

1 = Indicates that a Stop bit has been detected last (this bit is '0' on Reset)

0 = Stop bit was not detected last

S: Start bit bit 3

(I<sup>2</sup>C mode only. This bit is cleared when the MSSP module is disabled, SSPEN is cleared.)

1 = Indicates that a Start bit has been detected last (this bit is '0' on Reset)

0 = Start bit was not detected last

**R/W**: Read/Write bit information (I<sup>2</sup>C mode only) bit 2

This bit holds the  $R/\overline{W}$  bit information following the last address match. This bit is only valid from the address match

to the next Start bit, Stop bit, or not ACK bit.

In I<sup>2</sup>C Slave mode:

1 = Read

0 = Write

In I2C Master mode:

1 = Transmit is in progress

0 = Transmit is not in progress

OR-ing this bit with SEN, RSEN, PEN, RCEN or ACKEN will indicate if the MSSP is in Idle mode.

**UA:** Update Address bit (10-bit I<sup>2</sup>C mode only) bit 1

1 = Indicates that the user needs to update the address in the SSPADD register

0 = Address does not need to be updated

bit 0 BF: Buffer Full Status bit

Receive (SPI and I<sup>2</sup>C modes):

1 = Receive complete, SSPBUF is full

0 = Receive not complete, SSPBUF is empty

Transmit (I<sup>2</sup>C mode only):

1 = Data transmit in progress (does not include the ACK and Stop bits), SSPBUF is full

0 = Data transmit complete (does not include the ACK and Stop bits), SSPBUF is empty

#### **REGISTER 24-2:** SSPCON1: SSP CONTROL REGISTER 1

| R/C/HS-0/0 | R/C/HS-0/0 | R/W-0/0 | R/W-0/0 | R/W-0/0   | R/W-0/0 | R/W-0/0 | R/W-0/0 |
|------------|------------|---------|---------|-----------|---------|---------|---------|
| WCOL       | SSPOV      | SSPEN   | CKP     | SSPM<3:0> |         |         |         |
| bit 7      |            |         |         |           |         |         | bit 0   |

Legend: R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets '1' = Bit is set '0' = Bit is cleared HS = Bit is set by hardware C = User cleared

bit 7 WCOL: Write Collision Detect bit

Master mode:

1 = A write to the SSPBUF register was attempted while the I<sup>2</sup>C conditions were not valid for a transmission to be started

0 = No collision

Slave mode:

1 = The SSPBUF register is written while it is still transmitting the previous word (must be cleared in software)

0 = No collision

SSPOV: Receive Overflow Indicator bit(1) bit 6

In SPI mode:

A new byte is received while the SSPBUF register is still holding the previous data. In case of overflow, the data in SSPSR is lost. Overflow can only occur in Slave mode. In Slave mode, the user must read the SSPBUF, even if only transmitting data, to avoid setting overflow. In Master mode, the overflow bit is not set since each new reception (and transmission) is initiated by writing to the SSPBUF register (must be cleared in software).

No overflow

In 12C mode:

1 = A byte is received while the SSPBUF register is still holding the previous byte. SSPOV is a "don't care" in Transmit mode

No overflow

bit 5 SSPEN: Synchronous Serial Port Enable bit

In both modes, when enabled, these pins must be properly configured as input or output

In SPI mode:

1 = Enables serial port and configures SCK, SDO, SDI and SS as the source of the serial port pins<sup>(2)</sup>

Disables serial port and configures these pins as I/O port pins

Enables the serial port and configures the SDA and SCL pins as the source of the serial port pins (3)

0 = Disables serial port and configures these pins as I/O port pins

bit 4 CKP: Clock Polarity Select bit

In SPI mode:
1 = Idle state for clock is a high level

0 = Idle state for clock is a low level

In I2C Slave mode:

1 = Enable clock

0 = Holds clock low (clock stretch). (Used to ensure data setup time.)

In I<sup>2</sup>C Master mode: Unused in this mode

bit 3-0 SSPM<3:0>: Synchronous Serial Port Mode Select bits

0000 = SPI Master mode, clock = Fosc/4

0001 = SPI Master mode, clock = Fosc/16

0010 = SPI Master mode, clock = Fosc/64

0011 = SPI Master mode, clock = TMR2 output/2

0100 = SPI Slave mode, clock = SCK pin,  $\overline{SS}$  pin control enabled

0101 = SPI Slave mode, clock = SCK pin, SS pin control disabled, SS can be used as I/O pin

 $0110 = I^2C$  Slave mode, 7-bit address

 $0111 = I^2C$  Slave mode, 10-bit address

1000 =  $I^2$ C Master mode, clock = Fosc /  $(4 * (SSPADD+1))^{(4)}$ 

1001 = Reserved

1010 = SPI Master mode, clock = Fosc/(4 \* (SSPADD+1))(5)

1011 = I<sup>2</sup>C firmware controlled Master mode (Slave Idle)

1100 = Reserved

1101 = Reserved

1110 = I<sup>2</sup>C Slave mode, 7-bit address with Start and Stop bit interrupts enabled

1111 = I<sup>2</sup>C Slave mode, 10-bit address with Start and Stop bit interrupts enabled

Note 1: In Master mode, the overflow bit is not set since each new reception (and transmission) is initiated by writing to the SSPBUF register.

- 2: When enabled, these pins must be properly configured as input or output.
- When enabled, the SDA and SCL pins must be configured as inputs. 3:
- 4: SSPADD values of 0, 1 or 2 are not supported for I<sup>2</sup>C Mode.
- SSPADD value of '0' is not supported. Use SSPM = 0000 instead.

#### REGISTER 24-3: SSPCON2: SSP CONTROL REGISTER 2

| R/W-0/0 | R-0/0   | R/W-0/0 | R/S/HS-0/0 | R/S/HS-0/0 | R/S/HS-0/0 | R/S/HS-0/0 | R/W/HS-0/0 |
|---------|---------|---------|------------|------------|------------|------------|------------|
| GCEN    | ACKSTAT | ACKDT   | ACKEN      | RCEN       | PEN        | RSEN       | SEN        |
| bit 7   |         |         |            |            |            |            | bit 0      |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared HC = Cleared by hardware S = User set

bit 7 **GCEN:** General Call Enable bit (in I<sup>2</sup>C Slave mode only)

1 = Enable interrupt when a general call address (0x00 or 00h) is received in the SSPSR

0 = General call address disabled

bit 6 ACKSTAT: Acknowledge Status bit (in I<sup>2</sup>C mode only)

1 = Acknowledge was not received0 = Acknowledge was received

bit 5 **ACKDT:** Acknowledge Data bit (in I<sup>2</sup>C mode only)

In Receive mode:

Value transmitted when the user initiates an Acknowledge sequence at the end of a receive

1 = Not Acknowledge0 = Acknowledge

bit 4 **ACKEN:** Acknowledge Sequence Enable bit (in I<sup>2</sup>C Master mode only)

In Master Receive mode:

1 = Initiate Acknowledge sequence on SDA and SCL pins, and transmit ACKDT data bit. Automatically cleared by hardware.

0 = Acknowledge sequence Idle

bit 3 RCEN: Receive Enable bit (in I<sup>2</sup>C Master mode only)

1 = Enables Receive mode for I<sup>2</sup>C

0 = Receive Idle

bit 2 **PEN:** Stop Condition Enable bit (in I<sup>2</sup>C Master mode only)

SCKMSSP Release Control:

1 = Initiate Stop condition on SDA and SCL pins. Automatically cleared by hardware.

0 = Stop condition Idle

bit 1 **RSEN:** Repeated Start Condition Enabled bit (in I<sup>2</sup>C Master mode only)

1 = Initiate Repeated Start condition on SDA and SCL pins. Automatically cleared by hardware.

0 = Repeated Start condition Idle

bit 0 **SEN:** Start Condition Enabled bit (in I<sup>2</sup>C Master mode only)

In Master mode:

1 = Initiate Start condition on SDA and SCL pins. Automatically cleared by hardware.

0 = Start condition Idle

In Slave mode:

1 = Clock stretching is enabled for both slave transmit and slave receive (stretch enabled)

0 = Clock stretching is disabled

**Note 1:** For bits ACKEN, RCEN, PEN, RSEN, SEN: If the I<sup>2</sup>C module is not in the Idle mode, this bit may not be set (no spooling) and the SSPBUF may not be written (or writes to the SSPBUF are disabled).

### REGISTER 24-4: SSPCON3: SSP CONTROL REGISTER 3

| R-0/0  | R/W-0/0 | R/W-0/0 | R/W-0/0 | R/W-0/0 | R/W-0/0 R/W-0/0 |      | R/W-0/0 |
|--------|---------|---------|---------|---------|-----------------|------|---------|
| ACKTIM | PCIE    | SCIE    | BOEN    | SDAHT   | SBCDE           | AHEN | DHEN    |
| bit 7  |         |         |         |         |                 |      | bit 0   |

Legend:R = Readable bitW = Writable bitU = Unimplemented bit, read as '0'u = Bit is unchangedx = Bit is unknown-n/n = Value at POR and BOR/Value at all other Resets'1' = Bit is set'0' = Bit is cleared

bit 7 ACKTIM: Acknowledge Time Status bit (I<sup>2</sup>C mode only)<sup>(3)</sup>

1 = Indicates the I<sup>2</sup>C bus is in an Acknowledge sequence, set on 8<sup>TH</sup> falling edge of SCL clock

0 = Not an Acknowledge sequence, cleared on 9<sup>TH</sup> rising edge of SCL clock

bit 6 **PCIE**: Stop Condition Interrupt Enable bit (I<sup>2</sup>C mode only)

1 = Enable interrupt on detection of Stop condition

0 = Stop detection interrupts are disabled<sup>(2)</sup>

bit 5 SCIE: Start Condition Interrupt Enable bit (I<sup>2</sup>C mode only)

1 = Enable interrupt on detection of Start or Restart conditions

0 = Start detection interrupts are disabled<sup>(2)</sup>

bit 4 **BOEN:** Buffer Overwrite Enable bit

In SPI Slave mode: (1)

1 = SSPBUF updates every time that a new data byte is shifted in ignoring the BF bit

0 = If new byte is received with BF bit of the SSPSTAT register already set, SSPOV bit of the SSPCON1 register is set, and the buffer is not updated

### In I<sup>2</sup>C Master and SPI Master mode:

This bit is ignored.

## In I<sup>2</sup>C Slave mode:

- 1 = SSPBUF is updated and  $\overline{ACK}$  is generated for a received address/data byte, ignoring the state of the SSPOV bit only if the BF bit = 0.
- 0 = SSPBUF is only updated when SSPOV is clear
- bit 3 **SDAHT:** SDA Hold Time Selection bit (I<sup>2</sup>C mode only)
  - 1 = Minimum of 300 ns hold time on SDA after the falling edge of SCL
  - 0 = Minimum of 100 ns hold time on SDA after the falling edge of SCL
- bit 2 SBCDE: Slave Mode Bus Collision Detect Enable bit (I<sup>2</sup>C Slave mode only)

If on the rising edge of SCL, SDA is sampled low when the module is outputting a high state, the BCLIF bit of the PIR2 register is set, and bus goes Idle

- 1 = Enable slave bus collision interrupts
- 0 = Slave bus collision interrupts are disabled
- bit 1 AHEN: Address Hold Enable bit (I<sup>2</sup>C Slave mode only)
  - 1 = Following the 8th falling edge of SCL for a matching received address byte; CKP bit of the SSPCON1 register will be cleared and the SCL will be held low.
  - 0 = Address holding is disabled
- bit 0 **DHEN:** Data Hold Enable bit (I<sup>2</sup>C Slave mode only)
  - 1 = Following the 8th falling edge of SCL for a received data byte; slave hardware clears the CKP bit of the SSPCON1 register and SCL is held low.
  - 0 = Data holding is disabled
- **Note 1:** For daisy-chained SPI operation; allows the user to ignore all but the last received byte. SSPOV is still set when a new byte is received and BF = 1, but hardware continues to write the most recent byte to SSPBUF.
  - 2: This bit has no effect in Slave modes that Start and Stop condition detection is explicitly listed as enabled.
  - The ACKTIM Status bit is only active when the AHEN bit or DHEN bit is set.

### **REGISTER 24-5: SSPMSK: SSP MASK REGISTER**

| R/W-1/1 |
|---------|---------|---------|---------|---------|---------|---------|---------|
|         |         |         | MSK     | <7:0>   |         |         |         |
| bit 7   |         |         |         |         |         |         | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-1 **MSK<7:1>:** Mask bits

1 = The received address bit n is compared to SSPADD<n> to detect I<sup>2</sup>C address match

0 = The received address bit n is not used to detect I<sup>2</sup>C address match

bit 0 MSK<0>: Mask bit for I<sup>2</sup>C Slave mode, 10-bit Address

 $I^{2}C$  Slave mode, 10-bit address (SSPM<3:0> = 0111 or 1111):

1 = The received address bit 0 is compared to SSPADD<0> to detect  $I^2C$  address match

0 = The received address bit 0 is not used to detect I<sup>2</sup>C address match

I<sup>2</sup>C Slave mode, 7-bit address, the bit is ignored

## REGISTER 24-6: SSPADD: MSSP ADDRESS AND BAUD RATE REGISTER (I<sup>2</sup>C MODE)

| R/W-0/0 |
|---------|---------|---------|---------|---------|---------|---------|---------|
|         |         |         | ADD<    | <7:0>   |         |         |         |
| bit 7   |         |         |         |         |         |         | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

#### Master mode:

bit 7-0 ADD<7:0>: Baud Rate Clock Divider bits

SCL pin clock period = ((ADD<7:0> + 1)\*4)/Fosc

### 10-Bit Slave mode — Most Significant Address byte:

bit 7-3 Not used: Unused for Most Significant Address byte. Bit state of this register is a "don't care". Bit pat-

tern sent by master is fixed by I<sup>2</sup>C specification and must be equal to '11110'. However, those bits are

compared by hardware and are not affected by the value in this register.

bit 2-1 ADD<2:1>: Two Most Significant bits of 10-bit address

bit 0 **Not used:** Unused in this mode. Bit state is a "don't care".

#### <u>10-Bit Slave mode — Least Significant Address byte:</u>

bit 7-0 ADD<7:0>: Eight Least Significant bits of 10-bit address

## 7-Bit Slave mode:

bit 7-1 **ADD<7:1>:** 7-bit address

bit 0 **Not used:** Unused in this mode. Bit state is a "don't care".

## 25.0 **ENHANCED UNIVERSAL SYNCHRONOUS ASYNCHRONOUS RECEIVER** TRANSMITTER (EUSART)

The Enhanced Universal Synchronous Asynchronous Receiver Transmitter (EUSART) module is a serial I/O communications peripheral. It contains all the clock generators, shift registers and data buffers necessary to perform an input or output serial data transfer independent of device program execution. The EUSART, also known as a Serial Communications Interface (SCI), can be configured as a full-duplex asynchronous system or half-duplex synchronous system. Full-Duplex mode is useful communications with peripheral systems, such as CRT terminals and personal computers. Half-Duplex Synchronous mode is intended for communications with peripheral devices, such as A/D or D/A integrated circuits, serial EEPROMs or other microcontrollers. These devices typically do not have internal clocks for baud rate generation and require the external clock signal provided by a master synchronous device.

The EUSART module includes the following capabilities:

- Full-duplex asynchronous transmit and receive
- · Two-character input buffer
- · One-character output buffer
- · Programmable 8-bit or 9-bit character length
- · Address detection in 9-bit mode
- · Input buffer overrun error detection
- Received character framing error detection
- · Half-duplex synchronous master
- · Half-duplex synchronous slave
- · Programmable clock polarity in synchronous modes
- · Sleep operation

The EUSART module implements the following additional features, making it ideally suited for use in Local Interconnect Network (LIN) bus systems:

- · Automatic detection and calibration of the baud rate
- · Wake-up on Break reception
- · 13-bit Break character transmit

Block diagrams of the EUSART transmitter and receiver are shown in Figure 25-1 and Figure 25-2.

**FIGURE 25-1: EUSART TRANSMIT BLOCK DIAGRAM** 





FIGURE 25-2: EUSART RECEIVE BLOCK DIAGRAM



The operation of the EUSART module is controlled through three registers:

- Transmit Status and Control (TXSTA)
- · Receive Status and Control (RCSTA)
- Baud Rate Control (BAUDCON)

These registers are detailed in Register 25-1, Register 25-2 and Register 25-3, respectively.

When the receiver or transmitter section is not enabled then the corresponding RX or TX pin may be used for general purpose input and output.

## 25.1 EUSART Asynchronous Mode

The EUSART transmits and receives data using the standard non-return-to-zero (NRZ) format. NRZ is implemented with two levels: a VOH mark state which represents a '1' data bit, and a Vol space state which represents a '0' data bit. NRZ refers to the fact that consecutively transmitted data bits of the same value stay at the output level of that bit without returning to a neutral level between each bit transmission. An NRZ transmission port idles in the mark state. Each character transmission consists of one Start bit followed by eight or nine data bits and is always terminated by one or more Stop bits. The Start bit is always a space and the Stop bits are always marks. The most common data format is 8 bits. Each transmitted bit persists for a period of 1/(Baud Rate). An on-chip dedicated 8-bit/16-bit Baud Rate Generator is used to derive standard baud rate frequencies from the system oscillator. See Table 25-5 for examples of baud rate configurations.

The EUSART transmits and receives the LSb first. The EUSART's transmitter and receiver are functionally independent, but share the same data format and baud rate. Parity is not supported by the hardware, but can be implemented in software and stored as the ninth data bit.

## 25.1.1 EUSART ASYNCHRONOUS TRANSMITTER

The EUSART transmitter block diagram is shown in Figure 25-1. The heart of the transmitter is the serial Transmit Shift Register (TSR), which is not directly accessible by software. The TSR obtains its data from the transmit buffer, which is the TXREG register.

## 25.1.1.1 Enabling the Transmitter

The EUSART transmitter is enabled for asynchronous operations by configuring the following three control bits:

- TXEN = 1
- SYNC = 0
- SPEN = 1

All other EUSART control bits are assumed to be in their default state.

Setting the TXEN bit of the TXSTA register enables the transmitter circuitry of the EUSART. Clearing the SYNC bit of the TXSTA register configures the EUSART for asynchronous operation. Setting the SPEN bit of the RCSTA register enables the EUSART and automatically configures the TX/CK I/O pin as an output. If the TX/CK pin is shared with an analog peripheral, the analog I/O function must be disabled by clearing the corresponding ANSEL bit.

**Note 1:** The TXIF Transmitter Interrupt flag is set when the TXEN enable bit is set.

### 25.1.1.2 Transmitting Data

A transmission is initiated by writing a character to the TXREG register. If this is the first character, or the previous character has been completely flushed from the TSR, the data in the TXREG is immediately transferred to the TSR register. If the TSR still contains all or part of a previous character, the new character data is held in the TXREG until the Stop bit of the previous character has been transmitted. The pending character in the TXREG is then transferred to the TSR in one Tcy immediately following the Stop bit transmission. The transmission of the Start bit, data bits and Stop bit sequence commences immediately following the transfer of the data to the TSR from the TXREG.

### 25.1.1.3 Transmit Data Polarity

The polarity of the transmit data can be controlled with the SCKP bit of the BAUDCON register. The default state of this bit is '0' which selects high true transmit Idle and data bits. Setting the SCKP bit to '1' will invert the transmit data resulting in low true Idle and data bits. The SCKP bit controls transmit data polarity in Asynchronous mode only. In Synchronous mode, the SCKP bit has a different function. See Section 25.4.1.2 "Clock Polarity".

### 25.1.1.4 Transmit Interrupt Flag

The TXIF interrupt flag bit of the PIR1 register is set whenever the EUSART transmitter is enabled and no character is being held for transmission in the TXREG. In other words, the TXIF bit is only clear when the TSR is busy with a character and a new character has been queued for transmission in the TXREG. The TXIF flag bit is not cleared immediately upon writing TXREG. TXIF becomes valid in the second instruction cycle following the write execution. Polling TXIF immediately following the TXREG write will return invalid results. The TXIF bit is read-only, it cannot be set or cleared by software.

The TXIF interrupt can be enabled by setting the TXIE interrupt enable bit of the PIE1 register. However, the TXIF flag bit will be set whenever the TXREG is empty, regardless of the state of TXIE enable bit.

To use interrupts when transmitting data, set the TXIE bit only when there is more data to send. Clear the TXIE interrupt enable bit upon writing the last character of the transmission to the TXREG.

#### 25.1.1.5 TSR Status

The TRMT bit of the TXSTA register indicates the status of the TSR register. This is a read-only bit. The TRMT bit is set when the TSR register is empty and is cleared when a character is transferred to the TSR register from the TXREG. The TRMT bit remains clear until all bits have been shifted out of the TSR register. No interrupt logic is tied to this bit, so the user has to poll this bit to determine the TSR status.

**Note:** The TSR register is not mapped in data memory, so it is not available to the user.

## 25.1.1.6 Transmitting 9-Bit Characters


The EUSART supports 9-bit character transmissions. When the TX9 bit of the TXSTA register is set, the EUSART will shift 9 bits out for each character transmitted. The TX9D bit of the TXSTA register is the ninth, and Most Significant, data bit. When transmitting 9-bit data, the TX9D data bit must be written before writing the 8 Least Significant bits into the TXREG. All nine bits of data will be transferred to the TSR shift register immediately after the TXREG is written.

A special 9-bit Address mode is available for use with multiple receivers. See **Section 25.1.2.7 "Address Detection"** for more information on the address mode.

### 25.1.1.7 Asynchronous Transmission Set-up:

- Initialize the SPBRGH, SPBRGL register pair and the BRGH and BRG16 bits to achieve the desired baud rate (see Section 25.3 "EUSART Baud Rate Generator (BRG)").
- Enable the asynchronous serial port by clearing the SYNC bit and setting the SPEN bit.
- If 9-bit transmission is desired, set the TX9 control bit. A set ninth data bit will indicate that the 8
  Least Significant data bits are an address when the receiver is set for address detection.
- Set SCKP bit if inverted transmit is desired.
- Enable the transmission by setting the TXEN control bit. This will cause the TXIF interrupt bit to be set.
- If interrupts are desired, set the TXIE interrupt enable bit of the PIE1 register. An interrupt will occur immediately provided that the GIE and PEIE bits of the INTCON register are also set.
- 7. If 9-bit transmission is selected, the ninth bit should be loaded into the TX9D data bit.
- Load 8-bit data into the TXREG register. This will start the transmission.





## FIGURE 25-4: ASYNCHRONOUS TRANSMISSION (BACK-TO-BACK)




TABLE 25-1: SUMMARY OF REGISTERS ASSOCIATED WITH ASYNCHRONOUS TRANSMISSION

| Name    | Bit 7    | Bit 6                        | Bit 5  | Bit 4  | Bit 3  | Bit 2  | Bit 1  | Bit 0  | Register on Page |  |
|---------|----------|------------------------------|--------|--------|--------|--------|--------|--------|------------------|--|
| BAUDCON | ABDOVF   | RCIDL                        | _      | SCKP   | BRG16  | _      | WUE    | ABDEN  | 302              |  |
| INTCON  | GIE      | PEIE                         | TMR0IE | INTE   | IOCIE  | TMR0IF | INTF   | IOCIF  | 98               |  |
| PIE1    | TMR1GIE  | ADIE                         | RCIE   | TXIE   | SSPIE  | CCP1IE | TMR2IE | TMR1IE | 99               |  |
| PIR1    | TMR1GIF  | ADIF                         | RCIF   | TXIF   | SSPIF  | CCP1IF | TMR2IF | TMR1IF | 102              |  |
| RCSTA   | SPEN     | RX9                          | SREN   | CREN   | ADDEN  | FERR   | OERR   | RX9D   | 301              |  |
| SPBRGL  |          |                              |        | BRG    | <7:0>  |        |        |        | 303*             |  |
| SPBRGH  |          |                              |        | BRG<   | :15:8> |        |        |        | 303*             |  |
| TRISC   | TRISC7   | TRISC6                       | TRISC5 | TRISC4 | TRISC3 | TRISC2 | TRISC1 | TRISC0 | 142              |  |
| TXREG   | EUSART T | JSART Transmit Data Register |        |        |        |        |        |        |                  |  |
| TXSTA   | CSRC     | TX9                          | TXEN   | SYNC   | SENDB  | BRGH   | TRMT   | TX9D   | 300              |  |

**Legend:** — = unimplemented location, read as '0'. Shaded cells are not used for Asynchronous Transmission.

<sup>\*</sup> Page provides register information.

## 25.1.2 EUSART ASYNCHRONOUS RECEIVER

The Asynchronous mode is typically used in RS-232 systems. The receiver block diagram is shown in Figure 25-2. The data is received on the RX/DT pin and drives the data recovery block. The data recovery block is actually a high-speed shifter operating at 16 times the baud rate, whereas the serial Receive Shift Register (RSR) operates at the bit rate. When all 8 or 9 bits of the character have been shifted in, they are immediately transferred to a two character First-In-First-Out (FIFO) memory. The FIFO buffering allows reception of two complete characters and the start of a third character before software must start servicing the EUSART receiver. The FIFO and RSR registers are not directly accessible by software. Access to the received data is via the RCREG register.

## 25.1.2.1 Enabling the Receiver

The EUSART receiver is enabled for asynchronous operation by configuring the following three control bits:

- CREN = 1
- SYNC = 0
- SPEN = 1

All other EUSART control bits are assumed to be in their default state.

Setting the CREN bit of the RCSTA register enables the receiver circuitry of the EUSART. Clearing the SYNC bit of the TXSTA register configures the EUSART for asynchronous operation. Setting the SPEN bit of the RCSTA register enables the EUSART. The programmer must set the corresponding TRIS bit to configure the RX/DT I/O pin as an input.

Note 1: If the RX/DT function is on an analog pin, the corresponding ANSEL bit must be cleared for the receiver to function.

### 25.1.2.2 Receiving Data

The receiver data recovery circuit initiates character reception on the falling edge of the first bit. The first bit, also known as the Start bit, is always a zero. The data recovery circuit counts one-half bit time to the center of the Start bit and verifies that the bit is still a zero. If it is not a zero then the data recovery circuit aborts character reception, without generating an error, and resumes looking for the falling edge of the Start bit. If the Start bit zero verification succeeds then the data recovery circuit counts a full bit time to the center of the next bit. The bit is then sampled by a majority detect circuit and the resulting '0' or '1' is shifted into the RSR. This repeats until all data bits have been sampled and shifted into the RSR. One final bit time is measured and the level sampled. This is the Stop bit, which is always a '1'. If the data recovery circuit samples a '0' in the Stop bit position then a framing error is set for this character, otherwise the framing error is cleared for this character. See Section 25.1.2.4 "Receive Framing **Error**" for more information on framing errors.

Immediately after all data bits and the Stop bit have been received, the character in the RSR is transferred to the EUSART receive FIFO and the RCIF interrupt flag bit of the PIR1 register is set. The top character in the FIFO is transferred out of the FIFO by reading the RCREG register.

Note: If the receive FIFO is overrun, no additional characters will be received until the overrun condition is cleared. See Section 25.1.2.5 
"Receive Overrun Error" for more information on overrun errors.

### 25.1.2.3 Receive Interrupts

The RCIF interrupt flag bit of the PIR1 register is set whenever the EUSART receiver is enabled and there is an unread character in the receive FIFO. The RCIF interrupt flag bit is read-only, it cannot be set or cleared by software.

RCIF interrupts are enabled by setting all of the following bits:

- · RCIE interrupt enable bit of the PIE1 register
- PEIE, Peripheral Interrupt Enable bit of the INTCON register
- GIE, Global Interrupt Enable bit of the INTCON register

The RCIF interrupt flag bit will be set when there is an unread character in the FIFO, regardless of the state of interrupt enable bits.

## 25.1.2.4 Receive Framing Error

Each character in the receive FIFO buffer has a corresponding framing error Status bit. A framing error indicates that a Stop bit was not seen at the expected time. The framing error status is accessed via the FERR bit of the RCSTA register. The FERR bit represents the status of the top unread character in the receive FIFO. Therefore, the FERR bit must be read before reading the RCREG.

The FERR bit is read-only and only applies to the top unread character in the receive FIFO. A framing error (FERR = 1) does not preclude reception of additional characters. It is not necessary to clear the FERR bit. Reading the next character from the FIFO buffer will advance the FIFO to the next character and the next corresponding framing error.

The FERR bit can be forced clear by clearing the SPEN bit of the RCSTA register which resets the EUSART. Clearing the CREN bit of the RCSTA register does not affect the FERR bit. A framing error by itself does not generate an interrupt.

**Note:** If all receive characters in the receive FIFO have framing errors, repeated reads of the RCREG will not clear the FERR bit.

#### 25.1.2.5 Receive Overrun Error

The receive FIFO buffer can hold two characters. An overrun error will be generated if a third character, in its entirety, is received before the FIFO is accessed. When this happens the OERR bit of the RCSTA register is set. The characters already in the FIFO buffer can be read but no additional characters will be received until the error is cleared. The error must be cleared by either clearing the CREN bit of the RCSTA register or by resetting the EUSART by clearing the SPEN bit of the RCSTA register.

## 25.1.2.6 Receiving 9-bit Characters

The EUSART supports 9-bit character reception. When the RX9 bit of the RCSTA register is set the EUSART will shift 9 bits into the RSR for each character received. The RX9D bit of the RCSTA register is the ninth and Most Significant data bit of the top unread character in the receive FIFO. When reading 9-bit data from the receive FIFO buffer, the RX9D data bit must be read before reading the 8 Least Significant bits from the RCREG.

#### 25.1.2.7 Address Detection

A special Address Detection mode is available for use when multiple receivers share the same transmission line, such as in RS-485 systems. Address detection is enabled by setting the ADDEN bit of the RCSTA register.

Address detection requires 9-bit character reception. When address detection is enabled, only characters with the ninth data bit set will be transferred to the receive FIFO buffer, thereby setting the RCIF interrupt bit. All other characters will be ignored.

Upon receiving an address character, user software determines if the address matches its own. Upon address match, user software must disable address detection by clearing the ADDEN bit before the next Stop bit occurs. When user software detects the end of the message, determined by the message protocol used, software places the receiver back into the Address Detection mode by setting the ADDEN bit.

### 25.1.2.8 Asynchronous Reception Set-up:

- Initialize the SPBRGH, SPBRGL register pair and the BRGH and BRG16 bits to achieve the desired baud rate (see Section 25.3 "EUSART Baud Rate Generator (BRG)").
- 2. Clear the ANSEL bit for the RX pin (if applicable).
- Enable the serial port by setting the SPEN bit.
   The SYNC bit must be clear for asynchronous operation.
- If interrupts are desired, set the RCIE bit of the PIE1 register and the GIE and PEIE bits of the INTCON register.
- 5. If 9-bit reception is desired, set the RX9 bit.
- 6. Enable reception by setting the CREN bit.
- The RCIF interrupt flag bit will be set when a character is transferred from the RSR to the receive buffer. An interrupt will be generated if the RCIE interrupt enable bit was also set.
- Read the RCSTA register to get the error flags and, if 9-bit data reception is enabled, the ninth data bit.
- Get the received 8 Least Significant data bits from the receive buffer by reading the RCREG register.
- If an overrun occurred, clear the OERR flag by clearing the CREN receiver enable bit.

### 25.1.2.9 9-bit Address Detection Mode Set-up

This mode would typically be used in RS-485 systems. To set up an Asynchronous Reception with Address Detect Enable:

- Initialize the SPBRGH, SPBRGL register pair and the BRGH and BRG16 bits to achieve the desired baud rate (see Section 25.3 "EUSART Baud Rate Generator (BRG)").
- Clear the ANSEL bit for the RX pin (if applicable).
- Enable the serial port by setting the SPEN bit.
   The SYNC bit must be clear for asynchronous operation.
- If interrupts are desired, set the RCIE bit of the PIE1 register and the GIE and PEIE bits of the INTCON register.
- 5. Enable 9-bit reception by setting the RX9 bit.
- 6. Enable address detection by setting the ADDEN bit.
- 7. Enable reception by setting the CREN bit.
- The RCIF interrupt flag bit will be set when a character with the ninth bit set is transferred from the RSR to the receive buffer. An interrupt will be generated if the RCIE interrupt enable bit was also set.
- Read the RCSTA register to get the error flags.
   The ninth data bit will always be set.
- Get the received 8 Least Significant data bits from the receive buffer by reading the RCREG register. Software determines if this is the device's address.
- 11. If an overrun occurred, clear the OERR flag by clearing the CREN receiver enable bit.
- 12. If the device has been addressed, clear the ADDEN bit to allow all received data into the receive buffer and generate interrupts.

## FIGURE 25-5: ASYNCHRONOUS RECEPTION




TABLE 25-2: SUMMARY OF REGISTERS ASSOCIATED WITH ASYNCHRONOUS RECEPTION

| Name    | Bit 7    | Bit 6       | Bit 5      | Bit 4  | Bit 3  | Bit 2  | Bit 1  | Bit 0  | Register on Page |
|---------|----------|-------------|------------|--------|--------|--------|--------|--------|------------------|
| BAUDCON | ABDOVF   | RCIDL       | _          | SCKP   | BRG16  | _      | WUE    | ABDEN  | 302              |
| INTCON  | GIE      | PEIE        | TMR0IE     | INTE   | IOCIE  | TMR0IF | INTF   | IOCIF  | 98               |
| PIE1    | TMR1GIE  | ADIE        | RCIE       | TXIE   | SSPIE  | CCP1IE | TMR2IE | TMR1IE | 99               |
| PIR1    | TMR1GIF  | ADIF        | RCIF       | TXIF   | SSPIF  | CCP1IF | TMR2IF | TMR1IF | 102              |
| RCREG   | EUSART R | Receive Dat | a Register |        |        |        |        |        | 296*             |
| RCSTA   | SPEN     | RX9         | SREN       | CREN   | ADDEN  | FERR   | OERR   | RX9D   | 301              |
| SPBRGL  |          |             |            | BRG•   | <7:0>  |        |        |        | 303*             |
| SPBRGH  |          | BRG<15:8>   |            |        |        |        |        |        | 303*             |
| TRISC   | TRISC7   | TRISC6      | TRISC5     | TRISC4 | TRISC3 | TRISC2 | TRISC1 | TRISC0 | 142              |
| TXSTA   | CSRC     | TX9         | TXEN       | SYNC   | SENDB  | BRGH   | TRMT   | TX9D   | 300              |

**Legend:** — = unimplemented, read as '0'. Shaded cells are not used for asynchronous reception.

<sup>\*</sup> Page provides register information.

## 25.2 Clock Accuracy with Asynchronous Operation

The factory calibrates the internal oscillator block output (INTOSC). However, the INTOSC frequency may drift as VDD or temperature changes, and this directly affects the asynchronous baud rate. Two methods may be used to adjust the baud rate clock, but both require a reference clock source of some kind.

The first (preferred) method uses the OSCTUNE register to adjust the INTOSC output. Adjusting the value in the OSCTUNE register allows for fine resolution changes to the system clock source. See Section 5.2.2 "Internal Clock Sources" for more information.

The other method adjusts the value in the Baud Rate Generator. This can be done automatically with the Auto-Baud Detect feature (see Section 25.3.1 "Auto-Baud Detect"). There may not be fine enough resolution when adjusting the Baud Rate Generator to compensate for a gradual change in the peripheral clock frequency.

#### REGISTER 25-1: TXSTA: TRANSMIT STATUS AND CONTROL REGISTER

| R/W-/0 | R/W-0/0 | R/W-0/0             | R/W-0/0 | R/W-0/0 | R/W-0/0 | R-1/1 | R/W-0/0 |
|--------|---------|---------------------|---------|---------|---------|-------|---------|
| CSRC   | TX9     | TXEN <sup>(1)</sup> | SYNC    | SENDB   | BRGH    | TRMT  | TX9D    |
| bit 7  |         |                     |         |         |         |       | bit 0   |

| Legend:              |                      |   |
|----------------------|----------------------|---|
| R = Readable bit     | W = Writable bit     | U = Unimplemented bit, read as '0'                    |
| u = Bit is unchanged | x = Bit is unknown   | -n/n = Value at POR and BOR/Value at all other Resets |
| '1' = Bit is set     | '0' = Bit is cleared |   |

bit 7 CSRC: Clock Source Select bit

Asynchronous mode:

Don't care

Synchronous mode:

1 = Master mode (clock generated internally from BRG)

0 = Slave mode (clock from external source)

bit 6 **TX9:** 9-bit Transmit Enable bit

1 = Selects 9-bit transmission

0 = Selects 8-bit transmission

bit 5 **TXEN:** Transmit Enable bit<sup>(1)</sup>

1 = Transmit enabled

0 = Transmit disabled

bit 4 SYNC: EUSART Mode Select bit

1 = Synchronous mode0 = Asynchronous mode

bit 3 **SENDB:** Send Break Character bit

Asynchronous mode:

1 = Send Sync Break on next transmission (cleared by hardware upon completion)

0 = Sync Break transmission completed

Synchronous mode:

Don't care

bit 2 BRGH: High Baud Rate Select bit

Asynchronous mode:

1 = High speed

0 = Low speed

Synchronous mode:

Unused in this mode

bit 1 TRMT: Transmit Shift Register Status bit

1 = TSR empty 0 = TSR full

bit 0 **TX9D:** Ninth bit of Transmit Data

Can be address/data bit or a parity bit.

Note 1: SREN/CREN overrides TXEN in Sync mode.

## REGISTER 25-2: RCSTA: RECEIVE STATUS AND CONTROL REGISTER<sup>(1)</sup>

| R/W-0/0 | R/W-0/0 | R/W-0/0 | R/W-0/0 | R/W-0/0 | R-0/0 | R-0/0 | R-x/x |
|---------|---------|---------|---------|---------|-------|-------|-------|
| SPEN    | RX9     | SREN    | CREN    | ADDEN   | FERR  | OERR  | RX9D  |
| bit 7   |         |         |         |         |       |       | bit 0 |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7 SPEN: Serial Port Enable bit

1 = Serial port enabled (configures RX/DT and TX/CK pins as serial port pins)

0 = Serial port disabled (held in Reset)

bit 6 **RX9:** 9-bit Receive Enable bit

1 = Selects 9-bit reception0 = Selects 8-bit reception

bit 5 **SREN:** Single Receive Enable bit

Asynchronous mode:

Don't care

Synchronous mode – Master:

1 = Enables single receive

0 = Disables single receive

This bit is cleared after reception is complete.

Synchronous mode - Slave

Don't care

bit 4 CREN: Continuous Receive Enable bit

Asynchronous mode:

1 = Enables receiver

0 = Disables receiver

Synchronous mode:

1 = Enables continuous receive until enable bit CREN is cleared (CREN overrides SREN)

0 = Disables continuous receive

bit 3 ADDEN: Address Detect Enable bit

Asynchronous mode 9-bit (RX9 = 1):

1 = Enables address detection, enable interrupt and load the receive buffer when RSR<8> is set

0 = Disables address detection, all bytes are received and ninth bit can be used as parity bit

Asynchronous mode 8-bit (RX9 = 0):

Don't care

bit 2 **FERR:** Framing Error bit

1 = Framing error (can be updated by reading RCREG register and receive next valid byte)

0 = No framing error

bit 1 **OERR:** Overrun Error bit

1 = Overrun error (can be cleared by clearing bit CREN)

0 = No overrun error

bit 0 **RX9D:** Ninth bit of Received Data

This can be address/data bit or a parity bit and must be calculated by user firmware.

### REGISTER 25-3: BAUDCON: BAUD RATE CONTROL REGISTER

| R-0/0  | R-1/1 | U-0 | R/W-0/0 | R/W-0/0 | U-0 | R/W-0/0 | R/W-0/0 |
|--------|-------|-----|---------|---------|-----|---------|---------|
| ABDOVF | RCIDL | _   | SCKP    | BRG16   | _   | WUE     | ABDEN   |
| bit 7  |       |     |         |         |     |         | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7 ABDOVF: Auto-Baud Detect Overflow bit

Asynchronous mode:

1 = Auto-baud timer overflowed0 = Auto-baud timer did not overflow

Synchronous mode:

Don't care

bit 6 RCIDL: Receive Idle Flag bit

<u>Asynchronous mode</u>: 1 = Receiver is Idle

0 = Start bit has been received and the receiver is receiving

Synchronous mode:

Don't care

bit 5 **Unimplemented:** Read as '0'

bit 4 SCKP: Synchronous Clock Polarity Select bit

Asynchronous mode:

1 = Transmit inverted data to the TX/CK pin 0 = Transmit non-inverted data to the TX/CK pin

Synchronous mode:

1 = Data is clocked on rising edge of the clock0 = Data is clocked on falling edge of the clock

bit 3 BRG16: 16-bit Baud Rate Generator bit

1 = 16-bit Baud Rate Generator is used0 = 8-bit Baud Rate Generator is used

bit 2 **Unimplemented:** Read as '0' bit 1 **WUE:** Wake-up Enable bit

Asynchronous mode:

1 = Receiver is waiting for a falling edge. No character will be received, byte RCIF will be set. WUE will automatically clear after RCIF is set.

0 = Receiver is operating normally

Synchronous mode:

Don't care

bit 0 ABDEN: Auto-Baud Detect Enable bit

Asynchronous mode:

1 = Auto-Baud Detect mode is enabled (clears when auto-baud is complete)

0 = Auto-Baud Detect mode is disabled

Synchronous mode:

Don't care

## 25.3 EUSART Baud Rate Generator (BRG)

The Baud Rate Generator (BRG) is an 8-bit or 16-bit timer that is dedicated to the support of both the asynchronous and synchronous EUSART operation. By default, the BRG operates in 8-bit mode. Setting the BRG16 bit of the BAUDCON register selects 16-bit mode.

The SPBRGH, SPBRGL register pair determines the period of the free running baud rate timer. In Asynchronous mode the multiplier of the baud rate period is determined by both the BRGH bit of the TXSTA register and the BRG16 bit of the BAUDCON register. In Synchronous mode, the BRGH bit is ignored.

Table 25-3 contains the formulas for determining the baud rate. Example 25-1 provides a sample calculation for determining the baud rate and baud rate error.

Typical baud rates and error values for various asynchronous modes have been computed for your convenience and are shown in Table 25-3. It may be advantageous to use the high baud rate (BRGH = 1), or the 16-bit BRG (BRG16 = 1) to reduce the baud rate error. The 16-bit BRG mode is used to achieve slow baud rates for fast oscillator frequencies.

Writing a new value to the SPBRGH, SPBRGL register pair causes the BRG timer to be reset (or cleared). This ensures that the BRG does not wait for a timer overflow before outputting the new baud rate.

If the system clock is changed during an active receive operation, a receive error or data loss may result. To avoid this problem, check the status of the RCIDL bit to make sure that the receive operation is Idle before changing the system clock.

## EXAMPLE 25-1: CALCULATING BAUD RATE ERROR

For a device with Fosc of 16 MHz, desired baud rate of 9600, Asynchronous mode, 8-bit BRG:

$$Desired \ Baud \ Rate \ = \frac{FOSC}{64([SPBRGH:SPBRG] + I)}$$

Solving for SPBRGH:SPBRGL:

Solving tot SFBRGH.SFBRGL.
$$X = \frac{Fosc}{\frac{Desired Baud Rate}{64}} - 1$$

$$= \frac{\frac{16000000}{9600}}{\frac{9600}{64}} - 1$$

$$= [25.042] = 25$$

$$Calculated Baud Rate = \frac{16000000}{64(25+1)}$$

$$= 9615$$

$$Error = \frac{Calc. Baud Rate - Desired Baud Rate}{Desired Baud Rate}$$

$$= \frac{(9615 - 9600)}{9600} = 0.16\%$$

TABLE 25-3: BAUD RATE FORMULAS

| (    | Configuration Bi | ts   | DDC/EUCADT Mada     | Baud Rate Formula |
|------|------------------|------|---------------------|-------------------|
| SYNC | BRG16            | BRGH | BRG/EUSART Mode     | Baud Kate Formula |
| 0    | 0                | 0    | 8-bit/Asynchronous  | Fosc/[64 (n+1)]   |
| 0    | 0                | 1    | 8-bit/Asynchronous  | F-20//40 (- 14)1  |
| 0    | 1                | 0    | 16-bit/Asynchronous | Fosc/[16 (n+1)]   |
| 0    | 1                | 1    | 16-bit/Asynchronous |                   |
| 1    | 0                | х    | 8-bit/Synchronous   | Fosc/[4 (n+1)]    |
| 1    | 1                | х    | 16-bit/Synchronous  |                   |

**Legend:** x = Don't care, n = value of SPBRGH, SPBRGL register pair

TABLE 25-4: SUMMARY OF REGISTERS ASSOCIATED WITH THE BAUD RATE GENERATOR

| Name    | Bit 7  | Bit 6     | Bit 5 | Bit 4 | Bit 3 | Bit 2 | Bit 1 | Bit 0 | Register on Page |
|---------|--------|-----------|-------|-------|-------|-------|-------|-------|------------------|
| BAUDCON | ABDOVF | RCIDL     | _     | SCKP  | BRG16 | _     | WUE   | ABDEN | 302              |
| RCSTA   | SPEN   | RX9       | SREN  | CREN  | ADDEN | FERR  | OERR  | RX9D  | 301              |
| SPBRGL  |        |           |       | BRG.  | <7:0> |       |       |       | 303*             |
| SPBRGH  |        | BRG<15:8> |       |       |       |       |       |       | 303*             |
| TXSTA   | CSRC   | TX9       | TXEN  | SYNC  | SENDB | BRGH  | TRMT  | TX9D  | 300              |

**Legend:** — = unimplemented read as '0'. Shaded cells are not used for the Baud Rate Generator.

<sup>\*</sup> Page provides register information.

TABLE 25-5: BAUD RATES FOR ASYNCHRONOUS MODES

|        |                |            |                             |                   | SYNC       | = 0, BRGH                   | l = 0, BRG     | <b>316 =</b> 0 |                             |                |                    |                             |  |
|--------|----------------|------------|-----------------------------|-------------------|------------|-----------------------------|----------------|----------------|-----------------------------|----------------|--------------------|-----------------------------|--|
| BAUD   | Fosc           | = 32.00    | 0 MHz                       | Fosc = 20.000 MHz |            |                             | Fosc           | = 18.43        | 2 MHz                       | Fosc           | Fosc = 11.0592 MHz |                             |  |
| RATE   | Actual<br>Rate | %<br>Error | SPBRG<br>value<br>(decimal) | Actual<br>Rate    | %<br>Error | SPBRG<br>value<br>(decimal) | Actual<br>Rate | %<br>Error     | SPBRG<br>value<br>(decimal) | Actual<br>Rate | %<br>Error         | SPBRG<br>value<br>(decimal) |  |
| 300    | _              | _          | _                           | -                 | _          | _                           | _              | _              | _                           | -              | _                  | _                           |  |
| 1200   | _              | _          | _                           | 1221              | 1.73       | 255                         | 1200           | 0.00           | 239                         | 1200           | 0.00               | 143                         |  |
| 2400   | 2404           | 0.16       | 207                         | 2404              | 0.16       | 129                         | 2400           | 0.00           | 119                         | 2400           | 0.00               | 71                          |  |
| 9600   | 9615           | 0.16       | 51                          | 9470              | -1.36      | 32                          | 9600           | 0.00           | 29                          | 9600           | 0.00               | 17                          |  |
| 10417  | 10417          | 0.00       | 47                          | 10417             | 0.00       | 29                          | 10286          | -1.26          | 27                          | 10165          | -2.42              | 16                          |  |
| 19.2k  | 19.23k         | 0.16       | 25                          | 19.53k            | 1.73       | 15                          | 19.20k         | 0.00           | 14                          | 19.20k         | 0.00               | 8                           |  |
| 57.6k  | 55.55k         | -3.55      | 3                           | _                 | _          | _                           | 57.60k         | 0.00           | 7                           | 57.60k         | 0.00               | 2                           |  |
| 115.2k | _              | _          | _                           | _                 | _          | _                           | _              | _              | _                           | _              | _                  | _                           |  |

|        |                |            |                             |                | SYNC       | = 0, BRGH                   | l = 0, BRG     | <b>616</b> = 0 |                             |                |            |                             |
|--------|----------------|------------|-----------------------------|----------------|------------|-----------------------------|----------------|----------------|-----------------------------|----------------|------------|-----------------------------|
| BAUD   | Fos            | c = 8.000  | ) MHz                       | Fos            | c = 4.000  | ) MHz                       | Fosc           | = 3.686        | 4 MHz                       | Fos            | c = 1.000  | ) MHz                       |
| RATE   | Actual<br>Rate | %<br>Error | SPBRG<br>value<br>(decimal) | Actual<br>Rate | %<br>Error | SPBRG<br>value<br>(decimal) | Actual<br>Rate | %<br>Error     | SPBRG<br>value<br>(decimal) | Actual<br>Rate | %<br>Error | SPBRG<br>value<br>(decimal) |
| 300    | _              | _          | _                           | 300            | 0.16       | 207                         | 300            | 0.00           | 191                         | 300            | 0.16       | 51                          |
| 1200   | 1202           | 0.16       | 103                         | 1202           | 0.16       | 51                          | 1200           | 0.00           | 47                          | 1202           | 0.16       | 12                          |
| 2400   | 2404           | 0.16       | 51                          | 2404           | 0.16       | 25                          | 2400           | 0.00           | 23                          | _              | _          | _                           |
| 9600   | 9615           | 0.16       | 12                          | _              | _          | _                           | 9600           | 0.00           | 5                           | _              | _          | _                           |
| 10417  | 10417          | 0.00       | 11                          | 10417          | 0.00       | 5                           | _              | _              | _                           | _              | _          | _                           |
| 19.2k  | _              | _          | _                           | _              | _          | _                           | 19.20k         | 0.00           | 2                           | _              | _          | _                           |
| 57.6k  | _              | _          | _                           | _              | _          | _                           | 57.60k         | 0.00           | 0                           | _              | _          | _                           |
| 115.2k | _              | _          | _                           | 1              | _          | _                           | 1              | _              | _                           | _              | _          | _                           |

|        |                |            |                             |                | SYNC       | C = 0, BRGH                 | l = 1, BRG     | <b>316</b> = 0 |                             |                |            |                             |
|--------|----------------|------------|-----------------------------|----------------|------------|-----------------------------|----------------|----------------|-----------------------------|----------------|------------|-----------------------------|
| BAUD   | Fosc           | = 32.00    | 0 MHz                       | Fosc           | = 20.00    | 0 MHz                       | Fosc           | = 18.43        | 2 MHz                       | Fosc           | = 11.059   | 92 MHz                      |
| RATE   | Actual<br>Rate | %<br>Error | SPBRG<br>value<br>(decimal) | Actual<br>Rate | %<br>Error | SPBRG<br>value<br>(decimal) | Actual<br>Rate | %<br>Error     | SPBRG<br>value<br>(decimal) | Actual<br>Rate | %<br>Error | SPBRG<br>value<br>(decimal) |
| 300    | _              | _          | _                           | _              | _          | _                           | _              | _              | _                           | _              | _          | _                           |
| 1200   | _              | _          | _                           | _              | _          | _                           | _              | _              | _                           | _              | _          | _                           |
| 2400   | _              | _          | _                           | _              | _          | _                           | _              | _              | _                           | _              | _          | _                           |
| 9600   | 9615           | 0.16       | 207                         | 9615           | 0.16       | 129                         | 9600           | 0.00           | 119                         | 9600           | 0.00       | 71                          |
| 10417  | 10417          | 0.00       | 191                         | 10417          | 0.00       | 119                         | 10378          | -0.37          | 110                         | 10473          | 0.53       | 65                          |
| 19.2k  | 19.23k         | 0.16       | 103                         | 19.23k         | 0.16       | 64                          | 19.20k         | 0.00           | 59                          | 19.20k         | 0.00       | 35                          |
| 57.6k  | 57.14k         | -0.79      | 34                          | 56.82k         | -1.36      | 21                          | 57.60k         | 0.00           | 19                          | 57.60k         | 0.00       | 11                          |
| 115.2k | 117.64k        | 2.12       | 16                          | 113.64k        | -1.36      | 10                          | 115.2k         | 0.00           | 9                           | 115.2k         | 0.00       | 5                           |

TABLE 25-5: BAUD RATES FOR ASYNCHRONOUS MODES (CONTINUED)

|        |                |            |                             |                | SYNC       | C = 0, BRGH                 | l = 1, BR0     | <b>316 =</b> 0 |                             |                |            |                             |
|--------|----------------|------------|-----------------------------|----------------|------------|-----------------------------|----------------|----------------|-----------------------------|----------------|------------|-----------------------------|
| BAUD   | Fos            | c = 8.000  | ) MHz                       | Fos            | c = 4.000  | ) MHz                       | Fosc           | = 3.686        | 4 MHz                       | Fos            | c = 1.000  | ) MHz                       |
| RATE   | Actual<br>Rate | %<br>Error | SPBRG<br>value<br>(decimal) | Actual<br>Rate | %<br>Error | SPBRG<br>value<br>(decimal) | Actual<br>Rate | %<br>Error     | SPBRG<br>value<br>(decimal) | Actual<br>Rate | %<br>Error | SPBRG<br>value<br>(decimal) |
| 300    | _              | _          | _                           | _              | _          | _                           |                | _              | _                           | 300            | 0.16       | 207                         |
| 1200   | _              | _          | _                           | 1202           | 0.16       | 207                         | 1200           | 0.00           | 191                         | 1202           | 0.16       | 51                          |
| 2400   | 2404           | 0.16       | 207                         | 2404           | 0.16       | 103                         | 2400           | 0.00           | 95                          | 2404           | 0.16       | 25                          |
| 9600   | 9615           | 0.16       | 51                          | 9615           | 0.16       | 25                          | 9600           | 0.00           | 23                          | _              | _          | _                           |
| 10417  | 10417          | 0.00       | 47                          | 10417          | 0.00       | 23                          | 10473          | 0.53           | 21                          | 10417          | 0.00       | 5                           |
| 19.2k  | 19231          | 0.16       | 25                          | 19.23k         | 0.16       | 12                          | 19.2k          | 0.00           | 11                          | _              | _          | _                           |
| 57.6k  | 55556          | -3.55      | 8                           | _              | _          | _                           | 57.60k         | 0.00           | 3                           | _              | _          | _                           |
| 115.2k | _              | _          | _                           | _              | _          | _                           | 115.2k         | 0.00           | 1                           | _              | _          | _                           |

|        |                |            |                             |                | SYNC       | C = 0, BRGH                 | l = 0, BRC     | 316 = 1    |                             |                |            |                             |
|--------|----------------|------------|-----------------------------|----------------|------------|-----------------------------|----------------|------------|-----------------------------|----------------|------------|-----------------------------|
| BAUD   | Fosc           | = 32.00    | 0 MHz                       | Fosc           | = 20.00    | 0 MHz                       | Fosc           | = 18.43    | 2 MHz                       | Fosc           | = 11.059   | 92 MHz                      |
| RATE   | Actual<br>Rate | %<br>Error | SPBRG<br>value<br>(decimal) |
| 300    | 300.0          | 0.00       | 6666                        | 300.0          | -0.01      | 4166                        | 300.0          | 0.00       | 3839                        | 300.0          | 0.00       | 2303                        |
| 1200   | 1200           | -0.02      | 3332                        | 1200           | -0.03      | 1041                        | 1200           | 0.00       | 959                         | 1200           | 0.00       | 575                         |
| 2400   | 2401           | -0.04      | 832                         | 2399           | -0.03      | 520                         | 2400           | 0.00       | 479                         | 2400           | 0.00       | 287                         |
| 9600   | 9615           | 0.16       | 207                         | 9615           | 0.16       | 129                         | 9600           | 0.00       | 119                         | 9600           | 0.00       | 71                          |
| 10417  | 10417          | 0.00       | 191                         | 10417          | 0.00       | 119                         | 10378          | -0.37      | 110                         | 10473          | 0.53       | 65                          |
| 19.2k  | 19.23k         | 0.16       | 103                         | 19.23k         | 0.16       | 64                          | 19.20k         | 0.00       | 59                          | 19.20k         | 0.00       | 35                          |
| 57.6k  | 57.14k         | -0.79      | 34                          | 56.818         | -1.36      | 21                          | 57.60k         | 0.00       | 19                          | 57.60k         | 0.00       | 11                          |
| 115.2k | 117.6k         | 2.12       | 16                          | 113.636        | -1.36      | 10                          | 115.2k         | 0.00       | 9                           | 115.2k         | 0.00       | 5                           |

|        |                |            |                             |                | SYNC       | C = 0, BRGH                 | I = 0, BRG     | 616 = 1    |                             |                |            |                             |
|--------|----------------|------------|-----------------------------|----------------|------------|-----------------------------|----------------|------------|-----------------------------|----------------|------------|-----------------------------|
| BAUD   | Fos            | c = 8.000  | ) MHz                       | Fos            | c = 4.000  | ) MHz                       | Fosc           | = 3.686    | 4 MHz                       | Fos            | c = 1.000  | ) MHz                       |
| RATE   | Actual<br>Rate | %<br>Error | SPBRG<br>value<br>(decimal) |
| 300    | 299.9          | -0.02      | 1666                        | 300.1          | 0.04       | 832                         | 300.0          | 0.00       | 767                         | 300.5          | 0.16       | 207                         |
| 1200   | 1199           | -0.08      | 416                         | 1202           | 0.16       | 207                         | 1200           | 0.00       | 191                         | 1202           | 0.16       | 51                          |
| 2400   | 2404           | 0.16       | 207                         | 2404           | 0.16       | 103                         | 2400           | 0.00       | 95                          | 2404           | 0.16       | 25                          |
| 9600   | 9615           | 0.16       | 51                          | 9615           | 0.16       | 25                          | 9600           | 0.00       | 23                          | _              | _          | _                           |
| 10417  | 10417          | 0.00       | 47                          | 10417          | 0.00       | 23                          | 10473          | 0.53       | 21                          | 10417          | 0.00       | 5                           |
| 19.2k  | 19.23k         | 0.16       | 25                          | 19.23k         | 0.16       | 12                          | 19.20k         | 0.00       | 11                          | _              | _          | _                           |
| 57.6k  | 55556          | -3.55      | 8                           | _              | _          | _                           | 57.60k         | 0.00       | 3                           | _              | _          | _                           |
| 115.2k | _              | _          | _                           | _              | _          | _                           | 115.2k         | 0.00       | 1                           | _              | _          | _                           |

TABLE 25-5: BAUD RATES FOR ASYNCHRONOUS MODES (CONTINUED)

|        |                |            |                             | SYNC = 0       | , BRGH     | = 1, BRG16                  | = 1 or SY      | 'NC = 1,   | BRG16 = 1                   |                |            |                             |
|--------|----------------|------------|-----------------------------|----------------|------------|-----------------------------|----------------|------------|-----------------------------|----------------|------------|-----------------------------|
| BAUD   | Fosc           | = 32.00    | 0 MHz                       | Fosc           | = 20.00    | 0 MHz                       | Fosc           | = 18.43    | 2 MHz                       | Fosc           | = 11.059   | 92 MHz                      |
| RATE   | Actual<br>Rate | %<br>Error | SPBRG<br>value<br>(decimal) |
| 300    | 300.0          | 0.00       | 26666                       | 300.0          | 0.00       | 16665                       | 300.0          | 0.00       | 15359                       | 300.0          | 0.00       | 9215                        |
| 1200   | 1200           | 0.00       | 6666                        | 1200           | -0.01      | 4166                        | 1200           | 0.00       | 3839                        | 1200           | 0.00       | 2303                        |
| 2400   | 2400           | 0.01       | 3332                        | 2400           | 0.02       | 2082                        | 2400           | 0.00       | 1919                        | 2400           | 0.00       | 1151                        |
| 9600   | 9604           | 0.04       | 832                         | 9597           | -0.03      | 520                         | 9600           | 0.00       | 479                         | 9600           | 0.00       | 287                         |
| 10417  | 10417          | 0.00       | 767                         | 10417          | 0.00       | 479                         | 10425          | 80.0       | 441                         | 10433          | 0.16       | 264                         |
| 19.2k  | 19.18k         | -0.08      | 416                         | 19.23k         | 0.16       | 259                         | 19.20k         | 0.00       | 239                         | 19.20k         | 0.00       | 143                         |
| 57.6k  | 57.55k         | -0.08      | 138                         | 57.47k         | -0.22      | 86                          | 57.60k         | 0.00       | 79                          | 57.60k         | 0.00       | 47                          |
| 115.2k | 115.9k         | 0.64       | 68                          | 116.3k         | 0.94       | 42                          | 115.2k         | 0.00       | 39                          | 115.2k         | 0.00       | 23                          |

|        |                |            |                             | SYNC = 0       | , BRGH     | = 1, BRG16                  | = 1 or SY      | NC = 1,    | BRG16 = 1                   |                |            |                             |
|--------|----------------|------------|-----------------------------|----------------|------------|-----------------------------|----------------|------------|-----------------------------|----------------|------------|-----------------------------|
| BAUD   | Fos            | c = 8.000  | MHz                         | Fos            | c = 4.000  | ) MHz                       | Fosc           | = 3.686    | 4 MHz                       | Fos            | c = 1.000  | ) MHz                       |
| RATE   | Actual<br>Rate | %<br>Error | SPBRG<br>value<br>(decimal) |
| 300    | 300.0          | 0.00       | 6666                        | 300.0          | 0.01       | 3332                        | 300.0          | 0.00       | 3071                        | 300.1          | 0.04       | 832                         |
| 1200   | 1200           | -0.02      | 1666                        | 1200           | 0.04       | 832                         | 1200           | 0.00       | 767                         | 1202           | 0.16       | 207                         |
| 2400   | 2401           | 0.04       | 832                         | 2398           | 0.08       | 416                         | 2400           | 0.00       | 383                         | 2404           | 0.16       | 103                         |
| 9600   | 9615           | 0.16       | 207                         | 9615           | 0.16       | 103                         | 9600           | 0.00       | 95                          | 9615           | 0.16       | 25                          |
| 10417  | 10417          | 0          | 191                         | 10417          | 0.00       | 95                          | 10473          | 0.53       | 87                          | 10417          | 0.00       | 23                          |
| 19.2k  | 19.23k         | 0.16       | 103                         | 19.23k         | 0.16       | 51                          | 19.20k         | 0.00       | 47                          | 19.23k         | 0.16       | 12                          |
| 57.6k  | 57.14k         | -0.79      | 34                          | 58.82k         | 2.12       | 16                          | 57.60k         | 0.00       | 15                          | _              | _          | _                           |
| 115.2k | 117.6k         | 2.12       | 16                          | 111.1k         | -3.55      | 8                           | 115.2k         | 0.00       | 7                           | _              |            | _                           |

#### 25.3.1 AUTO-BAUD DETECT

The EUSART module supports automatic detection and calibration of the baud rate.

In the Auto-Baud Detect (ABD) mode, the clock to the BRG is reversed. Rather than the BRG clocking the incoming RX signal, the RX signal is timing the BRG. The Baud Rate Generator is used to time the period of a received 55h (ASCII "U") which is the Sync character for the LIN bus. The unique feature of this character is that it has five rising edges including the Stop bit edge.

Setting the ABDEN bit of the BAUDCON register starts the auto-baud calibration sequence (Figure 25-6). While the ABD sequence takes place, the EUSART state machine is held in Idle. On the first rising edge of the receive line, after the Start bit, the SPBRG begins counting up using the BRG counter clock as shown in Table 25-6. The fifth rising edge will occur on the RX pin at the end of the eighth bit period. At that time, an accumulated value totaling the proper BRG period is left in the SPBRGH, SPBRGL register pair, the ABDEN bit is automatically cleared and the RCIF interrupt flag is set. The value in the RCREG needs to be read to clear the RCIF interrupt. RCREG content should be discarded. When calibrating for modes that do not use the SPBRGH register the user can verify that the SPBRGL register did not overflow by checking for 00h in the SPBRGH register.

The BRG auto-baud clock is determined by the BRG16 and BRGH bits as shown in Table 25-6. During ABD, both the SPBRGH and SPBRGL registers are used as a 16-bit counter, independent of the BRG16 bit setting. While calibrating the baud rate period, the SPBRGH

and SPBRGL registers are clocked at 1/8th the BRG base clock rate. The resulting byte measurement is the average bit time when clocked at full speed.


- Note 1: If the WUE bit is set with the ABDEN bit, auto-baud detection will occur on the byte following the Break character (see Section 25.3.3 "Auto-Wake-up on Break").
  - 2: It is up to the user to determine that the incoming character baud rate is within the range of the selected BRG clock source. Some combinations of oscillator frequency and EUSART baud rates are not possible.
  - 3: During the auto-baud process, the auto-baud counter starts counting at 1. Upon completion of the auto-baud sequence, to achieve maximum accuracy, subtract 1 from the SPBRGH:SPBRGL register pair.

TABLE 25-6: BRG COUNTER CLOCK RATES

| BRG16 | BRGH | BRG Base<br>Clock | BRG ABD<br>Clock |
|-------|------|-------------------|------------------|
| 0     | 0    | Fosc/64           | Fosc/512         |
| 0     | 1    | Fosc/16           | Fosc/128         |
| 1     | 0    | Fosc/16           | Fosc/128         |
| 1     | 1    | Fosc/4            | Fosc/32          |

Note: During the ABD sequence, SPBRGL and SPBRGH registers are both used as a 16-bit counter, independent of BRG16 setting.

FIGURE 25-6: AUTOMATIC BAUD RATE CALIBRATION



#### 25.3.2 AUTO-BAUD OVERFLOW

During the course of automatic baud detection, the ABDOVF bit of the BAUDCON register will be set if the baud rate counter overflows before the fifth rising edge is detected on the RX pin. The ABDOVF bit indicates that the counter has exceeded the maximum count that can fit in the 16 bits of the SPBRGH:SPBRGL register pair. After the ABDOVF has been set, the counter continues to count until the fifth rising edge is detected on the RX pin. Upon detecting the fifth RX edge, the hardware will set the RCIF interrupt flag and clear the ABDEN bit of the BAUDCON register. The RCIF flag can be subsequently cleared by reading the RCREG register. The ABDOVF flag of the BAUDCON register can be cleared by software directly.

To terminate the auto-baud process before the RCIF flag is set, clear the ABDEN bit then clear the ABDOVF bit of the BAUDCON register. The ABDOVF bit will remain set if the ABDEN bit is not cleared first.

### 25.3.3 AUTO-WAKE-UP ON BREAK

During Sleep mode, all clocks to the EUSART are suspended. Because of this, the Baud Rate Generator is inactive and a proper character reception cannot be performed. The Auto-Wake-up feature allows the controller to wake-up due to activity on the RX/DT line. This feature is available only in Asynchronous mode.

The Auto-Wake-up feature is enabled by setting the WUE bit of the BAUDCON register. Once set, the normal receive sequence on RX/DT is disabled, and the EUSART remains in an Idle state, monitoring for a wake-up event independent of the CPU mode. A wake-up event consists of a high-to-low transition on the RX/DT line. (This coincides with the start of a Sync Break or a wake-up signal character for the LIN protocol.)

The EUSART module generates an RCIF interrupt coincident with the wake-up event. The interrupt is generated synchronously to the Q clocks in normal CPU operating modes (Figure 25-7), and asynchronously if the device is in Sleep mode (Figure 25-8). The interrupt condition is cleared by reading the RCREG register.

The WUE bit is automatically cleared by the low-to-high transition on the RX line at the end of the Break. This signals to the user that the Break event is over. At this point, the EUSART module is in Idle mode waiting to receive the next character.

#### 25.3.3.1 Special Considerations

### **Break Character**

To avoid character errors or character fragments during a wake-up event, the wake-up character must be all zeros

When the wake-up is enabled the function works independent of the low time on the data stream. If the WUE bit is set and a valid non-zero character is received, the low time from the Start bit to the first rising edge will be interpreted as the wake-up event. The remaining bits in the character will be received as a fragmented character and subsequent characters can result in framing or overrun errors.

Therefore, the initial character in the transmission must be all '0's. This must be 10 or more bit times, 13-bit times recommended for LIN bus, or any number of bit times for standard RS-232 devices.

#### Oscillator Start-up Time


Oscillator start-up time must be considered, especially in applications using oscillators with longer start-up intervals (i.e., LP, XT or HS/PLL mode). The Sync Break (or wake-up signal) character must be of sufficient length, and be followed by a sufficient interval, to allow enough time for the selected oscillator to start and provide proper initialization of the EUSART.

#### **WUE Bit**


The wake-up event causes a receive interrupt by setting the RCIF bit. The WUE bit is cleared in hardware by a rising edge on RX/DT. The interrupt condition is then cleared in software by reading the RCREG register and discarding its contents.

To ensure that no actual data is lost, check the RCIDL bit to verify that a receive operation is not in process before setting the WUE bit. If a receive operation is not occurring, the WUE bit may then be set just prior to entering the Sleep mode.

## FIGURE 25-7: AUTO-WAKE-UP BIT (WUE) TIMING DURING NORMAL OPERATION



## FIGURE 25-8: AUTO-WAKE-UP BIT (WUE) TIMINGS DURING SLEEP



2: The EUSART remains in Idle while the WUE bit is set.

#### 25.3.4 BREAK CHARACTER SEQUENCE

The EUSART module has the capability of sending the special Break character sequences that are required by the LIN bus standard. A Break character consists of a Start bit, followed by 12 '0' bits and a Stop bit.

To send a Break character, set the SENDB and TXEN bits of the TXSTA register. The Break character transmission is then initiated by a write to the TXREG. The value of data written to TXREG will be ignored and all '0's will be transmitted.

The SENDB bit is automatically reset by hardware after the corresponding Stop bit is sent. This allows the user to preload the transmit FIFO with the next transmit byte following the Break character (typically, the Sync character in the LIN specification).

The TRMT bit of the TXSTA register indicates when the transmit operation is active or Idle, just as it does during normal transmission. See Figure 25-9 for the timing of the Break character sequence.

## 25.3.4.1 Break and Sync Transmit Sequence

The following sequence will start a message frame header made up of a Break, followed by an auto-baud Sync byte. This sequence is typical of a LIN bus master.

- 1. Configure the EUSART for the desired mode.
- Set the TXEN and SENDB bits to enable the Break sequence.
- 3. Load the TXREG with a dummy character to initiate transmission (the value is ignored).
- Write '55h' to TXREG to load the Sync character into the transmit FIFO buffer.

After the Break has been sent, the SENDB bit is reset by hardware and the Sync character is then transmitted.

When the TXREG becomes empty, as indicated by the TXIF, the next data byte can be written to TXREG.

#### 25.3.5 RECEIVING A BREAK CHARACTER

The Enhanced EUSART module can receive a Break character in two ways.

The first method to detect a Break character uses the FERR bit of the RCSTA register and the Received data as indicated by RCREG. The Baud Rate Generator is assumed to have been initialized to the expected baud rate.


A Break character has been received when:

- · RCIF bit is set
- · FERR bit is set
- RCREG = 00h

The second method uses the Auto-Wake-up feature described in Section 25.3.3 "Auto-Wake-up on Break". By enabling this feature, the EUSART will sample the next two transitions on RX/DT, cause an RCIF interrupt, and receive the next data byte followed by another interrupt.

Note that following a Break character, the user will typically want to enable the Auto-Baud Detect feature. For both methods, the user can set the ABDEN bit of the BAUDCON register before placing the EUSART in Sleep mode.





## 25.4 EUSART Synchronous Mode

Synchronous serial communications are typically used in systems with a single master and one or more slaves. The master device contains the necessary circuitry for baud rate generation and supplies the clock for all devices in the system. Slave devices can take advantage of the master clock by eliminating the internal clock generation circuitry.

There are two signal lines in Synchronous mode: a bidirectional data line and a clock line. Slaves use the external clock supplied by the master to shift the serial data into and out of their respective receive and transmit shift registers. Since the data line is bidirectional, synchronous operation is half-duplex only. Half-duplex refers to the fact that master and slave devices can receive and transmit data but not both simultaneously. The EUSART can operate as either a master or slave device.

Start and Stop bits are not used in synchronous transmissions.

#### 25.4.1 SYNCHRONOUS MASTER MODE

The following bits are used to configure the EUSART for Synchronous Master operation:

- SYNC = 1
- CSRC = 1
- SREN = 0 (for transmit); SREN = 1 (for receive)
- CREN = 0 (for transmit); CREN = 1 (for receive)
- SPFN = 1

Setting the SYNC bit of the TXSTA register configures the device for synchronous operation. Setting the CSRC bit of the TXSTA register configures the device as a master. Clearing the SREN and CREN bits of the RCSTA register ensures that the device is in the Transmit mode, otherwise the device will be configured to receive. Setting the SPEN bit of the RCSTA register enables the EUSART.

## 25.4.1.1 Master Clock

Synchronous data transfers use a separate clock line, which is synchronous with the data. A device configured as a master transmits the clock on the TX/CK line. The TX/CK pin output driver is automatically enabled when the EUSART is configured for synchronous transmit or receive operation. Serial data bits change on the leading edge to ensure they are valid at the trailing edge of each clock. One clock cycle is generated for each data bit. Only as many clock cycles are generated as there are data bits.

### 25.4.1.2 Clock Polarity

A clock polarity option is provided for Microwire compatibility. Clock polarity is selected with the SCKP bit of the BAUDCON register. Setting the SCKP bit sets the clock Idle state as high. When the SCKP bit is set, the data changes on the falling edge of each clock.

Clearing the SCKP bit sets the Idle state as low. When the SCKP bit is cleared, the data changes on the rising edge of each clock.

## 25.4.1.3 Synchronous Master Transmission

Data is transferred out of the device on the RX/DT pin. The RX/DT and TX/CK pin output drivers are automatically enabled when the EUSART is configured for synchronous master transmit operation.

A transmission is initiated by writing a character to the TXREG register. If the TSR still contains all or part of a previous character the new character data is held in the TXREG until the last bit of the previous character has been transmitted. If this is the first character, or the previous character has been completely flushed from the TSR, the data in the TXREG is immediately transferred to the TSR. The transmission of the character commences immediately following the transfer of the data to the TSR from the TXREG.

Each data bit changes on the leading edge of the master clock and remains valid until the subsequent leading clock edge.

**Note:** The TSR register is not mapped in data memory, so it is not available to the user.

## 25.4.1.4 Synchronous Master Transmission Set-up:

- Initialize the SPBRGH, SPBRGL register pair and the BRGH and BRG16 bits to achieve the desired baud rate (see Section 25.3 "EUSART Baud Rate Generator (BRG)").
- Enable the synchronous master serial port by setting bits SYNC, SPEN and CSRC.
- Disable Receive mode by clearing bits SREN and CREN.
- 4. Enable Transmit mode by setting the TXEN bit.
- 5. If 9-bit transmission is desired, set the TX9 bit.
- If interrupts are desired, set the TXIE bit of the PIE1 register and the GIE and PEIE bits of the INTCON register.
- If 9-bit transmission is selected, the ninth bit should be loaded in the TX9D bit.
- Start transmission by loading data to the TXREG register.

FIGURE 25-10: SYNCHRONOUS TRANSMISSION




FIGURE 25-11: SYNCHRONOUS TRANSMISSION (THROUGH TXEN)




TABLE 25-7: SUMMARY OF REGISTERS ASSOCIATED WITH SYNCHRONOUS MASTER TRANSMISSION

| Name    | Bit 7      | Bit 6         | Bit 5    | Bit 4  | Bit 3  | Bit 2  | Bit 1  | Bit 0  | Register<br>on Page |
|---------|------------|---------------|----------|--------|--------|--------|--------|--------|---------------------|
| BAUDCON | ABDOVF     | RCIDL         | _        | SCKP   | BRG16  | _      | WUE    | ABDEN  | 302                 |
| INTCON  | GIE        | PEIE          | TMR0IE   | INTE   | IOCIE  | TMR0IF | INTF   | IOCIF  | 98                  |
| PIE1    | TMR1GIE    | ADIE          | RCIE     | TXIE   | SSPIE  | CCP1IE | TMR2IE | TMR1IE | 99                  |
| PIR1    | TMR1GIF    | ADIF          | RCIF     | TXIF   | SSPIF  | CCP1IF | TMR2IF | TMR1IF | 102                 |
| RCSTA   | SPEN       | RX9           | SREN     | CREN   | ADDEN  | FERR   | OERR   | RX9D   | 301                 |
| SPBRGL  |            |               |          | BRG·   | <7:0>  |        |        |        | 303*                |
| SPBRGH  |            |               |          | BRG<   | :15:8> |        |        |        | 303*                |
| TRISC   | TRISC7     | TRISC6        | TRISC5   | TRISC4 | TRISC3 | TRISC2 | TRISC1 | TRISC0 | 142                 |
| TXREG   | EUSART Tra | ansmit Data I | Register |        |        |        |        |        | 293*                |
| TXSTA   | CSRC       | TX9           | TXEN     | SYNC   | SENDB  | BRGH   | TRMT   | TX9D   | 300                 |

**Legend:** — = unimplemented read as '0'. Shaded cells are not used for synchronous master transmission.

Page provides register information.

## 25.4.1.5 Synchronous Master Reception

Data is received at the RX/DT pin. The RX/DT pin output driver is automatically disabled when the EUSART is configured for synchronous master receive operation.

In Synchronous mode, reception is enabled by setting either the Single Receive Enable bit (SREN of the RCSTA register) or the Continuous Receive Enable bit (CREN of the RCSTA register).

When SREN is set and CREN is clear, only as many clock cycles are generated as there are data bits in a single character. The SREN bit is automatically cleared at the completion of one character. When CREN is set, clocks are continuously generated until CREN is cleared. If CREN is cleared in the middle of a character the CK clock stops immediately and the partial character is discarded. If SREN and CREN are both set, then SREN is cleared at the completion of the first character and CREN takes precedence.

To initiate reception, set either SREN or CREN. Data is sampled at the RX/DT pin on the trailing edge of the TX/CK clock pin and is shifted into the Receive Shift Register (RSR). When a complete character is received into the RSR, the RCIF bit is set and the character is automatically transferred to the two character receive FIFO. The Least Significant eight bits of the top character in the receive FIFO are available in RCREG. The RCIF bit remains set as long as there are unread characters in the receive FIFO.

### 25.4.1.6 Slave Clock

Synchronous data transfers use a separate clock line, which is synchronous with the data. A device configured as a slave receives the clock on the TX/CK line. The TX/CK pin output driver is automatically disabled when the device is configured for synchronous slave transmit or receive operation. Serial data bits change on the leading edge to ensure they are valid at the trailing edge of each clock. One data bit is transferred for each clock cycle. Only as many clock cycles should be received as there are data bits.

### 25.4.1.7 Receive Overrun Error

The receive FIFO buffer can hold two characters. An overrun error will be generated if a third character, in its entirety, is received before RCREG is read to access the FIFO. When this happens the OERR bit of the RCSTA register is set. Previous data in the FIFO will not be overwritten. The two characters in the FIFO buffer can be read, however, no additional characters will be received until the error is cleared. The OERR bit can only be cleared by clearing the overrun condition. If the overrun error occurred when the SREN bit is set and CREN is clear then the error is cleared by reading RCREG. If the overrun occurred when the CREN bit is

set then the error condition is cleared by either clearing the CREN bit of the RCSTA register or by clearing the SPEN bit which resets the EUSART.

## 25.4.1.8 Receiving 9-bit Characters

The EUSART supports 9-bit character reception. When the RX9 bit of the RCSTA register is set the EUSART will shift 9-bits into the RSR for each character received. The RX9D bit of the RCSTA register is the ninth, and Most Significant, data bit of the top unread character in the receive FIFO. When reading 9-bit data from the receive FIFO buffer, the RX9D data bit must be read before reading the 8 Least Significant bits from the RCREG.

## 25.4.1.9 Synchronous Master Reception Set-up:

- Initialize the SPBRGH, SPBRGL register pair for the appropriate baud rate. Set or clear the BRGH and BRG16 bits, as required, to achieve the desired baud rate.
- 2. Clear the ANSEL bit for the RX pin (if applicable).
- Enable the synchronous master serial port by setting bits SYNC, SPEN and CSRC.
- 4. Ensure bits CREN and SREN are clear.
- If interrupts are desired, set the RCIE bit of the PIE1 register and the GIE and PEIE bits of the INTCON register.
- 6. If 9-bit reception is desired, set bit RX9.
- Start reception by setting the SREN bit or for continuous reception, set the CREN bit.
- Interrupt flag bit RCIF will be set when reception of a character is complete. An interrupt will be generated if the enable bit RCIE was set.
- Read the RCSTA register to get the ninth bit (if enabled) and determine if any error occurred during reception.
- 10. Read the 8-bit received data by reading the RCREG register.
- If an overrun error occurs, clear the error by either clearing the CREN bit of the RCSTA register or by clearing the SPEN bit which resets the EUSART.






TABLE 25-8: SUMMARY OF REGISTERS ASSOCIATED WITH SYNCHRONOUS MASTER RECEPTION

| Name    | Bit 7    | Bit 6       | Bit 5      | Bit 4  | Bit 3  | Bit 2  | Bit 1  | Bit 0  | Register on Page |
|---------|----------|-------------|------------|--------|--------|--------|--------|--------|------------------|
| BAUDCON | ABDOVF   | RCIDL       | _          | SCKP   | BRG16  | _      | WUE    | ABDEN  | 302              |
| INTCON  | GIE      | PEIE        | TMR0IE     | INTE   | IOCIE  | TMR0IF | INTF   | IOCIF  | 98               |
| PIE1    | TMR1GIE  | ADIE        | RCIE       | TXIE   | SSPIE  | CCP1IE | TMR2IE | TMR1IE | 99               |
| PIR1    | TMR1GIF  | ADIF        | RCIF       | TXIF   | SSPIF  | CCP1IF | TMR2IF | TMR1IF | 102              |
| RCREG   | EUSART R | Receive Dat | a Register |        |        |        |        |        | 296*             |
| RCSTA   | SPEN     | RX9         | SREN       | CREN   | ADDEN  | FERR   | OERR   | RX9D   | 301              |
| SPBRGL  |          |             |            | BRG-   | <7:0>  |        |        |        | 303*             |
| SPBRGH  |          | BRG<15:8>   |            |        |        |        |        |        |                  |
| TRISC   | TRISC7   | TRISC6      | TRISC5     | TRISC4 | TRISC3 | TRISC2 | TRISC1 | TRISC0 | 142              |
| TXSTA   | CSRC     | TX9         | TXEN       | SYNC   | SENDB  | BRGH   | TRMT   | TX9D   | 300              |

**Legend:** — = unimplemented read as '0'. Shaded cells are not used for synchronous master reception.

<sup>\*</sup> Page provides register information.

#### 25.4.2 SYNCHRONOUS SLAVE MODE

The following bits are used to configure the EUSART for Synchronous slave operation:

- SYNC = 1
- CSRC = 0
- SREN = 0 (for transmit); SREN = 1 (for receive)
- CREN = 0 (for transmit); CREN = 1 (for receive)
- SPEN = 1

Setting the SYNC bit of the TXSTA register configures the device for synchronous operation. Clearing the CSRC bit of the TXSTA register configures the device as a slave. Clearing the SREN and CREN bits of the RCSTA register ensures that the device is in the Transmit mode, otherwise the device will be configured to receive. Setting the SPEN bit of the RCSTA register enables the EUSART.

## 25.4.2.1 EUSART Synchronous Slave Transmit

The operation of the Synchronous Master and Slave modes are identical (see Section 25.4.1.3 "Synchronous Master Transmission"), except in the case of the Sleep mode.

If two words are written to the TXREG and then the SLEEP instruction is executed, the following will occur:

- The first character will immediately transfer to the TSR register and transmit.
- 2. The second word will remain in TXREG register.
- 3. The TXIF bit will not be set.
- After the first character has been shifted out of TSR, the TXREG register will transfer the second character to the TSR and the TXIF bit will now be set
- If the PEIE and TXIE bits are set, the interrupt will wake the device from Sleep and execute the next instruction. If the GIE bit is also set, the program will call the Interrupt Service Routine.

## 25.4.2.2 Synchronous Slave Transmission Set-up:

- Set the SYNC and SPEN bits and clear the CSRC bit.
- 2. Clear the ANSEL bit for the CK pin (if applicable).
- 3. Clear the CREN and SREN bits.
- If interrupts are desired, set the TXIE bit of the PIE1 register and the GIE and PEIE bits of the INTCON register.
- 5. If 9-bit transmission is desired, set the TX9 bit.
- 6. Enable transmission by setting the TXEN bit.
- If 9-bit transmission is selected, insert the Most Significant bit into the TX9D bit.
- 8. Start transmission by writing the Least Significant 8 bits to the TXREG register.

TABLE 25-9: SUMMARY OF REGISTERS ASSOCIATED WITH SYNCHRONOUS SLAVE TRANSMISSION

| Name    | Bit 7    | Bit 6      | Bit 5       | Bit 4  | Bit 3  | Bit 2  | Bit 1  | Bit 0  | Register on Page |
|---------|----------|------------|-------------|--------|--------|--------|--------|--------|------------------|
| BAUDCON | ABDOVF   | RCIDL      | _           | SCKP   | BRG16  | _      | WUE    | ABDEN  | 302              |
| INTCON  | GIE      | PEIE       | TMR0IE      | INTE   | IOCIE  | TMR0IF | INTF   | IOCIF  | 98               |
| PIE1    | TMR1GIE  | ADIE       | RCIE        | TXIE   | SSPIE  | CCP1IE | TMR2IE | TMR1IE | 99               |
| PIR1    | TMR1GIF  | ADIF       | RCIF        | TXIF   | SSPIF  | CCP1IF | TMR2IF | TMR1IF | 102              |
| RCSTA   | SPEN     | RX9        | SREN        | CREN   | ADDEN  | FERR   | OERR   | RX9D   | 301              |
| TRISC   | TRISC7   | TRISC6     | TRISC5      | TRISC4 | TRISC3 | TRISC2 | TRISC1 | TRISC0 | 142              |
| TXREG   | EUSART T | ransmit Da | ta Register |        |        |        |        |        | 293*             |
| TXSTA   | CSRC     | TX9        | TXEN        | SYNC   | SENDB  | BRGH   | TRMT   | TX9D   | 300              |

**Legend:** — = unimplemented read as '0'. Shaded cells are not used for synchronous slave transmission.

<sup>\*</sup> Page provides register information.

## 25.4.2.3 EUSART Synchronous Slave Reception

The operation of the Synchronous Master and Slave modes is identical (Section 25.4.1.5 "Synchronous Master Reception"), with the following exceptions:

- Sleep
- CREN bit is always set, therefore the receiver is never Idle
- · SREN bit, which is a "don't care" in Slave mode

A character may be received while in Sleep mode by setting the CREN bit prior to entering Sleep. Once the word is received, the RSR register will transfer the data to the RCREG register. If the RCIE enable bit is set, the interrupt generated will wake the device from Sleep and execute the next instruction. If the GIE bit is also set, the program will branch to the interrupt vector.

## 25.4.2.4 Synchronous Slave Reception Set-up:

- Set the SYNC and SPEN bits and clear the CSRC bit.
- 2. Clear the ANSEL bit for both the CK and DT pins (if applicable).
- If interrupts are desired, set the RCIE bit of the PIE1 register and the GIE and PEIE bits of the INTCON register.
- 4. If 9-bit reception is desired, set the RX9 bit.
- 5. Set the CREN bit to enable reception.
- The RCIF bit will be set when reception is complete. An interrupt will be generated if the RCIE bit was set.
- If 9-bit mode is enabled, retrieve the Most Significant bit from the RX9D bit of the RCSTA register.
- Retrieve the 8 Least Significant bits from the receive FIFO by reading the RCREG register.
- If an overrun error occurs, clear the error by either clearing the CREN bit of the RCSTA register or by clearing the SPEN bit which resets the EUSART.

TABLE 25-10: SUMMARY OF REGISTERS ASSOCIATED WITH SYNCHRONOUS SLAVE RECEPTION

| Name    | Bit 7    | Bit 6       | Bit 5      | Bit 4  | Bit 3  | Bit 2  | Bit 1  | Bit 0  | Register on Page |
|---------|----------|-------------|------------|--------|--------|--------|--------|--------|------------------|
| BAUDCON | ABDOVF   | RCIDL       | _          | SCKP   | BRG16  | _      | WUE    | ABDEN  | 302              |
| INTCON  | GIE      | PEIE        | TMR0IE     | INTE   | IOCIE  | TMR0IF | INTF   | IOCIF  | 98               |
| PIE1    | TMR1GIE  | ADIE        | RCIE       | TXIE   | SSPIE  | CCP1IE | TMR2IE | TMR1IE | 99               |
| PIR1    | TMR1GIF  | ADIF        | RCIF       | TXIF   | SSPIF  | CCP1IF | TMR2IF | TMR1IF | 102              |
| RCREG   | EUSART R | Receive Dat | a Register |        |        |        |        |        | 296*             |
| RCSTA   | SPEN     | RX9         | SREN       | CREN   | ADDEN  | FERR   | OERR   | RX9D   | 301              |
| TRISC   | TRISC7   | TRISC6      | TRISC5     | TRISC4 | TRISC3 | TRISC2 | TRISC1 | TRISC0 | 142              |
| TXSTA   | CSRC     | TX9         | TXEN       | SYNC   | SENDB  | BRGH   | TRMT   | TX9D   | 300              |

Legend: — = unimplemented read as '0'. Shaded cells are not used for synchronous slave reception.

<sup>\*</sup> Page provides register information.

## 25.5 EUSART Operation During Sleep

The EUSART will remain active during Sleep only in the Synchronous Slave mode. All other modes require the system clock and therefore cannot generate the necessary signals to run the Transmit or Receive Shift registers during Sleep.

Synchronous Slave mode uses an externally generated clock to run the Transmit and Receive Shift registers.

## 25.5.1 SYNCHRONOUS RECEIVE DURING SLEEP

To receive during Sleep, all the following conditions must be met before entering Sleep mode:

- RCSTA and TXSTA Control registers must be configured for Synchronous Slave Reception (see Section 25.4.2.4 "Synchronous Slave Reception Set-up:").
- If interrupts are desired, set the RCIE bit of the PIE1 register and the GIE and PEIE bits of the INTCON register.
- The RCIF interrupt flag must be cleared by reading RCREG to unload any pending characters in the receive buffer.

Upon entering Sleep mode, the device will be ready to accept data and clocks on the RX/DT and TX/CK pins, respectively. When the data word has been completely clocked in by the external device, the RCIF interrupt flag bit of the PIR1 register will be set. Thereby, waking the processor from Sleep.

Upon waking from Sleep, the instruction following the SLEEP instruction will be executed. If the Global Interrupt Enable (GIE) bit of the INTCON register is also set, then the Interrupt Service Routine at address 004h will be called.

## 25.5.2 SYNCHRONOUS TRANSMIT DURING SLEEP

To transmit during Sleep, all the following conditions must be met before entering Sleep mode:

- RCSTA and TXSTA Control registers must be configured for Synchronous Slave Transmission (see Section 25.4.2.2 "Synchronous Slave Transmission Set-up:").
- The TXIF interrupt flag must be cleared by writing the output data to the TXREG, thereby filling the TSR and transmit buffer.
- If interrupts are desired, set the TXIE bit of the PIE1 register and the PEIE bit of the INTCON register
- Interrupt enable bits TXIE of the PIE1 register and PEIE of the INTCON register must set.

Upon entering Sleep mode, the device will be ready to accept clocks on TX/CK pin and transmit data on the RX/DT pin. When the data word in the TSR has been completely clocked out by the external device, the pending byte in the TXREG will transfer to the TSR and the TXIF flag will be set. Thereby, waking the processor from Sleep. At this point, the TXREG is available to accept another character for transmission, which will clear the TXIF flag.


Upon waking from Sleep, the instruction following the SLEEP instruction will be executed. If the Global Interrupt Enable (GIE) bit is also set then the Interrupt Service Routine at address 0004h will be called.

# 26.0 CAPACITIVE SENSING (CPS) MODULE

The Capacitive Sensing (CPS) module allows for an interaction with an end user without a mechanical interface. In a typical application, the CPS module is attached to a pad on a Printed Circuit Board (PCB), which is electrically isolated from the end user. When the end user places their finger over the PCB pad, a capacitive load is added, causing a frequency shift in the CPS module. The CPS module requires software and at least one timer resource to determine the change in frequency. Key features of this module include:

- · Analog MUX for monitoring multiple inputs
- · Capacitive sensing oscillator
- · Multiple power ranges
- · Multiple timer resources
- · Software control
- · Operation during Sleep

FIGURE 26-1: CAPACITIVE SENSING BLOCK DIAGRAM



## 26.1 Analog MUX

The CPS module can monitor up to 16 inputs. The capacitive sensing inputs are defined as CPS<15:0>. To determine if a frequency change has occurred the user must:

- Select the appropriate CPS pin by setting the CPSCH<3:0> bits of the CPSCON1 register.
- · Set the corresponding ANSEL bit.
- · Set the corresponding TRIS bit.
- · Run the software algorithm.

Selection of the CPSx pin while the module is enabled will cause the capacitive sensing oscillator to be on the CPSx pin. Failure to set the corresponding ANSEL and TRIS bits can cause the capacitive sensing oscillator to stop, leading to false frequency readings.

## 26.2 Capacitive Sensing Oscillator

The capacitive sensing oscillator consists of a constant current source and a constant current sink, to produce a triangle waveform. The CPSOUT bit of the CPSCON0 register shows the status of the capacitive sensing oscillator, whether it is a sinking or sourcing current. The oscillator is designed to drive a capacitive load (single PCB pad) and at the same time, be a clock source to either Timer0 or Timer1. The oscillator has three different current settings as defined by CPSRNG<1:0> of the CPSCON0 register. The different current settings for the oscillator serve two purposes:

- Maximize the number of counts in a timer for a fixed time base.
- Maximize the count differential in the timer during a change in frequency.

### 26.3 Voltage References

The capacitive sensing oscillator uses voltage references to provide two voltage thresholds for oscillation. The upper voltage threshold is referred to as Ref+ and the lower voltage threshold is referred to as Ref-.

The Vss voltage determines the lower threshold level (Ref-) and the VDD voltage determines the upper threshold level (Ref+).

## 26.4 Power Ranges

The capacitive sensing oscillator can operate in one of three different power modes.

There are three distinct power ranges; low, medium and high. Current consumption is dependent upon the range selected. See Table 26-1 for proper power range selection.

The remaining mode is a Noise Detection mode that resides within the high range. The Noise Detection mode is unique in that it disables the sinking and sourcing of current on the analog pin but leaves the rest of the oscillator circuitry active. This reduces the oscillation frequency on the analog pin to zero and also greatly reduces the current consumed by the oscillator module.

When noise is introduced onto the pin, the oscillator is driven at the frequency determined by the noise. This produces a detectable signal at the comparator output, indicating the presence of activity on the pin.

Figure 26-2 shows a more detailed drawing of the current sources and comparators associated with the oscillator.

TABLE 26-1: POWER RANGE SELECTION

| CPSRNG<1:0> | Mode   | Nominal Current <sup>(1)</sup> |  |  |
|-------------|--------|--------------------------------|--|--|
| 0.0         | Off    | 0.0 μΑ                         |  |  |
| 01          | Low    | 0.1 μΑ                         |  |  |
| 10          | Medium | 1.2 μΑ                         |  |  |
| 11          | High   | 18 μΑ                          |  |  |

Note 1: See the applicable Electrical Specifications Chapter for more information.

### 26.5 Timer Resources

To measure the change in frequency of the capacitive sensing oscillator, a fixed time base is required. For the period of the fixed time base, the capacitive sensing oscillator is used to clock either Timer0 or Timer1. The frequency of the capacitive sensing oscillator is equal to the number of counts in the timer divided by the period of the fixed time base.

### 26.6 Fixed Time Base

To measure the frequency of the capacitive sensing oscillator, a fixed time base is required. Any timer resource or software loop can be used to establish the fixed time base. It is up to the end user to determine the method in which the fixed time base is generated.

| Note: | The fixed time base can not be generated  |  |  |  |  |
|-------|---|--|--|--|--|
|       | by the timer resource that the capacitive |  |  |  |  |
|       | sensing oscillator is clocking.           |  |  |  |  |

### 26.6.1 TIMER0

To select Timer0 as the timer resource for the CPS module:

- Set the T0XCS bit of the CPSCON0 register.
- Clear the TMR0CS bit of the OPTION\_REG register.

When Timer0 is chosen as the timer resource, the capacitive sensing oscillator will be the clock source for Timer0. Refer to **Section 20.0 "Timer0 Module"** for additional information.

### 26.6.2 TIMER1

To select Timer1 as the timer resource for the CPS module, set the TMR1CS<1:0> of the T1CON register to '11'. When Timer1 is chosen as the timer resource, the capacitive sensing oscillator will be the clock source for Timer1. Because the Timer1 module has a gate control, developing a time base for the frequency measurement can be simplified by using the Timer0 overflow flag.

It is recommend that the Timer0 overflow flag, in conjunction with the Toggle mode of the Timer1 gate, be used to develop the fixed time base required by the software portion of the CPS module. Refer to Section 21.12 "Timer1 Gate Control Register" for additional information.

**TABLE 26-2: TIMER1 ENABLE FUNCTION** 

| TMR10N | TMR1GE | Timer1 Operation       |  |  |
|--------|--------|------------------------|--|--|
| 0      | 0      | Off                    |  |  |
| 0      | 1      | Off                    |  |  |
| 1      | 0      | On                     |  |  |
| 1      | 1      | Count Enabled by input |  |  |

### 26.7 Software Control

The software portion of the CPS module is required to determine the change in frequency of the capacitive sensing oscillator. This is accomplished by the following:

- Setting a fixed time base to acquire counts on Timer0 or Timer1.
- Establishing the nominal frequency for the capacitive sensing oscillator.
- Establishing the reduced frequency for the capacitive sensing oscillator due to an additional capacitive load.
- · Set the frequency threshold.

## 26.7.1 NOMINAL FREQUENCY (NO CAPACITIVE LOAD)

To determine the nominal frequency of the capacitive sensing oscillator:

- Remove any extra capacitive load on the selected CPSx pin.
- At the start of the fixed time base, clear the timer resource.
- At the end of the fixed time base save the value in the timer resource.

The value of the timer resource is the number of oscillations of the capacitive sensing oscillator for the given time base. The frequency of the capacitive sensing oscillator is equal to the number of counts on in the timer divided by the period of the fixed time base.

## 26.7.2 REDUCED FREQUENCY (ADDITIONAL CAPACITIVE LOAD)

The extra capacitive load will cause the frequency of the capacitive sensing oscillator to decrease. To determine the reduced frequency of the capacitive sensing oscillator:

- Add a typical capacitive load on the selected CPSx pin.
- Use the same fixed time base as the nominal frequency measurement.
- At the start of the fixed time base, clear the timer resource.
- At the end of the fixed time base save the value in the timer resource.

The value of the timer resource is the number of oscillations of the capacitive sensing oscillator with an additional capacitive load. The frequency of the capacitive sensing oscillator is equal to the number of counts on in the timer divided by the period of the fixed time base. This frequency should be less than the value obtained during the nominal frequency measurement.

### 26.7.3 FREQUENCY THRESHOLD

The frequency threshold should be placed midway between the value of nominal frequency and the reduced frequency of the capacitive sensing oscillator. Refer to Application Note AN1103, "Software Handling for Capacitive Sensing" (DS01103) for more detailed information on the software required for CPS module.

Note:

For more information on general capacitive sensing refer to Application Notes:

- AN1101, "Introduction to Capacitive Sensing" (DS01101)
- AN1102, "Layout and Physical Design Guidelines for Capacitive Sensing" (DS01102)

## 26.8 Operation during Sleep

The capacitive sensing oscillator will continue to run as long as the module is enabled, independent of the part being in Sleep. In order for the software to determine if a frequency change has occurred, the part must be awake. However, the part does not have to be awake when the timer resource is acquiring counts.

Note

Timer0 does not operate when in Sleep, and therefore cannot be used for capacitive sense measurements in Sleep.

### REGISTER 26-1: CPSCON0: CAPACITIVE SENSING CONTROL REGISTER 0

| R/W-0/0 | R/W-0/0 | U-0 | U-0 | R/W-0/0     | R/W-0/0 | R-0/0  | R/W-0/0 |
|---------|---------|-----|-----|-------------|---------|--------|---------|
| CPSON   | _       | _   | _   | CPSRNG<1:0> |         | CPSOUT | T0XCS   |
| bit 7   |         |     |     |             |         |        | bit 0   |

Legend:R = Readable bitW = Writable bitU = Unimplemented bit, read as '0'u = Bit is unchangedx = Bit is unknown-n/n = Value at POR and BOR/Value at all other Resets'1' = Bit is set'0' = Bit is cleared

bit 7 **CPSON:** CPS Module Enable bit 1 = CPS module is enabled

0 = CPS module is disabled

bit 6-4 **Unimplemented:** Read as '0'

bit 3-2 CPSRNG<1:0>: Capacitive Sensing Current Range

00 = Oscillator is off

01 = Oscillator is in Low Range. Charge/Discharge Current is nominally 0.1 μA 10 = Oscillator is in Medium Range. Charge/Discharge Current is nominally 1.2 μA 11 = Oscillator is in High Range. Charge/Discharge Current is nominally 18 μA

bit 1 CPSOUT: Capacitive Sensing Oscillator Status bit

1 = Oscillator is sourcing current (Current flowing out of the pin)
 0 = Oscillator is sinking current (Current flowing into the pin)

bit 0 TOXCS: Timer0 External Clock Source Select bit

If TMR0CS = 1:

The T0XCS bit controls which clock external to the core/Timer0 module supplies Timer0:

1 = Timer0 clock source is the capacitive sensing oscillator

0 = Timer0 clock source is the T0CKI pin

If TMR0CS = 0:

Timer0 clock source is controlled by the core/Timer0 module and is Fosc/4

### REGISTER 26-2: CPSCON1: CAPACITIVE SENSING CONTROL REGISTER 1

| U-0   | U-0 | U-0 | U-0 | R/W-0/0 <sup>(1)</sup> | R/W-0/0 | R/W-0/0 | R/W-0/0 |
|-------|-----|-----|-----|------------------------|---------|---------|---------|
| _     | _   | _   | _   | CPSCH<3:0>             |         |         |         |
| bit 7 |     |     |     |                        |         |         | bit 0   |

Legend:R = Readable bitW = Writable bitU = Unimplemented bit, read as '0'u = Bit is unchangedx = Bit is unknown-n/n = Value at POR and BOR/Value at all other Resets'1' = Bit is set'0' = Bit is cleared

bit 7-4 Unimplemented: Read as '0'

bit 3-0 CPSCH<3:0>: Capacitive Sensing Channel Select bits

If CPSON = 0:

These bits are ignored. No channel is selected.

If CPSON = 1:

0000 = channel 0, (CPS0) 0001 = channel 1, (CPS1) 0010 = channel 2, (CPS2) 0011 = channel 3, (CPS3) 0100 = channel 4, (CPS4) 0101 = channel 5, (CPS5) 0110 = channel 6, (CPS6) 0111 = channel 7, (CPS7)

1000 = channel 8, (CPS8<sup>(1)</sup>) 1001 = channel 9, (CPS9<sup>(1)</sup>) 1010 = channel 10, (CPS10<sup>(1)</sup>) 1011 = channel 11, (CPS11<sup>(1)</sup>) 1100 = channel 12, (CPS12<sup>(1)</sup>)

1101 = channel 13, (CPS13<sup>(1)</sup>) 1110 = channel 14, (CPS14<sup>(1)</sup>) 1111 = channel 15, (CPS15<sup>(1)</sup>)

Note 1: These channels are not implemented on the PIC16(L)F1936.

2: This bit is not implemented on PIC16(L)F1936, read as '0'

TABLE 26-3: SUMMARY OF REGISTERS ASSOCIATED WITH CAPACITIVE SENSING

| Name       | Bit 7  | Bit 6  | Bit 5  | Bit 4  | Bit 3   | Bit 2  | Bit 1  | Bit 0  | Register on Page |
|------------|--------|--------|--------|--------|---------|--------|--------|--------|------------------|
| ANSELA     | -      | _      | ANSA5  | ANSA4  | ANSA3   | ANSA2  | ANSA1  | ANSA0  | 134              |
| ANSELB     | _      | _      | ANSB5  | ANSB4  | ANSB3   | ANSB2  | ANSB1  | ANSB0  | 139              |
| ANSELD     | ANSD7  | ANSD6  | ANSD5  | ANSD4  | ANSD3   | ANSD2  | ANSD1  | ANSD0  | 146              |
| CPSCON0    | CPSON  | _      | _      | _      | CPSRN   | G<1:0> | CPSOUT | T0XCS  | 323              |
| CPSCON1    | _      | _      | _      | _      |         | CPSCI  | H<3:0> |        | 324              |
| OPTION_REG | WPUEN  | INTEDG | TMR0CS | TMR0SE | PSA     | PS2    | PS1    | PS0    | 193              |
| T1CON      | TMR1C  | S<1:0> | T1CKP  | S<1:0> | T10SCEN | T1SYNC | _      | TMR10N | 203              |
| TRISA      | TRISA7 | TRISA6 | TRISA5 | TRISA4 | TRISA3  | TRISA2 | TRISA1 | TRISA0 | 133              |
| TRISB      | TRISB7 | TRISB6 | TRISB5 | TRISB4 | TRISB3  | TRISB2 | TRISB1 | TRISB0 | 138              |
| TRISD      | TRISD7 | TRISD6 | TRISD5 | TRISD4 | TRISD3  | TRISD2 | TRISD1 | TRISD0 | 145              |

**Legend:** — = Unimplemented location, read as '0'. Shaded cells are not used by the CPS module.

**NOTES:** 

## 27.0 LIQUID CRYSTAL DISPLAY (LCD) DRIVER MODULE


The Liquid Crystal Display (LCD) Driver module generates the timing control to drive a static or multiplexed LCD panel. In the PIC16(L)F1934/6/7 device, the module drives the panels of up to four commons and up to 24 segments. The LCD module also provides control of the LCD pixel data.

The LCD Driver module supports:

- · Direct driving of LCD panel
- · Three LCD clock sources with selectable prescaler
- Up to four common pins:
  - Static (1 common)
  - 1/2 multiplex (2 commons)
  - 1/3 multiplex (3 commons)
  - 1/4 multiplex (4 commons)
- · Segment pins up to:
  - 16 (PIC16(L)F1936)
  - 24 (PIC16(L)F1934/7)
- · Static, 1/2 or 1/3 LCD Bias

Note: COM3 and SEG15 share the same physical pin on the PIC16(L)F1936, therefore SEG15 is not available when using 1/4 multiplex displays.

#### FIGURE 27-1: LCD DRIVER MODULE BLOCK DIAGRAM



3: COM3 and SEG15 share the same physical pin on the PIC16(L)F1936, therefore SEG15 is not available

2: SEG<23:0> on PIC16F1934/1937, SEG<15:0> on PIC16(L)F1936.

when using 1/4 multiplex displays.

#### 27.1 LCD Registers

The module contains the following registers:

- LCD Control register (LCDCON)
- LCD Phase register (LCDPS)
- LCD Reference Ladder register (LCDRL)
- LCD Contrast Control register (LCDCST)
- LCD Reference Voltage Control register (LCDREF)
- Up to 3 LCD Segment Enable registers (LCDSEn)
- · Up to 12 LCD data registers (LCDDATAn)

TABLE 27-1: LCD SEGMENT AND DATA REGISTERS

|                 | # of LCD Registers |      |  |
|-----------------|--------------------|------|--|
| Device          | Segment<br>Enable  | Data |  |
| PIC16(L)F1936   | 2                  | 8    |  |
| PIC16(L)F1934/7 | 3                  | 12   |  |

The LCDCON register (Register 27-1) controls the operation of the LCD driver module. The LCDPS register (Register 27-2) configures the LCD clock source prescaler and the type of waveform; Type-A or Type-B. The LCDSEn registers (Register 27-5) configure the functions of the port pins.

The following LCDSEn registers are available:

- LCDSE0 SE<7:0>
- LCDSE1 SE<15:8>
- LCDSE2 SE<23:16><sup>(1)</sup>

Note 1: PIC16(L)F1934/7 only.

Once the module is initialized for the LCD panel, the individual bits of the LCDDATAn registers are cleared/set to represent a clear/dark pixel, respectively:

- LCDDATA0 SEG<7:0>COM0
- LCDDATA1 SEG<15:8>COM0
- LCDDATA2 SEG<23:16>COM0<sup>(1)</sup>
- LCDDATA3 SEG<7:0>COM1
- LCDDATA4 SEG<15:8>COM1
- LCDDATA5 SEG<23:16>COM1<sup>(1)</sup>
- LCDDATA6 SEG<7:0>COM2
- LCDDATA7 SEG<15:8>COM2
- LCDDATA8 SEG<23:16>COM2<sup>(1)</sup>
- LCDDATA9 SEG<7:0>COM3
- LCDDATA10 SEG<15:8>COM3
- LCDDATA11 SEG<23:16>COM3<sup>(1)</sup>

Note 1: PIC16(L)F1934/7 only.

As an example, LCDDATAn is detailed in Register 27-6.

Once the module is configured, the LCDEN bit of the LCDCON register is used to enable or disable the LCD module. The LCD panel can also operate during Sleep by clearing the SLPEN bit of the LCDCON register.

#### REGISTER 27-1: LCDCON: LIQUID CRYSTAL DISPLAY (LCD) CONTROL REGISTER

| R/W-0/0 | R/W-0/0 | R/C-0/0 | U-0 | R/W-0/0 | R/W-0/0 | R/W-1/1 | R/W-1/1 |
|---------|---------|---------|-----|---------|---------|---------|---------|
| LCDEN   | SLPEN   | WERR    | _   | CS<     | <1:0>   | LMUX    | <1:0>   |
| bit 7   |         |         |     |         |         | •       | bit 0   |

Legend:R = Readable bitW = Writable bitU = Unimplemented bit, read as '0'u = Bit is unchangedx = Bit is unknown-n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared C = Only clearable bit

bit 7 LCDEN: LCD Driver Enable bit

1 = LCD Driver module is enabled0 = LCD Driver module is disabled

bit 6 SLPEN: LCD Driver Enable in Sleep Mode bit

1 = LCD Driver module is disabled in Sleep mode0 = LCD Driver module is enabled in Sleep mode

bit 5 WERR: LCD Write Failed Error bit

1 = LCDDATAn register written while the WA bit of the LCDPS register = 0 (must be cleared in

software)

0 = No LCD write error

bit 4 Unimplemented: Read as '0'

bit 3-2 CS<1:0>: Clock Source Select bits

00 = Fosc/256

01 = T1OSC (Timer1)

1x = LFINTOSC (31 kHz)

bit 1-0 LMUX<1:0>: Commons Select bits

| LMUX<1:0>   | Multiplay      | Maximum Nur       | Bias            |            |
|-------------|----------------|-------------------|-----------------|------------|
| LIVIUX<1.0> | Multiplex      | PIC16(L)F1936     | PIC16(L)F1934/7 | Dias       |
| 0.0         | Static (COM0)  | 16                | 24              | Static     |
| 01          | 1/2 (COM<1:0>) | 32                | 48              | 1/2 or 1/3 |
| 10          | 1/3 (COM<2:0>) | 48                | 72              | 1/2 or 1/3 |
| 11          | 1/4 (COM<3:0>) | 60 <sup>(1)</sup> | 96              | 1/3        |

Note 1: On these devices, COM3 and SEG15 are shared on one pin, limiting the device from driving 64 pixels.

#### REGISTER 27-2: LCDPS: LCD PHASE REGISTER

| R/W-0/0 | R/W-0/0 | R-0/0 | R-0/0 | R/W-0/0 | R/W-0/0 | R/W-1/1 | R/W-1/1 |
|---------|---------|-------|-------|---------|---------|---------|---------|
| WFT     | BIASMD  | LCDA  | WA    |         | LP<     | 3:0>    |         |
| bit 7   |         |       |       |         |         |         | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared C = Only clearable bit

bit 7 WFT: Waveform Type bit

1 = Type-B phase changes on each frame boundary

0 = Type-A phase changes within each common type

bit 6 BIASMD: Bias Mode Select bit

When LMUX<1:0> = 00:

0 = Static Bias mode (do not set this bit to '1')

When LMUX<1:0> = 01:

1 = 1/2 Bias mode

0 = 1/3 Bias mode

When LMUX<1:0> = 10:

1 = 1/2 Bias mode

0 = 1/3 Bias mode

When LMUX<1:0> = 11:

0 = 1/3 Bias mode (do not set this bit to '1')

bit 5 LCDA: LCD Active Status bit

1 = LCD Driver module is active

0 = LCD Driver module is inactive

bit 4 WA: LCD Write Allow Status bit

1 = Writing to the LCDDATAn registers is allowed

0 = Writing to the LCDDATAn registers is not allowed

bit 3-0 LP<3:0>: LCD Prescaler Selection bits

1111 = 1:16

1110 = 1:15

1101 = 1:14

1100 = 1:13

1011 = 1:12

1010 = 1:11

1001 = 1:10

1000 = 1:9

0111 = 1:8

0111 - 1.0

0110 = 1:70101 = 1:6

0100 = 1:5

0011 = 1:4

0010 = 1:3

0001 = 1:2

0000 = 1:1

#### REGISTER 27-3: LCDREF: LCD REFERENCE VOLTAGE CONTROL REGISTER

| R/W-0/0 | R/W-0/0 | R/W-0/0 | U-0 | R/W-0/0 | R/W-0/0 | R/W-0/0 | U-0   |
|---------|---------|---------|-----|---------|---------|---------|-------|
| LCDIRE  | LCDIRS  | LCDIRI  | _   | VLCD3PE | VLCD2PE | VLCD1PE | _     |
| bit 7   |         |         |     |         |         |         | bit 0 |

| Legend:              |                      |   |
|----------------------|----------------------|---|
| R = Readable bit     | W = Writable bit     | U = Unimplemented bit, read as '0'                    |
| u = Bit is unchanged | x = Bit is unknown   | -n/n = Value at POR and BOR/Value at all other Resets |
| '1' = Bit is set     | '0' = Bit is cleared | C = Only clearable bit                                |
|                      |                      |   |

bit 7 LCDIRE: LCD Internal Reference Enable bit 1 = Internal LCD Reference is enabled and connected to the Internal Contrast Control circuit 0 = Internal LCD Reference is disabled bit 6 LCDIRS: LCD Internal Reference Source bit If LCDIRE = 1: 0 = Internal LCD Contrast Control is powered by VDD 1 = Internal LCD Contrast Control is powered by a 3.072V output of the FVR If LCDIRE = 0: Internal LCD Contrast Control is unconnected. LCD bandgap buffer is disabled. bit 5 LCDIRI: LCD Internal Reference Ladder Idle Enable bit Allows the Internal FVR buffer to shut down when the LCD Reference Ladder is in power mode 'B' 1 = When the LCD Reference Ladder is in power mode 'B', the LCD Internal FVR buffer is disabled 0 = The LCD Internal FVR Buffer ignores the LCD Reference Ladder Power mode bit 4 Unimplemented: Read as '0'

bit 3

VLCD3PE: VLCD3 Pin Enable bit

1 = The VLCD3 pin is connected to the internal bias voltage LCDBIAS3<sup>(1)</sup>

0 = The VLCD3 pin is not connected

bit 2

VLCD2PE: VLCD2 Pin Enable bit

1 = The VLCD2 pin is connected to the internal bias voltage LCDBIAS2<sup>(1)</sup>

0 = The VLCD2 pin is not connected

bit 1

VLCD1PE: VLCD1 Pin Enable bit

1 = The VLCD1 pin is connected to the internal bias voltage LCDBIAS1<sup>(1)</sup>

0 = The VLCD1 pin is not connected

bit 0

Unimplemented: Read as '0'

Note 1: Normal pin controls of TRISx and ANSELx are unaffected.

#### REGISTER 27-4: LCDCST: LCD CONTRAST CONTROL REGISTER

| U-0   | U-0 | U-0 | U-0 | U-0 | R/W-0/0 | R/W-0/0     | R/W-0/0 |
|-------|-----|-----|-----|-----|---------|-------------|---------|
| _     | _   | _   | _   | _   | ı       | _CDCST<2:0> |         |
| bit 7 |     |     |     |     |         |             | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared C = Only clearable bit

bit 7-3 **Unimplemented:** Read as '0'

bit 2-0 LCDCST<2:0>: LCD Contrast Control bits

Selects the resistance of the LCD contrast control resistor ladder

Bit Value = Resistor ladder

000 = Minimum Resistance (Maximum contrast). Resistor ladder is shorted.

001 = Resistor ladder is at 1/7th of maximum resistance

010 = Resistor ladder is at 2/7th of maximum resistance

011 = Resistor ladder is at 3/7th of maximum resistance

100 = Resistor ladder is at 4/7th of maximum resistance

101 = Resistor ladder is at 5/7th of maximum resistance

110 = Resistor ladder is at 6/7th of maximum resistance

111 = Resistor ladder is at maximum resistance (Minimum contrast).

#### REGISTER 27-5: LCDSEn: LCD SEGMENT ENABLE REGISTERS

| R/W-0/0 |
|---------|---------|---------|---------|---------|---------|---------|---------|
| SEn     |
| bit 7   |         |         |         |         |         |         | bit 0   |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 **SEn:** Segment Enable bits

1 = Segment function of the pin is enabled

0 = I/O function of the pin is enabled

#### **REGISTER 27-6: LCDDATAn: LCD DATA REGISTERS**

| R/W-x/u   |
|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|
| SEGx-COMy |
| bit 7     |           |           |           |           |           |           | bit 0     |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

u = Bit is unchanged x = Bit is unknown -n/n = Value at POR and BOR/Value at all other Resets

'1' = Bit is set '0' = Bit is cleared

bit 7-0 **SEGx-COMy:** Pixel On bits

1 = Pixel on (dark)

0 = Pixel off (clear)

#### 27.2 LCD Clock Source Selection

The LCD module has 3 possible clock sources:

- Fosc/256
- T10SC
- LFINTOSC

The first clock source is the system clock divided by 256 (Fosc/256). This divider ratio is chosen to provide about 1 kHz output when the system clock is 8 MHz. The divider is not programmable. Instead, the LCD prescaler bits LP<3:0> of the LCDPS register are used to set the LCD frame clock rate.

The second clock source is the T1OSC. This also gives about 1 kHz when a 32.768 kHz crystal is used with the Timer1 oscillator. To use the Timer1 oscillator as a clock source, the T1OSCEN bit of the T1CON register should be set.

The third clock source is the 31 kHz LFINTOSC, which provides approximately 1 kHz output.

The second and third clock sources may be used to continue running the LCD while the processor is in Sleep.


Using bits CS<1:0> of the LCDCON register can select any of these clock sources.

#### 27.2.1 LCD PRESCALER

A 4-bit counter is available as a prescaler for the LCD clock. The prescaler is not directly readable or writable; its value is set by the LP<3:0> bits of the LCDPS register, which determine the prescaler assignment and prescale ratio

The prescale values are selectable from 1:1 through 1:16.

FIGURE 27-2: LCD CLOCK GENERATION



#### 27.3 LCD Bias Voltage Generation

The LCD module can be configured for one of three bias types:


- Static Bias (2 voltage levels: Vss and VLCD)
- 1/2 Bias (3 voltage levels: Vss, 1/2 VLCD and VLCD)
- 1/3 Bias (4 voltage levels: Vss, 1/3 VLCD, 2/3 VLCD and VLCD)

**TABLE 27-2: LCD BIAS VOLTAGES** 

|            | Static Bias | 1/2 Bias | 1/3 Bias |
|------------|-------------|----------|----------|
| LCD Bias 0 | Vss         | Vss      | Vss      |
| LCD Bias 1 | _           | 1/2 VDD  | 1/3 VDD  |
| LCD Bias 2 | _           | 1/2 VDD  | 2/3 VDD  |
| LCD Bias 3 | VLCD3       | VLCD3    | VLCD3    |

So that the user is not forced to place external components and use up to three pins for bias voltage generation, internal contrast control and an internal reference ladder are provided internally. Both of these features may be used in conjunction with the external VLCD<3:1> pins, to provide maximum flexibility. Refer to Figure 27-3.

FIGURE 27-3: LCD BIAS VOLTAGE GENERATION BLOCK DIAGRAM



#### 27.4 LCD Bias Internal Reference Ladder

The internal reference ladder can be used to divide the LCD bias voltage two or three equally spaced voltages that will be supplied to the LCD segment pins. To create this, the reference ladder consists of three matched resistors. Refer to Figure 27-3.

#### 27.4.1 BIAS MODE INTERACTION

When in 1/2 Bias mode (BIASMD = 1), then the middle resistor of the ladder is shorted out so that only two voltages are generated. The current consumption of the ladder is higher in this mode, with the one resistor removed.

TABLE 27-3: LCD INTERNAL LADDER POWER MODES (1/3 BIAS)

| Power<br>Mode | Nominal Resistance of<br>Entire Ladder | Nominal<br>IDD |
|---------------|--|----------------|
| Low           | 3 Mohm                                 | 1 µA           |
| Medium        | 300 kohm                               | 10 μA          |
| High          | 30 kohm                                | 100 μΑ         |

#### 27.4.2 POWER MODES

The internal reference ladder may be operated in one of three power modes. This allows the user to trade off LCD contrast for power in the specific application. The larger the LCD glass, the more capacitance is present on a physical LCD segment, requiring more current to maintain the same contrast level.

Three different power modes are available, LP, MP and HP. The internal reference ladder can also be turned off for applications that wish to provide an external ladder or to minimize power consumption. Disabling the internal reference ladder results in all of the ladders being disconnected, allowing external voltages to be supplied.

Whenever the LCD module is inactive (LCDA = 0), the internal reference ladder will be turned off.


### 27.4.3 AUTOMATIC POWER MODE SWITCHING


As an LCD segment is electrically only a capacitor, current is drawn only during the interval where the voltage is switching. To minimize total device current, the LCD internal reference ladder can be operated in a different power mode for the transition portion of the duration. This is controlled by the LCDRL register (Register 27-7).


The LCDRL register allows switching between two power modes, designated 'A' and 'B'. 'A' Power mode is active for a programmable time, beginning at the time when the LCD segments transition. 'B' Power mode is the remaining time before the segments or commons change again. The LRLAT<2:0> bits select how long, if any, that the 'A' Power mode is active. Refer to Figure 27-4.

To implement this, the 5-bit prescaler used to divide the 32 kHz clock down to the LCD controller's 1 kHz base rate is used to select the power mode.

FIGURE 27-4: LCD INTERNAL REFERENCE LADDER POWER MODE SWITCHING DIAGRAM – TYPE A







#### REGISTER 27-7: LCDRL: LCD REFERENCE LADDER CONTROL REGISTERS

| R/W-0/0    | R/W-0/0 | R/W-0/0 R/W-0/0 |  | U-0 | R/W-0/0    | R/W-0/0 | R/W-0/0 |
|------------|---------|-----------------|--|-----|------------|---------|---------|
| LRLAP<1:0> |         | LRLBP<1:0>      |  | _   | LRLAT<2:0> |         |         |
| bit 7      |         |                 |  |     |            |         | bit 0   |

Legend:R = Readable bitW = Writable bitU = Unimplemented bit, read as '0'u = Bit is unchangedx = Bit is unknown-n/n = Value at POR and BOR/Value at all other Resets'1' = Bit is set'0' = Bit is cleared

bit 7-6 LRLAP<1:0>: LCD Reference Ladder A Time Power Control bits

During Time interval A (Refer to Figure 27-4):

00 = Internal LCD Reference Ladder is powered down and unconnected

01 = Internal LCD Reference Ladder is powered in Low-Power mode

10 = Internal LCD Reference Ladder is powered in Medium-Power mode

11 = Internal LCD Reference Ladder is powered in High-Power mode

bit 5-4 LRLBP<1:0>: LCD Reference Ladder B Time Power Control bits

During Time interval B (Refer to Figure 27-4):

00 = Internal LCD Reference Ladder is powered down and unconnected

01 = Internal LCD Reference Ladder is powered in Low-Power mode

10 = Internal LCD Reference Ladder is powered in Medium-Power mode

11 = Internal LCD Reference Ladder is powered in High-Power mode

bit 3 **Unimplemented:** Read as '0'

bit 2-0 LRLAT<2:0>: LCD Reference Ladder A Time Interval Control bits

Sets the number of 32 kHz clocks that the A Time Interval Power mode is active

For type A waveforms (WFT = 0):

000 = Internal LCD Reference Ladder is always in 'B' Power mode

001 = Internal LCD Reference Ladder is in 'A' Power mode for 1 clock and 'B' Power mode for 15 clocks

010 = Internal LCD Reference Ladder is in 'A' Power mode for 2 clocks and 'B' Power mode for 14 clocks

011 = Internal LCD Reference Ladder is in 'A' Power mode for 3 clocks and 'B' Power mode for 13 clocks

100 = Internal LCD Reference Ladder is in 'A' Power mode for 4 clocks and 'B' Power mode for 12 clocks

101 = Internal LCD Reference Ladder is in 'A' Power mode for 5 clocks and 'B' Power mode for 11 clocks

110 = Internal LCD Reference Ladder is in 'A' Power mode for 6 clocks and 'B' Power mode for 10 clocks 111 = Internal LCD Reference Ladder is in 'A' Power mode for 7 clocks and 'B' Power mode for 9 clocks

For type B waveforms (WFT = 1):

000 = Internal LCD Reference Ladder is always in 'B' Power mode.

001 = Internal LCD Reference Ladder is in 'A' Power mode for 1 clock and 'B' Power mode for 31 clocks

010 = Internal LCD Reference Ladder is in 'A' Power mode for 2 clocks and 'B' Power mode for 30 clocks

011 = Internal LCD Reference Ladder is in 'A' Power mode for 3 clocks and 'B' Power mode for 29 clocks

100 = Internal LCD Reference Ladder is in 'A' Power mode for 4 clocks and 'B' Power mode for 28 clocks

101 = Internal LCD Reference Ladder is in 'A' Power mode for 5 clocks and 'B' Power mode for 27 clocks

110 = Internal LCD Reference Ladder is in 'A' Power mode for 6 clocks and 'B' Power mode for 26 clocks

111 = Internal LCD Reference Ladder is in 'A' Power mode for 7 clocks and 'B' Power mode for 25 clocks


#### 27.4.4 CONTRAST CONTROL

The LCD contrast control circuit consists of a seven-tap resistor ladder, controlled by the LCDCST bits. Refer to Figure 27-7.

The contrast control circuit is used to decrease the output voltage of the signal source by a total of approximately 10%, when LCDCST = 111.

Whenever the LCD module is inactive (LCDA = 0), the contrast control ladder will be turned off (open).

FIGURE 27-7: INTERNAL REFERENCE AND CONTRAST CONTROL BLOCK DIAGRAM



#### 27.4.5 INTERNAL REFERENCE

Under firmware control, an internal reference for the LCD bias voltages can be enabled. When enabled, the source of this voltage can be either VDDIO or a voltage 3 times the main fixed voltage reference (3.072V). When no internal reference is selected, the LCD contrast control circuit is disabled and LCD bias must be provided externally.

Whenever the LCD module is inactive (LCDA = 0), the internal reference will be turned off.

When the internal reference is enabled and the Fixed Voltage Reference is selected, the LCDIRI bit can be used to minimize power consumption by tieing into the LCD Reference Ladder Automatic Power mode switching. When LCDIRI = 1 and the LCD reference ladder is in Power mode 'B', the LCD internal FVR buffer is disabled.

**Note:** The LCD module automatically turns on the Fixed Voltage Reference when needed.

#### 27.4.6 VLCD<3:1> PINS

The VLCD<3:1> pins provide the ability for an external LCD bias network to be used instead of the internal ladder. Use of the VLCD<3:1> pins does not prevent use of the internal ladder. Each VLCD pin has an independent control in the LCDREF register (Register 27-3), allowing access to any or all of the LCD Bias signals. This architecture allows for maximum flexibility in different applications

For example, the VLCD<3:1> pins may be used to add capacitors to the internal reference ladder, increasing the drive capacity.

For applications where the internal contrast control is insufficient, the firmware can choose to only enable the VLCD3 pin, allowing an external contrast control circuit to use the internal reference divider.

© 2008-2011 Microchip Technology Inc.

#### 27.5 LCD Multiplex Types

The LCD driver module can be configured into one of four multiplex types:

- Static (only COM0 is used)
- 1/2 multiplex (COM<1:0> are used)
- 1/3 multiplex (COM<2:0> are used)
- 1/4 multiplex (COM<3:0> are used)

The LMUX<1:0> bit setting of the LCDCON register decides which of the LCD common pins are used (see Table 27-4 for details).

If the pin is a digital I/O, the corresponding TRIS bit controls the data direction. If the pin is a COM drive, then the TRIS setting of that pin is overridden.

TABLE 27-4: COMMON PIN USAGE

| Multiplex | LMUX<br><1:0> | СОМЗ   | COM2   | COM1   |
|-----------|---------------|--------|--------|--------|
| Static    | 00            | Unused | Unused | Unused |
| 1/2       | 01            | Unused | Unused | Active |
| 1/3       | 10            | Unused | Active | Active |
| 1/4       | 11            | Active | Active | Active |

#### 27.6 Segment Enables

The LCDSEn registers are used to select the pin function for each segment pin. The selection allows each pin to operate as either an LCD segment driver or as one of the pin's alternate functions. To configure the pin as a segment pin, the corresponding bits in the LCDSEn registers must be set to '1'.

If the pin is a digital I/O, the corresponding TRIS bit controls the data direction. Any bit set in the LCDSEn registers overrides any bit settings in the corresponding TRIS register.

**Note:** On a Power-on Reset, these pins are configured as normal I/O, not LCD pins.

#### 27.7 Pixel Control

The LCDDATAx registers contain bits which define the state of each pixel. Each bit defines one unique pixel.

Register 27-6 shows the correlation of each bit in the LCDDATAx registers to the respective common and segment signals.

Any LCD pixel location not being used for display can be used as general purpose RAM.

#### 27.8 LCD Frame Frequency

The rate at which the COM and SEG outputs change is called the LCD frame frequency.

TABLE 27-5: FRAME FREQUENCY FORMULAS

| Multiplex | Frame Frequency =                            |  |  |  |  |  |
|-----------|--|--|--|--|--|--|
| Static    | Clock source/(4 x 1 x (LPD Prescaler) x 32)) |  |  |  |  |  |
| 1/2       | Clock source/(2 x 2 x (LPD Prescaler) x 32)) |  |  |  |  |  |
| 1/3       | Clock source/(1 x 3 x (LPD Prescaler) x 32)) |  |  |  |  |  |
| 1/4       | Clock source/(1 x 4 x (LPD Prescaler) x 32)) |  |  |  |  |  |

**Note:** Clock source is Fosc/256, T1OSC or LFINTOSC.

TABLE 27-6: APPROXIMATE FRAME FREQUENCY (IN Hz) USING Fosc @ 8 MHz, TIMER1 @ 32.768 kHz OR LFINTOSC

| LP<3:0> | Static | 1/2 | 1/3 | 1/4 |
|---------|--------|-----|-----|-----|
| 2       | 122    | 122 | 162 | 122 |
| 3       | 81     | 81  | 108 | 81  |
| 4       | 61     | 61  | 81  | 61  |
| 5       | 49     |     | 65  | 49  |
| 6 41    |        | 41  | 54  | 41  |
| 7       | 7 35   |     | 47  | 35  |

TABLE 27-7: LCD SEGMENT MAPPING WORKSHEET

| LCD<br>Function | СОМО                |                | COM1                |                | COM2                |                | СОМЗ                |                |
|-----------------|---------------------|----------------|---------------------|----------------|---------------------|----------------|---------------------|----------------|
|                 | LCDDATAx<br>Address | LCD<br>Segment | LCDDATAx<br>Address | LCD<br>Segment | LCDDATAx<br>Address | LCD<br>Segment | LCDDATAx<br>Address | LCD<br>Segment |
| SEG0            | LCDDATA0, 0         |                | LCDDATA3, 0         |                | LCDDATA6, 0         |                | LCDDATA9, 0         |                |
| SEG1            | LCDDATA0, 1         |                | LCDDATA3, 1         |                | LCDDATA6, 1         |                | LCDDATA9, 1         |                |
| SEG2            | LCDDATA0, 2         |                | LCDDATA3, 2         |                | LCDDATA6, 2         |                | LCDDATA9, 2         |                |
| SEG3            | LCDDATA0, 3         |                | LCDDATA3, 3         |                | LCDDATA6, 3         |                | LCDDATA9, 3         |                |
| SEG4            | LCDDATA0, 4         |                | LCDDATA3, 4         |                | LCDDATA6, 4         |                | LCDDATA9, 4         |                |
| SEG5            | LCDDATA0, 5         |                | LCDDATA3, 5         |                | LCDDATA6, 5         |                | LCDDATA9, 5         |                |
| SEG6            | LCDDATA0, 6         |                | LCDDATA3, 6         |                | LCDDATA6, 6         |                | LCDDATA9, 6         |                |
| SEG7            | LCDDATA0, 7         |                | LCDDATA3, 7         |                | LCDDATA6, 7         |                | LCDDATA9, 7         |                |
| SEG8            | LCDDATA1, 0         |                | LCDDATA4, 0         |                | LCDDATA7, 0         |                | LCDDATA10, 0        |                |
| SEG9            | LCDDATA1, 1         |                | LCDDATA4, 1         |                | LCDDATA7, 1         |                | LCDDATA10, 1        |                |
| SEG10           | LCDDATA1, 2         |                | LCDDATA4, 2         |                | LCDDATA7, 2         |                | LCDDATA10, 2        |                |
| SEG11           | LCDDATA1, 3         |                | LCDDATA4, 3         |                | LCDDATA7, 3         |                | LCDDATA10, 3        |                |
| SEG12           | LCDDATA1, 4         |                | LCDDATA4, 4         |                | LCDDATA7, 4         |                | LCDDATA10, 4        |                |
| SEG13           | LCDDATA1, 5         |                | LCDDATA4, 5         |                | LCDDATA7, 5         |                | LCDDATA10, 5        |                |
| SEG14           | LCDDATA1, 6         |                | LCDDATA4, 6         |                | LCDDATA7, 6         |                | LCDDATA10, 6        |                |
| SEG15           | LCDDATA1, 7         |                | LCDDATA4, 7         |                | LCDDATA7, 7         |                | LCDDATA10, 7        |                |
| SEG16           | LCDDATA2, 0         |                | LCDDATA5, 0         |                | LCDDATA8, 0         |                | LCDDATA11, 0        |                |
| SEG17           | LCDDATA2, 1         |                | LCDDATA5, 1         |                | LCDDATA8, 1         |                | LCDDATA11, 1        |                |
| SEG18           | LCDDATA2, 2         |                | LCDDATA5, 2         |                | LCDDATA8, 2         |                | LCDDATA11, 2        |                |
| SEG19           | LCDDATA2, 3         |                | LCDDATA5, 3         |                | LCDDATA8, 3         |                | LCDDATA11, 3        |                |
| SEG20           | LCDDATA2, 4         |                | LCDDATA5, 4         |                | LCDDATA8, 4         |                | LCDDATA11, 4        |                |
| SEG21           | LCDDATA2, 5         |                | LCDDATA5, 5         |                | LCDDATA8, 5         |                | LCDDATA11, 5        |                |
| SEG22           | LCDDATA2, 6         |                | LCDDATA5, 6         |                | LCDDATA8, 6         |                | LCDDATA11, 6        |                |
| SEG23           | LCDDATA2, 7         |                | LCDDATA5, 7         |                | LCDDATA8, 7         |                | LCDDATA11, 7        |                |

#### 27.9 LCD Waveform Generation

LCD waveforms are generated so that the net AC voltage across the dark pixel should be maximized and the net AC voltage across the clear pixel should be minimized. The net DC voltage across any pixel should be zero.

The COM signal represents the time slice for each common, while the SEG contains the pixel data.

The pixel signal (COM-SEG) will have no DC component and it can take only one of the two RMS values. The higher RMS value will create a dark pixel and a lower RMS value will create a clear pixel.


As the number of commons increases, the delta between the two RMS values decreases. The delta represents the maximum contrast that the display can have.


The LCDs can be driven by two types of waveform: Type-A and Type-B. In Type-A waveform, the phase changes within each common type, whereas in Type-B waveform, the phase changes on each frame boundary. Thus, Type-A waveform maintains 0 VDC over a single frame, whereas Type-B waveform takes two frames.


- Note 1: If Sleep has to be executed with LCD Sleep disabled (LCDCON<SLPEN> is '1'), then care must be taken to execute Sleep only when VDC on all the pixels is '0'.
  - 2: When the LCD clock source is Fosc/256, if Sleep is executed, irrespective of the LCDCON<SLPEN> setting, the LCD immediately goes into Sleep. Thus, take care to see that VDC on all pixels is '0' when Sleep is executed.


Figure 27-8 through Figure 27-18 provide waveforms for static, half-multiplex, 1/3-multiplex and 1/4-multiplex drives for Type-A and Type-B waveforms.


FIGURE 27-8: TYPE-A/TYPE-B WAVEFORMS IN STATIC DRIVE





























#### 27.10 LCD Interrupts

The LCD module provides an interrupt in two cases. An interrupt when the LCD controller goes from active to inactive controller. An interrupt also provides unframed boundaries for Type B waveform. The LCD timing generation provides an interrupt that defines the LCD frame timing.

### 27.10.1 LCD INTERRUPT ON MODULE SHUTDOWN

An LCD interrupt is generated when the module completes shutting down (LCDA goes from '1' to '0').

#### 27.10.2 LCD FRAME INTERRUPTS

A new frame is defined to begin at the leading edge of the COM0 common signal. The interrupt will be set immediately after the LCD controller completes accessing all pixel data required for a frame. This will occur at a fixed interval before the frame boundary (TFINT), as shown in Figure 27-19. The LCD controller will begin to access data for the next frame within the interval from the interrupt to when the controller begins to access data after the interrupt (TFWR). New data must be written within TFWR, as this is when the LCD controller will begin to access the data for the next frame.


When the LCD driver is running with Type-B waveforms and the LMUX<1:0> bits are not equal to '00' (static drive), there are some additional issues that must be addressed. Since the DC voltage on the pixel takes two frames to maintain zero volts, the pixel data must not change between subsequent frames. If the pixel data were allowed to change, the waveform for the odd frames would not necessarily be the complement of the waveform generated in the even frames and a DC component would be introduced into the panel. Therefore, when using Type-B waveforms, the user must synchronize the LCD pixel updates to occur within a subframe after the frame interrupt.

To correctly sequence writing while in Type-B, the interrupt will only occur on complete phase intervals. If the user attempts to write when the write is disabled, the WERR bit of the LCDCON register is set and the write does not occur.

Note:

The LCD frame interrupt is not generated when the Type-A waveform is selected and when the Type-B with no multiplex (static) is selected.

FIGURE 27-19: WAVEFORMS AND INTERRUPT TIMING IN QUARTER-DUTY CYCLE DRIVE (EXAMPLE – TYPE-B, NON-STATIC)



#### 27.11 Operation During Sleep

The LCD module can operate during Sleep. The selection is controlled by bit SLPEN of the LCDCON register. Setting the SLPEN bit allows the LCD module to go to Sleep. Clearing the SLPEN bit allows the module to continue to operate during Sleep.

If a SLEEP instruction is executed and SLPEN = 1, the LCD module will cease all functions and go into a very low-current Consumption mode. The module will stop operation immediately and drive the minimum LCD voltage on both segment and common lines. Figure 27-20 shows this operation.

The LCD module can be configured to operate during Sleep. The selection is controlled by bit SLPEN of the LCDCON register. Clearing SLPEN and correctly configuring the LCD module clock will allow the LCD module to operate during Sleep. Setting SLPEN and correctly executing the LCD module shutdown will disable the LCD module during Sleep and save power.

If a SLEEP instruction is executed and SLPEN = 1, the LCD module will immediately cease all functions, drive the outputs to Vss and go into a very Low-Current mode. The SLEEP instruction should only be executed after the LCD module has been disabled and the current cycle completed, thus ensuring that there are no DC voltages on the glass. To disable the LCD module, clear the LCDEN bit. The LCD module will complete the disabling process after the current frame, clear the LCDA bit and optionally cause an interrupt.

The steps required to properly enter Sleep with the LCD disabled are:

- Clear LCDEN
- Wait for LCDA = 0 either by polling or by interrupt
- Execute SLEEP

If SLPEN = 0 and SLEEP is executed while the LCD module clock source is Fosc/4, then the LCD module will halt with the pin driving the last LCD voltage pattern. Prolonged exposure to a fixed LCD voltage pattern will cause damage to the LCD glass. To prevent LCD glass damage, either perform the proper LCD module shutdown prior to Sleep, or change the LCD module clock to allow the LCD module to continue operation during Sleep.

If a SLEEP instruction is executed and SLPEN = 0 and the LCD module clock is either T1OSC or LFINTOSC, the module will continue to display the current contents of the LCDDATA registers. While in Sleep, the LCD data cannot be changed. If the LCDIE bit is set, the device will wake from Sleep on the next LCD frame boundary. The LCD module current consumption will not decrease in this mode; however, the overall device power consumption will be lower due to the shutdown of the CPU and other peripherals.

Table 27-8 shows the status of the LCD module during a Sleep while using each of the three available clock sources

Note:

When the LCDEN bit is cleared, the LCD module will be disabled at the completion of frame. At this time, the port pins will revert to digital functionality. To minimize power consumption due to floating digital inputs, the LCD pins should be driven low using the PORT and TRIS registers.

If a SLEEP instruction is executed and SLPEN = 0, the module will continue to display the current contents of the LCDDATA registers. To allow the module to continue operation while in Sleep, the clock source must be either the LFINTOSC or T1OSC external oscillator. While in Sleep, the LCD data cannot be changed. The LCD module current consumption will not decrease in this mode; however, the overall consumption of the device will be lower due to shut down of the core and other peripheral functions.


Table 27-8 shows the status of the LCD module during Sleep while using each of the three available clock sources:

TABLE 27-8: LCD MODULE STATUS DURING SLEEP

| Clock Source | SLPEN | Operational<br>During Sleep |
|--------------|-------|-----------------------------|
| T1OSC        | 0     | Yes                         |
| 11030        | 1     | No                          |
| LFINTOSC     | 0     | Yes                         |
| LFINTOSC     | 1     | No                          |
| Fosc/4       | 0     | No                          |
| FUSC/4       | 1     | No                          |

Note: The LFINTOSC or external T1OSC oscillator must be used to operate the LCD module during Sleep.

If LCD interrupts are being generated (Type-B waveform with a multiplex mode not static) and LCDIE = 1, the device will awaken from Sleep on the next frame boundary.



#### 27.12 Configuring the LCD Module

The following is the sequence of steps to configure the LCD module.

- 1. Select the frame clock prescale using bits LP<3:0> of the LCDPS register.
- Configure the appropriate pins to function as segment drivers using the LCDSEn registers.
- 3. Configure the LCD module for the following using the LCDCON register:
  - Multiplex and Bias mode, bits LMUX<1:0>
  - Timing source, bits CS<1:0>
  - Sleep mode, bit SLPEN
- 4. Write initial values to pixel data registers, LCDDATA0 through LCDDATA11.
- Clear LCD Interrupt Flag, LCDIF bit of the PIR2 register and if desired, enable the interrupt by setting bit LCDIE of the PIE2 register.
- Configure bias voltages by setting the LCDRL, LCDREF and the associated ANSELx registers as needed.
- 7. Enable the LCD module by setting bit LCDEN of the LCDCON register.

#### 27.13 Disabling the LCD Module

To disable the LCD module, write all '0's to the LCDCON register.

#### 27.14 LCD Current Consumption

When using the LCD module the current consumption consists of the following three factors:

- Oscillator Selection
- · LCD Bias Source
- · Capacitance of the LCD segments

The current consumption of just the LCD module can be considered negligible compared to these other factors.

#### 27.14.1 OSCILLATOR SELECTION

The current consumed by the clock source selected must be considered when using the LCD module. See the applicable Electrical Specifications Chapter for oscillator current consumption information.

#### 27.14.2 LCD BIAS SOURCE

The LCD bias source, internal or external, can contribute significantly to the current consumption. Use the highest possible resistor values while maintaining contrast to minimize current.

### 27.14.3 CAPACITANCE OF THE LCD SEGMENTS

The LCD segments which can be modeled as capacitors which must be both charged and discharged every frame. The size of the LCD segment and its technology determines the segment's capacitance.

TABLE 27-9: SUMMARY OF REGISTERS ASSOCIATED WITH LCD OPERATION

| Name      | Bit 7         | Bit 6         | Bit 5         | Bit 4         | Bit 3         | Bit 2         | Bit 1         | Bit 0         | Register<br>on Page |
|-----------|---------------|---------------|---------------|---------------|---------------|---------------|---------------|---------------|---------------------|
| INTCON    | GIE           | PEIE          | TMR0IE        | INTE          | IOCIE         | TMR0IF        | INTF          | IOCIF         | 98                  |
| LCDCON    | LCDEN         | SLPEN         | WERR          | _             | CS<1:0>       |               | LMUX          | LMUX<1:0>     |                     |
| LCDCST    | _             | _             | 1             | _             |               | I             | _CDCST<2:0    | >             | 332                 |
| LCDDATA0  | SEG7<br>COM0  | SEG6<br>COM0  | SEG5<br>COM0  | SEG4<br>COM0  | SEG3<br>COM0  | SEG2<br>COM0  | SEG1<br>COM0  | SEG0<br>COM0  | 333                 |
| LCDDATA1  | SEG15<br>COM0 | SEG14<br>COM0 | SEG13<br>COM0 | SEG12<br>COM0 | SEG11<br>COM0 | SEG10<br>COM0 | SEG9<br>COM0  | SEG8<br>COM0  | 333                 |
| LCDDATA2  | SEG23<br>COM0 | SEG22<br>COM0 | SEG21<br>COM0 | SEG20<br>COM0 | SEG19<br>COM0 | SEG18<br>COM0 | SEG17<br>COM0 | SEG16<br>COM0 | 333                 |
| LCDDATA3  | SEG7<br>COM1  | SEG6<br>COM1  | SEG5<br>COM1  | SEG4<br>COM1  | SEG3<br>COM1  | SEG2<br>COM1  | SEG1<br>COM1  | SEG0<br>COM1  | 333                 |
| LCDDATA4  | SEG15<br>COM1 | SEG14<br>COM1 | SEG13<br>COM1 | SEG12<br>COM1 | SEG11<br>COM1 | SEG10<br>COM1 | SEG9<br>COM1  | SEG8<br>COM1  | 333                 |
| LCDDATA5  | SEG23<br>COM1 | SEG22<br>COM1 | SEG21<br>COM1 | SEG20<br>COM1 | SEG19<br>COM1 | SEG18<br>COM1 | SEG17<br>COM1 | SEG16<br>COM1 | 333                 |
| LCDDATA6  | SEG7<br>COM2  | SEG6<br>COM2  | SEG5<br>COM2  | SEG4<br>COM2  | SEG3<br>COM2  | SEG2<br>COM2  | SEG1<br>COM2  | SEG0<br>COM2  | 333                 |
| LCDDATA7  | SEG15<br>COM2 | SEG14<br>COM2 | SEG13<br>COM2 | SEG12<br>COM2 | SEG11<br>COM2 | SEG10<br>COM2 | SEG9<br>COM2  | SEG8<br>COM2  | 333                 |
| LCDDATA8  | SEG23<br>COM2 | SEG22<br>COM2 | SEG21<br>COM2 | SEG20<br>COM2 | SEG19<br>COM2 | SEG18<br>COM2 | SEG17<br>COM2 | SEG16<br>COM2 | 333                 |
| LCDDATA9  | SEG7<br>COM3  | SEG6<br>COM3  | SEG5<br>COM3  | SEG4<br>COM3  | SEG3<br>COM3  | SEG2<br>COM3  | SEG1<br>COM3  | SEG0<br>COM3  | 333                 |
| LCDDATA10 | SEG15<br>COM3 | SEG14<br>COM3 | SEG13<br>COM3 | SEG12<br>COM3 | SEG11<br>COM3 | SEG10<br>COM3 | SEG9<br>COM3  | SEG8<br>COM3  | 333                 |
| LCDDATA11 | SEG23<br>COM3 | SEG22<br>COM3 | SEG21<br>COM3 | SEG20<br>COM3 | SEG19<br>COM3 | SEG18<br>COM3 | SEG17<br>COM3 | SEG16<br>COM3 | 333                 |
| LCDPS     | WFT           | BIASMD        | LCDA          | WA            | LP<3:0>       |               |               | 330           |                     |
| LCDREF    | LCDIRE        | LCDIRS        | LCDIRI        | _             | VLCD3PE       | VLCD2PE       | VLCD1PE       | _             | 331                 |
| LCDRL     | LRLAP<1:0>    |               |               |               |               |               | 340           |               |                     |
| LCDSE0    |               |               |               | SE            | E<7:0>        |               |               |               | 333                 |
| LCDSE1    | SE<15:8>      |               |               |               |               |               |               | 333           |                     |
| LCDSE2    | SE<23:16>     |               |               |               |               |               | 333           |               |                     |
| PIE2      | OSFIE         | C2IE          | C1IE          | EEIE          | BCLIE         | LCDIE         | _             | CCP2IE        | 100                 |
| PIR2      | OSFIF         | C2IF          | C1IF          | EEIF          | BCLIF         | LCDIF         | _             | CCP2IF        | 103                 |
| T1CON     | TMR1C         | S<1:0>        | T1CKP         | S<1:0>        | T10SCEN       | T1SYNC        | _             | TMR10N        | 203                 |

**Legend:** — = unimplemented location, read as '0'. Shaded cells are not used by the LCD module.

# 28.0 IN-CIRCUIT SERIAL PROGRAMMING™ (ICSP™)

ICSP<sup>TM</sup> programming allows customers to manufacture circuit boards with unprogrammed devices. Programming can be done after the assembly process allowing the device to be programmed with the most recent firmware or a custom firmware. Five pins are needed for ICSP<sup>TM</sup> programming:

- ICSPCLK
- ICSPDAT
- MCLR/VPP
- VDD
- Vss


In Program/Verify mode the Program Memory, User IDs and the Configuration Words are programmed through serial communications. The ICSPDAT pin is a bidirectional I/O used for transferring the serial data and the ICSPCLK pin is the clock input. For more information on ICSP™ refer to the "PIC16193X/PIC16LF193X Memory Programming Specification" (DS41360).

# 28.1 High-Voltage Programming Entry Mode

The device is placed into High-Voltage Programming Entry mode by holding the ICSPCLK and ICSPDAT pins low then raising the voltage on MCLR/VPP to VIHH.

Some programmers produce VPP greater than VIHH (9.0V), an external circuit is required to limit the VPP voltage. See Figure 28-1 for example circuit.

FIGURE 28-1: VPP LIMITER EXAMPLE CIRCUIT



**Note:** The MPLAB<sup>®</sup> ICD 2 produces a VPP voltage greater than the maximum VPP specification of the PIC16(L)F1934/6/7.

# 28.2 Low-Voltage Programming Entry Mode

The Low-Voltage Programming Entry mode allows the PIC16(L)F1934/6/7 devices to be programmed using VDD only, without high voltage. When the LVP bit of Configuration Word 2 is set to '1', the low-voltage ICSP programming entry is enabled. To disable the Low-Voltage ICSP mode, the LVP bit must be programmed to '0'.

Entry into the Low-Voltage Programming Entry mode requires the following steps:

- 1. MCLR is brought to VIL.
- A 32-bit key sequence is presented on ICSPDAT, while clocking ICSPCLK.

Once the key sequence is complete,  $\overline{\text{MCLR}}$  must be held at VIL for as long as Program/Verify mode is to be maintained.


If low-voltage programming is enabled (LVP = 1), the  $\overline{\text{MCLR}}$  Reset function is automatically enabled and cannot be disabled. See **Section 6.3** "MCLR" for more information.

The LVP bit can only be reprogrammed to '0' by using the High-Voltage Programming mode.

## 28.3 Common Programming Interfaces


Connection to a target device is typically done through an ICSP™ header. A commonly found connector on development tools is the RJ-11 in the 6P6C (6 pin, 6 connector) configuration. See Figure 28-2.

FIGURE 28-2: ICD RJ-11 STYLE CONNECTOR INTERFACE



Another connector often found in use with the PICkit™ programmers is a standard 6-pin header with 0.1 inch spacing. Refer to Figure 28-3.


FIGURE 28-3: PICkit™ STYLE CONNECTOR INTERFACE



For additional interface recommendations, refer to your specific device programmer manual prior to PCB design.

It is recommended that isolation devices be used to separate the programming pins from other circuitry. The type of isolation is highly dependent on the specific application and may include devices such as resistors, diodes, or even jumpers. See Figure 28-4 for more information.

FIGURE 28-4: TYPICAL CONNECTION FOR ICSP™ PROGRAMMING



**NOTES:** 

### 29.0 INSTRUCTION SET SUMMARY

Each PIC16 instruction is a 14-bit word containing the operation code (opcode) and all required operands. The opcodes are broken into three broad categories.

- Byte Oriented
- · Bit Oriented
- · Literal and Control

The literal and control category contains the most varied instruction word format.

Table 29-3 lists the instructions recognized by the MPASM $^{\text{TM}}$  assembler.

All instructions are executed within a single instruction cycle, with the following exceptions, which may take two or three cycles:

- Subroutine takes two cycles (CALL, CALLW)
- Returns from interrupts or subroutines take two cycles (RETURN, RETLW, RETFIE)
- Program branching takes two cycles (GOTO, BRA, BRW, BTFSS, BTFSC, DECFSZ, INCSFZ)
- One additional instruction cycle will be used when any instruction references an indirect file register and the file select register is pointing to program memory.

One instruction cycle consists of 4 oscillator cycles; for an oscillator frequency of 4 MHz, this gives a nominal instruction execution rate of 1 MHz.

All instruction examples use the format '0xhh' to represent a hexadecimal number, where 'h' signifies a hexadecimal digit.

#### 29.1 Read-Modify-Write Operations

Any instruction that specifies a file register as part of the instruction performs a Read-Modify-Write (R-M-W) operation. The register is read, the data is modified, and the result is stored according to either the instruction, or the destination designator 'd'. A read operation is performed on a register even if the instruction writes to that register.

TABLE 29-1: OPCODE FIELD DESCRIPTIONS

| Field | Description   |
|-------|---|
| f     | Register file address (0x00 to 0x7F)  |
| W     | Working register (accumulator)  |
| b     | Bit address within an 8-bit file register   |
| k     | Literal field, constant data or label   |
| х     | Don't care location (= 0 or 1).  The assembler will generate code with x = 0.  It is the recommended form of use for compatibility with all Microchip software tools. |
| d     | Destination select; $d = 0$ : store result in W, $d = 1$ : store result in file register f. Default is $d = 1$ .  |
| n     | FSR or INDF number. (0-1)   |
| mm    | Pre-post increment-decrement mode selection   |

# TABLE 29-2: ABBREVIATION DESCRIPTIONS

| Field | Description     |  |
|-------|-----------------|--|
| PC    | Program Counter |  |
| TO    | Time-out bit    |  |
| С     | Carry bit       |  |
| DC    | Digit carry bit |  |
| Z     | Zero bit        |  |
| PD    | Power-down bit  |  |

# FIGURE 29-1: GENERAL FORMAT FOR INSTRUCTIONS

| Byte-oriented file register operations 13 8 7 6 0                               |
|---|
| OPCODE d f (FILE #)   |
| d = 0 for destination W d = 1 for destination f f = 7-bit file register address |
| Bit-oriented file register operations 13 10 9 7 6 0                             |
| OPCODE b (BIT #) f (FILE #)   |
| b = 3-bit bit address<br>f = 7-bit file register address                        |
| Literal and control operations  |
| General   |
| 13 8 7 0 OPCODE k (literal)   |
|   |
| k = 8-bit immediate value   |
| CALL and GOTO instructions only   |
| 13 11 10 0  |
| OPCODE k (literal)  |
| k = 11-bit immediate value  |
| MOVLP instruction only 13 7 6 0   |
| OPCODE k (literal)  |
| k = 7-bit immediate value   |
| MOVLB instruction only  |
| 13 5 4 0 OPCODE k (literal)   |
| k = 5-bit immediate value   |
| BRA instruction only  |
| 13 9 8 0 OPCODE k (literal)   |
| <u> </u>  |
| k = 9-bit immediate value   |
| FSR Offset instructions 13 7 6 5 0  |
| OPCODE n k (literal)  |
| n = appropriate FSR<br>k = 6-bit immediate value                                |
| FSR Increment instructions  13 3 2 1 0  |
| OPCODE n m (mode)   |
| n = appropriate FSR<br>m = 2-bit mode value                                     |
| OPCODE only 13 0  |
| OPCODE  |
|   |

TABLE 29-3: PIC16(L)F1934/6/7 ENHANCED INSTRUCTION SET

| Mnen     | nonic,     | December 1   | 0          |          | 14-Bit | Opcode | )    | Status   | Natar      |
|----------|------------|--|------------|----------|--------|--------|------|----------|------------|
| Oper     | rands      | Description  | Cycles     | MSb      |        |        | LSb  | Affected | Notes      |
|          |            | BYTE-ORIENTED FILE REGIS                             | TER OPE    | RATIO    | NS     |        |      |          |            |
| ADDWF    | f, d       | Add W and f  | 1          | 00       | 0111   | dfff   | ffff | C, DC, Z | 2          |
| ADDWFC   | f, d       | Add with Carry W and f                               | 1          | 11       | 1101   | dfff   | ffff | C, DC, Z | 2          |
| ANDWF    | f, d       | AND W with f   | 1          | 00       | 0101   | dfff   | ffff | Z        | 2          |
| ASRF     | f, d       | Arithmetic Right Shift                               | 1          | 11       | 0111   | dfff   | ffff | C, Z     | 2          |
| LSLF     | f, d       | Logical Left Shift                                   | 1          | 11       | 0101   | dfff   | ffff | C, Z     | 2          |
| LSRF     | f, d       | Logical Right Shift                                  | 1          | 11       | 0110   | dfff   | ffff | C, Z     | 2          |
| CLRF     | f          | Clear f  | 1          | 00       | 0001   | lfff   | ffff | Z        | 2          |
| CLRW     | _          | Clear W  | 1          | 00       | 0001   | 0000   | 00xx | Z        |            |
| COMF     | f, d       | Complement f   | 1          | 00       | 1001   | dfff   | ffff | Z        | 2          |
| DECF     | f, d       | Decrement f  | 1          | 00       | 0011   | dfff   | ffff | Z        | 2          |
| INCF     | f, d       | Increment f  | 1          | 00       | 1010   | dfff   | ffff | Z        | 2          |
| IORWF    | f, d       | Inclusive OR W with f                                | 1          | 00       | 0100   | dfff   | ffff | Z        | 2          |
| MOVF     | f, d       | Move f   | 1          | 00       | 1000   | dfff   | ffff | Z        | 2          |
| MOVWF    | f          | Move W to f  | 1          | 00       | 0000   | 1fff   | ffff |          | 2          |
| RLF      | f, d       | Rotate Left f through Carry                          | 1          | 00       | 1101   | dfff   | ffff | С        | 2          |
| RRF      | f, d       | Rotate Right f through Carry                         | 1          | 00       | 1100   | dfff   | ffff | С        | 2          |
| SUBWF    | f, d       | Subtract W from f                                    | 1          | 00       | 0010   | dfff   | ffff | C, DC, Z | 2          |
| SUBWFB   | f, d       | Subtract with Borrow W from f                        | 1          | 11       | 1011   | dfff   | ffff | C, DC, Z | 2          |
| SWAPF    | f, d       | Swap nibbles in f                                    | 1          | 00       | 1110   | dfff   | ffff | , ,      | 2          |
| XORWF    | f, d       | Exclusive OR W with f                                | 1          | 00       | 0110   | dfff   | ffff | Z        | 2          |
|          |            | BYTE ORIENTED SKIP O                                 | PERATIO    | ONS      |        |        |      |          | •          |
| DECFSZ   | f, d       | Decrement f, Skip if 0                               | 1(2)       | 00       | 1011   | dfff   | ffff |          | 1, 2       |
| INCFSZ   | f, d       | Increment f, Skip if 0                               | 1(2)       | 00       | 1111   | dfff   | ffff |          | 1, 2       |
|          |            | BIT-ORIENTED FILE REGIST                             | ER OPER    | RATION   | IS     |        | •    |          |            |
| BCF      | f, b       | Bit Clear f  | 1          | 01       | 00bb   | bfff   | ffff |          | 2          |
| BSF      | f, b       | Bit Set f  | 1          | 01       | 01bb   | bfff   | ffff |          | 2          |
|          |            | BIT-ORIENTED SKIP O                                  | PERATIO    | NS       |        |        | ı    |          | •          |
| BTFSC    | f, b       | Bit Test f, Skip if Clear                            | 1 (2)      | 01       | 10bb   | bfff   | ffff |          | 1, 2       |
| BTFSS    | f, b       | Bit Test f, Skip if Set                              | 1 (2)      | 01       | 11bb   | bfff   | ffff |          | 1, 2       |
| LITERAL  | OPERATIO   | •  | , ,        |          |        |        |      |          |            |
| ADDLW    | k          | Add literal and W                                    | 1          | 11       | 1110   | kkkk   | kkkk | C, DC, Z |            |
| ANDLW    | k          | AND literal with W                                   | 1          | 11       | 1001   |        |      | Z        |            |
| IORLW    | k          | Inclusive OR literal with W                          | 1          | 11       | 1000   | kkkk   |      | Z        |            |
| MOVLB    | k          | Move literal to BSR                                  | 1          | 00       | 0000   | 001k   |      |          |            |
| MOVLP    | k          | Move literal to PCLATH                               | 1          | 11       | 0001   | 1kkk   |      |          |            |
| MOVLW    | k          | Move literal to W                                    | 1          | 11       | 0000   | kkkk   | kkkk |          |            |
| SUBLW    | k          | Subtract W from literal                              | 1          | 11       | 1100   | kkkk   |      | C, DC, Z |            |
| XORLW    | k          | Exclusive OR literal with W                          | 1          | 11       |        | kkkk   |      | Z Z      |            |
| <u> </u> | he Program | Counter (PC) is modified, or a conditional test is t | rue the in | etructio |        |        |      |          | L cycle is |

Note 1:If the Program Counter (PC) is modified, or a conditional test is true, the instruction requires two cycles. The second cycle is executed as a NOP.

<sup>2:</sup> If this instruction addresses an INDF register and the MSb of the corresponding FSR is set, this instruction will require one additional instruction cycle.

TABLE 29-3: PIC16(L)F1938/9 ENHANCED INSTRUCTION SET (CONTINUED)

|                       |                     | †   | 1      |               |      |      |        |          |        |
|-----------------------|---------------------|---|--------|---------------|------|------|--------|----------|--------|
| Mnemonic,<br>Operands |                     | Description                                   | Cycles | 14-Bit Opcode |      |      | Status | Notes    |        |
|                       |                     | Description                                   |        | MSb           |      |      | LSb    | Affected | 140162 |
|                       | •                   | CONTROL OPERA                                 | TIONS  | •             |      | •    | •      | •        |        |
| BRA                   | k                   | Relative Branch                               | 2      | 11            | 001k | kkkk | kkkk   |          |        |
| BRW                   | _                   | Relative Branch with W                        | 2      | 00            | 0000 | 0000 | 1011   |          |        |
| CALL                  | k                   | Call Subroutine                               | 2      | 10            | 0kkk | kkkk | kkkk   |          |        |
| CALLW                 | _                   | Call Subroutine with W                        | 2      | 00            | 0000 | 0000 | 1010   |          |        |
| GOTO                  | k                   | Go to address                                 | 2      | 10            | 1kkk | kkkk | kkkk   |          |        |
| RETFIE                | k                   | Return from interrupt                         | 2      | 00            | 0000 | 0000 | 1001   |          |        |
| RETLW                 | k                   | Return with literal in W                      | 2      | 11            | 0100 | kkkk | kkkk   |          |        |
| RETURN                | _                   | Return from Subroutine                        | 2      | 00            | 0000 | 0000 | 1000   |          |        |
|                       | INHERENT OPERATIONS |   |        |               |      |      |        |          |        |
| CLRWDT                | _                   | Clear Watchdog Timer                          | 1      | 00            | 0000 | 0110 | 0100   | TO, PD   |        |
| NOP                   | _                   | No Operation                                  | 1      | 00            | 0000 | 0000 | 0000   |          |        |
| OPTION                | _                   | Load OPTION_REG register with W               | 1      | 00            | 0000 | 0110 | 0010   |          |        |
| RESET                 | _                   | Software device Reset                         | 1      | 00            | 0000 | 0000 | 0001   |          |        |
| SLEEP                 | _                   | Go into Standby mode                          | 1      | 00            | 0000 | 0110 | 0011   | TO, PD   |        |
| TRIS                  | f                   | Load TRIS register with W                     | 1      | 00            | 0000 | 0110 | Offf   |          |        |
|                       |                     | C-COMPILER OPT                                | IMIZED | •             |      |      |        |          |        |
| ADDFSR                | n, k                | Add Literal k to FSRn                         | 1      | 11            | 0001 | 0nkk | kkkk   |          |        |
| MOVIW                 | n mm                | Move Indirect FSRn to W with pre/post inc/dec | 1      | 00            | 0000 | 0001 | 0nmm   | Z        | 2, 3   |
|                       |                     | modifier, mm                                  |        |               |      |      |        |          |        |
|                       | k[n]                | Move INDFn to W, Indexed Indirect.            | 1      | 11            | 1111 | 0nkk | kkkk   | Z        | 2      |
| MOVWI                 | n mm                | Move W to Indirect FSRn with pre/post inc/dec | 1      | 00            | 0000 | 0001 | 1nmm   |          | 2, 3   |
|                       |                     | modifier, mm                                  |        |               |      |      |        |          |        |
|                       | k[n]                | Move W to INDFn, Indexed Indirect.            | 1      | 11            | 1111 | 1nkk | kkkk   |          | 2      |

Note 1:If the Program Counter (PC) is modified, or a conditional test is true, the instruction requires two cycles. The second cycle is executed as a NOP.

<sup>2:</sup> If this instruction addresses an INDF register and the MSb of the corresponding FSR is set, this instruction will require one additional instruction cycle.

<sup>3:</sup> See Table in the MOVIW and MOVWI instruction descriptions.

## 29.2 Instruction Descriptions

| ADDFSR           | Add Literal to FSRn   |  |  |  |  |
|------------------|---|--|--|--|--|
| Syntax:          | [ label ] ADDFSR FSRn, k  |  |  |  |  |
| Operands:        | $-32 \le k \le 31$<br>$n \in [0, 1]$  |  |  |  |  |
| Operation:       | $FSR(n) + k \to FSR(n)$   |  |  |  |  |
| Status Affected: | None  |  |  |  |  |
| Description:     | The signed 6-bit literal 'k' is added to the contents of the FSRnH:FSRnL register pair.                   |  |  |  |  |
|                  | FSRn is limited to the range 0000h - FFFFh. Moving beyond these bounds will cause the FSR to wrap around. |  |  |  |  |

| ANDLW            | AND literal with W  |
|------------------|---|
| Syntax:          | [ label ] ANDLW k   |
| Operands:        | $0 \leq k \leq 255$   |
| Operation:       | (W) .AND. $(k) \rightarrow (W)$   |
| Status Affected: | Z   |
| Description:     | The contents of W register are AND'ed with the eight-bit literal 'k'. The result is placed in the W register. |

| ADDLW            | Add literal and W   |  |  |  |
|------------------|---|--|--|--|
| Syntax:          | [ label ] ADDLW k   |  |  |  |
| Operands:        | $0 \leq k \leq 255$   |  |  |  |
| Operation:       | $(W) + k \rightarrow (W)$   |  |  |  |
| Status Affected: | C, DC, Z  |  |  |  |
| Description:     | The contents of the W register are added to the eight-bit literal 'k' and the result is placed in the W register. |  |  |  |

| ANDWF            | AND W with f   |
|------------------|--|
| Syntax:          | [ label ] ANDWF f,d  |
| Operands:        | $0 \le f \le 127$<br>$d \in [0,1]$   |
| Operation:       | (W) .AND. (f) $\rightarrow$ (destination)  |
| Status Affected: | Z  |
| Description:     | AND the W register with register 'f'. If 'd' is '0', the result is stored in the W register. If 'd' is '1', the result is stored back in register 'f'. |

| ADDWF            | Add W and f  |  |  |  |  |
|------------------|--|--|--|--|--|
| Syntax:          | [ label ] ADDWF f,d  |  |  |  |  |
| Operands:        | $0 \le f \le 127$<br>$d \in [0,1]$   |  |  |  |  |
| Operation:       | (W) + (f) $\rightarrow$ (destination)  |  |  |  |  |
| Status Affected: | C, DC, Z   |  |  |  |  |
| Description:     | Add the contents of the W register with register 'f'. If 'd' is '0', the result is stored in the W register. If 'd' is '1', the result is stored back in register 'f'. |  |  |  |  |

| ASRF             | Arithmetic Right Shift   |  |  |  |  |  |
|------------------|--|--|--|--|--|--|
| Syntax:          | [ label ] ASRF f {,d}  |  |  |  |  |  |
| Operands:        | $0 \le f \le 127$<br>$d \in [0,1]$   |  |  |  |  |  |
| Operation:       | $(f<7>)\rightarrow dest<7>$<br>$(f<7:1>)\rightarrow dest<6:0>,$<br>$(f<0>)\rightarrow C,$  |  |  |  |  |  |
| Status Affected: | C, Z   |  |  |  |  |  |
| Description:     | The contents of register 'f' are shifted one bit to the right through the Carry flag. The MSb remains unchanged. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is stored back in register 'f'. |  |  |  |  |  |

| ADDWFC           | ADD W and CARRY bit to f   |  |  |  |  |
|------------------|--|--|--|--|--|
| Syntax:          | [ label ] ADDWFC f {,d}  |  |  |  |  |
| Operands:        | $0 \le f \le 127$<br>$d \in [0,1]$   |  |  |  |  |
| Operation:       | $(W) + (f) + (C) \rightarrow dest$   |  |  |  |  |
| Status Affected: | C, DC, Z   |  |  |  |  |
| Description:     | Add W, the Carry flag and data memory location 'f'. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is placed in data memory location 'f'. |  |  |  |  |

| BCF              | Bit Clear f  |
|------------------|--|
| Syntax:          | [ label ] BCF f,b  |
| Operands:        | $\begin{aligned} 0 &\leq f \leq 127 \\ 0 &\leq b \leq 7 \end{aligned}$ |
| Operation:       | $0 \rightarrow (f < b >)$  |
| Status Affected: | None   |
| Description:     | Bit 'b' in register 'f' is cleared.                                    |

| BTFSC            | Bit Test f, Skip if Clear   |
|------------------|---|
| Syntax:          | [ label ] BTFSC f,b   |
| Operands:        | $\begin{array}{l} 0 \leq f \leq 127 \\ 0 \leq b \leq 7 \end{array}$   |
| Operation:       | skip if (f < b >) = 0   |
| Status Affected: | None  |
| Description:     | If bit 'b' in register 'f' is '1', the next instruction is executed.  If bit 'b', in register 'f', is '0', the next instruction is discarded, and a NOP is executed instead, making this a 2-cycle instruction. |

| BRA              | Relative Branch   |
|------------------|---|
| Syntax:          | [ label ] BRA label<br>[ label ] BRA \$+k   |
| Operands:        | -256 $\leq$ label - PC + 1 $\leq$ 255 -256 $\leq$ k $\leq$ 255  |
| Operation:       | $(PC) + 1 + k \rightarrow PC$   |
| Status Affected: | None  |
| Description:     | Add the signed 9-bit literal 'k' to the PC. Since the PC will have incremented to fetch the next instruction, the new address will be PC + 1 + k. This instruction is a two-cycle instruction. This branch has a limited range. |

| k' to the incre-struction, + 1 + k. cle instruc-ied range. |  |  |
|--|--|--|
|  | incre-<br>struction,<br>+ 1 + k.<br>cle instruc- |  |

| BRW              | Relative Branch with W   |
|------------------|--|
| Syntax:          | [ label ] BRW  |
| Operands:        | None   |
| Operation:       | $(PC) + (W) \rightarrow PC$  |
| Status Affected: | None   |
| Description:     | Add the contents of W (unsigned) to the PC. Since the PC will have incremented to fetch the next instruction, the new address will be PC + 1 + (W). This instruction is a two-cycle instruction. |

| BSF              | Bit Set f                            |
|------------------|--------------------------------------|
| Syntax:          | [ label ] BSF f,b                    |
| Operands:        | $0 \le f \le 127$<br>$0 \le b \le 7$ |
| Operation:       | $1 \rightarrow (f < b >)$            |
| Status Affected: | None                                 |
| Description:     | Bit 'b' in register 'f' is set.      |

| BTFSS            | Bit Test f, Skip if Set   |
|------------------|---|
| Syntax:          | [ label ] BTFSS f,b   |
| Operands:        | $0 \le f \le 127$<br>$0 \le b < 7$  |
| Operation:       | skip if (f <b>) = 1</b>   |
| Status Affected: | None  |
| Description:     | If bit 'b' in register 'f' is '0', the next instruction is executed.  If bit 'b' is '1', then the next instruction is discarded and a NOP is executed instead, making this a 2-cycle instruction. |

| CALL             | Call Subroutine   |
|------------------|---|
| Syntax:          | [label] CALL k  |
| Operands:        | $0 \leq k \leq 2047$  |
| Operation:       | (PC)+ 1 $\rightarrow$ TOS,<br>k $\rightarrow$ PC<10:0>,<br>(PCLATH<6:3>) $\rightarrow$ PC<14:11>  |
| Status Affected: | None  |
| Description:     | Call Subroutine. First, return address (PC + 1) is pushed onto the stack. The eleven-bit immediate address is loaded into PC bits <10:0>. The upper bits of the PC are loaded from PCLATH. CALL is a two-cycle instruction. |

| CLRWDT           | Clear Watchdog Timer  |
|------------------|---|
| Syntax:          | [label] CLRWDT  |
| Operands:        | None  |
| Operation:       | $00h \to WDT$ $0 \to \underline{WDT} \text{ prescaler,}$ $1 \to \underline{TO}$ $1 \to \overline{PD}$                 |
| Status Affected: | TO, PD  |
| Description:     | CLRWDT instruction resets the Watchdog Timer. It also resets the prescaler of the WDT. Status bits TO and PD are set. |

| CALLW            | Subroutine Call With W  |
|------------------|---|
| Syntax:          | [ label ] CALLW   |
| Operands:        | None  |
| Operation:       | $(PC) +1 \rightarrow TOS,$<br>$(W) \rightarrow PC <7:0>,$<br>$(PCLATH <6:0>) \rightarrow PC <14:8>$   |
| Status Affected: | None  |
| Description:     | Subroutine call with W. First, the return address (PC + 1) is pushed onto the return stack. Then, the contents of W is loaded into PC<7:0>, and the contents of PCLATH into |

PC<14:8>. CALLW is a two-cycle

| COMF             | Complement f   |
|------------------|--|
| Syntax:          | [ label ] COMF f,d   |
| Operands:        | $0 \le f \le 127$<br>$d \in [0,1]$   |
| Operation:       | $(\overline{f}) \rightarrow (destination)$   |
| Status Affected: | Z  |
| Description:     | The contents of register 'f' are complemented. If 'd' is '0', the result is stored in W. If 'd' is '1', the result is stored back in register 'f'. |
|                  |  |
|                  |  |

| CLRF             | Clear f  |
|------------------|--|
| Syntax:          | [label] CLRF f   |
| Operands:        | $0 \leq f \leq 127$  |
| Operation:       | $00h \to (f)$ $1 \to Z$  |
| Status Affected: | Z  |
| Description:     | The contents of register 'f' are cleared and the Z bit is set. |

instruction.

| DECF             | Decrement f  |
|------------------|--|
| Syntax:          | [ label ] DECF f,d   |
| Operands:        | $0 \le f \le 127$<br>$d \in [0,1]$   |
| Operation:       | (f) - 1 $\rightarrow$ (destination)  |
| Status Affected: | Z  |
| Description:     | Decrement register 'f'. If 'd' is '0', the result is stored in the W register. If 'd' is '1', the result is stored back in register 'f'. |

| CLRW             | Clear W                                |
|------------------|--|
| Syntax:          | [ label ] CLRW                         |
| Operands:        | None                                   |
| Operation:       | $00h \to (W)$ $1 \to Z$                |
| Status Affected: | Z                                      |
| Description:     | W register is cleared. Zero bit (Z) is |

| DECFSZ           | Decrement f, Skip if 0  |
|------------------|---|
| Syntax:          | [label] DECFSZ f,d  |
| Operands:        | $0 \le f \le 127$<br>$d \in [0,1]$  |
| Operation:       | (f) - 1 $\rightarrow$ (destination);<br>skip if result = 0  |
| Status Affected: | None  |
| Description:     | The contents of register 'f' are decremented. If 'd' is '0', the result is placed in the W register. If 'd' is '1', the result is placed back in register 'f'. If the result is '1', the next instruction is executed. If the result is '0', then a NOP is executed instead, making it a 2-cycle instruction. |

| INCFSZ           | Increment f, Skip if 0   |
|------------------|--|
| Syntax:          | [ label ] INCFSZ f,d   |
| Operands:        | $0 \le f \le 127$<br>$d \in [0,1]$   |
| Operation:       | (f) + 1 $\rightarrow$ (destination),<br>skip if result = 0   |
| Status Affected: | None   |
| Description:     | The contents of register 'f' are incremented. If 'd' is 'o', the result is placed in the W register. If 'd' is '1', the result is placed back in register 'f'. If the result is '1', the next instruction is executed. If the result is 'o', a NOP is executed instead, making it a 2-cycle instruction. |

| GOTO             | Unconditional Branch   |
|------------------|--|
| Syntax:          | [ label ] GOTO k   |
| Operands:        | $0 \leq k \leq 2047$   |
| Operation:       | $k \rightarrow PC<10:0>$<br>PCLATH<6:3> $\rightarrow$ PC<14:11>  |
| Status Affected: | None   |
| Description:     | GOTO is an unconditional branch. The eleven-bit immediate value is loaded into PC bits <10:0>. The upper bits of PC are loaded from PCLATH<4:3>.  GOTO is a two-cycle instruction. |

| IORLW            | Inclusive OR literal with W  |
|------------------|--|
| Syntax:          | [label] IORLW k  |
| Operands:        | $0 \leq k \leq 255$  |
| Operation:       | (W) .OR. $k \rightarrow (W)$   |
| Status Affected: | Z  |
| Description:     | The contents of the W register are OR'ed with the eight-bit literal 'k'. The result is placed in the W register. |

| INCF             | Increment f  |
|------------------|--|
| Syntax:          | [ label ] INCF f,d   |
| Operands:        | $0 \le f \le 127$<br>$d \in [0,1]$   |
| Operation:       | (f) + 1 $\rightarrow$ (destination)  |
| Status Affected: | Z  |
| Description:     | The contents of register 'f' are incremented. If 'd' is '0', the result is placed in the W register. If 'd' is '1', the result is placed back in register 'f'. |

| IORWF            | Inclusive OR W with f   |
|------------------|---|
| Syntax:          | [ label ] IORWF f,d   |
| Operands:        | $0 \le f \le 127$<br>$d \in [0,1]$  |
| Operation:       | (W) .OR. (f) $\rightarrow$ (destination)  |
| Status Affected: | Z   |
| Description:     | Inclusive OR the W register with register 'f'. If 'd' is '0', the result is placed in the W register. If 'd' is '1', the result is placed back in register 'f'. |

| LSLF             | Logical Left Shift  |
|------------------|---|
| Syntax:          | [ label ] LSLF f {,d}   |
| Operands:        | $0 \le f \le 127$<br>$d \in [0,1]$  |
| Operation:       | $(f<7>) \rightarrow C$<br>$(f<6:0>) \rightarrow dest<7:1>$<br>$0 \rightarrow dest<0>$   |
| Status Affected: | C, Z  |
| Description:     | The contents of register 'f' are shifted one bit to the left through the Carry flag. A '0' is shifted into the LSb. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is stored back in register 'f'. |
|                  | C register f ←0   |

| LSRF             | Logical Right Shift  |
|------------------|--|
| Syntax:          | [ label ] LSLF f {,d}  |
| Operands:        | $0 \le f \le 127$<br>d $\in [0,1]$   |
| Operation:       | $0 \rightarrow \text{dest<7>}$ $(f<7:1>) \rightarrow \text{dest<6:0>},$ $(f<0>) \rightarrow C,$  |
| Status Affected: | C, Z   |
| Description:     | The contents of register 'f' are shifted one bit to the right through the Carry flag. A '0' is shifted into the MSb. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is stored back in register 'f'. |
|                  | 0 → register f C   |

| MOVF             | Move f  |
|------------------|---|
| Syntax:          | [ label ] MOVF f,d  |
| Operands:        | $0 \le f \le 127$<br>$d \in [0,1]$  |
| Operation:       | $(f) \rightarrow (dest)$  |
| Status Affected: | Z   |
| Description:     | The contents of register f is moved to a destination dependent upon the status of d. If d = 0, destination is W register. If d = 1, the destination is file register f itself. d = 1 is useful to test a file register since status flag Z is affected. |
| Words:           | 1   |
| Cycles:          | 1   |
| Example:         | MOVF FSR, 0   |
|                  | After Instruction  W = value in FSR register  Z = 1   |

| MOVIW            | Move INDFn to W  |
|------------------|--|
| Syntax:          | [ label ] MOVIW ++FSRn<br>[ label ] MOVIWFSRn<br>[ label ] MOVIW FSRn++<br>[ label ] MOVIW FSRn<br>[ label ] MOVIW k[FSRn]   |
| Operands:        | $\begin{split} & n \in [0,1] \\ & mm \in [00,01,10,11] \\ & -32 \le k \le 31 \end{split}$  |
| Operation:       | INDFn → W Effective address is determined by • FSR + 1 (preincrement) • FSR - 1 (predecrement) • FSR + k (relative offset) After the Move, the FSR value will be either: • FSR + 1 (all increments) • FSR - 1 (all decrements) • Unchanged |
| Status Affected: | Z  |

| Mode          | Syntax | mm |
|---------------|--------|----|
| Preincrement  | ++FSRn | 00 |
| Predecrement  | FSRn   | 01 |
| Postincrement | FSRn++ | 10 |
| Postdecrement | FSRn   | 11 |

Description: This instruction is used to move data

between W and one of the indirect registers (INDFn). Before/after this move, the pointer (FSRn) is updated by pre/post incrementing/decrementing it.

Note: The INDFn registers are not physical registers. Any instruction that accesses an INDFn register actually accesses the register at the address specified by the FSRn.

FSRn is limited to the range 0000h - FFFFh. Incrementing/decrementing it beyond these bounds will cause it to wrap around.

### MOVLB Move literal to BSR

Syntax: [ label ] MOVLB k

 $\begin{tabular}{lll} Operands: & 0 \le k \le 15 \\ Operation: & k \to BSR \\ Status \ Affected: & None \\ \end{tabular}$ 

Description: The five-bit literal 'k' is loaded into the

Bank Select Register (BSR).

Syntax: [label] MOVLP k

Operands:  $0 \le k \le 127$ Operation:  $k \to PCLATH$ Status Affected: None

Description: The seven-bit literal 'k' is loaded into the

PCLATH register.

[label] MOVLW k

#### MOVLW Move literal to W

Operands:  $0 \le k \le 255$ Operation:  $k \to (W)$ Status Affected: None

Description: The eight-bit literal 'k' is loaded into W

register. The "don't cares" will assem-

ble as '0's.

Words: 1
Cycles: 1

Syntax:

Example: MOVLW 0x5A

After Instruction

W = 0x5A

#### MOVWF Move W to f

Syntax: [ label ] MOVWF

 $\label{eq:continuous} \begin{array}{ll} \text{Operands:} & 0 \leq \text{f} \leq 127 \\ \text{Operation:} & (\text{W}) \rightarrow (\text{f}) \\ \text{Status Affected:} & \text{None} \end{array}$ 

Description: Move data from W register to register

Ϋ́.

Words: 1
Cycles: 1

Example: MOVWF OPTION\_REG

Before Instruction

OPTION\_REG = 0xFF

W = 0x4F

After Instruction

OPTION\_REG = 0x4F W = 0x4F

| MOVWI            | Move W to INDFn  |
|------------------|--|
| Syntax:          | [ label ] MOVWI ++FSRn<br>[ label ] MOVWIFSRn<br>[ label ] MOVWI FSRn++<br>[ label ] MOVWI FSRn<br>[ label ] MOVWI k[FSRn]   |
| Operands:        | $n \in [0,1]$<br>$mm \in [00,01, 10, 11]$<br>$-32 \le k \le 31$  |
| Operation:       | <ul> <li>W → INDFn</li> <li>Effective address is determined by</li> <li>FSR + 1 (preincrement)</li> <li>FSR - 1 (predecrement)</li> <li>FSR + k (relative offset)</li> <li>After the Move, the FSR value will be either:</li> <li>FSR + 1 (all increments)</li> <li>FSR - 1 (all decrements)</li> <li>Unchanged</li> </ul> |
| Status Affected: | None   |

| Mode          | Syntax | mm |
|---------------|--------|----|
| Preincrement  | ++FSRn | 00 |
| Predecrement  | FSRn   | 01 |
| Postincrement | FSRn++ | 10 |
| Postdecrement | FSRn   | 11 |

Description:

This instruction is used to move data between W and one of the indirect registers (INDFn). Before/after this move, the pointer (FSRn) is updated by pre/post incrementing/decrementing it.

Note: The INDFn registers are not physical registers. Any instruction that accesses an INDFn register actually accesses the register at the address specified by the FSRn.

FSRn is limited to the range 0000h - FFFFh. Incrementing/decrementing it

around.

The increment/decrement operation on FSRn WILL NOT affect any Status bits.

beyond these bounds will cause it to wrap

| NOP                 | No Operation   |
|---------------------|--|
| Syntax:             | [ label ] NOP  |
| Operands:           | None   |
| Operation:          | No operation   |
| Status Affected:    | None   |
| Description:        | No operation.  |
| Words:              | 1  |
| Cycles:             | 1  |
| Example:            | NOP  |
|                     | Lead OPTION DEC Desistes                             |
|                     |  |
| OPTION              | Load OPTION_REG Register with W                      |
| Syntax:             | [ label ] OPTION                                     |
| Operands:           | None   |
| Operation:          | $(W) \to OPTION\_REG$                                |
| Status Affected:    | None   |
| Description:        | Move data from W register to<br>OPTION_REG register. |
| Words:              | 1  |
|                     | 1  |
| Cycles:             | į.   |
| •                   | OPTION   |
| Cycles:<br>Example: | ·  |
| •                   | OPTION  Before Instruction  OPTION_REG = 0xFF        |

| RESET            | Software Reset   |
|------------------|--|
| Syntax:          | [label] RESET  |
| Operands:        | None   |
| Operation:       | Execute a device Reset. Resets the nRI flag of the PCON register.                |
| Status Affected: | None   |
| Description:     | This instruction provides a way to<br>execute a hardware Reset by soft-<br>ware. |

| RETFIE           | Return from Interrupt  |  |
|------------------|--|--|
| Syntax:          | [label] RETFIE   |  |
| Operands:        | None   |  |
| Operation:       | $TOS \rightarrow PC,$ $1 \rightarrow GIE$  |  |
| Status Affected: | None   |  |
| Description:     | Return from Interrupt. Stack is POPed and Top-of-Stack (TOS) is loaded in the PC. Interrupts are enabled by setting Global Interrupt Enable bit, GIE (INTCON<7>). This is a two-cycle instruction. |  |
| Words:           | 1  |  |
| Cycles:          | 2  |  |
| Example:         | RETFIE   |  |
|                  | After Interrupt PC = TOS GIE = 1   |  |

| RETURN           | Return from Subroutine   |
|------------------|--|
| Syntax:          | [label] RETURN   |
| Operands:        | None   |
| Operation:       | $TOS \to PC$   |
| Status Affected: | None   |
| Description:     | Return from subroutine. The stack is POPed and the top of the stack (TOS) is loaded into the program counter. This is a two-cycle instruction. |

| RETLW            | Return with literal in W  |
|------------------|---|
| Syntax:          | [label] RETLW k   |
| Operands:        | $0 \leq k \leq 255$   |
| Operation:       | $\begin{aligned} k \to (W); \\ TOS \to PC \end{aligned}$  |
| Status Affected: | None  |
| Description:     | The W register is loaded with the eight bit literal 'k'. The program counter is loaded from the top of the stack (the return address). This is a two-cycle instruction. |
| Words:           | 1   |
| Cycles:          | 2   |
| Example:         | CALL TABLE;W contains table ;offset value • ;W now has table value  |
| TABLE            | . ADDWF PC ;W = offset RETLW k1 ;Begin table RETLW k2 ; RETLW kn ; End of table   |
|                  | Before Instruction W = 0x07  After Instruction  |

W = value of k8

| RLF              | Rotate Left f through Carry   |
|------------------|---|
| Syntax:          | [ label ] RLF f,d   |
| Operands:        | $0 \le f \le 127$<br>$d \in [0,1]$  |
| Operation:       | See description below   |
| Status Affected: | С   |
| Description:     | The contents of register 'f' are rotated one bit to the left through the Carry flag. If 'd' is '0', the result is placed in the W register. If 'd' is '1', the result is stored back in register 'f'. |
| Words:           | 1   |
| Cycles:          | 1   |
| Example:         | RLF REG1,0  |
|                  | Before Instruction  |
|                  | REG1 = 1110 0110  |
|                  | C = 0   |
|                  | After Instruction   |
|                  | REG1 = 1110 0110  |
|                  | W = 1100 1100   |
|                  | C = 1   |
|                  |   |

**Subtract W from literal** 

#### RRF Rotate Right f through Carry

Syntax: [ label ] RRF f,d

Operands:  $0 \le f \le 127$ 

 $d \in [0,1]$ 


Operation: See description below

Status Affected: C

Description: The contents of register 'f' are rotated

one bit to the right through the Carry flag. If 'd' is 'o', the result is placed in the W register. If 'd' is '1', the result is

placed back in register 'f'.



# Syntax: [label] SUBLW k Operands: $0 \le k \le 255$

Operation:  $k - (W) \rightarrow (W)$ Status Affected: C, DC, Z

**SUBLW** 

Description: The W register is subtracted (2's com-

plement method) from the eight-bit literal 'k'. The result is placed in the W

register.

| <b>C</b> = 0 | W > k           |
|--------------|-----------------|
| C = 1        | $W \leq k$      |
| DC = 0       | W<3:0> > k<3:0> |
| DC = 1       | W<3:0> ≤ k<3:0> |

### SLEEP Enter Sleep mode

Syntax: [ label ] SLEEP

Operands: None

Operation:  $00h \rightarrow WDT$ ,

 $0 \to \underline{\text{WD}} \text{T prescaler,}$ 

 $\begin{array}{c}
1 \to \overline{\mathsf{TO}}, \\
0 \to \overline{\mathsf{PD}}
\end{array}$ 

Status Affected: TO, PD

Description: The power-down Status bit,  $\overline{PD}$  is

cleared. Time-out Status bit,  $\overline{\text{TO}}$  is set. Watchdog Timer and its pres-

caler are cleared.

The processor is put into Sleep mode

with the oscillator stopped.

## SUBWF Subtract W from f

Syntax: [label] SUBWF f,d

Operands:  $0 \le f \le 127$ 

 $d \in [0,1]$ 

Operation: (f) - (W)  $\rightarrow$  (destination)

Status Affected: C, DC, Z

Description: Subtract (2's complement method) W

register from register 'f'. If 'd' is '0', the

result is stored in the W

register. If 'd' is '1', the result is stored

back in register 'f.

| <b>C</b> = 0 | W > f           |
|--------------|-----------------|
| C = 1        | $W \leq f$      |
| DC = 0       | W<3:0> > f<3:0> |
| DC = 1       | W<3:0> ≤ f<3:0> |

#### SUBWFB Subtract W from f with Borrow

Syntax: SUBWFB f {,d}

Operands:  $0 \le f \le 127$ 

 $d\in [0,1]$ 

Operation:  $(f) - (W) - (\overline{B}) \rightarrow dest$ 

Status Affected: C, DC, Z

Description: Subtract W and the BORROW flag

(CARRY) from register 'f' (2's complement method). If 'd' is '0', the result is stored in W. If 'd' is '1', the result is

stored back in register 'f'.

| SWAPF            | Swap Nibbles in f  |
|------------------|--|
| Syntax:          | [ label ] SWAPF f,d  |
| Operands:        | $0 \le f \le 127$<br>$d \in [0,1]$   |
| Operation:       | $(f<3:0>) \rightarrow (destination<7:4>),$<br>$(f<7:4>) \rightarrow (destination<3:0>)$  |
| Status Affected: | None   |
| Description:     | The upper and lower nibbles of register 'f' are exchanged. If 'd' is '0', the result is placed in the W register. If 'd' is '1' the result is placed in register 'f' |

| XORLW            | Exclusive OR literal with W   |  |  |  |  |  |  |  |  |
|------------------|---|--|--|--|--|--|--|--|--|
| Syntax:          | [ label ] XORLW k   |  |  |  |  |  |  |  |  |
| Operands:        | $0 \leq k \leq 255$   |  |  |  |  |  |  |  |  |
| Operation:       | (W) .XOR. $k \rightarrow (W)$   |  |  |  |  |  |  |  |  |
| Status Affected: | Z   |  |  |  |  |  |  |  |  |
| Description:     | The contents of the W register are XOR'ed with the eight-bit literal 'k'. The result is placed in the W register. |  |  |  |  |  |  |  |  |

| TRIS             | Load TRIS Register with W  |  |  |  |  |  |  |
|------------------|--|--|--|--|--|--|--|
| Syntax:          | [ label ] TRIS f   |  |  |  |  |  |  |
| Operands:        | $5 \leq f \leq 7$  |  |  |  |  |  |  |
| Operation:       | $(W) \rightarrow TRIS register 'f'$  |  |  |  |  |  |  |
| Status Affected: | None   |  |  |  |  |  |  |
| Description:     | Move data from W register to TRIS register. When 'f' = 5, TRISA is loaded. When 'f' = 6, TRISB is loaded. When 'f' = 7, TRISC is loaded. |  |  |  |  |  |  |

| XORWF            | Exclusive OR W with f   |
|------------------|---|
| Syntax:          | [ label ] XORWF f,d   |
| Operands:        | $0 \le f \le 127$<br>$d \in [0,1]$  |
| Operation:       | (W) .XOR. (f) $\rightarrow$ (destination)   |
| Status Affected: | Z   |
| Description:     | Exclusive OR the contents of the W register with register 'f'. If 'd' is '0', the result is stored in the W register. If 'd' is '1', the result is stored back in register 'f'. |

## 30.0 ELECTRICAL SPECIFICATIONS


## Absolute Maximum Ratings<sup>(†)</sup>


| Ambient temperature under bias  | 40°C to +125°C       |
|---|----------------------|
| Storage temperature   | 65°C to +150°C       |
| Voltage on VDD with respect to Vss  | 0.3V to +6.5V        |
| Voltage on VCAP pin with respect to Vss   | 0.3V to +4.0V        |
| Voltage on VDD with respect to Vss  | -0.3V to +4.0V       |
| Voltage on MCLR with respect to Vss   | 0.3V to +9.0V        |
| Voltage on all other pins with respect to Vss   | 0.3V to (VDD + 0.3V) |
| Total power dissipation <sup>(1)</sup>  | 800 mW               |
| Maximum current out of Vss <sup>(2)</sup> pin, $-40^{\circ}$ C $\leq$ TA $\leq$ +85 $^{\circ}$ C for industrial |                      |
| Maximum current out of Vss <sup>(2)</sup> pin, -40°C ≤ TA ≤ +125°C for extended                                 | 105 mA               |
| Maximum current into $VDD^{(2)}$ pin, $-40^{\circ}C \le TA \le +85^{\circ}C$ for industrial                     | 170 mA               |
| Maximum current into $VDD^{(2)}$ pin, $-40^{\circ}C \le TA \le +125^{\circ}C$ for extended                      | 70 mA                |
| Clamp current, IK (VPIN < 0 or VPIN > VDD)  | ± 20 mA              |
| Maximum output current sunk by any I/O pin  | 25 mA                |
| Maximum output current sourced by any I/O pin   | 25 mA                |
| <b>Note 1:</b> Power dissipation is calculated as follows: PDIS = VDD x {IDD $-\Sigma$ IOH} + $\Sigma$ {(VDD    |                      |
|   |                      |

2: For 28-pin devices.

† NOTICE: Stresses above those listed under "Absolute Maximum Ratings" may cause permanent damage to the device. This is a stress rating only and functional operation of the device at those or any other conditions above those indicated in the operation listings of this specification is not implied. Exposure above maximum rating conditions for extended periods may affect device reliability.

Note 1: The shaded region indicates the permissible combinations of voltage and frequency.
2: Refer to Table 30-1 for each Oscillator mode's supported frequencies.





## 30.1 DC Characteristics: PIC16(L)F1934/6/7-I/E (Industrial, Extended)

| PIC16LF       | 1934/36/37 |   | Standard Operating Conditions (unless otherwise stated)  Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for industrial $-40^{\circ}\text{C} \le \text{TA} \le +125^{\circ}\text{C}$ for extended |      |            |          |   |  |  |  |
|---------------|------------|---|---|------|------------|----------|---|--|--|--|
| PIC16F1       | 934/36/37  |   | Standard Operating Conditions (unless otherwise stated)  Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for industrial $-40^{\circ}\text{C} \le \text{TA} \le +125^{\circ}\text{C}$ for extended |      |            |          |   |  |  |  |
| Param.<br>No. | Sym.       | Characteristic  | Min.  | Тур† | Max.       | Units    | Conditions  |  |  |  |
| D001          | VDD        | Supply Voltage  |   |      |            |          |   |  |  |  |
|               |            | PIC16LF1934/36/37   | 1.8<br>2.3  | _    | 3.6<br>3.6 | V<br>V   | Fosc ≤ 16 MHz:<br>Fosc ≤ 32 MHz ( <b>Note 2</b> )                                       |  |  |  |
| D001          |            | PIC16F1934/36/37  | 1.8<br>2.3  | _    | 5.5<br>5.5 | V<br>V   | Fosc ≤ 16 MHz:<br>Fosc ≤ 32 MHz ( <b>Note 2</b> )                                       |  |  |  |
| D002*         | VDR        | RAM Data Retention Voltage <sup>(1)</sup>                 |   |      |            |          |   |  |  |  |
|               |            | PIC16LF1934/36/37   | 1.5   | _    | _          | V        | Device in Sleep mode  |  |  |  |
| D002*         |            | PIC16F1934/36/37  | 1.7   | _    | _          | V        | Device in Sleep mode  |  |  |  |
|               | VPOR*      | Power-on Reset Release Voltage                            | _   | 1.6  | _          | V        |   |  |  |  |
|               | VPORR*     | Power-on Reset Rearm Voltage                              |   |      |            |          |   |  |  |  |
|               |            | PIC16LF1934/36/37   | 1   | 8.0  |            | ٧        | Device in Sleep mode  |  |  |  |
|               |            | PIC16F1934/36/37  | ı   | 1.7  |            | <b>V</b> | Device in Sleep mode  |  |  |  |
| D003          | VADFVR     | Fixed Voltage Reference Voltage for ADC                   | -8  |      | 6          | %        | $1.024V$ , VDD $\geq 2.5V$<br>$2.048V$ , VDD $\geq 2.5V$<br>$4.096V$ , VDD $\geq 4.75V$ |  |  |  |
| D003A         | VCDAFVR    | Fixed Voltage Reference Voltage for Comparator and DAC    | -11   |      | 7          | %        | 1.024V, VDD $\geq$ 2.5V<br>2.048V, VDD $\geq$ 2.5V<br>4.096V, VDD $\geq$ 4.75V          |  |  |  |
| D003B         | VLCDFVR    | Fixed Voltage Reference Voltage for LCD Bias              | -11   | _    | 10         | %        | 3.072V, VDD ≥ 3.6V  |  |  |  |
| D004*         | SVDD       | VDD Rise Rate to ensure internal<br>Power-on Reset signal | 0.05  | _    | _          | V/ms     | See Section 6.1 "Power-on Reset (POR)" for details.                                     |  |  |  |


<sup>\*</sup> These parameters are characterized but not tested.

<sup>†</sup> Data in "Typ" column is at 3.3V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

Note 1: This is the limit to which VDD can be lowered in Sleep mode without losing RAM data.

<sup>2:</sup> PLL required for 32 MHz operation.





## 30.2 DC Characteristics: PIC16(L)F1934/6/7-I/E (Industrial, Extended)

| PIC16LF                                | 1934/36/37      | Standard Operating Conditions (unless otherwise stated)  Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for industrial $-40^{\circ}\text{C} \le \text{TA} \le +125^{\circ}\text{C}$ for extended |      |                        |        |           |   |  |  |  |  |
|--|-----------------|---|------|------------------------|--------|-----------|---|--|--|--|--|
| PIC16F19                               | 934/36/37       |   |      | d Operati<br>g tempera | ture - | -40°C ≤ T | less otherwise stated)<br>A ≤ +85°C for industrial<br>A ≤ +125°C for extended   |  |  |  |  |
| Param                                  | Device          | Min.  | Typ† | Max.                   | Units  |           | Conditions  |  |  |  |  |
| No.                                    | Characteristics |   | 1961 | IVIUX.                 | Onno   | VDD       | Note  |  |  |  |  |
| Supply Current (IDD) <sup>(1, 2)</sup> |                 |   |      |                        |        |           |   |  |  |  |  |
| D009                                   | LDO Regulator   | _   | 350  | _                      | μА     | 1         | HS, EC OR INTOSC/INTOSCIO (8-16 MHz)<br>Clock modes with all VCAP pins disabled |  |  |  |  |
|  |                 | _   | 50   | _                      | μА     | _         | All VCAP pins disabled  |  |  |  |  |
|  |                 | _   | 30   | _                      | μА     | _         | VCAP enabled on RA0, RA5 or RA6   |  |  |  |  |
|  |                 | _   | 5    | _                      | μА     | _         | LP Clock mode and Sleep (requires FVR and BOR to be disabled)                   |  |  |  |  |
| D010                                   |                 | _   | 7.0  | 16                     | μА     | 1.8       | Fosc = 32 kHz   |  |  |  |  |
|  |                 |   | 9.0  | 20                     | μΑ     | 3.0       | LP Oscillator mode (Note 4),<br>-40°C $\leq$ TA $\leq$ +85°C                    |  |  |  |  |
| D010                                   |                 | _   | 29   | 63                     | μΑ     | 1.8       | Fosc = 32 kHz   |  |  |  |  |
|  |                 | _   | 37   | 74                     | μΑ     | 3.0       | LP Oscillator mode (Note 4, 5),<br>-40°C ≤ TA ≤ +85°C                           |  |  |  |  |
|  |                 | _   | 40   | 79                     | μА     | 5.0       | -40 C \( \text{IX} \( \text{IX} \( \text{IX} \( \text{IX} \)                    |  |  |  |  |
| D010A                                  |                 | _   | 7.0  | 23                     | μΑ     | 1.8       | Fosc = 32 kHz   |  |  |  |  |
|  |                 | _   | 9.0  | 27                     | μА     | 3.0       | LP Oscillator mode (Note 4) $-40^{\circ}$ C $\leq$ TA $\leq$ +125 $^{\circ}$ C  |  |  |  |  |
| D010A                                  |                 | _   | 29   | 68                     | μΑ     | 1.8       | Fosc = 32 kHz   |  |  |  |  |
|  |                 | _   | 37   | 88                     | μА     | 3.0       | LP Oscillator mode (Note 4, 5)  -40°C ≤ TA ≤ +125°C                             |  |  |  |  |
|  |                 | _   | 40   | 95                     | μА     | 5.0       | 40 C S IA S + 123 C   |  |  |  |  |
| D011                                   |                 | _   | 140  | 200                    | μА     | 1.8       | Fosc = 1 MHz  |  |  |  |  |
|  |                 | _   | 250  | 330                    | μΑ     | 3.0       | XT Oscillator mode  |  |  |  |  |
| D011                                   |                 | _   | 160  | 260                    | μΑ     | 1.8       | Fosc = 1 MHz  |  |  |  |  |
|  |                 | _   | 280  | 480                    | μΑ     | 3.0       | XT Oscillator mode (Note 5)   |  |  |  |  |
|  |                 | _   | 390  | 690                    | μΑ     | 5.0       |   |  |  |  |  |
| D012                                   |                 | _   | 430  | 650                    | μΑ     | 1.8       | FOSC = 4 MHz  |  |  |  |  |
|  |                 | _   | 750  | 1000                   | μΑ     | 3.0       | XT Oscillator mode  |  |  |  |  |
| D012                                   |                 | _   | 450  | 700                    | μΑ     | 1.8       | Fosc = 4 MHz  |  |  |  |  |
|  |                 | _   | 770  | 1100                   | μΑ     | 3.0       | XT Oscillator mode (Note 5)   |  |  |  |  |
|  |                 | _   | 930  | 1300                   | μΑ     | 5.0       |   |  |  |  |  |

- Note 1: The test conditions for all IDD measurements in active operation mode are: OSC1 = external square wave, from rail-to-rail; all I/O pins tri-stated, pulled to VDD; MCLR = VDD; WDT disabled.
  - 2: The supply current is mainly a function of the operating voltage and frequency. Other factors, such as I/O pin loading and switching rate, oscillator type, internal code execution pattern and temperature, also have an impact on the current consumption.
  - 3: For RC oscillator configurations, current through REXT is not included. The current through the resistor can be extended by the formula IR = VDD/2REXT (mA) with REXT in  $k\Omega$ .
  - 4: FVR and BOR are disabled.
  - 5: 0.1  $\mu$ F capacitor on VCAP (RA0).
  - 6: 8 MHz crystal oscillator with 4x PLL enabled.

## 30.2 DC Characteristics: PIC16(L)F1934/6/7-I/E (Industrial, Extended) (Continued)

| PIC16LF | 1934/36/37                          |       | d <b>Operati</b><br>g tempera | ture -                        | itions (unless otherwise stated) $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for industrial $-40^{\circ}\text{C} \le \text{TA} \le +125^{\circ}\text{C}$ for extended |   |  |  |  |
|---------|-------------------------------------|-------|-------------------------------|-------------------------------|---|---|--|--|--|
| PIC16F1 | 934/36/37                           |       |                               | d <b>Operati</b><br>g tempera | ture -  | itions (unless otherwise stated) $-40^{\circ}C \leq TA \leq +85^{\circ}C \text{ for industrial}$ $-40^{\circ}C \leq TA \leq +125^{\circ}C \text{ for extended}$ |  |  |  |
| Param   | Device                              | Min.  | Typ†                          | Max.                          | Units   |   | Conditions   |  |  |
| No.     | Characteristics                     | WIII. | ТУРТ                          | IVIAA.                        | Offics  | VDD   | Note   |  |  |
|         | Supply Current (IDD) <sup>(1,</sup> | 2)    |                               |                               |   |   |  |  |  |
| D013    |                                     | _     | 50                            | 100                           | μА  | 1.8   | Fosc = 500 kHz   |  |  |
|         |                                     | _     | 85                            | 150                           | μΑ  | 3.0   | EC Oscillator Low-Power mode   |  |  |
| D013    |                                     | _     | 70                            | 120                           | μΑ  | 1.8   | Fosc = 500 kHz   |  |  |
|         |                                     | _     | 115                           | 170                           | μΑ  | 3.0   | EC Oscillator Low-Power mode (Note 5)  |  |  |
|         |                                     | _     | 120                           | 200                           | μΑ  | 5.0   |  |  |  |
| D014    |                                     | _     | 400                           | 550                           | μΑ  | 1.8   | Fosc = 4 MHz   |  |  |
|         |                                     | _     | 700                           | 1100                          | μΑ  | 3.0   | EC Oscillator mode<br>Medium Power mode  |  |  |
| D014    |                                     | _     | 430                           | 650                           | μА  | 1.8   | Fosc = 4 MHz   |  |  |
|         |                                     | _     | 720                           | 1000                          | μΑ  | 3.0   | EC Oscillator mode (Note 5)  Medium Power mode   |  |  |
|         |                                     | _     | 850                           | 1200                          | μΑ  | 5.0   |  |  |  |
| D015    |                                     |       | 5.3                           | 6.2                           | mA  | 3.0   | Fosc = 32 MHz EC Oscillator High-Power mode  |  |  |
|         |                                     | _     | 6.3                           | 7.5                           | mA  | 3.6   | , and the second |  |  |
| D015    |                                     | _     | 5.3                           | 6.5                           | mA  | 3.0   | FOSC = 32 MHz  |  |  |
|         |                                     | _     | 5.4                           | 7.5                           | mA  | 5.0   | EC Oscillator High-Power mode (Note 5)   |  |  |
| D016    |                                     |       | 5                             | 12                            | μА  | 1.8   | Fosc = 32 kHz, LFINTOSC mode (Note 4)  |  |  |
|         |                                     | _     | 8                             | 16                            | μΑ  | 3.0   | -40°C ≤ TA ≤ +85°C   |  |  |
| D016    |                                     | _     | 27                            | 70                            | μΑ  | 1.8   | Fosc = 32 kHz, LFINTOSC mode   |  |  |
|         |                                     | _     | 34                            | 80                            | μΑ  | 3.0   | (Note 4, Note 5)<br>-40°C ≤ TA ≤ +85°C   |  |  |
|         |                                     | _     | 36                            | 90                            | μΑ  | 5.0   |  |  |  |

Note 1: The test conditions for all IDD measurements in active operation mode are: OSC1 = external square wave, from rail-to-rail; all I/O pins tri-stated, pulled to VDD; MCLR = VDD; WDT disabled.

- 2: The supply current is mainly a function of the operating voltage and frequency. Other factors, such as I/O pin loading and switching rate, oscillator type, internal code execution pattern and temperature, also have an impact on the current consumption.
- **3:** For RC oscillator configurations, current through REXT is not included. The current through the resistor can be extended by the formula IR = VDD/2REXT (mA) with REXT in kΩ.
- 4: FVR and BOR are disabled.
- 5: 0.1 μF capacitor on VCAP (RA0).
- 6: 8 MHz crystal oscillator with 4x PLL enabled.

## 30.2 DC Characteristics: PIC16(L)F1934/6/7-I/E (Industrial, Extended) (Continued)

| PIC16LF1 | 1934/36/37                             | Standard Operating Conditions (unless otherwise stated)  Operating temperature $-40^{\circ}\text{C} \le \text{Ta} \le +85^{\circ}\text{C}$ for industrial $-40^{\circ}\text{C} \le \text{Ta} \le +125^{\circ}\text{C}$ for extended |      |             |         |            |  |  |  |
|----------|--|---|------|-------------|---------|------------|--|--|--|
| PIC16F19 | 934/36/37                              |   |      | d Operation | iture - | -40°C ≤ TA | ess otherwise stated)  \( \leq +85^\circ \) for industrial  \( \leq +125^\circ \) for extended |  |  |
| Param    | Device                                 | Min.  | Typ† | Max.        | Units   |            | Conditions   |  |  |
| No.      | Characteristics                        | 141111.   | iypi | wax.        | Onits   | VDD        | Note   |  |  |
| D017     | Supply Current (IDD) <sup>(1, 2)</sup> | 2)  |      |             |         | ,          |  |  |  |
| ווטטו    |  | _   | 110  | 180         | μΑ      | 1.8        | Fosc = 500 kHz   |  |  |
|          |  | _   | 140  | 250         | μΑ      | 3.0        | MFINTOSC mode  |  |  |
| D017     |  | _   | 150  | 250         | μΑ      | 1.8        | Fosc = 500 kHz   |  |  |
|          |  | _   | 210  | 330         | μΑ      | 3.0        | MFINTOSC mode (Note 5)   |  |  |
|          |  | _   | 270  | 430         | μΑ      | 5.0        |  |  |  |
| D018     |  | _   | 1.0  | 1.4         | mA      | 1.8        | FOSC = 8 MHz   |  |  |
|          |  | _   | 1.8  | 2.3         | mA      | 3.0        | HFINTOSC mode  |  |  |
| D018     |  | -   | 1.0  | 1.5         | mA      | 1.8        | Fosc = 8 MHz   |  |  |
|          |  | 1   | 1.8  | 2.3         | mA      | 3.0        | HFINTOSC mode (Note 5)   |  |  |
|          |  | _   | 2.0  | 2.8         | mA      | 5.0        |  |  |  |
| D019     |  | -   | 1.5  | 2.2         | mA      | 1.8        | Fosc = 16 MHz  |  |  |
|          |  | -   | 2.8  | 3.7         | mA      | 3.0        | HFINTOSC mode  |  |  |
| D019     |  | -   | 1.7  | 2.3         | mA      | 1.8        | Fosc = 16 MHz  |  |  |
|          |  | -   | 2.9  | 3.9         | mA      | 3.0        | HFINTOSC mode (Note 5)   |  |  |
|          |  | _   | 3.1  | 4.1         | mA      | 5.0        |  |  |  |
| D020     |  | _   | 4.8  | 6.2         | mA      | 3.0        | Fosc = 32 MHz  |  |  |
|          |  | _   | 5.0  | 7.5         | mA      | 3.6        | HFINTOSC mode  |  |  |
| D020     |  | _   | 4.8  | 6.5         | mA      | 3.0        | Fosc = 32 MHz  |  |  |
|          |  | _   | 5.0  | 7.5         | mA      | 5.0        | HFINTOSC mode  |  |  |
| D021     |  | _   | 410  | 550         | μΑ      | 1.8        | Fosc = 4 MHz   |  |  |
|          |  | _   | 710  | 990         | μΑ      | 3.0        | EXTRC mode (Note 3)  |  |  |
| D021     |  | -   | 430  | 700         | μΑ      | 1.8        | Fosc = 4 MHz   |  |  |
|          |  | _   | 730  | 1100        | μΑ      | 3.0        | EXTRC mode (Note 3, Note 5)  |  |  |
|          |  | _   | 860  | 1400        | μΑ      | 5.0        |  |  |  |
| D022     |  |   | 5.0  | 6.2         | mA      | 3.0        | Fosc = 32 MHz  |  |  |
|          |  | _   | 6.0  | 7.5         | mA      | 3.6        | HS Oscillator mode (Note 6)  |  |  |
| D022     |  | _   | 5.0  | 6.5         | mA      | 3.0        | Fosc = 32 MHz  |  |  |
|          |  |   | 5.2  | 7.5         | mA      | 5.0        | HS Oscillator mode (Note 5, Note 6)  |  |  |

- Note 1: The test conditions for all IDD measurements in active operation mode are: OSC1 = external square wave, from rail-to-rail; all I/O pins tri-stated, pulled to VDD; MCLR = VDD; WDT disabled.
  - 2: The supply current is mainly a function of the operating voltage and frequency. Other factors, such as I/O pin loading and switching rate, oscillator type, internal code execution pattern and temperature, also have an impact on the current consumption.
  - 3: For RC oscillator configurations, current through REXT is not included. The current through the resistor can be extended by the formula IR = VDD/2REXT (mA) with REXT in kΩ.
  - 4: FVR and BOR are disabled.
  - 5: 0.1 μF capacitor on VCAP (RA0).
  - **6:** 8 MHz crystal oscillator with 4x PLL enabled.

## 30.3 DC Characteristics: PIC16(L)F1934/6/7-I/E (Power-Down)

| PIC16LF1934/36/37 |   |          |      | Standard Operating Conditions (unless otherwise stated)  Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for industrial $-40^{\circ}\text{C} \le \text{TA} \le +125^{\circ}\text{C}$ for extended |                |       |            |                                    |  |  |  |
|-------------------|---|----------|------|---|----------------|-------|------------|------------------------------------|--|--|--|
| PIC16F19          | 34/36/37  |          |      | Standard Operating Conditions (unless otherwise stated)  Operating temperature $-40^{\circ}\text{C} \le \text{Ta} \le +85^{\circ}\text{C}$ for industrial $-40^{\circ}\text{C} \le \text{Ta} \le +125^{\circ}\text{C}$ for extended |                |       |            |                                    |  |  |  |
| Param<br>No.      | Device Characteristics  | Min.     | Тур† | Max.<br>+85°C   | Max.<br>+125°C | Units | Conditions |                                    |  |  |  |
|                   | Barren darren Barra Crimana   | (1==)(2) |      | 100 0   | 1.20 0         |       | VDD        | Note                               |  |  |  |
| D023              | Power-down Base Current   | (IPD)\-/ | 0.06 | 1.0   | 8.0            | μА    | 1.8        | WDT, BOR, FVR, and T10SC           |  |  |  |
| D023              |   |          | 0.08 | 2.0   | 9.0            | μА    | 3.0        | disabled, all Peripherals Inactive |  |  |  |
| D023              |   |          | 21   | 55  | 63             | μА    | 1.8        | WDT, BOR, FVR, and T1OSC           |  |  |  |
| D023              |   |          | 25   | 58  | 78             | μА    | 3.0        | disabled, all Peripherals Inactive |  |  |  |
|                   |   |          | 27   | 60  | 88             | μА    | 5.0        |                                    |  |  |  |
| D024              |   | _        | 0.5  | 4.0   | 9.0            | μА    | 1.8        | LPWDT Current (Note 1)             |  |  |  |
|                   |   |          | 0.8  | 5.0   | 10             | μА    | 3.0        |                                    |  |  |  |
| D024              |   | _        | 23   | 57  | 65             | μΑ    | 1.8        | LPWDT Current (Note 1)             |  |  |  |
|                   |   | _        | 26   | 59  | 80             | μΑ    | 3.0        | ·                                  |  |  |  |
|                   |   | _        | 28   | 61  | 90             | μА    | 5.0        |                                    |  |  |  |
| D025              |   | _        | 15   | 28  | 30             | μА    | 1.8        | FVR current                        |  |  |  |
|                   |   | _        | 15   | 30  | 33             | μА    | 3.0        | 1                                  |  |  |  |
| D025              |   | _        | 38   | 96  | 100            | μΑ    | 1.8        | FVR current (Note 4)               |  |  |  |
|                   |   | _        | 45   | 110   | 120            | μΑ    | 3.0        |                                    |  |  |  |
|                   |   | _        | 90   | 140   | 155            | μА    | 5.0        |                                    |  |  |  |
| D026              |   | _        | 13   | 25  | 28             | μА    | 3.0        | BOR Current (Note 1)               |  |  |  |
| D026              |   | _        | 40   | 110   | 120            | μΑ    | 3.0        | BOR Current (Note 1, Note 4)       |  |  |  |
|                   |   | _        | 87   | 140   | 155            | μΑ    | 5.0        |                                    |  |  |  |
| D027              |   | _        | 0.6  | 5.0   | 9.0            | μΑ    | 1.8        | T1OSC Current (Note 1)             |  |  |  |
|                   |   | _        | 1.8  | 7.0   | 12             | μА    | 3.0        |                                    |  |  |  |
| D027              |   | _        | 22   | 57  | 60             | μА    | 1.8        | T1OSC Current (Note 1)             |  |  |  |
|                   |   | _        | 29   | 62  | 70             | μА    | 3.0        |                                    |  |  |  |
|                   | There is a second to the second | _        | 35   | 66  | 85             | μА    | 5.0        |                                    |  |  |  |

- \* These parameters are characterized but not tested.
- † Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.
- Note 1: The peripheral current is the sum of the base IDD or IPD and the additional current consumed when this peripheral is enabled. The peripheral Δ current can be determined by subtracting the base IDD or IPD current from this limit. Max values should be used when calculating total current consumption.
  - 2: The power-down current in Sleep mode does not depend on the oscillator type. Power-down current is measured with the part in Sleep mode, with all I/O pins in high-impedance state and tied to VDD.
  - 3: A/D oscillator source is FRC.
  - 4: 0.1 μF capacitor on VCAP (RA0).

## 30.3 DC Characteristics: PIC16(L)F1934/6/7-I/E (Power-Down) (Continued)

| PIC16LF1934/36/37                            |                         |        |      | Standard Operating Conditions (unless otherwise stated)  Operating temperature $-40^{\circ}\text{C} \le \text{Ta} \le +85^{\circ}\text{C}$ for industrial $-40^{\circ}\text{C} \le \text{Ta} \le +125^{\circ}\text{C}$ for extended |        |       |     |                                  |  |  |  |  |
|--|-------------------------|--------|------|---|--------|-------|-----|----------------------------------|--|--|--|--|
| PIC16F19                                     | 34/36/37                |        |      | Standard Operating Conditions (unless otherwise stated)  Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for industrial $-40^{\circ}\text{C} \le \text{TA} \le +125^{\circ}\text{C}$ for extended |        |       |     |                                  |  |  |  |  |
| Param  | Device Characteristics  | Min.   | Typ† | Max.  | Max.   | Units |     | Conditions                       |  |  |  |  |
| No.  | Devide Gildidoteriotics | 141111 | 1961 | +85°C   | +125°C | Ointo | VDD | Note                             |  |  |  |  |
| Power-down Base Current (IPD) <sup>(2)</sup> |                         |        |      |   |        |       |     |                                  |  |  |  |  |
| D028   |                         | _      | 0.1  | 4.0   | 8.0    | μА    | 1.8 | A/D Current (Note 1, Note 3), no |  |  |  |  |
|  |                         | _      | 0.1  | 5.0   | 9.0    | μА    | 3.0 | conversion in progress           |  |  |  |  |
| D028   |                         | _      | 22   | 56  | 63     | μА    | 1.8 | A/D Current (Note 1, Note 3), no |  |  |  |  |
|  |                         | _      | 26   | 58  | 78     | μА    | 3.0 | conversion in progress           |  |  |  |  |
|  |                         | _      | 27   | 61  | 88     | μА    | 5.0 |                                  |  |  |  |  |
| D029   |                         | _      | 250  | _   | _      | μА    | 1.8 | A/D Current (Note 1, Note 3),    |  |  |  |  |
|  |                         | _      | 250  | _   | _      | μА    | 3.0 | conversion in progress           |  |  |  |  |
| D029   |                         | _      | 280  | _   | _      | μА    | 1.8 | A/D Current (Note 1, Note 3,     |  |  |  |  |
|  |                         | _      | 280  | _   | _      | μА    | 3.0 | Note 4), conversion in progress  |  |  |  |  |
|  |                         | _      | 280  | _   | _      | μΑ    | 5.0 |                                  |  |  |  |  |
| D030   |                         | _      | 2    | 7   | 11     | μΑ    | 1.8 | Cap Sense, Low-Power mode        |  |  |  |  |
|  |                         | _      | 3    | 9   | 13     | μА    | 3.0 |                                  |  |  |  |  |
| D030   |                         | _      | 21   | 61  | 63     | μΑ    | 1.8 | Cap Sense, Low-Power mode        |  |  |  |  |
|  |                         | _      | 27   | 63  | 78     | μА    | 3.0 |                                  |  |  |  |  |
|  |                         | _      | 28   | 66  | 88     | μА    | 5.0 |                                  |  |  |  |  |
| D031   |                         | _      | 1    | _   | _      | μΑ    | 3.0 | LCD Bias Ladder, Low-power       |  |  |  |  |
|  |                         | _      | 10   | _   | _      | μΑ    | 3.0 | LCD Bias Ladder, Medium-power    |  |  |  |  |
|  |                         | _      | 75   | _   | _      | μА    | 3.0 | LCD Bias Ladder, High-power      |  |  |  |  |
| D031   |                         | _      | 1    | _   | _      | μΑ    | 5.0 | LCD Bias Ladder, Low-power       |  |  |  |  |
|  |                         | _      | 10   | _   | _      | μΑ    | 5.0 | LCD Bias Ladder, Medium-power    |  |  |  |  |
|  |                         | _      | 75   |   |        | μА    | 5.0 | LCD Bias Ladder, High-power      |  |  |  |  |
| D032   |                         |        | 7.6  | 22  | 25     | μΑ    | 1.8 | Comparator, Low-Power mode       |  |  |  |  |
|  |                         | _      | 8.0  | 23  | 27     | μΑ    | 3.0 |                                  |  |  |  |  |
| D032   |                         | _      | 24   | 65  | 75     | μА    | 1.8 | Comparator, Low-Power mode       |  |  |  |  |
|  |                         | _      | 26   | 75  | 88     | μΑ    | 3.0 |                                  |  |  |  |  |
|  |                         | _      | 28   | 77  | 97     | μА    | 5.0 |                                  |  |  |  |  |

<sup>\*</sup> These parameters are characterized but not tested.

- 2: The power-down current in Sleep mode does not depend on the oscillator type. Power-down current is measured with the part in Sleep mode, with all I/O pins in high-impedance state and tied to VDD.
- 3: A/D oscillator source is FRC.
- 4:  $0.1 \mu F$  capacitor on VCAP (RA0).

<sup>†</sup> Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

Note 1: The peripheral current is the sum of the base IDD or IPD and the additional current consumed when this peripheral is enabled. The peripheral Δ current can be determined by subtracting the base IDD or IPD current from this limit. Max values should be used when calculating total current consumption.

## 30.4 DC Characteristics: PIC16(L)F1934/6/7-I/E

|              |       |                                      | Standard Operating Conditions (unless otherwise stated) Operating temperature -40°C $\leq$ TA $\leq$ +85°C for industrial -40°C $\leq$ TA $\leq$ +125°C for extended |      |          |       |   |  |
|--------------|-------|--------------------------------------|--|------|----------|-------|---|--|
| Param<br>No. | Sym.  | Characteristic                       | Min.   | Тур† | Max.     | Units | Conditions  |  |
|              | VIL   | Input Low Voltage                    |  |      |          |       |   |  |
|              |       | I/O PORT:                            |  |      |          |       |   |  |
| D032         |       | with TTL buffer                      | _  | _    | 8.0      | >     | $4.5V \leq V \text{DD} \leq 5.5V$                                       |  |
| D032A        |       |                                      | _  | _    | 0.15 VDD | V     | $1.8V \le VDD \le 4.5V$   |  |
| D033         |       | with Schmitt Trigger buffer          | _  | _    | 0.2 VDD  | V     | $2.0V \le VDD \le 5.5V$   |  |
|              |       | with I <sup>2</sup> C™ levels        | _  | _    | 0.3 VDD  | V     |   |  |
|              |       | with SMBus levels                    | _  | _    | 0.8      | V     | $2.7V \le VDD \le 5.5V$   |  |
| D034         |       | MCLR, OSC1 (RC mode) <sup>(1)</sup>  | _  | _    | 0.2 VDD  | V     |   |  |
| D034A        |       | OSC1 (HS mode)                       | _  | _    | 0.3 VDD  | V     |   |  |
|              | VIH   | Input High Voltage                   | •  |      |          |       |   |  |
|              |       | I/O ports:                           |  |      |          |       |   |  |
| D040         |       | with TTL buffer                      | 2.0  | _    | _        | V     | $4.5V \le VDD \le 5.5V$   |  |
| D040A        |       |                                      | 0.25 VDD+<br>0.8   | _    | _        | V     | $1.8V \le VDD \le 4.5V$   |  |
| D041         |       | with Schmitt Trigger buffer          | 0.8 VDD  | _    | _        | V     | $2.0V \le VDD \le 5.5V$   |  |
|              |       | with I <sup>2</sup> C™ levels        | 0.7 VDD  | _    | _        | V     |   |  |
|              |       | with SMBus levels                    | 2.1  | _    | _        | V     | $2.7V \le VDD \le 5.5V$   |  |
| D042         |       | MCLR                                 | 0.8 VDD  | _    | _        | V     |   |  |
| D043A        |       | OSC1 (HS mode)                       | 0.7 VDD  | _    | _        | V     |   |  |
| D043B        |       | OSC1 (RC mode)                       | 0.9 VDD  | _    | _        | V     | VDD > 2.0V (Note 1)   |  |
|              | lıL   | Input Leakage Current <sup>(2)</sup> | I .  |      | · L      |       |   |  |
| D060         |       | I/O ports                            | _  | ± 5  | ± 125    | nA    | Vss ≤ VPIN ≤ VDD, Pin at high-<br>impedance @ 85°C                      |  |
|              |       |                                      |  | ± 5  | ± 1000   | nA    | 125°C   |  |
| D061         |       | MCLR <sup>(3)</sup>                  | _  | ± 50 | ± 200    | nA    | Vss ≤ Vpin ≤ Vdd @ 85°C   |  |
|              | IPUR  | Weak Pull-up Current                 |  |      |          | •     |   |  |
| D070*        |       |                                      | 25   | 100  | 200      |       | VDD = 3.3V, VPIN = VSS  |  |
|              | 14-   | 2                                    | 25   | 140  | 300      | μΑ    | VDD = 5.0V, VPIN = VSS  |  |
| Door         | Vol   | Output Low Voltage <sup>(4)</sup>    | <u> </u>   |      |          |       | Li. 0 A V 5V  |  |
| D080         |       | I/O ports                            | _  | _    | 0.6      | ٧     | IOL = 8mA, VDD = 5V<br>IOL = 6mA, VDD = 3.3V                            |  |
|              |       | (4)                                  |  |      |          |       | IOL = 1.8mA, VDD = 1.8V   |  |
|              | Vон   | Output High Voltage <sup>(4)</sup>   | I  |      |          | 1     | [   |  |
| D090         |       | I/O ports                            | VDD - 0.7  | _    | _        | ٧     | IOH = 3.5mA, VDD = 5V<br>IOH = 3mA, VDD = 3.3V<br>IOH = 1mA, VDD = 1.8V |  |
|              |       | Capacitive Loading Specs on          | Output Pins  |      | 1        |       | ı   |  |
| D101*        | COSC2 |                                      | _  | _    | 15       | pF    | In XT, HS and LP modes when external clock is used to drive OSC1        |  |
| D101A*       | Cio   | All I/O pins                         |  | _    | 50       | pF    |   |  |

<sup>\*</sup> These parameters are characterized but not tested.

<sup>†</sup> Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

Note 1: In RC oscillator configuration, the OSC1/CLKIN pin is a Schmitt Trigger input. It is not recommended to use an external clock in RC mode.

<sup>2:</sup> Negative current is defined as current sourced by the pin.

<sup>3:</sup> The leakage current on the MCLR pin is strongly dependent on the applied voltage level. The specified levels represent normal operating conditions. Higher leakage current may be measured at different input voltages.

<sup>4:</sup> Including OSC2 in CLKOUT mode.

## 30.4 DC Characteristics: PIC16(L)F1934/6/7-I/E (Continued)

| DC CHARACTERISTICS |      |   | Standard Operating Conditions (unless otherwise stated) Operating temperature -40°C $\leq$ TA $\leq$ +85°C for industrial -40°C $\leq$ TA $\leq$ +125°C for extended |     |   |    |            |  |  |
|--------------------|------|---|--|-----|---|----|------------|--|--|
| Param<br>No.       | Sym. | Characteristic                                | Min. Typ† Max. Units Conditions  |     |   |    | Conditions |  |  |
|                    |      | VCAP Capacitor Charging                       |  |     |   |    |            |  |  |
| D102               |      | Charging current                              | _  | 200 | _ | μΑ |            |  |  |
| D102A              |      | Source/sink capability when charging complete | _  | 0.0 | _ | mA |            |  |  |

- \* These parameters are characterized but not tested.
- † Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.
- Note 1: In RC oscillator configuration, the OSC1/CLKIN pin is a Schmitt Trigger input. It is not recommended to use an external clock in RC mode.
  - 2: Negative current is defined as current sourced by the pin.
  - 3: The leakage current on the MCLR pin is strongly dependent on the applied voltage level. The specified levels represent normal operating conditions. Higher leakage current may be measured at different input voltages.
  - 4: Including OSC2 in CLKOUT mode.

## 30.5 Memory Programming Requirements

| DC CHARACTERISTICS |        |   | Standard Operating Conditions (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +125^{\circ}\text{C}$ |      |                      |       |   |  |
|--------------------|--------|---|--|------|----------------------|-------|---|--|
| Param<br>No.       | Sym.   | Characteristic  | Min.   | Тур† | Max.                 | Units | Conditions                                    |  |
|                    |        | Program Memory Programming Specifications                           |  |      |                      |       |   |  |
| D110               | VIHH   | Voltage on MCLR/VPP/RE3 pin   | 8.0  | _    | 9.0                  | V     | (Note 3, Note 4)                              |  |
| D111               | IDDP   | Supply Current during Programming                                   | _  | _    | 10                   | mA    |   |  |
| D112               |        | VDD for Bulk Erase  | 2.7  | _    | V <sub>DD</sub> max. | V     |   |  |
| D113               | VPEW   | VDD for Write or Row Erase  | V <sub>DD</sub> min.   | _    | V <sub>DD</sub> max. | V     |   |  |
| D114               | IPPPGM | Current on MCLR/VPP during Erase/<br>Write                          | _  | _    | 1.0                  | mA    |   |  |
| D115               | IDDPGM | Current on VDD during Erase/Write                                   | _  |      | 5.0                  | mA    |   |  |
|                    |        | Data EEPROM Memory  |  |      |                      |       |   |  |
| D116               | ED     | Byte Endurance  | 100K   | _    | _                    | E/W   | -40°C to +85°C                                |  |
| D117               | VDRW   | VDD for Read/Write  | V <sub>DD</sub><br>min.  | _    | V <sub>DD</sub> max. | V     |   |  |
| D118               | TDEW   | Erase/Write Cycle Time  | _  | 4.0  | 5.0                  | ms    |   |  |
| D119               | TRETD  | Characteristic Retention  | _  | 40   | _                    | Year  | Provided no other specifications are violated |  |
| D120               | TREF   | Number of Total Erase/Write<br>Cycles before Refresh <sup>(2)</sup> | 1M   | 10M  | _                    | E/W   | -40°C to +85°C                                |  |
|                    |        | Program Flash Memory  |  |      |                      |       |   |  |
| D121               | EP     | Cell Endurance  | 10K  | _    |                      | E/W   | -40°C to +85°C ( <b>Note 1</b> )              |  |
| D122               | VPR    | VDD for Read  | V <sub>DD</sub> min.   | _    | V <sub>DD</sub> max. | V     |   |  |
| D123               | Tıw    | Self-timed Write Cycle Time   |  | 2    | 2.5                  | ms    |   |  |
| D124               | TRETD  | Characteristic Retention  | _  | 40   | _                    | Year  | Provided no other specifications are violated |  |

<sup>†</sup> Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

- Note 1: Self-write and Block Erase.
  - 2: Refer to Section 11.2 "Using the Data EEPROM" for a more detailed discussion on data EEPROM endurance.
  - **3:** Required only if single-supply programming is disabled.
  - **4:** The MPLAB ICD 2 does not support variable VPP output. Circuitry to limit the ICD 2 VPP voltage must be placed between the ICD 2 and target system when programming or debugging with the ICD 2.

#### 30.6 Thermal Considerations

Standard Operating Conditions (unless otherwise stated) Operating temperature  $-40\,^{\circ}\text{C} \le \text{TA} \le +125\,^{\circ}\text{C}$ 

| Operating temperature -40 C \( \frac{1}{2} \) (A \( \frac{1}{2} \) (7 \( \frac{1}{2} \) |  |                                     |      |                          |  |  |  |  |
|---|--|-------------------------------------|------|--------------------------|--|--|--|--|
| Param<br>No.  | Sym.                                       | Characteristic                      | Тур. | Units                    | Conditions   |  |  |  |
| TH01  | TH01 θJA Thermal Resistance Junction to Am |                                     | 60   | °C/W                     | 28-pin SPDIP package                                     |  |  |  |
|   |  |                                     | 80   | °C/W                     | 28-pin SOIC package                                      |  |  |  |
|   |  |                                     | 90   | °C/W                     | 28-pin SSOP package                                      |  |  |  |
|   |  |                                     | 27.5 | °C/W                     | 28-pin UQFN 4x4mm package                                |  |  |  |
|   |  |                                     | 27.5 | °C/W                     | 28-pin QFN 6x6mm package                                 |  |  |  |
|   |  |                                     | 47.2 | °C/W                     | 40-pin PDIP package                                      |  |  |  |
|   |  |                                     | 46   | °C/W                     | 44-pin TQFP package                                      |  |  |  |
|   |  |                                     | 24.4 | °C/W                     | 44-pin QFN 8x8mm package                                 |  |  |  |
| TH02  | θЈС  | Thermal Resistance Junction to Case | 31.4 | °C/W                     | 28-pin SPDIP package                                     |  |  |  |
|   |  |                                     | 24   | °C/W                     | 28-pin SOIC package                                      |  |  |  |
|   |  |                                     | 24   | °C/W                     | 28-pin SSOP package                                      |  |  |  |
|   |  |                                     | 24   | °C/W                     | 28-pin UQFN 4x4mm package                                |  |  |  |
|   |  |                                     | °C/W | 28-pin QFN 6x6mm package |  |  |  |  |
|   |  |                                     | 24.7 | °C/W                     | 40-pin PDIP package                                      |  |  |  |
|   |  |                                     | 14.5 | °C/W                     | 44-pin TQFP package                                      |  |  |  |
|   |  |                                     | 20   | °C/W                     | 44-pin QFN 8x8mm package                                 |  |  |  |
| TH03  | ТЈМАХ                                      | Maximum Junction Temperature        | 150  | °C                       |  |  |  |  |
| TH04  | PD   | Power Dissipation                   | _    | W                        | PD = PINTERNAL + PI/O                                    |  |  |  |
| TH05  | PINTERNAL                                  | Internal Power Dissipation          | _    | W                        | PINTERNAL = IDD x VDD <sup>(1)</sup>                     |  |  |  |
| TH06  | Pı/o                                       | I/O Power Dissipation               | _    | W                        | $PI/O = \Sigma (IOL * VOL) + \Sigma (IOH * (VDD - VOH))$ |  |  |  |
| TH07  | PDER                                       | Derated Power                       | _    | W                        | PDER = PDMAX (TJ - TA)/θJA <sup>(2)</sup>                |  |  |  |

Note 1: IDD is current to run the chip alone without driving any load on the output pins.

2: TA = Ambient Temperature

**3:** T<sub>J</sub> = Junction Temperature

## 30.7 Timing Parameter Symbology

The timing parameter symbols have been created with one of the following formats:


- 1. TppS2ppS
- 2. TppS

| 1       |                                       |     |          |
|---------|---------------------------------------|-----|----------|
| F       | Frequency                             | Т   | Time     |
| Lowerd  | case letters (pp) and their meanings: |     |          |
| рр      |                                       |     |          |
| СС      | CCP1                                  | osc | OSC1     |
| ck      | CLKOUT                                | rd  | RD       |
| cs      | <del>CS</del>                         | rw  | RD or WR |
| di      | SDI                                   | sc  | SCK      |
| do      | SDO                                   | ss  | SS       |
| dt      | Data in                               | tO  | T0CKI    |
| io      | I/O PORT                              | t1  | T1CKI    |
| mc      | MCLR                                  | wr  | WR       |
| Llanore | age letters and their meanings:       |     |          |

Uppercase letters and their meanings:


| S |                          |   |                |  |
|---|--------------------------|---|----------------|--|
| F | Fall                     | Р | Period         |  |
| Н | High                     | R | Rise           |  |
| 1 | Invalid (High-impedance) | V | Valid          |  |
| L | Low                      | Z | High-impedance |  |

### FIGURE 30-5: LOAD CONDITIONS



### 30.8 AC Characteristics: PIC16(L)F1934/6/7-I/E





#### TABLE 30-1: CLOCK OSCILLATOR TIMING REQUIREMENTS

Standard Operating Conditions (unless otherwise stated) Operating temperature  $-40^{\circ}C \le TA \le +125^{\circ}C$ **Param** Sym. Characteristic Min. Typ† Max. Units Conditions No. External CLKIN Frequency<sup>(1)</sup> OS01 DC 0.5 MHz EC Oscillator mode (low) DC EC Oscillator mode (medium) 4 MHz DC 20 MHz EC Oscillator mode (high) Oscillator Frequency<sup>(1)</sup> LP Oscillator mode 32.768 kHz 0.1 4 MHz XT Oscillator mode 1 4 MHz HS Oscillator mode 20 MHz HS Oscillator mode. VDD > 2.7V 1 DC 4 MHz RC Oscillator mode,  $VDD \le 2.0V$ OS02 Tosc External CLKIN Period<sup>(1)</sup> 27 LP Oscillator mode μS 250 XT Oscillator mode HS Oscillator mode 50 00 ns 50 EC Oscillator mode ns Oscillator Period<sup>(1)</sup> LP Oscillator mode 30.5 μS 250 10,000 XT Oscillator mode ns HS Oscillator mode 1,000 50 ns 250 RC Oscillator mode ns **OS03** Instruction Cycle Time<sup>(1)</sup> DC Tcy = 4/Fosc TCY 200 TCY ns OS04<sup>3</sup> TosH. External CLKIN High. 2 μS LP oscillator TosL External CLKIN Low XT oscillator 100 ns 20 HS oscillator ns OS05\* External CLKIN Rise. TosR. 0 LP oscillator ns External CLKIN Fall TosF XT oscillator 0 00 ns ns HS oscillator

<sup>\*</sup> These parameters are characterized but not tested.

<sup>†</sup> Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

Note 1: Instruction cycle period (TcY) equals four times the input oscillator time base period. All specified values are based on characterization data for that particular oscillator type under standard operating conditions with the device executing code. Exceeding these specified limits may result in an unstable oscillator operation and/or higher than expected current consumption. All devices are tested to operate at "min" values with an external clock applied to OSC1 pin. When an external clock input is used, the "max" cycle time limit is "DC" (no clock) for all devices.

#### **TABLE 30-2: OSCILLATOR PARAMETERS**

| Standard Operating Conditions (unless otherwise stated)  Operating Temperature $-40^{\circ}C \le TA \le +125^{\circ}C$ |          |   |                    |        |              |        |            |   |  |
|--|----------|---|--------------------|--------|--------------|--------|------------|---|--|
| Param<br>No.   | Sym.     | Characteristic  | Freq.<br>Tolerance | Min.   | Тур†         | Max.   | Units      | Conditions  |  |
| OS08   | HFosc    | Internal Calibrated HFINTOSC Frequency <sup>(2)</sup> | ±2%<br>±3%         | _<br>_ | 16.0<br>16.0 | _<br>_ | MHz<br>MHz | $0^{\circ}C \le TA \le +60^{\circ}C$ , $VDD \ge 2.5V$<br>$60^{\circ}C \le TA \le 85^{\circ}C$ , $VDD \ge 2.5V$  |  |
|  |          |   | ±5%                | _      | 16.0         | _      | MHz        | -40°C ≤ TA ≤ +125°C   |  |
| OS08A  | MFosc    | Internal Calibrated MFINTOSC Frequency <sup>(2)</sup> | ±2%<br>±3%         |        | 500<br>500   |        | kHz<br>kHz | $\label{eq:control_control_control} \begin{split} 0^{\circ}C \leq T & A \leq +60^{\circ}C, \ V \text{DD} \geq 2.5 \text{V} \\ 60^{\circ}C \leq T & A \leq 85^{\circ}C, \ V \text{DD} \geq 2.5 \text{V} \end{split}$ |  |
|  |          |   | ±5%                | _      | 500          | _      | kHz        | -40°C ≤ TA ≤ +125°C   |  |
| OS09   | LFosc    | Internal LFINTOSC Frequency                           | _                  | _      | 31           | _      | kHz        | $-40^{\circ}\text{C} \le \text{Ta} \le +125^{\circ}\text{C}$  |  |
| OS10*  | Tiosc st | HFINTOSC<br>Wake-up from Sleep Start-up Time          | _                  | _      | 3.2          | 8      | μS         |   |  |
|  |          | MFINTOSC<br>Wake-up from Sleep Start-up Time          | _                  | _      | 24           | 35     | μS         |   |  |

- \* These parameters are characterized but not tested.
- † Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.
- Note 1: Instruction cycle period (TcY) equals four times the input oscillator time base period. All specified values are based on characterization data for that particular oscillator type under standard operating conditions with the device executing code. Exceeding these specified limits may result in an unstable oscillator operation and/or higher than expected current consumption. All devices are tested to operate at "min" values with an external clock applied to the OSC1 pin. When an external clock input is used, the "max" cycle time limit is "DC" (no clock) for all devices.
  - 2: To ensure these oscillator frequency tolerances, VDD and Vss must be capacitively decoupled as close to the device as possible.  $0.1~\mu F$  and  $0.01~\mu F$  values in parallel are recommended.
  - 3: By design.

#### TABLE 30-3: PLL CLOCK TIMING SPECIFICATIONS (VDD = 2.7V TO 5.5V)

| Param<br>No. | Sym.         | Characteristic                | Min.   | Typ† | Max.   | Units | Conditions |
|--------------|--------------|-------------------------------|--------|------|--------|-------|------------|
| F10          | Fosc         | Oscillator Frequency Range    | 4      | _    | 8      | MHz   |            |
| F11          | Fsys         | On-Chip VCO System Frequency  | 16     | _    | 32     | MHz   |            |
| F12          | TRC          | PLL Start-up Time (Lock Time) | _      | _    | 2      | ms    |            |
| F13*         | $\Delta$ CLK | CLKOUT Stability (Jitter)     | -0.25% | _    | +0.25% | %     |            |

- \* These parameters are characterized but not tested.
- † Data in "Typ" column is at 5V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.







TABLE 30-4: CLKOUT AND I/O TIMING PARAMETERS

|              |          | g Conditions (unless otherwise stated) ure $-40^{\circ}C \le TA \le +125^{\circ}C$ |               |      |      |       |                |
|--------------|----------|--|---------------|------|------|-------|----------------|
| Param<br>No. | Sym.     | Characteristic   | Min.          | Тур† | Max. | Units | Conditions     |
| OS11         | TosH2ckL | Fosc↑ to CLKOUT↓ (1)   | _             |      | 70   | ns    | VDD = 3.3-5.0V |
| OS12         | TosH2ckH | Fosc↑ to CLKOUT↑ (1)   | _             |      | 72   | ns    | VDD = 3.3-5.0V |
| OS13         | TckL2ioV | CLKOUT↓ to Port out valid <sup>(1)</sup>   | _             |      | 20   | ns    |                |
| OS14         | TioV2ckH | Port input valid before CLKOUT <sup>(1)</sup>                                      | Tosc + 200 ns | _    | _    | ns    |                |
| OS15         | TosH2ioV | Fosc↑ (Q1 cycle) to Port out valid   | _             | 50   | 70*  | ns    | VDD = 3.3-5.0V |
| OS16         | TosH2ioI | Fosc↑ (Q2 cycle) to Port input invalid (I/O in hold time)                          | 50            | _    | _    | ns    | VDD = 3.3-5.0V |
| OS17         | TioV2osH | Port input valid to Fosc↑ (Q2 cycle) (I/O in setup time)                           | 20            | _    | _    | ns    |                |
| OS18         | TioR     | Port output rise time  | _             | 40   | 72   | ns    | VDD = 1.8V     |
|              |          |  | _             | 15   | 32   |       | VDD = 3.3-5.0V |
| OS19         | TioF     | Port output fall time  | _             | 28   | 55   | ns    | VDD = 1.8V     |
|              |          |  | _             | 15   | 30   |       | VDD = 3.3-5.0V |
| OS20*        | Tinp     | INT pin input high or low time   | 25            |      |      | ns    |                |
| OS21*        | Tioc     | Interrupt-on-change new input level time   | 25            | _    | _    | ns    |                |

<sup>\*</sup> These parameters are characterized but not tested.


**Note 1:** Measurements are taken in RC mode where CLKOUT output is 4 x Tosc.

FIGURE 30-8: RESET, WATCHDOG TIMER, OSCILLATOR START-UP TIMER AND POWER-UP TIMER TIMING



<sup>†</sup> Data in "Typ" column is at 3.0V, 25°C unless otherwise stated.

### FIGURE 30-9: BROWN-OUT RESET TIMING AND CHARACTERISTICS



Note 1: 64 ms delay only if PWRTE bit in the Configuration Word register is programmed to '0'.


2 ms delay if PWRTE = 0 and VREGEN = 1.

TABLE 30-5: RESET, WATCHDOG TIMER, OSCILLATOR START-UP TIMER, POWER-UP TIMER AND BROWN-OUT RESET PARAMETERS

Standard Operating Conditions (unless otherwise stated) Operating Temperature -40°C ≤ TA ≤ +125°C **Param** Sym. Characteristic Min. Typ† Max. Units Conditions No. 30 **TMCL** MCLR Pulse Width (low) 2 μS 31 **TWDTLP** Low-Power Watchdog Timer 10 16 27 ms VDD = 3.3V-5VTime-out Period 1:16 Prescaler used Oscillator Start-up Timer Period(1), (2) 32 1024 **Tost** Tosc (Note 3) 33\* Power-up Timer Period,  $\overline{PWRTE} = 0$ **T**PWRT 40 65 140 ms 34\* Tıoz I/O high-impedance from MCLR Low 2.0 us or Watchdog Timer Reset 35 Brown-out Reset Voltage **V**BOR 2.38 2.5 2.73 BORV=2.5V 1.80 BORV=1.9V 1.9 2.11 36\* Brown-out Reset Hysteresis 0 25 -40°C to +85°C **VHYST** 60 mV 37\* **TBORDC** Brown-out Reset DC Response 1 3 35 VDD ≤ VBOR μS Time

- \* These parameters are characterized but not tested.
- † Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.
- Note 1: Instruction cycle period (TcY) equals four times the input oscillator time base period. All specified values are based on characterization data for that particular oscillator type under standard operating conditions with the device executing code. Exceeding these specified limits may result in an unstable oscillator operation and/or higher than expected current consumption. All devices are tested to operate at "min" values with an external clock applied to the OSC1 pin. When an external clock input is used, the "max" cycle time limit is "DC" (no clock) for all devices.
  - 2: By design.
  - 3: Period of the slower clock.
  - **4:** To ensure these voltage tolerances, VDD and Vss must be capacitively decoupled as close to the device as possible. 0.1 µF and 0.01 µF values in parallel are recommended.


FIGURE 30-10: TIMERO AND TIMER1 EXTERNAL CLOCK TIMINGS



### TABLE 30-6: TIMERO AND TIMER1 EXTERNAL CLOCK REQUIREMENTS

Standard Operating Conditions (unless otherwise stated) Operating Temperature -40°C ≤ TA ≤ +125°C **Param** Characteristic Min. Units **Conditions** Sym. Typ† Max. No. 40\* Тт0Н T0CKI High Pulse Width No Prescaler 0.5 Tcy + 20 ns With Prescaler 10 ns 41\* TT0L T0CKI Low Pulse Width No Prescaler 0.5 Tcy + 20 ns With Prescaler 10 ns 42\* Тт0Р T0CKI Period Greater of: ns N = prescale value 20 or TCY + 40 (2, 4, ..., 256) 45\* TT1H T1CKI High Synchronous, No Prescaler 0.5 Tcy + 20ns Time Synchronous, 15 ns with Prescaler Asynchronous 30 ns 46\* TT1L T1CKI Low Synchronous, No Prescaler 0.5 Tcy + 20 ns Time Synchronous, with Prescaler 15 ns 30 Asynchronous ns N = prescale value 47\* TT1P T1CKI Input Synchronous Greater of: ns Period 30 or TCY + 40 (1, 2, 4, 8)Ν Asynchronous 60 ns 48 FT1 Timer1 Oscillator Input Frequency Range 32.768 33.1 kHz 32.4 (oscillator enabled by setting bit T1OSCEN) 49\* TCKEZTMR1 Delay from External Clock Edge to Timer 2 Tosc 7 Tosc Timers in Sync Increment mode

### FIGURE 30-11: CAPTURE/COMPARE/PWM TIMINGS (CCP)



### TABLE 30-7: CAPTURE/COMPARE/PWM REQUIREMENTS (CCP)

|   | Standard Operating Conditions (unless otherwise stated)<br>Operating Temperature $-40^{\circ}\text{C} \le \text{TA} \le +125^{\circ}\text{C}$ |                      |                |                |   |   |    |                                 |  |  |  |  |
|---|---|----------------------|----------------|----------------|---|---|----|---------------------------------|--|--|--|--|
| Param No.     Sym.     Characteristic     Min.     Typ†     Max.     Units     Conditions |   |                      |                |                |   |   |    |                                 |  |  |  |  |
| CC01*   | TccL  | CCPx Input Low Time  | No Prescaler   | 0.5Tcy + 20    | _ | _ | ns |                                 |  |  |  |  |
|   |   |                      | With Prescaler | 20             | _ | _ | ns |                                 |  |  |  |  |
| CC02*   | TccH  | CCPx Input High Time | No Prescaler   | 0.5Tcy + 20    | _ | _ | ns |                                 |  |  |  |  |
|   |   |                      | With Prescaler | 20             | _ | _ | ns |                                 |  |  |  |  |
| CC03*   | TccP  | CCPx Input Period    |                | 3Tcy + 40<br>N | _ | _ | ns | N = prescale value (1, 4 or 16) |  |  |  |  |

<sup>\*</sup> These parameters are characterized but not tested.

<sup>\*</sup> These parameters are characterized but not tested.

<sup>†</sup> Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

<sup>†</sup> Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

### TABLE 30-8: PIC16(L)F1934/6/7 A/D CONVERTER (ADC) CHARACTERISTICS:

|              | Standard Operating Conditions (unless otherwise stated) Operating temperature Tested at 25°C |   |      |      |      |       |  |  |  |  |  |
|--------------|--|---|------|------|------|-------|--|--|--|--|--|
| Param<br>No. | Sym.   | Characteristic                                    | Min. | Typ† | Max. | Units | Conditions   |  |  |  |  |
| AD01         | NR   | Resolution  | _    | _    | 10   | bit   |  |  |  |  |  |
| AD02         | EIL  | Integral Error                                    | _    | _    | ±1.7 | LSb   | VREF = 3.0V  |  |  |  |  |
| AD03         | EDL  | Differential Error                                | _    | _    | ±1   | LSb   | No missing codes<br>VREF = 3.0V  |  |  |  |  |
| AD04         | Eoff   | Offset Error                                      | _    | _    | ±2.5 | LSb   | VREF = 3.0V  |  |  |  |  |
| AD05         | Egn  | Gain Error  | _    | _    | ±2.0 | LSb   | VREF = 3.0V  |  |  |  |  |
| AD06         | VREF   | Reference Voltage <sup>(3)</sup>                  | 1.8  | _    | VDD  | V     | VREF = (VREF+ minus VREF-) (Note 5)                                      |  |  |  |  |
| AD07         | Vain   | Full-Scale Range                                  | Vss  | _    | VREF | V     |  |  |  |  |  |
| AD08         | ZAIN   | Recommended Impedance of<br>Analog Voltage Source | _    | _    | 10   | kΩ    | Can go higher if external $0.01\mu F$ capacitor is present on input pin. |  |  |  |  |

- These parameters are characterized but not tested.
- † Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.
- Note 1: Total Absolute Error includes integral, differential, offset and gain errors.
  - 2: The A/D conversion result never decreases with an increase in the input voltage and has no missing codes.
  - 3: ADC VREF is from external VREF, VDD pin or FVR, whichever is selected as reference input.
  - **4:** When ADC is off, it will not consume any current other than leakage current. The power-down current specification includes any such leakage from the ADC module.
  - 5: FVR voltage selected must be 2.048V or 4.096V.


### TABLE 30-9: PIC16(L)F1934/6/7 A/D CONVERSION REQUIREMENTS

|              | Standard Operating Conditions (unless otherwise stated)  Operating temperature -40°C ≤ Ta ≤ +125°C |   |      |      |      |       |  |  |  |  |  |
|--------------|--|---|------|------|------|-------|--|--|--|--|--|
| Param<br>No. | Sym.   | Characteristic  | Min. | Тур† | Max. | Units | Conditions                             |  |  |  |  |
| AD130*       | TAD  | A/D Clock Period  | 1.0  |      | 9.0  | μS    | Tosc-based                             |  |  |  |  |
|              |  | A/D Internal RC Oscillator<br>Period                            | 1.0  | 2.5  | 6.0  | μS    | ADCS<1:0> = 11 (ADRC mode)             |  |  |  |  |
| AD131        | TCNV   | Conversion Time (not including Acquisition Time) <sup>(1)</sup> | -    | 11   | _    | TAD   | Set GO/DONE bit to conversion complete |  |  |  |  |
| AD132*       | TACQ   | Acquisition Time  | _    | 5.0  | _    | μS    |  |  |  |  |  |

- \* These parameters are characterized but not tested.
- † Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.


Note 1: The ADRES register may be read on the following TcY cycle.

### FIGURE 30-12: PIC16(L)F1934/6/7 A/D CONVERSION TIMING (NORMAL MODE)



**Note 1:** If the A/D clock source is selected as RC, a time of Tcy is added before the A/D clock starts. This allows the SLEEP instruction to be executed.

### FIGURE 30-13: PIC16(L)F1934/6/7 A/D CONVERSION TIMING (SLEEP MODE)



**Note 1:** If the A/D clock source is selected as RC, a time of Tcy is added before the A/D clock starts. This allows the SLEEP instruction to be executed.

**TABLE 30-10: COMPARATOR SPECIFICATIONS** 

| Operating    | Operating Conditions: 1.8V < VDD < 5.5V, -40°C < TA < +125°C (unless otherwise stated). |   |      |      |      |       |                 |  |  |  |  |
|--------------|---|---|------|------|------|-------|-----------------|--|--|--|--|
| Param<br>No. | Sym.   Characteristics   N  |   | Min. | Тур. | Max. | Units | Comments        |  |  |  |  |
| CM01         | VIOFF   | Input Offset Voltage                    | _    | ±7.5 | ±60  | mV    | High-Power mode |  |  |  |  |
| CM02         | VICM  | Input Common Mode Voltage               | 0    | _    | VDD  | V     |                 |  |  |  |  |
| CM03         | CMRR  | Common Mode Rejection Ratio             | _    | 50   | _    | dB    |                 |  |  |  |  |
| CM04A        |   | Response Time Rising Edge               | _    | 400  | 800  | ns    | High-Power mode |  |  |  |  |
| CM04B        | TRESP   | Response Time Falling Edge              | _    | 200  | 400  | ns    | High-Power mode |  |  |  |  |
| CM04C        | TRESP   | Response Time Rising Edge               | _    | 1200 | _    | ns    | Low-Power mode  |  |  |  |  |
| CM04D        |   | Response Time Falling Edge              | _    | 550  | _    | ns    | Low-Power mode  |  |  |  |  |
| CM05         | TMC2OV  | Comparator Mode Change to Output Valid* | _    | _    | 10   | μS    |                 |  |  |  |  |
| CM06         | CHYSTER   | Comparator Hysteresis                   | _    | 45   | _    | mV    | Hysteresis on   |  |  |  |  |

<sup>\*</sup> These parameters are characterized but not tested.

- **Note 1:** Response time measured with one comparator input at VDD/2, while the other input transitions from Vss to VDD.
  - 2: Comparator Hysteresis is available when the CxHYS bit of the CMxCON0 register is enabled.


TABLE 30-11: DIGITAL-TO-ANALOG CONVERTER (DAC) SPECIFICATIONS

| Operating    | Operating Conditions: 2.5V < V <sub>DD</sub> < 5.5V, -40°C < T <sub>A</sub> < +125°C (unless otherwise stated). |                              |   |        |       |     |  |  |  |  |  |
|--------------|---|------------------------------|---|--------|-------|-----|--|--|--|--|--|
| Param<br>No. | Sym   Characteristics   Min   Ivn   Max   Units   Comments  |                              |   |        |       |     |  |  |  |  |  |
| DAC01*       | CLSB  | Step Size                    | _ | VDD/32 |       | V   |  |  |  |  |  |
| DAC02*       | CACC  | Absolute Accuracy            | _ | _      | ± 1/2 | LSb |  |  |  |  |  |
| DAC03*       | CR  | Unit Resistor Value (R)      | _ | 5000   | _     | Ω   |  |  |  |  |  |
| DAC04*       | CsT   | Settling Time <sup>(1)</sup> | _ | _      | 10    | μS  |  |  |  |  |  |

These parameters are characterized but not tested.

Note 1: Settling time measured while DACR<4:0> transitions from '0000' to '1111'.


### FIGURE 30-14: USART SYNCHRONOUS TRANSMISSION (MASTER/SLAVE) TIMING



### TABLE 30-12: USART SYNCHRONOUS TRANSMISSION REQUIREMENTS

|   | Standard Operating Conditions (unless otherwise stated)  Operating Temperature $-40^{\circ}\text{C} \le \text{TA} \le +125^{\circ}\text{C}$ |                                   |          |   |     |    |  |  |  |  |  |  |
|---|---|-----------------------------------|----------|---|-----|----|--|--|--|--|--|--|
| Param. No. Symbol Characteristic Min. Max. Units Conditions   |   |                                   |          |   |     |    |  |  |  |  |  |  |
| US120   | TCKH2DTV  | SYNC XMIT (Master and Slave)      | 3.0-5.5V | _ | 80  | ns |  |  |  |  |  |  |
|   |   | Clock high to data-out valid      | 1.8-5.5V | _ | 100 | ns |  |  |  |  |  |  |
| US121   | TCKRF   | Clock out rise time and fall time | 3.0-5.5V | _ | 45  | ns |  |  |  |  |  |  |
|   |   | (Master mode)                     | 1.8-5.5V | _ | 50  | ns |  |  |  |  |  |  |
| US122 TDTRF Data-out rise time and fall time 3.0-5.5V — 45 ns |   |                                   |          |   |     |    |  |  |  |  |  |  |
|   |   |                                   | 1.8-5.5V | _ | 50  | ns |  |  |  |  |  |  |

### FIGURE 30-15: USART SYNCHRONOUS RECEIVE (MASTER/SLAVE) TIMING



### **TABLE 30-13: USART SYNCHRONOUS RECEIVE REQUIREMENTS**

|               | Standard Operating Conditions (unless otherwise stated)<br>Operating Temperature $-40^{\circ}\text{C} \le \text{TA} \le +125^{\circ}\text{C}$ |                                     |    |  |    |  |  |  |  |  |
|---------------|---|-------------------------------------|----|--|----|--|--|--|--|--|
| Param.<br>No. | Symbol   Characteristic   Min   May   Units   Conditions  |                                     |    |  |    |  |  |  |  |  |
| US125         | US125 TDTV2CKL SYNC RCV (Master and Slave) Data-hold before CK ↓ (DT hold time) 10 — ns   |                                     |    |  |    |  |  |  |  |  |
| US126         | TCKL2DTL  | Data-hold after CK ↓ (DT hold time) | 15 |  | ns |  |  |  |  |  |

FIGURE 30-16: SPI MASTER MODE TIMING (CKE = 0, SMP = 0)




FIGURE 30-17: SPI MASTER MODE TIMING (CKE = 1, SMP = 1)




FIGURE 30-18: SPI SLAVE MODE TIMING (CKE = 0)





FIGURE 30-19: SPI SLAVE MODE TIMING (CKE = 1)




**TABLE 30-14: SPI MODE REQUIREMENTS** 

| Param<br>No. | Symbol                | Characteristic                              |                            | Min.        | Тур† | Max. | Units | Conditions |
|--------------|-----------------------|---|----------------------------|-------------|------|------|-------|------------|
| SP70*        | TssL2scH,<br>TssL2scL | SS↓ to SCK↓ or SCK↑ input                   |                            | Tcy         | _    | _    | ns    |            |
| SP71*        | TscH                  | SCK input high time (Slave mode             | ∋)                         | Tcy + 20    | _    | _    | ns    |            |
| SP72*        | TscL                  | SCK input low time (Slave mode              | )                          | Tcy + 20    | _    | _    | ns    |            |
| SP73*        | TDIV2scH,<br>TDIV2scL | Setup time of SDI data input to S           | CK edge                    | 100         | _    | _    | ns    |            |
| SP74*        | TscH2DIL,<br>TscL2DIL | Hold time of SDI data input to SC           | CK edge                    | 100         | _    | _    | ns    |            |
| SP75*        | TDOR                  | SDO data output rise time                   | 3.0-5.5V                   | _           | 10   | 25   | ns    |            |
|              |                       |   | 1.8-5.5V                   | _           | 25   | 50   | ns    |            |
| SP76*        | TDOF                  | SDO data output fall time                   |                            | _           | 10   | 25   | ns    |            |
| SP77*        | TssH2DoZ              | SS↑ to SDO output high-impeda               | nce                        | 10          | _    | 50   | ns    |            |
| SP78*        | TscR                  | SCK output rise time                        | 3.0-5.5V                   | _           | 10   | 25   | ns    |            |
|              |                       | (Master mode)                               | 1.8-5.5V                   | _           | 25   | 50   | ns    |            |
| SP79*        | TscF                  | SCK output fall time (Master mod            | de)                        | _           | 10   | 25   | ns    |            |
| SP80*        | TscH2DoV,             | SDO data output valid after                 | 3.0-5.5V                   | _           | _    | 50   | ns    |            |
|              | TscL2DoV              | SCK edge                                    | 1.8-5.5V                   | _           | _    | 145  | ns    |            |
| SP81*        | TDOV2scH,<br>TDOV2scL | SDO data output setup to SCK e              | out setup to SCK edge      |             | _    | _    | ns    |            |
| SP82*        | TssL2DoV              | SDO data output valid after <del>SS</del> ↓ | utput valid after SS↓ edge |             | _    | 50   | ns    |            |
| SP83*        | TscH2ssH,<br>TscL2ssH | SS ↑ after SCK edge                         |                            | 1.5Tcy + 40 | _    | _    | ns    |            |

These parameters are characterized but not tested.

FIGURE 30-20: I<sup>2</sup>C™ BUS START/STOP BITS TIMING



<sup>†</sup> Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

TABLE 30-15: I<sup>2</sup>C™ BUS START/STOP BITS REQUIREMENTS

| Param<br>No. | Symbol  | Characteristic  |              | Min. | Тур | Max. | Units | Conditions                   |
|--------------|---------|-----------------|--------------|------|-----|------|-------|------------------------------|
| SP90*        | Tsu:sta | Start condition | 100 kHz mode | 4700 | _   | _    | ns    | Only relevant for Repeated   |
|              |         | Setup time      | 400 kHz mode | 600  | _   | _    |       | Start condition              |
| SP91*        | THD:STA | Start condition | 100 kHz mode | 4000 | _   | _    |       | After this period, the first |
|              |         | Hold time       | 400 kHz mode | 600  | _   | _    |       | clock pulse is generated     |
| SP92*        | Tsu:sto | Stop condition  | 100 kHz mode | 4700 | _   | _    | ns    |                              |
|              |         | Setup time      | 400 kHz mode | 600  | -   | _    |       |                              |
| SP93         | THD:STO | Stop condition  | 100 kHz mode | 4000 | _   |      | ns    |                              |
|              |         | Hold time       | 400 kHz mode | 600  | _   | _    |       |                              |

<sup>\*</sup> These parameters are characterized but not tested.

### FIGURE 30-21: I<sup>2</sup>C™ BUS DATA TIMING




TABLE 30-16: I<sup>2</sup>C™ BUS DATA REQUIREMENTS

| Param.<br>No. | Symbol  | Characte              | eristic      | Min.       | Max. | Units | Conditions                                  |
|---------------|---------|-----------------------|--------------|------------|------|-------|---|
| SP100*        | THIGH   | Clock high time       | 100 kHz mode | 4.0        |      | μS    | Device must operate at a minimum of 1.5 MHz |
|               |         |                       | 400 kHz mode | 0.6        | I    | μ\$   | Device must operate at a minimum of 10 MHz  |
|               |         |                       | SSP module   | 1.5TcY     | _    |       |   |
| SP101*        | TLOW    | Clock low time        | 100 kHz mode | 4.7        | 1    | μS    | Device must operate at a minimum of 1.5 MHz |
|               |         |                       | 400 kHz mode | 1.3        | I    | μ\$   | Device must operate at a minimum of 10 MHz  |
|               |         |                       | SSP module   | 1.5Tcy     |      |       |   |
| SP102*        | Tr      | SDA and SCL rise      | 100 kHz mode | _          | 1000 | ns    |   |
|               |         | time                  | 400 kHz mode | 20 + 0.1CB | 300  | ns    | CB is specified to be from 10-400 pF        |
| SP103*        | TF      | SDA and SCL fall      | 100 kHz mode | _          | 250  | ns    |   |
|               |         | time                  | 400 kHz mode | 20 + 0.1CB | 250  | ns    | CB is specified to be from 10-400 pF        |
| SP106*        | THD:DAT | Data input hold time  | 100 kHz mode | 0          | _    | ns    |   |
|               |         |                       | 400 kHz mode | 0          | 0.9  | μS    |   |
| SP107*        | TSU:DAT | Data input setup      | 100 kHz mode | 250        | _    | ns    | (Note 2)                                    |
|               |         | time                  | 400 kHz mode | 100        | _    | ns    |   |
| SP109*        | ТАА     | Output valid from     | 100 kHz mode | _          | 3500 | ns    | (Note 1)                                    |
|               |         | clock                 | 400 kHz mode | _          | _    | ns    |   |
| SP110*        | TBUF    | Bus free time         | 100 kHz mode | 4.7        |      | μS    | Time the bus must be free                   |
|               |         |                       | 400 kHz mode | 1.3        |      | μS    | before a new transmission can start         |
| SP111         | Св      | Bus capacitive loadir | ng           | _          | 400  | pF    |   |

<sup>\*</sup> These parameters are characterized but not tested.


- **Note 1:** As a transmitter, the device must provide this internal minimum delay time to bridge the undefined region (min. 300 ns) of the falling edge of SCL to avoid unintended generation of Start or Stop conditions.
  - 2: A Fast mode (400 kHz) I<sup>2</sup>C™ bus device can be used in a Standard mode (100 kHz) I<sup>2</sup>C bus system, but the requirement Tsu:DAT ≥ 250 ns must then be met. This will automatically be the case if the device does not stretch the low period of the SCL signal. If such a device does stretch the low period of the SCL signal, it must output the next data bit to the SDA line TR max. + Tsu:DAT = 1000 + 250 = 1250 ns (according to the Standard mode I<sup>2</sup>C bus specification), before the SCL line is released.

TABLE 30-17: CAP SENSE OSCILLATOR SPECIFICATIONS

| Param.<br>No. | Symbol | Characteristic                |                       | Min.              | Typ†              | Max.              | Units          | Conditions |
|---------------|--------|-------------------------------|-----------------------|-------------------|-------------------|-------------------|----------------|------------|
| CS01          | ISRC   | Current Source                | High                  | -3                | -8                | -15               | μΑ             |            |
|               |        |                               | Medium                | -0.8              | -1.5              | -3                | μΑ             |            |
|               |        |                               | Low                   | -0.1              | -0.3              | -0.4              | μΑ             |            |
| CS02          | ISNK   | Current Sink                  | High                  | 2.5               | 7.5               | 14                | μΑ             |            |
|               |        |                               | Medium                | 0.6               | 1.5               | 2.9               | μΑ             |            |
|               |        |                               | Low                   | 0.1               | 0.25              | 0.6               | μΑ             |            |
| CS03          | VСтн   | Cap Threshold                 |                       | _                 | 8.0               | _                 | mV             |            |
| CS04          | VCTL   | Cap Threshold                 |                       | _                 | 0.4               | _                 | mV             |            |
| CS05          | VCHYST | Cap Hysteresis<br>(VCTH-VCTL) | High<br>Medium<br>Low | 350<br>250<br>175 | 525<br>375<br>300 | 725<br>500<br>425 | mV<br>mV<br>mV |            |

<sup>\*</sup> These parameters are characterized but not tested.

FIGURE 30-22: CAP SENSE OSCILLATOR



<sup>†</sup> Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

### 31.0 DC AND AC CHARACTERISTICS GRAPHS AND CHARTS

FIGURE 31-1: PIC16F1934/6/7 RESET VOLTAGE, BOR = 1.9V




FIGURE 31-2: PIC16F1934/6/7 HYSTERESIS, BOR = 1.9V




FIGURE 31-3: PIC16F1934/6/7 RESET VOLTAGE, BOR = 2.5V




FIGURE 31-4: PIC16F1934/6/7 HYSTERESIS, BOR = 2.5V




FIGURE 31-5: PIC16F1934/6/7 POR RELEASE




FIGURE 31-6: PIC16F1934/6/7 COMPARATOR HYSTERESIS, HIGH-POWER MODE




FIGURE 31-7: PIC16F1934/6/7 COMPARATOR HYSTERESIS, LOW-POWER MODE





FIGURE 31-8: PIC16F1934/6/7 COMPARATOR OFFSET, HIGH-POWER MODE, VDD = 5.5V



3


3.6

5.5

FIGURE 31-10: TYPICAL COMPARATOR RESPONSE TIME OVER TEMPERATURE, HIGH-POWER MODE

VDD (V)

2.5



1.8

2

FIGURE 31-11: VOH vs. IOH OVER TEMPERATURE (VDD = 5.0V)




FIGURE 31-12: Vol vs. Iol OVER TEMPERATURE (VDD = 5.0V)




FIGURE 31-13: VOH vs. IOH OVER TEMPERATURE (VDD = 3.0V)




FIGURE 31-14: Vol vs. Iol OVER TEMPERATURE (VDD = 3.0V)




FIGURE 31-15: VOH vs. IOH OVER TEMPERATURE (VDD = 1.8V)




FIGURE 31-16: Vol vs. Iol OVER TEMPERATURE (VDD = 1.8V)




FIGURE 31-17: PIC16LF1937 HF INTOSC MODE, Fosc = 8 MHz




FIGURE 31-18: PIC16F1937 MF INTOSC MODE, Fosc = 500 kHz




FIGURE 31-19: PIC16LF1937 HF INTOSC MODE, Fosc = 16 MHz




FIGURE 31-20: PIC16F1937 HF INTOSC MODE, Fosc = 16 MHz




FIGURE 31-21: PIC16F1937 HF INTOSC MODE, Fosc = 8 MHz




FIGURE 31-22: PIC16F1937 LF INTOSC MODE, Fosc = 32 kHz




FIGURE 31-23: PIC16LF1937 LF INTOSC MODE, Fosc = 32 kHz




FIGURE 31-24: PIC16LF1937 MF INTOSC MODE, Fosc = 500 kHz




FIGURE 31-25: PIC16LF1937 LP OSCILLATOR MODE, Fosc = 32 kHz




FIGURE 31-26: PIC16F1937 LP OSCILLATOR MODE, Fosc = 32 kHz




FIGURE 31-27: PIC16LF1937 HS OSCILLATOR MODE, Fosc = 32 MHz




FIGURE 31-28: PIC16F1937 HS OSCILLATOR MODE, Fosc = 32 MHz




FIGURE 31-29: PIC16LF1937 EXTRC MODE, Fosc = 4 MHz




FIGURE 31-30: PIC16LF1937 XT OSCILLATOR, Fosc = 1 MHz




FIGURE 31-31: PIC16F1937 XT OSCILLATOR, Fosc = 1 MHz




FIGURE 31-32: PIC16LF1937 XT OSCILLATOR, Fosc = 4 MHz




FIGURE 31-33: PIC16F1937 XT OSCILLATOR, Fosc = 4 MHz




FIGURE 31-34: PIC16LF1937 EC OSCILLATOR, HIGH-POWER MODE, Fosc = 32 MHz




FIGURE 31-35: PIC16F1937 EC OSCILLATOR, HIGH-POWER MODE, Fosc = 32 MHz




FIGURE 31-36: PIC16LF1937 EC OSCILLATOR, MEDIUM-POWER MODE, Fosc = 4 MHz




FIGURE 31-37: PIC16F1937 EC OSCILLATOR, MEDIUM-POWER MODE, Fosc = 4 MHz




FIGURE 31-38: PIC16LF1937 EC OSCILLATOR, LOW-POWER MODE, Fosc = 500 kHz




FIGURE 31-39: PIC16F1937 EC OSCILLATOR, LOW-POWER MODE, Fosc = 500 kHz




FIGURE 31-40: PIC16F1937 EXTRC MODE, Fosc = 4 MHz




FIGURE 31-41: PIC16LF1937 LCD, LOW POWER




FIGURE 31-42: PIC16LF1937 LCD, MEDIUM POWER




FIGURE 31-43: PIC16LF1937 LCD, HIGH POWER




FIGURE 31-44: PIC16LF1937 A/D CURRENT




FIGURE 31-45: PIC16F1937 A/D CURRENT




FIGURE 31-46: PIC16LF1937 HF INTOSC




FIGURE 31-47: PIC16F1937 HF INTOSC




FIGURE 31-48: PIC16LF1937 COMPARATOR 1, HIGH POWER




FIGURE 31-49: PIC16F1937 COMPARATOR 1, HIGH POWER




FIGURE 31-50: PIC16LF1937 COMPARATOR 1, LOW POWER






FIGURE 31-51: PIC16F1937 COMPARATOR 1, LOW POWER








FIGURE 31-53: PIC16F1937 CAP SENSE, HIGH POWER




FIGURE 31-54: PIC16LF1937 CAP SENSE, MEDIUM POWER




FIGURE 31-55: PIC16F1937 CAP SENSE, MEDIUM POWER




FIGURE 31-56: PIC16LF1937 COMPARATOR 2, HIGH POWER




FIGURE 31-57: PIC16F1937 COMPARATOR 2, HIGH POWER




FIGURE 31-58: PIC16LF1937 COMPARATOR 2, LOW POWER




FIGURE 31-59: PIC16F1937 COMPARATOR 2, LOW POWER




FIGURE 31-60: PIC16LF1937 CAP SENSE, LOW POWER




FIGURE 31-61: PIC16F1937 CAP SENSE, LOW POWER




FIGURE 31-62: PIC16LF1937 TIMER 1 OSCILLATOR




FIGURE 31-63: PIC16F1937 TIMER 1 OSCILLATOR




FIGURE 31-64: PIC16LF1937 BOR CURRENT




FIGURE 31-65: PIC16F1937 BOR CURRENT




FIGURE 31-66: PIC16LF1937 FVR\_ADC





FIGURE 31-67: PIC16F1937 FVR\_ADC



### FIGURE 31-68: PIC16LF1937 WDT




FIGURE 31-69: PIC16F1937 WDT




FIGURE 31-70: PIC16LF1937 FVR\_DAC




FIGURE 31-71: PIC16F1937 FVR\_DAC






FIGURE 31-72: PIC16LF1937 BASE IPD



### FIGURE 31-73: PIC16F1937 BASE IPD



### 32.0 DEVELOPMENT SUPPORT

The PIC® microcontrollers and dsPIC® digital signal controllers are supported with a full range of software and hardware development tools:

- · Integrated Development Environment
  - MPLAB® IDE Software
- · Compilers/Assemblers/Linkers
  - MPLAB C Compiler for Various Device Families
  - HI-TECH C for Various Device Families
  - MPASM™ Assembler
  - MPLINK<sup>™</sup> Object Linker/ MPLIB<sup>™</sup> Object Librarian
  - MPLAB Assembler/Linker/Librarian for Various Device Families
- Simulators
  - MPLAB SIM Software Simulator
- Emulators
  - MPLAB REAL ICE™ In-Circuit Emulator
- · In-Circuit Debuggers
  - MPLAB ICD 3
  - PICkit™ 3 Debug Express
- · Device Programmers
  - PICkit™ 2 Programmer
  - MPLAB PM3 Device Programmer
- Low-Cost Demonstration/Development Boards, Evaluation Kits, and Starter Kits

# 32.1 MPLAB Integrated Development Environment Software

The MPLAB IDE software brings an ease of software development previously unseen in the 8/16/32-bit microcontroller market. The MPLAB IDE is a Windows® operating system-based application that contains:

- · A single graphical interface to all debugging tools
  - Simulator
  - Programmer (sold separately)
  - In-Circuit Emulator (sold separately)
  - In-Circuit Debugger (sold separately)
- · A full-featured editor with color-coded context
- · A multiple project manager
- Customizable data windows with direct edit of contents
- · High-level source code debugging
- · Mouse over variable inspection
- Drag and drop variables from source to watch windows
- · Extensive on-line help
- Integration of select third party tools, such as IAR C Compilers

The MPLAB IDE allows you to:

- Edit your source files (either C or assembly)
- One-touch compile or assemble, and download to emulator and simulator tools (automatically updates all project information)
- · Debug using:
  - Source files (C or assembly)
  - Mixed C and assembly
  - Machine code

MPLAB IDE supports multiple debugging tools in a single development paradigm, from the cost-effective simulators, through low-cost in-circuit debuggers, to full-featured emulators. This eliminates the learning curve when upgrading to tools with increased flexibility and power.

# 32.2 MPLAB C Compilers for Various Device Families

The MPLAB C Compiler code development systems are complete ANSI C compilers for Microchip's PIC18, PIC24 and PIC32 families of microcontrollers and the dsPIC30 and dsPIC33 families of digital signal controllers. These compilers provide powerful integration capabilities, superior code optimization and ease of use.

For easy source level debugging, the compilers provide symbol information that is optimized to the MPLAB IDE debugger.

# 32.3 HI-TECH C for Various Device Families

The HI-TECH C Compiler code development systems are complete ANSI C compilers for Microchip's PIC family of microcontrollers and the dsPIC family of digital signal controllers. These compilers provide powerful integration capabilities, omniscient code generation and ease of use.

For easy source level debugging, the compilers provide symbol information that is optimized to the MPLAB IDE debugger.

The compilers include a macro assembler, linker, preprocessor, and one-step driver, and can run on multiple platforms.

#### 32.4 MPASM Assembler

The MPASM Assembler is a full-featured, universal macro assembler for PIC10/12/16/18 MCUs.

The MPASM Assembler generates relocatable object files for the MPLINK Object Linker, Intel® standard HEX files, MAP files to detail memory usage and symbol reference, absolute LST files that contain source lines and generated machine code and COFF files for debugging.

The MPASM Assembler features include:

- · Integration into MPLAB IDE projects
- User-defined macros to streamline assembly code
- Conditional assembly for multi-purpose source files
- Directives that allow complete control over the assembly process

### 32.5 MPLINK Object Linker/ MPLIB Object Librarian

The MPLINK Object Linker combines relocatable objects created by the MPASM Assembler and the MPLAB C18 C Compiler. It can link relocatable objects from precompiled libraries, using directives from a linker script.

The MPLIB Object Librarian manages the creation and modification of library files of precompiled code. When a routine from a library is called from a source file, only the modules that contain that routine will be linked in with the application. This allows large libraries to be used efficiently in many different applications.

The object linker/library features include:

- Efficient linking of single libraries instead of many smaller files
- Enhanced code maintainability by grouping related modules together
- Flexible creation of libraries with easy module listing, replacement, deletion and extraction

# 32.6 MPLAB Assembler, Linker and Librarian for Various Device Families

MPLAB Assembler produces relocatable machine code from symbolic assembly language for PIC24, PIC32 and dsPIC devices. MPLAB C Compiler uses the assembler to produce its object file. The assembler generates relocatable object files that can then be archived or linked with other relocatable object files and archives to create an executable file. Notable features of the assembler include:

- Support for the entire device instruction set
- · Support for fixed-point and floating-point data
- · Command line interface
- · Rich directive set
- · Flexible macro language
- MPLAB IDE compatibility

#### 32.7 MPLAB SIM Software Simulator

The MPLAB SIM Software Simulator allows code development in a PC-hosted environment by simulating the PIC MCUs and dsPIC® DSCs on an instruction level. On any given instruction, the data areas can be examined or modified and stimuli can be applied from a comprehensive stimulus controller. Registers can be logged to files for further run-time analysis. The trace buffer and logic analyzer display extend the power of the simulator to record and track program execution, actions on I/O, most peripherals and internal registers.

The MPLAB SIM Software Simulator fully supports symbolic debugging using the MPLAB C Compilers, and the MPASM and MPLAB Assemblers. The software simulator offers the flexibility to develop and debug code outside of the hardware laboratory environment, making it an excellent, economical software development tool.

# 32.8 MPLAB REAL ICE In-Circuit Emulator System

MPLAB REAL ICE In-Circuit Emulator System is Microchip's next generation high-speed emulator for Microchip Flash DSC and MCU devices. It debugs and programs PIC<sup>®</sup> Flash MCUs and dsPIC<sup>®</sup> Flash DSCs with the easy-to-use, powerful graphical user interface of the MPLAB Integrated Development Environment (IDE), included with each kit.

The emulator is connected to the design engineer's PC using a high-speed USB 2.0 interface and is connected to the target with either a connector compatible with incircuit debugger systems (RJ11) or with the new high-speed, noise tolerant, Low-Voltage Differential Signal (LVDS) interconnection (CAT5).

The emulator is field upgradable through future firmware downloads in MPLAB IDE. In upcoming releases of MPLAB IDE, new devices will be supported, and new features will be added. MPLAB REAL ICE offers significant advantages over competitive emulators including low-cost, full-speed emulation, run-time variable watches, trace analysis, complex breakpoints, a ruggedized probe interface and long (up to three meters) interconnection cables.

# 32.9 MPLAB ICD 3 In-Circuit Debugger System

MPLAB ICD 3 In-Circuit Debugger System is Microchip's most cost effective high-speed hardware debugger/programmer for Microchip Flash Digital Signal Controller (DSC) and microcontroller (MCU) devices. It debugs and programs PIC<sup>®</sup> Flash microcontrollers and dsPIC<sup>®</sup> DSCs with the powerful, yet easy-to-use graphical user interface of MPLAB Integrated Development Environment (IDE).

The MPLAB ICD 3 In-Circuit Debugger probe is connected to the design engineer's PC using a high-speed USB 2.0 interface and is connected to the target with a connector compatible with the MPLAB ICD 2 or MPLAB REAL ICE systems (RJ-11). MPLAB ICD 3 supports all MPLAB ICD 2 headers.

# 32.10 PICkit 3 In-Circuit Debugger/ Programmer and PICkit 3 Debug Express

The MPLAB PICkit 3 allows debugging and programming of PIC<sup>®</sup> and dsPIC<sup>®</sup> Flash microcontrollers at a most affordable price point using the powerful graphical user interface of the MPLAB Integrated Development Environment (IDE). The MPLAB PICkit 3 is connected to the design engineer's PC using a full speed USB interface and can be connected to the target via an Microchip debug (RJ-11) connector (compatible with MPLAB ICD 3 and MPLAB REAL ICE). The connector uses two device I/O pins and the reset line to implement in-circuit debugging and In-Circuit Serial Programming ™.

The PICkit 3 Debug Express include the PICkit 3, demo board and microcontroller, hookup cables and CDROM with user's guide, lessons, tutorial, compiler and MPLAB IDE software.

# 32.11 PICkit 2 Development Programmer/Debugger and PICkit 2 Debug Express

The PICkit™ 2 Development Programmer/Debugger is a low-cost development tool with an easy to use interface for programming and debugging Microchip's Flash families of microcontrollers. The full featured Windows® programming interface supports baseline (PIC10F, PIC12F5xx, PIC16F5xx), midrange (PIC12F6xx, PIC16F), PIC18F, PIC24, dsPIC30, dsPIC33, and PIC32 families of 8-bit, 16-bit, and 32-bit microcontrollers, and many Microchip Serial EEPROM products. With Microchip's powerful MPLAB Integrated Development Environment (IDE) the PICkit™ 2 enables in-circuit debugging on most PIC® microcontrollers. In-Circuit-Debugging runs, halts and single steps the program while the PIC microcontroller is embedded in the application. When halted at a breakpoint, the file registers can be examined and modified.

The PICkit 2 Debug Express include the PICkit 2, demo board and microcontroller, hookup cables and CDROM with user's guide, lessons, tutorial, compiler and MPLAB IDE software.

### 32.12 MPLAB PM3 Device Programmer

The MPLAB PM3 Device Programmer is a universal, CE compliant device programmer with programmable voltage verification at VDDMIN and VDDMAX for maximum reliability. It features a large LCD display (128 x 64) for menus and error messages and a modular, detachable socket assembly to support various package types. The ICSP™ cable assembly is included as a standard item. In Stand-Alone mode, the MPLAB PM3 Device Programmer can read, verify and program PIC devices without a PC connection. It can also set code protection in this mode. The MPLAB PM3 connects to the host PC via an RS-232 or USB cable. The MPLAB PM3 has high-speed communications and optimized algorithms for quick programming of large memory devices and incorporates an MMC card for file storage and data applications.

# 32.13 Demonstration/Development Boards, Evaluation Kits, and Starter Kits

A wide variety of demonstration, development and evaluation boards for various PIC MCUs and dsPIC DSCs allows quick application development on fully functional systems. Most boards include prototyping areas for adding custom circuitry and provide application firmware and source code for examination and modification.

The boards support a variety of features, including LEDs, temperature sensors, switches, speakers, RS-232 interfaces, LCD displays, potentiometers and additional EEPROM memory.

The demonstration and development boards can be used in teaching environments, for prototyping custom circuits and for learning about various microcontroller applications.


In addition to the PICDEM<sup>TM</sup> and dsPICDEM<sup>TM</sup> demonstration/development board series of circuits, Microchip has a line of evaluation kits and demonstration software for analog filter design, Keeloq® security ICs, CAN, IrDA®, PowerSmart battery management, Seevall® evaluation system, Sigma-Delta ADC, flow rate sensing, plus many more.

Also available are starter kits that contain everything needed to experience the specified device. This usually includes a single application and debug capability, all on one board.

Check the Microchip web page (www.microchip.com) for the complete list of demonstration, development and evaluation kits.

### 33.0 PACKAGING INFORMATION

## 33.1 Package Marking Information




Legend: XX...X Customer-specific information
Y Year code (last digit of calendar year)
YY Year code (last 2 digits of calendar year)
WW Week code (week of January 1 is week '01')
NNN Alphanumeric traceability code
Pb-free JEDEC designator for Matte Tin (Sn)
This package is Pb-free. The Pb-free JEDEC designator (a)
can be found on the outer packaging for this package.

**Note**: In the event the full Microchip part number cannot be marked on one line, it will be carried over to the next line, thus limiting the number of available characters for customer-specific information.


\* Standard PICmicro<sup>®</sup> device marking consists of Microchip part number, year code, week code and traceability code. For PICmicro device marking beyond this, certain price adders apply. Please check with your Microchip Sales Office. For QTP devices, any special marking adders are included in QTP price.

### **Package Marking Information (Continued)**


28-Lead SSOP (5.30 mm)




28-Lead UQFN (4x4x0.5 mm)




40-Lead UQFN (5x5x0.5 mm)




Example



Example




Example




### **Package Marking Information (Continued)**


44-Lead TQFP (10x10x1 mm)




44-Lead QFN (8x8x0.9 mm)



Example



Example




### 33.2 Package Details

The following sections give the technical details of the packages.

### 28-Lead Skinny Plastic Dual In-Line (SP) - 300 mil Body [SPDIP]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



|                            | Units    |       | INCHES   |       |
|----------------------------|----------|-------|----------|-------|
| Dimensio                   | n Limits | MIN   | NOM      | MAX   |
| Number of Pins             | N        |       | 28       |       |
| Pitch                      | е        |       | .100 BSC |       |
| Top to Seating Plane       | Α        | _     | _        | .200  |
| Molded Package Thickness   | A2       | .120  | .135     | .150  |
| Base to Seating Plane      | A1       | .015  | _        | _     |
| Shoulder to Shoulder Width | Е        | .290  | .310     | .335  |
| Molded Package Width       | E1       | .240  | .285     | .295  |
| Overall Length             | D        | 1.345 | 1.365    | 1.400 |
| Tip to Seating Plane       | L        | .110  | .130     | .150  |
| Lead Thickness             | С        | .008  | .010     | .015  |
| Upper Lead Width           | b1       | .040  | .050     | .070  |
| Lower Lead Width           | b        | .014  | .018     | .022  |
| Overall Row Spacing §      | eB       | _     | _        | .430  |

#### Notes:


- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. § Significant Characteristic.
- 3. Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed .010" per side.
- 4. Dimensioning and tolerancing per ASME Y14.5M.

BSC: Basic Dimension. Theoretically exact value shown without tolerances.

Microchip Technology Drawing C04-070B

## 40-Lead Plastic Dual In-Line (P) - 600 mil Body [PDIP]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



|                            | Units            |       | INCHES   |       |
|----------------------------|------------------|-------|----------|-------|
|                            | Dimension Limits | MIN   | NOM      | MAX   |
| Number of Pins             | N                |       | 40       | •     |
| Pitch                      | е                |       | .100 BSC |       |
| Top to Seating Plane       | A                | _     | -        | .250  |
| Molded Package Thickness   | A2               | .125  | -        | .195  |
| Base to Seating Plane      | A1               | .015  | _        | _     |
| Shoulder to Shoulder Width | E                | .590  | -        | .625  |
| Molded Package Width       | E1               | .485  | -        | .580  |
| Overall Length             | D                | 1.980 | -        | 2.095 |
| Tip to Seating Plane       | L                | .115  | -        | .200  |
| Lead Thickness             | С                | .008  | -        | .015  |
| Upper Lead Width           | b1               | .030  | _        | .070  |
| Lower Lead Width           | b                | .014  | -        | .023  |
| Overall Row Spacing §      | eB               | _     | _        | .700  |

#### Notes


- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. § Significant Characteristic.
- 3. Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed .010" per side.
- 4. Dimensioning and tolerancing per ASME Y14.5M.

BSC: Basic Dimension. Theoretically exact value shown without tolerances.

Microchip Technology Drawing C04-016B

# 28-Lead Plastic Small Outline (SO) - Wide, 7.50 mm Body [SOIC]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



|                          | Units       |           | MILLIMETERS |      |  |
|--------------------------|-------------|-----------|-------------|------|--|
| Dimen                    | sion Limits | MIN       | NOM         | MAX  |  |
| Number of Pins           | N           |           | 28          |      |  |
| Pitch                    | е           |           | 1.27 BSC    |      |  |
| Overall Height           | Α           | -         | _           | 2.65 |  |
| Molded Package Thickness | A2          | 2.05      | _           | _    |  |
| Standoff §               | A1          | 0.10      | _           | 0.30 |  |
| Overall Width            | E           | 10.30 BSC |             |      |  |
| Molded Package Width     | E1          | 7.50 BSC  |             |      |  |
| Overall Length           | D           |           | 17.90 BSC   |      |  |
| Chamfer (optional)       | h           | 0.25      | _           | 0.75 |  |
| Foot Length              | L           | 0.40      | _           | 1.27 |  |
| Footprint                | L1          |           | 1.40 REF    |      |  |
| Foot Angle Top           | ф           | 0°        | _           | 8°   |  |
| Lead Thickness           | С           | 0.18      | _           | 0.33 |  |
| Lead Width               | b           | 0.31      | _           | 0.51 |  |
| Mold Draft Angle Top     | α           | 5°        | _           | 15°  |  |
| Mold Draft Angle Bottom  | β           | 5°        | _           | 15°  |  |

#### Notes:

- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. § Significant Characteristic.
- 3. Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed 0.15 mm per side.
- 4. Dimensioning and tolerancing per ASME Y14.5M.


BSC: Basic Dimension. Theoretically exact value shown without tolerances.

REF: Reference Dimension, usually without tolerance, for information purposes only.

Microchip Technology Drawing C04-052B

## 28-Lead Plastic Shrink Small Outline (SS) - 5.30 mm Body [SSOP]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



|                          | Units    |      | MILLIMETERS |       |  |
|--------------------------|----------|------|-------------|-------|--|
| Dimension                | n Limits | MIN  | NOM         | MAX   |  |
| Number of Pins           | N        |      | 28          |       |  |
| Pitch                    | е        |      | 0.65 BSC    |       |  |
| Overall Height           | Α        | -    | -           | 2.00  |  |
| Molded Package Thickness | A2       | 1.65 | 1.75        | 1.85  |  |
| Standoff                 | A1       | 0.05 | _           | _     |  |
| Overall Width            | Е        | 7.40 | 7.80        | 8.20  |  |
| Molded Package Width     | E1       | 5.00 | 5.30        | 5.60  |  |
| Overall Length           | D        | 9.90 | 10.20       | 10.50 |  |
| Foot Length              | L        | 0.55 | 0.75        | 0.95  |  |
| Footprint                | L1       |      | 1.25 REF    |       |  |
| Lead Thickness           | С        | 0.09 | _           | 0.25  |  |
| Foot Angle               | ф        | 0°   | 4°          | 8°    |  |
| Lead Width               | b        | 0.22 | _           | 0.38  |  |

#### Notes:

- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed 0.20 mm per side.
- 3. Dimensioning and tolerancing per ASME Y14.5M.


BSC: Basic Dimension. Theoretically exact value shown without tolerances.

REF: Reference Dimension, usually without tolerance, for information purposes only.

Microchip Technology Drawing C04-073B

## 28-Lead Plastic Ultra Thin Quad Flat, No Lead Package (MV) – 4x4x0.5 mm Body [UQFN]


**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



Microchip Technology Drawing C04-152A Sheet 1 of 2

### 28-Lead Plastic Ultra Thin Quad Flat, No Lead Package (MV) - 4x4x0.5 mm Body [UQFN]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



|                        | Units  |      | MILLIMETERS |      |  |
|------------------------|--------|------|-------------|------|--|
| Dimension              | Limits | MIN  | NOM         | MAX  |  |
| Number of Pins         | N      |      | 28          |      |  |
| Pitch                  | е      |      | 0.40 BSC    |      |  |
| Overall Height         | Α      | 0.45 | 0.50        | 0.55 |  |
| Standoff               | A1     | 0.00 | 0.02        | 0.05 |  |
| Contact Thickness      | A3     |      | 0.127 REF   |      |  |
| Overall Width          | E      |      | 4.00 BSC    |      |  |
| Exposed Pad Width      | E2     | 2.55 | 2.65        | 2.75 |  |
| Overall Length         | D      |      | 4.00 BSC    | •    |  |
| Exposed Pad Length     | D2     | 2.55 | 2.65        | 2.75 |  |
| Contact Width          | b      | 0.15 | 0.20        | 0.25 |  |
| Contact Length         | L      | 0.30 | 0.40        | 0.50 |  |
| Contact-to-Exposed Pad | К      | 0.20 | -           | -    |  |

#### Notes:

- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. Package is saw singulated.
- 3. Dimensioning and tolerancing per ASME Y14.5M.


BSC: Basic Dimension. Theoretically exact value shown without tolerances.

REF: Reference Dimension, usually without tolerance, for information purposes only.

Microchip Technology Drawing C04-152A Sheet 2 of 2

### 40-Lead Ultra Thin Plastic Quad Flat, No Lead Package (MV) – 5x5x0.5 mm Body [UQFN]


**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



Microchip Technology Drawing C04-156A Sheet 1 of 2

### 40-Lead Ultra Thin Plastic Quad Flat, No Lead Package (MV) – 5x5x0.5 mm Body [UQFN]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



|                        | Units  |      | MILLIMETERS |      |  |
|------------------------|--------|------|-------------|------|--|
| Dimension              | Limits | MIN  | NOM         | MAX  |  |
| Number of Pins         | N      |      | 40          |      |  |
| Pitch                  | е      |      | 0.40 BSC    |      |  |
| Overall Height         | Α      | 0.45 | 0.50        | 0.55 |  |
| Standoff               | A1     | 0.00 | 0.02        | 0.05 |  |
| Contact Thickness      | A3     |      | 0.127 REF   |      |  |
| Overall Width          | E      |      | 5.00 BSC    |      |  |
| Exposed Pad Width      | E2     | 3.60 | 3.70        | 3.80 |  |
| Overall Length         | D      |      | 5.00 BSC    |      |  |
| Exposed Pad Length     | D2     | 3.60 | 3.70        | 3.80 |  |
| Contact Width          | р      | 0.15 | 0.20        | 0.25 |  |
| Contact Length         | L      | 0.30 | 0.40        | 0.50 |  |
| Contact-to-Exposed Pad | K      | 0.20 | -           | -    |  |

#### Notes:

- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. Package is saw singulated.
- 3. Dimensioning and tolerancing per ASME Y14.5M.


BSC: Basic Dimension. Theoretically exact value shown without tolerances.

REF: Reference Dimension, usually without tolerance, for information purposes only.

Microchip Technology Drawing C04-156A Sheet 2 of 2

### 40-Lead Plastic Ultra Thin Quad Flat, No Lead Package (MV) - 5x5 mm Body [UQFN]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



RECOMMENDED LAND PATTERN

| Units                      |        | MILLIMETERS |          |      |
|----------------------------|--------|-------------|----------|------|
| Dimension                  | Limits | MIN         | NOM      | MAX  |
| Contact Pitch              | Е      |             | 0.40 BSC |      |
| Optional Center Pad Width  | W2     |             |          | 3.80 |
| Optional Center Pad Length | T2     |             |          | 3.80 |
| Contact Pad Spacing        | C1     |             | 5.00     |      |
| Contact Pad Spacing        | C2     |             | 5.00     |      |
| Contact Pad Width (X40)    | X1     |             |          | 0.20 |
| Contact Pad Length (X40)   | Y1     |             |          | 0.75 |
| Distance Between Pads      | G      | 0.20        |          |      |

### Notes:


1. Dimensioning and tolerancing per ASME Y14.5M

BSC: Basic Dimension. Theoretically exact value shown without tolerances.

Microchip Technology Drawing No. C04-2156A

# 44-Lead Plastic Thin Quad Flatpack (PT) – 10x10x1 mm Body, 2.00 mm [TQFP]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



|                          | Units            |          | MILLIMETERS |      |  |
|--------------------------|------------------|----------|-------------|------|--|
| [                        | Dimension Limits | MIN      | NOM         | MAX  |  |
| Number of Leads          | N                |          | 44          |      |  |
| Lead Pitch               | е                |          | 0.80 BSC    |      |  |
| Overall Height           | А                | -        | _           | 1.20 |  |
| Molded Package Thickness | A2               | 0.95     | 1.00        | 1.05 |  |
| Standoff                 | A1               | 0.05     | _           | 0.15 |  |
| Foot Length              | L                | 0.45     | 0.60        | 0.75 |  |
| Footprint                | L1               | 1.00 REF |             |      |  |
| Foot Angle               | ф                | 0°       | 3.5°        | 7°   |  |
| Overall Width            | E                |          | 12.00 BSC   |      |  |
| Overall Length           | D                |          | 12.00 BSC   |      |  |
| Molded Package Width     | E1               |          | 10.00 BSC   |      |  |
| Molded Package Length    | D1               |          | 10.00 BSC   |      |  |
| Lead Thickness           | С                | 0.09     |             | 0.20 |  |
| Lead Width               | b                | 0.30     | 0.37        | 0.45 |  |
| Mold Draft Angle Top     | α                | 11°      | 12°         | 13°  |  |
| Mold Draft Angle Bottom  | β                | 11°      | 12°         | 13°  |  |

#### Notes:

- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. Chamfers at corners are optional; size may vary.
- 3. Dimensions D1 and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed 0.25 mm per side.
- 4. Dimensioning and tolerancing per ASME Y14.5M.


BSC: Basic Dimension. Theoretically exact value shown without tolerances.

REF: Reference Dimension, usually without tolerance, for information purposes only.

Microchip Technology Drawing C04-076B

## 44-Lead Plastic Thin Quad Flatpack (PT) - 10x10x1 mm Body, 2.00 mm [TQFP]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



RECOMMENDED LAND PATTERN

| Units                    |        | MILLIMETERS |          |      |
|--------------------------|--------|-------------|----------|------|
| Dimension                | Limits | MIN         | NOM      | MAX  |
| Contact Pitch            | E      |             | 0.80 BSC |      |
| Contact Pad Spacing      | C1     |             | 11.40    |      |
| Contact Pad Spacing      | C2     |             | 11.40    |      |
| Contact Pad Width (X44)  | X1     |             |          | 0.55 |
| Contact Pad Length (X44) | Y1     |             |          | 1.50 |
| Distance Between Pads    | G      | 0.25        |          |      |

#### Notes:


1. Dimensioning and tolerancing per ASME Y14.5M


BSC: Basic Dimension. Theoretically exact value shown without tolerances.


Microchip Technology Drawing No. C04-2076A

# 44-Lead Plastic Quad Flat, No Lead Package (ML) - 8x8 mm Body [QFN]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging







|                        | Units     |      | MILLIMETERS |      |  |
|------------------------|-----------|------|-------------|------|--|
| Dimension              | on Limits | MIN  | NOM         | MAX  |  |
| Number of Pins         | N         |      | 44          |      |  |
| Pitch                  | е         |      | 0.65 BSC    |      |  |
| Overall Height         | Α         | 0.80 | 0.90        | 1.00 |  |
| Standoff               | A1        | 0.00 | 0.02        | 0.05 |  |
| Contact Thickness      | A3        |      | 0.20 REF    |      |  |
| Overall Width          | Е         |      | 8.00 BSC    |      |  |
| Exposed Pad Width      | E2        | 6.30 | 6.45        | 6.80 |  |
| Overall Length         | D         |      | 8.00 BSC    |      |  |
| Exposed Pad Length     | D2        | 6.30 | 6.45        | 6.80 |  |
| Contact Width          | b         | 0.25 | 0.30        | 0.38 |  |
| Contact Length         | L         | 0.30 | 0.40        | 0.50 |  |
| Contact-to-Exposed Pad | K         | 0.20 | _           | -    |  |

#### Notes:

- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. Package is saw singulated.
- 3. Dimensioning and tolerancing per ASME Y14.5M.


BSC: Basic Dimension. Theoretically exact value shown without tolerances.

REF: Reference Dimension, usually without tolerance, for information purposes only.

Microchip Technology Drawing C04-103B

# 44-Lead Plastic Quad Flat, No Lead Package (ML) – 8x8 mm Body [QFN]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



RECOMMENDED LAND PATTERN

| Units                      |        | MILLIMETERS |          |      |
|----------------------------|--------|-------------|----------|------|
| Dimension                  | Limits | MIN         | NOM      | MAX  |
| Contact Pitch              | E      |             | 0.65 BSC |      |
| Optional Center Pad Width  | W2     |             |          | 6.80 |
| Optional Center Pad Length | T2     |             |          | 6.80 |
| Contact Pad Spacing        | C1     |             | 8.00     |      |
| Contact Pad Spacing        | C2     |             | 8.00     |      |
| Contact Pad Width (X44)    | X1     |             |          | 0.35 |
| Contact Pad Length (X44)   | Y1     |             |          | 0.80 |
| Distance Between Pads      | G      | 0.25        |          |      |

#### Notes:

1. Dimensioning and tolerancing per ASME Y14.5M

BSC: Basic Dimension. Theoretically exact value shown without tolerances.

Microchip Technology Drawing No. C04-2103A

# APPENDIX A: DATA SHEET REVISION HISTORY

# **Revision A (12/2008)**

Original release

### Revision B (04/2009)

Revised data sheet title; Revised Features section.

### **Revision C (10/2009)**

Added PIC16L/LF1933/34. General updates.

# **Revision D (12/2009)**

General updates.

### **Revision E (5/2011)**

Separated 193X data sheet into three separate data sheets. Added Characterization Data.

# APPENDIX B: MIGRATING FROM OTHER PIC® DEVICES

This discusses some of the issues in migrating from other PIC® devices to the PIC16(L)F1934/6/7 family of devices.

# B.1 PIC16F917 to PIC16F1937 TABLE B-1: FEATURE COMPARISON

| Feature                               | PIC16F917         | PIC16F1937          |
|---------------------------------------|-------------------|---------------------|
| Max. Operating Speed                  | 20 MHz            | 32 MHz              |
| Max. Program<br>Memory (Words)        | 8K                | 8K                  |
| Max. SRAM (Bytes)                     | 368               | 512                 |
| A/D Resolution                        | 10-bit            | 10-bit              |
| Timers (8/16-bit)                     | 2/1               | 4/1                 |
| Oscillator Modes                      | 4                 | 8                   |
| Brown-out Reset                       | Υ                 | Υ                   |
| Internal Pull-ups                     | RB<7:0>           | RB<7:0>             |
| Interrupt-on-change                   | RB<7:4>           | RB<7:0>             |
| Comparator                            | 2                 | 2                   |
| AUSART/EUSART                         | 1/0               | 0/1                 |
| Extended WDT                          | Y                 | Y                   |
| Software Control<br>Option of WDT/BOR | N                 | Y                   |
| INTOSC Frequencies                    | 30 kHz -<br>8 MHz | 500 kHz -<br>32 MHz |
| Clock Switching                       | Υ                 | Y                   |
| Capacitive Sensing                    | N                 | Y                   |
| CCP/ECCP                              | 2/0               | 2/3                 |
| Enhanced PIC16 CPU                    | N                 | Y                   |
| MSSP/SSP                              | 0/1               | 1/0                 |
| LCD                                   | Y                 | Y                   |

**NOTES:** 

### **INDEX**

| A  | Digital-to-Analog Converter (DAC) 170             |
|--|---|
| A/D  | EUSART Receive294                                 |
| Specifications403                                  | EUSART Transmit                                   |
| Absolute Maximum Ratings (PIC16F/LF1934/36/37) 381 | External RC Mode7                                 |
| AC Characteristics                                 | Fail-Safe Clock Monitor (FSCM) 8                  |
| Industrial and Extended                            | Generic I/O Port13                                |
| Load Conditions                                    | Interrupt Logic9                                  |
| ACKSTAT276   | LCD Bias Voltage Generation                       |
| ACKSTAT Status Flag                                | LCD Clock Generation                              |
| ADC  | On-Chip Reset Circuit8                            |
| Acquisition Requirements                           | PIC16F193X/LF193X                                 |
| Associated registers                               | PWM (Enhanced)22                                  |
| Block Diagram                                      | Resonator Operation7                              |
| Calculating Acquisition Time                       | Timer0  |
| Channel Selection                                  | Timer1 19   |
| Configuration                                      | Timer1 Gate 202, 203, 204                         |
| Configuration                                      | Timer2/4/6  |
| Conversion Clock                                   | Voltage Reference                                 |
| Conversion Procedure                               | Voltage Reference Output Buffer Example 170       |
|  | BORCON Register 89                                |
| Internal Sampling Switch (Rss) Impedance           | BRA   |
| Interrupts   | Break Character (12-bit) Transmit and Receive 313 |
| Operation 163                                      | Brown-out Reset (BOR)89                           |
| Operation During Sleep                             | Specifications                                    |
| Port Configuration                                 | Timing and Characteristics                        |
| Reference Voltage (VREF)                           |   |
| Source Impedance 169                               | C   |
| Special Event Trigger                              | C Compilers                                       |
| Starting an A/D Conversion                         | MPLAB C1844                                       |
| ADCON0 Register                                    | CALL  |
| ADCON1 Register                                    | CALLW   |
| ADDFSR   | Capacitive Sensing32                              |
| ADDWFC   | Associated registers w/ Capacitive Sensing 32     |
| ADRESH Register40                                  | Specifications41                                  |
| ADRESH Register (ADFM = 0)167                      | Capture Module. See Enhanced Capture/Compare/     |
| ADRESH Register (ADFM = 1)                         | PWM(ECCP)   |
| ADRESL Register (ADFM = 0)167                      | Capture/Compare/PWM21:                            |
| ADRESL Register (ADFM = 1)                         | Capture/Compare/PWM (CCP)                         |
| Alternate Pin Function                             | Associated Registers w/ Capture                   |
| Analog-to-Digital Converter. See ADC               | Associated Registers w/ Compare                   |
| ANSELA Register                                    | Associated Registers w/ PWM                       |
| ANSELB Register141                                 | Capture Mode21                                    |
| ANSELD Register 148                                | CCPx Pin Configuration21                          |
| ANSELE Register 151                                | Compare Mode21                                    |
| APFCON Register133                                 | CCPx Pin Configuration                            |
| Assembler  | Software Interrupt Mode                           |
| MPASM Assembler442                                 | Special Event Trigger                             |
| В  | Timer1 Mode Resource                              |
|  | Prescaler   |
| BAUDCON Register304                                | PWM Mode  |
| BF276, 278   | Duty Cycle21                                      |
| BF Status Flag                                     | Effects of Reset                                  |
| Block Diagram                                      | Example PWM Frequencies and                       |
| Capacitive Sensing321                              |   |
| Block Diagrams                                     | Resolutions, 20 MHZ                               |
| (CCP) Capture Mode Operation214                    | Example PWM Frequencies and                       |
| ADC159   | Resolutions, 32 MHZ                               |
| ADC Transfer Function170                           | Example PWM Frequencies and                       |
| Analog Input Model 170, 184                        | Resolutions, 8 MHz                                |
| CCP PWM218   | Operation in Sleep Mode                           |
| Clock Source70                                     | Resolution  |
| Comparator180                                      | System Clock Frequency Changes                    |
| Compare  | PWM Operation                                     |
| Crystal Operation72, 73                            | PWM Overview                                      |
|  | PWM Period21                                      |

| PWM Setup                                       | 219     | Industrial and Extended (PIC16F/LF1934/36/37)   | 384 |
|---|---------|---|-----|
| CCP1CON Register                                | 44, 45  | Development Support                             | 441 |
| CCPR1H Register                                 | 44, 45  | Device Configuration                            | 6′  |
| CCPR1L Register                                 |         | Code Protection                                 |     |
| CCPTMRS0 Register                               |         | Configuration Word                              |     |
| CCPTMRS1 Register                               |         | User ID   |     |
| CCPxAS Register                                 |         | Device Overview19                               |     |
| CCPxCON (ECCPx) Register                        |         | Digital-to-Analog Converter (DAC)               |     |
| Clock Accuracy with Asynchronous Operation      |         | Associated Registers                            |     |
| Clock Sources                                   |         | Effects of a Reset                              |     |
| External Modes                                  | 71      | Specifications                                  |     |
| EC  |         | Specifications                                  | 400 |
|   |         | E   |     |
| HS  |         | ECCD/CCD, Soo Enhanced Conture/Compare/DW/M     |     |
| LP  |         | ECCP/CCP. See Enhanced Capture/Compare/PWM      | 447 |
| OST   |         | EEADR Registers                                 |     |
| RC  |         | EEADRH Registers                                |     |
| XT  |         | EEADRL Register                                 |     |
| Internal Modes                                  |         | EEADRL Registers                                |     |
| HFINTOSC  |         | EECON1 Register11                               |     |
| Internal Oscillator Clock Switch Timing         |         | EECON2 Register117                              |     |
| LFINTOSC  | 75      | EEDATH Register                                 |     |
| MFINTOSC  | 74      | EEDATL Register                                 | 128 |
| Clock Switching                                 | 78      | EEPROM Data Memory                              |     |
| CMOUT Register                                  | 186     | Avoiding Spurious Write                         |     |
| CMxCON0 Register                                | 185     | Write Verify                                    | 127 |
| CMxCON1 Register                                | 186     | Effects of Reset                                |     |
| Code Examples                                   |         | PWM mode  | 221 |
| A/D Conversion                                  | 164     | Electrical Specifications (PIC16F/LF1934/36/37) | 381 |
| Changing Between Capture Prescalers             | 214     | Enhanced Capture/Compare/PWM (ECCP)             |     |
| Initializing PORTA                              |         | Enhanced PWM Mode                               | 222 |
| Initializing PORTE                              |         | Auto-Restart                                    | 231 |
| Write Verify                                    |         | Auto-shutdown                                   |     |
| Writing to Flash Program Memory                 |         | Direction Change in Full-Bridge Output Mode     |     |
| Comparator                                      |         | Full-Bridge Application                         |     |
| Associated Registers                            | 187 188 | Full-Bridge Mode                                |     |
| Operation                                       |         | Half-Bridge Application                         |     |
| Comparator Module                               |         | Half-Bridge Application Examples                |     |
| Cx Output State Versus Input Conditions         |         | Half-Bridge Mode                                |     |
| Comparator Specifications                       |         | Output Relationships (Active-High and           |     |
| Comparators                                     |         | Active-Low)                                     | 223 |
| C2OUT as T1 Gate                                | 100     | Output Relationships Diagram                    |     |
| Compare Module. See Enhanced Capture/Compare    |         | Programmable Dead Band Delay                    |     |
| PWM (ECCP)                                      | C/      | Shoot-through Current                           |     |
| CONFIG1 Register                                | 62      | Start-up Considerations                         |     |
|   |         | Specifications                                  |     |
| CONFIG2 Register                                |         | Enhanced Mid-range CPU                          |     |
| Core Registers                                  |         | Enhanced Universal Synchronous Asynchronous     | 20  |
| CPSCON0 Register                                |         | · · · · · · · · · · · · · · · · · · ·           | 202 |
| CPSCON1 Register                                |         | Receiver Transmitter (EUSART)                   |     |
| Customer Change Notification Service            |         | Errata  |     |
| Customer Notification Service                   |         | EUSART  | 293 |
| Customer Support                                | 471     | Associated Registers                            | 000 |
| D   |         | Baud Rate Generator                             |     |
|   |         | Asynchronous Mode                               |     |
| DACCON0 (Digital-to-Analog Converter Control 0) | 470     | 12-bit Break Transmit and Receive               | 313 |
| Register  | 178     | Associated Registers                            | 004 |
| DACCON1 (Digital-to-Analog Converter Control 1) | 470     | Receive   |     |
| Register  |         | Transmit  |     |
| Memory  |         | Auto-Wake-up on Break                           |     |
| Associated Registers                            |         | Baud Rate Generator (BRG)                       |     |
| Code Protection                                 |         | Clock Accuracy                                  |     |
| Reading   |         | Receiver  |     |
| Writing   |         | Setting up 9-bit Mode with Address Detect       |     |
| Data Memory                                     |         | Transmitter                                     | 295 |
| DC and AC Characteristics                       | 413     | Baud Rate Generator (BRG)                       |     |
| DC Characteristics                              |         | Auto Baud Rate Detect                           |     |
| Extended and Industrial (PIC16F/LF1934/36/3     | 37) 391 | Baud Rate Error, Calculating                    | 305 |

| Baud Rates, Asynchronous Modes                     |               | CALLW                                    | 373     |
|--|---------------|--|---------|
| Formulas   |               | LSLF                                     | 375     |
| High Baud Rate Select (BRGH Bit)                   | 305           | LSRF                                     | 375     |
| Synchronous Master Mode                            | 314, 318      | MOVF                                     | 375     |
| Associated Registers                               |               | MOVIW                                    | 376     |
| Receive  | 317           | MOVLB                                    | 376     |
| Transmit   | 315           | MOVWI                                    | 377     |
| Reception  | 316           | OPTION                                   | 377     |
| Transmission                                       |               | RESET                                    | 377     |
| Synchronous Slave Mode                             |               | SUBWFB                                   | 379     |
| Associated Registers                               |               | TRIS                                     | 380     |
| Receive  | 319           | BCF                                      | 372     |
| Transmit   |               | BSF                                      | 372     |
| Reception  |               | BTFSC                                    | 372     |
| Transmission                                       |               | BTFSS                                    |         |
| Extended Instruction Set                           |               | CALL                                     |         |
| ADDFSR   | 371           | CLRF                                     |         |
| ADDI OI  |               | CLRW                                     |         |
| F  |               | CLRWDT                                   |         |
| Fail-Safe Clock Monitor                            | 81            | COMF                                     |         |
| Fail-Safe Condition Clearing                       |               |  |         |
| Fail-Safe Detection                                |               | DECF                                     |         |
| Fail-Safe Operation                                |               | DECFSZ                                   |         |
| •  |               | GOTO                                     |         |
| Reset or Wake-up from Sleep                        |               | INCF                                     |         |
| Firmware Instructions                              | 307           | INCFSZ                                   |         |
| Fixed Voltage Reference (FVR)                      | 450           | IORLW                                    |         |
| Associated Registers                               |               | IORWF                                    |         |
| Flash Program Memory                               |               | MOVLW                                    |         |
| Erasing  |               | MOVWF                                    | 376     |
| Modifying  |               | NOP                                      |         |
| Writing  |               | RETFIE                                   | 378     |
| FSR Register39, 40, 41, 42, 43, 44, 45, 46, 47, 48 |               | RETLW                                    | 378     |
| FVRCON (Fixed Voltage Reference Control) Reg       | ister 158     | RETURN                                   | 378     |
|  |               | RLF                                      | 378     |
|  |               | RRF                                      | 379     |
| <sup>2</sup> C Mode (MSSP)                         |               | SLEEP                                    | 379     |
| Acknowledge Sequence Timing                        | 280           | SUBLW                                    | 379     |
| Bus Collision                                      |               | SUBWF                                    | 379     |
| During a Repeated Start Condition                  | 284           | SWAPF                                    | 380     |
| During a Stop Condition                            | 285           | XORLW                                    |         |
| Effects of a Reset                                 | 281           | XORWF                                    |         |
| I <sup>2</sup> C Clock Rate w/BRG                  | 287           | INTCON Register                          |         |
| Master Mode  |               | Internal Oscillator Block                |         |
| Operation  | 272           | INTOSC                                   |         |
| Reception  |               | Specifications                           | 307     |
| Start Condition Timing                             |               | Internal Sampling Switch (Rss) Impedance |         |
| Transmission                                       |               | , .                                      |         |
| Multi-Master Communication, Bus Collision          |               | Internet Address                         |         |
| Arbitration  |               | Interrupt-On-Change                      |         |
| Multi-Master Mode                                  |               | Associated Registers                     |         |
| _  |               | Interrupts                               |         |
| Read/Write Bit Information (R/W Bit)               | 237           | ADC                                      |         |
| Slave Mode   | 000           | Associated registers w/ Interrupts       |         |
| Transmission                                       |               | Configuration Word w/ Clock Sources      |         |
| Sleep Operation                                    |               | Configuration Word w/ LDO                | 109     |
| Stop Condition Timing                              |               | TMR1                                     | 201     |
| NDF Register39, 40, 41, 42, 43, 44, 45, 46, 47, 48 | 8, 49, 51, 52 | INTOSC Specifications                    | 397     |
| ndirect Addressing                                 | 56            | IOCBF Register                           | 154     |
| nstruction Format                                  | 368           | IOCBN Register                           |         |
| nstruction Set                                     | 367           | IOCBP Register                           |         |
| ADDLW  | 371           | •  |         |
| ADDWF  |               | L  |         |
| ADDWFC   |               | LATA Register                            | 135 144 |
| ANDLW  |               | LATB Register                            |         |
| ANDWF  |               | LATD Register                            |         |
| BRA  |               | <u> </u>                                 |         |
| CALL   |               | LATE Register                            | 131     |
| UNLL   |               | LCD                                      |         |

| Associated Registers                             | 362       | Oscillator Parameters                          | 397     |
|--|-----------|--|---------|
| Bias Voltage Generation                          | 337, 338  | Oscillator Specifications                      | 396     |
| Clock Source Selection                           | 336       | Oscillator Start-up Timer (OST)                |         |
| Configuring the Module                           | 361       | Specifications                                 | 401     |
| Disabling the Module                             | 361       | Oscillator Switching                           |         |
| Frame Frequency                                  | 344       | Fail-Safe Clock Monitor                        | 81      |
| Interrupts                                       | 357       | Two-Speed Clock Start-up                       | 79      |
| LCDCON Register                                  | 330       | OSCSTAT Register                               |         |
| LCDPS Register                                   |           | OSCTUNE Register                               |         |
| Multiplex Types                                  |           | •  |         |
| Operation During Sleep                           |           | Р  |         |
| Pixel Control                                    |           | P1A/P1B/P1C/P1D.See Enhanced Capture/C         | ompare/ |
| Prescaler  |           | PWM (ECCP)                                     |         |
| Segment Enables                                  |           | Packaging                                      |         |
| Waveform Generation                              |           | Marking  |         |
| LCDCON Register                                  |           | PDIP Details                                   |         |
| LCDCST Register                                  |           | PCL and PCLATH                                 |         |
| LCDDATAx Registers                               |           | PCL Register39, 40, 41, 42, 43, 44, 45, 46, 47 |         |
| LCDPS Register                                   |           | PCLATH Register39, 40, 41, 42, 43, 44, 45, 46  |         |
| _  |           |  |         |
| LP Bits  |           | PCON Register                                  |         |
| LCDRL Register                                   |           | PIE1 Register                                  |         |
| LCDRL Register                                   |           | PIE2 Register                                  |         |
| LCDSEn Registers                                 |           | <u> </u>                                       |         |
| Liquid Crystal Display (LCD) Driver              |           | PIE3 Register                                  | 103     |
| Load Conditions                                  |           | Pin Diagram                                    |         |
| LSLF   |           | PIC16(L)F1934/1937, 40-pin PDIP                |         |
| LSRF   | 375       | PIC16(L)F1934/1937, 40-pin UQFN                |         |
| M  |           | PIC16(L)F1934/1937, 44-pin QFN                 |         |
|  |           | PIC16(L)F1934/1937, 44-pin TQFP                |         |
| Master Synchronous Serial Port. See MSSP         |           | PIC16(L)F1936, 28-pin QFN/UQFN                 |         |
| MCLR   |           | PIC16(L)F1936, 28-pin SPDIP/SOIC/SS            | OP 5    |
| Internal   | 90        | Pinout Descriptions                            |         |
| Memory Organization                              |           | PIC16F193X/PIC16LF193X                         |         |
| Data   |           | PIR1 Register                                  |         |
| Program  |           | PIR2 Register                                  |         |
| Microchip Internet Web Site                      |           | PIR3 Register                                  |         |
| Migrating from other PIC Microcontroller Devices |           | PORTA  |         |
| MOVIW  |           | ANSELA Register                                |         |
| MOVLB  | 376       | Associated Registers                           |         |
| MOVWI  |           | Configuration Word w/ PORTA                    |         |
| MPLAB ASM30 Assembler, Linker, Librarian         | 442       | PORTA Register                                 |         |
| MPLAB Integrated Development Environment Sof     | tware 441 | Specifications                                 |         |
| MPLAB PM3 Device Programmer                      |           | PORTA Register                                 | 135     |
| MPLAB REAL ICE In-Circuit Emulator System        | 443       | PORTB  | 138     |
| MPLINK Object Linker/MPLIB Object Librarian      | 442       | Additional Pin Functions                       |         |
| MSSP   |           | Weak Pull-up                                   | 139     |
| SPI Mode   | 244       | ANSELB Register                                |         |
| SSPBUF Register                                  | 247       | Associated Registers                           |         |
| SSPSR Register                                   |           | Interrupt-on-Change                            |         |
| _  |           | P1B/P1C/P1D.See Enhanced Capture/C             |         |
| 0  |           | PWM+ (ECCP+)                                   |         |
| OPCODE Field Descriptions                        | 367       | Pin Descriptions and Diagrams                  |         |
| OPTION   |           | PORTB Register                                 |         |
| OPTION Register                                  |           | PORTB Register                                 |         |
| OSCCON Register                                  |           | PORTC  |         |
| Oscillator                                       |           | Associated Registers                           |         |
| Associated Registers                             | 85        | P1A.See Enhanced Capture/Compare/P             |         |
| Oscillator Module                                |           | ·  |         |
| ECH  |           | (ECCP+)  |         |
|  |           | Pin Descriptions and Diagrams                  |         |
| ECL  |           | PORTC Register                                 |         |
| ECM  |           | Specifications                                 |         |
| HS   |           | PORTC Register                                 |         |
| INTOSC   |           | PORTD  | 146     |
| LP   |           | Additional Pin Functions                       |         |
| RC   |           | ANSELD Register                                |         |
| XT   | 69        | Associated Registers                           | 148     |

| PWM+ (ECCP+)   | DIAMA: (ECOD.)  | CPSCON1 (Capacitive Sensing Control Register 1   | ) 326  |
|--|---|--|--|
| PORTO Register 99,41 PORTO Register 147 PORTE 149 PORTE Elegister 149 PORTE Elegister 149 ANSELE Register 149 ASSOciated Registers 52 EEDATL (EEPROM Control 2) 130 ANSELE Register 149 PORTE Register 152 PORTE Register 99,41 NTCON (Interrupt Control) 100 PORTE Register 99,41 NTCON (Interrupt Control) 100 PORTE Register 99,41 NTCON (Interrupt Control) 100 PORTE Register 150 POWER-Down Mode (Sleep) 111 OCBR (Interrupt-on-Change Negaliwe Edge) 154 Associated Registers 112 Power-on Reset 88 LATA (Data Latch PORTA) 135 Power-up Timer (PWRT) 88 LATE (Data Latch PORTB) 136 Specifications 401 LATC (Data Latch PORTB) 149 PRESCIPION (PROTE) 144 PROGRAMMENT 145 PROGRAMMENT | PWM+ (ECCP+)146   | DACCON0  | 178  |
| PORTID Register  | Pin Descriptions and Diagrams146  | DACCON1  | 178  |
| PORTE  | PORTD Register39, 41  | EEADRL (EEPROM Address)  | 128  |
| ANSELE Register   149  | PORTD Register 147  | EECON1 (EEPROM Control 1)  | 129  |
| Associated Registers   152   EEDATL (IEEPROM Data)   128   PIN Descriptions and Diagrams.   149   FVR.CON.   158   PORTE Register   39, 41   NTCON (Interrupt Control)   100   PORTE Register   150   ICGBr (Interrupt-on-Change Registre Edge).   154   Associated Registers   112   ICGBr (Interrupt-on-Change Registre Edge).   154   Associated Registers   112   ICGBr (Interrupt-on-Change Registre Edge).   154   Power-on Reset.   88   LATA (Data Latch PORTA).   135   Power-up Timer (PWRT).   88   LATB (Data Latch PORTB).   140   Specifications.   401   LATC (Data Latch PORTB).   140   Precision Internal Oscillator Parameters.   39, 47   LATD (Data Latch PORTD).   147   Precision Internal Oscillator Parameters.   397   LATE (Data Latch PORTD).   147   Precision Internal Oscillator Parameters.   397   LATE (Data Latch PORTD).   147   Precision Internal Oscillator Parameters.   397   LATE (Data Latch PORTD).   331   Map and Stack (PIC16(I)F1934).   25   LCDCST (LCD Contrast Control).   334   Map and Stack (PIC16(I)F1936, PIC16(I)F1937). 26   LCDCST (LCD Contrast Control).   334   Map and Stack (PIC16(I)F1936, PIC16(I)F1937).   31   LCDPS (LCD Phase).   335   Map and Stack (PIC16(I)F1936, PIC16(I)F1937).   31   LCDPS (LCD Phase).   335   Programming Mode Exit.   90   LCDSE (LCD Phase).   355   Programming Mode Exit.   90   LCDSE (LCD Reference Voltage Control).   324   PVM Steering.   233   CDRI (LCD Reference Voltage Control).   325   PSTR.CON Register   240   OSCCON (Oscillator Cuntrol).   38   PSTR.CON Register.   234   PVM Steering.   233   PVM Mode. See Enhanced Capture/Compare/PVM   222   PCNO (Power Control).   39   PVM Steering.   233   PIC16 (Peripheral Interrupt Enable 1)   104   RCREG Register.   42   PIC16 (Peripheral Interrupt Register).   30   RCREG Register.   42   PIC16 (Peripheral Interrupt Register).   30   ADCOM (ADC Control 0).   166   ADCAM (ADC Control 0).   167   ADCOM (ADC Control 0).   167   ADCAM (ADC Control 0).   168   ADCOM (ADC Control 0).   167   ADCAM (ADC Control 0).   167   ADCAM (ADC Res | PORTE149  | EECON2 (EEPROM Control 2)  | 130  |
| Pin Descriptions and Diagrams.   | ANSELE Register149  | EEDATH (EEPROM Data)   | 128  |
| PORTE Register   | Associated Registers152   | EEDATL (EEPROM Data)   | 128  |
| PORTE Register   | Pin Descriptions and Diagrams149  | FVRCON   | 158  |
| Power-Down Mode (Siepe)  | PORTE Register39, 41  | INTCON (Interrupt Control)   | 100  |
| Power-Down Mode (Siepe)  | PORTE Register 150  | IOCBF (Interrupt-on-Change Flag)   | 154  |
| Power-on Reset   |   | IOCBN (Interrupt-on-Change Negative Edge)  | 154  |
| Power-on Reset   |   | IOCBP (Interrupt-on-Change Positive Edge)  | 154  |
| Power-up Timer (PWRT)  | Power-on Reset 88   |  |  |
| Specifications   |   |  |  |
| PRZ Register. 39, 47 Precision Internal Oscillator Parameters 397 Precision Internal Oscillator Parameters 397 Map and Stack (PIC16(L)F1934). 25 Map and Stack (PIC16(L)F1934). 25 LCDCON (LCD Control). 331 Map and Stack (PIC16(L)F1936, PIC16(L)F1937). 26 LCDDST (LCD Control). 335, 342 Map and Stack (PIC16(L)F1936, PIC16(L)F1937). 31 LCDRE (LCD Reference Voltage Control). 323 PIC16F1937/LF1937). 31 LCDRE (LCD Reference Voltage Control). 323 Programming, Device Instructions. 367 Programming, Device Instructions. 367 PSTRXCON Register. 240 PSTRXCON Register. 240 PWM Steering. 233 PWM GECP Module). 25 Steering Synchronization. 234 PWM Steering. 233 Steering Synchronization. 234 PVM Steering. 233 PWM Mode. See Enhanced Capture/Compare/PWM. 222 PCON (Power Control Register). 39 PWM Steering. 239 PWM Steering. 239 PIE2 (Penpheral Interrupt Enable 1). 101 PWMXCON Register. 42 RCREG Register. 42 PRCREG Register. 430 PRIE2 (Penpheral Interrupt Enable 2). 102 PRRCREG Register. 42 PRCREG Register. 430 PRCREG Register. 442 PRCREG Register. 452 PRCREG Register. 452 PRCREG Register. 452 PRCREG Register. 454 PRCREG Register. 454 PRCREG Register. 455 PRCREG Register. 455 PRCREG Register. 456 PRCREG Register. 457 PRCREG Register. 457 PRCREG Register. 458 PRCREG Register. 459 PRCREG Register. 459 PRCREG Register. 450 PR |   | LATC (Data Latch PORTC)  | 144  |
| Precision Internal Oscillator Parameters   |   |  |  |
| Program Memory   |   |  |  |
| Map and Stack (PIC16(L)F1934)  |   | LCDCON (LCD Control)   | 331  |
| Map and Stack (PIC16(L)F1937).         26         LCDDATAx (LCD Data).         335, 342           Map and Stack (PIC16F1936(L)F1936).         LCDRS (LCD Phase).         32           Map and Stack (PIC16F1936(L)F1936).         LCDRE (LCD Reference Voltage Control).         342           Programming Mode Ext         90         LCDRE (LCD Segment Enable).         355           Programming Device Instructions         .367         OPTION_REG (OPTION).         195           PSTRXCON Register         .240         OSCCON (Oscillator Control).         .83           PWM Steering         .233         OSCSTAT (Oscillator Status).         .84           PWM Steering Synchronization.         .234         PCON (Power Control Register).         .93           PWM Mode. See Enhanced Capture/Compare/PWM.         .222         PCON (Power Control).         .93           PWM Steering.         .233         PIE1 (Peripheral Interrupt Enable 2).         102           PWM XCON Register         .239         PIE2 (Peripheral Interrupt Enable 2).         102           RCREG         .300         PIR2 (Peripheral Interrupt Request 2).         105           RCREG Register.         .42         PIR3 (Peripheral Interrupt Request 2).         105           RCREG Register.         .42         PIR3 (Peripheral Interrupt Request 2).         10  | •   |  |  |
| Map and Stack (PIC16F1934/LF1934)         31         LCDPS (LCD Phase)         332           Map and Stack (PIC16F1936/LF1936)         LCDREF (LCD Reference Voltage Control)         342           Programming Mode Exit         90         LCDREF (LCD Reference Voltage Control)         342           Programming Device Instructions         367         OPTION, REG (OPTION)         195           PSTRXCON Register         240         OSCCON (Oscillator Control)         83           PWM (ECCP Module)         OSCSTAT (Oscillator Status)         94           PWM Steering         233         OSCTUNE (Oscillator Tuning)         85           Steering Synchronization         234         PCON (Power Control Register)         93           PWM Steering         233         PIE (Peripheral Interrupt Enable 2)         93           PWM Steering         233         PIE (Peripheral Interrupt Enable 2)         102           PWM Steering         239         PIE (Peripheral Interrupt Enable 2)         102           PWMSteering         239         PIE (Peripheral Interrupt Enable 2)         102           PWMSCON Register         42         PRORTA         103           RCREG Register         42         PRIS (Peripheral Interrupt Request 2)         105           Reader Response         472  |   |  |  |
| Map and Stack (PIC16F1936/LF1936)  |   |  |  |
| PIC16F1937/LF1937    31  |   |  |  |
| Programming Mode Exit         90         LCDSEn (LCD Segment Enable)         335           Programming Device Instructions         367         OPTION, REG (OPTION)         195           PSTRXCON Register         240         OSCCON (Oscillator Control)         83           PWM ECCP Module)         OSCTAT (Oscillator Status)         84           PWM Modes, See Enhanced Capture/Compare/PWM         233         OSCTUNE (Oscillator Tuning)         85           Steering Synchronization         234         PCON (Power Control)         93           PWM Steering         233         PIE1 (Peripheral Interrupt Enable 1)         101           PWMxCON Register         239         PIE2 (Peripheral Interrupt Enable 2)         102           R         PIE3 (Peripheral Interrupt Enable 3)         103           RCREG         300         PIR2 (Peripheral Interrupt Enable 3)         103           RCREG Register         42         PIR3 (Peripheral Interrupt Enable 3)         103           RCSTA Register         42         PIR3 (Peripheral Interrupt Enable 3)         106           RCSTA Register         42         PIR3 (Peripheral Interrupt Request 2)         105           Reader Response         472         PORTA         135           Reader Response         472         PORTB  |   |  |  |
| Programming, Device Instructions   367   OPTION, REG (OPTION)   195  |   |  |  |
| PSTRXCON Register  |   |  |  |
| PWM (ECCP Module)  |   |  |  |
| PVM Steering   | ŭ   | ,  |  |
| Steering Synchronization   234   PCON (Power Control Register)   93  | · ·   |  |  |
| PWM Node. See Enhanced Capture/Compare/PWM         222         PCON (Power Control)         93           PWM Steering         233         PIE1 (Peripheral Interrupt Enable 1)         101           PWMxCON Register         239         PIE2 (Peripheral Interrupt Enable 3)         103           R         1912 (Peripheral Interrupt Enable 3)         103           RCREG         300         PIR2 (Peripheral Interrupt Request 2)         105           RCSTA Register         42         PIR3 (Peripheral Interrupt Request 2)         105           RCSTA Register         42         PIR3 (Peripheral Interrupt Request 3)         106           RCSTA Register         42         PORTA         135           Reader Response         472         PORTB         140           Red-Modify-Write Operations         367         PORTC         144           Register         PORTD         147           RCREG Register         310         PORTE         150           Registers         310         PORTE         150           ADCON1 (ADC Control 0)         165         PWMxCON (Enhanced PWM Control)         230           ADRESH (ADC Result High) with ADFM = 0)         167         Special Function, Summary         39           ADRESH (ADC Result High) with ADFM = 1)   |   |  |  |
| PWM Steering         233         PIE1 (Peripheral Interrupt Enable 1)         101           PWMxCON Register         239         PIE3 (Peripheral Interrupt Enable 2)         102           R         PIR3 (Peripheral Interrupt Register 1)         104           RCREG         300         PIR3 (Peripheral Interrupt Register 1)         104           RCREG Register         42         PIR3 (Peripheral Interrupt Reguest 2)         105           RCSTA Register         42         PIR3 (Peripheral Interrupt Reguest 3)         106           RCSTA Register         42         PIR3 (Peripheral Interrupt Request 3)         105           Reader Response         472         PORTB         135           Reader Response         472         PORTB         140           Read-Modify-Write Operations         367         PORTC         144           Register         310         PORTD         147           RCREG Register         310         PORTE         150           Registers         310         PORTE         150           ADCON0 (ADC Control 0)         165         PVMXxCON (FWM Steering Control)         239           ADRESH (ADC Result High) with ADFM = 0)         167         SRCSTA (Receive Status and Control)         303           ADRESL (ADC  |   |  |  |
| PWMxCON Register   |   |  |  |
| R RCREG  |   | , , ,  |  |
| RCREG Register   | ·   | ` ' ' '  |  |
| RCREG         300         PIR2 (Peripheral Interrupt Request 2)         105           RCREG Register         42         PIR3 (Peripheral Interrupt Request 3)         106           RCSTA Register         42, 303         PORTA         135           Reader Response         472         PORTB         140           Read-Modify-Write Operations         367         PORTC         144           Register         PORTD         147           RCREG Register         310         PORTE         150           REgisters         PSTRxCON (PWM Steering Control)         240           ADCON0 (ADC Control 0)         165         PWMXCON (Enhanced PWM Control)         239           ADCON1 (ADC Control 1)         166         RCSTA (Receive Status and Control)         303           ADRESH (ADC Result High) with ADFM = 0)         167         Special Function, Summary         39           ADRESH (ADC Result Low) with ADFM = 1)         168         SRCON0 (SR Latch Control 0)         191           ADRESL (ADC Result Low) with ADFM = 1)         168         SRCON1 (SR Latch Control 0)         191           ADRESL (ADC Result Low) with ADFM = 1)         168         SSPADD (MSSP Address and Baud Rate,         192           ANSELA (PORTA Analog Select)         136         1 <sup>2</sup> C Mode)         <  | R   |  |  |
| RCREG Register         42         PIR3 (Peripheral Interrupt Request 3)         106           RCSTA Register         42, 303         PORTA         135           Reader Response         472         PORTB         140           Read-Modify-Write Operations         367         PORTD         144           Register         PORTD         147           RCREG Register         PORTD         150           Registers         PSTRXCON (PWM Steering Control)         220           ADCON0 (ADC Control 0)         165         PWMxCON (Enhanced PWM Control)         339           ADRESH (ADC Result High) with ADFM = 0)         167         Special Function, Summary         39           ADRESH (ADC Result High) with ADFM = 1)         168         RCSTA (Receive Status and Control)         191           ADRESL (ADC Result Low) with ADFM = 1)         168         SRCON0 (SR Latch Control 0)         191           ADRESL (ADC Result Low) with ADFM = 1)         168         SRCON1 (SR Latch Control 1)         192           ANSELB (PORTA Analog Select)         136         12° C Mode)         292           ANSELB (PORTB Analog Select)         141         SPCON1 (MSSP Control 1)         289           ANSELD (PORTD Analog Select)         148         SPCON3 (SSP Control 3)         291 </td <td>RCREG300</td> <td></td> <td></td>   | RCREG300  |  |  |
| RCSTA Register         42, 303         PORTA         135           Reader Response         472         PORTB         140           Read-Modify-Write Operations         367         PORTC         144           Register         PORTD         147           RCREG Register         310         PORTE         150           Registers         PSTRXCON (PWM Steering Control)         240           ADCON0 (ADC Control 0)         165         PWMXCON (Enhanced PWM Control)         239           ADCON1 (ADC Control 1)         166         RCSTA (Receive Status and Control)         303           ADRESH (ADC Result High) with ADFM = 1)         168         SRCON0 (SR Latch Control 0)         191           ADRESL (ADC Result Low) with ADFM = 1)         168         SRCON1 (SR Latch Control 1)         192           ANSELA (PORTA Analog Select)         136         1²C Mode)         292           ANSELD (PORTB Analog Select)         141         SSPCON1 (MSSP Control 1)         289           ANSELD (PORTD Analog Select)         148         SSPCON2 (SSP Control 2)         290           ANSELD (PORTE Analog Select)         151         SSPCON3 (SSP Control 3)         291           APFCON (Alternate Pin Function Control)         133         SSPMSK (SSP Mask)         292 <td>RCREG Register42</td> <td></td> <td></td>  | RCREG Register42  |  |  |
| Reader Response         472         PORTB         140           Read-Modify-Write Operations         367         PORTC         144           Register         PORTD         147           RCREG Register         310         PORTE         150           Registers         PSTRXCON (PWM Steering Control)         240           ADCON0 (ADC Control 0)         165         PWMXCON (Enhanced PWM Control)         239           ADCON1 (ADC Control 1)         166         RCSTA (Receive Status and Control)         303           ADRESH (ADC Result High) with ADFM = 0)         167         Special Function, Summary         39           ADRESH (ADC Result Low) with ADFM = 1)         168         SRCON0 (SR Latch Control 0)         191           ADRESL (ADC Result Low) with ADFM = 1)         168         SRCON1 (SR Latch Control 1)         192           ADRESL (ADC Result Low) with ADFM = 1)         168         SRCON1 (SR Latch Control 1)         192           ANSELA (PORTA Analog Select)         136         I²C Mode)         292           ANSELB (PORTB Analog Select)         141         SSPCON1 (MSSP Control 1)         289           ANSELB (PORTB Analog Select)         148         SSPCON2 (SSP Control 2)         290           APFCON (Alternate Pin Function Control)         133 <t< td=""><td>RCSTA Register42, 303</td><td></td><td></td></t<>   | RCSTA Register42, 303   |  |  |
| Register   RCREG Register  | Reader Response472  |  |  |
| Register   RCREG Register  |   | PORTB  | 135  |
| Registers  | Read-Modify-Write Operations367   |  | 135<br>140   |
| ADCON0 (ADC Control 0) 165 PWMxCON (Enhanced PWM Control) 239 ADCON1 (ADC Control 1) 166 RCSTA (Receive Status and Control) 303 ADRESH (ADC Result High) with ADFM = 0) 167 Special Function, Summary 39 ADRESH (ADC Result Low) with ADFM = 1) 168 SRCON0 (SR Latch Control 0) 191 ADRESL (ADC Result Low) with ADFM = 0) 167 SRCON1 (SR Latch Control 1) 192 ADRESL (ADC Result Low) with ADFM = 1) 168 SPADD (MSSP Address and Baud Rate, ANSELA (PORTA Analog Select) 136 SPADD (MSSP Address and Baud Rate, ANSELA (PORTB Analog Select) 141 SSPCON1 (MSSP Control 1) 289 ANSELB (PORTB Analog Select) 148 SPCON2 (SSP Control 2) 290 ANSELE (PORTE Analog Select) 151 SSPCON3 (SSP Control 3) 291 APFCON (Alternate Pin Function Control) 133 SSPMSK (SSP Mask) 292 BAUDCON (Baud Rate Control) 304 SSPSTAT (SSP Status) 288 BORCON Brown-out Reset Control) 89 STATUS 29 CCPTMRS0 (PWM Timer Selection Control 0) 237 T1CON (Timer1 Control) 205 CCPTMRS1 (PWM Timer Selection Control 1) 237 T1GCON (Timer1 Gate Control) 206 CCPXAS (CCPx Auto-Shutdown Control) 238 TRISA (Tri-State PORTA) 135 CCPxCON (ECCPx Control) 236 TRISB (Tri-State PORTA) 135 CCPxCON (ECCPx Control) 186 TRISC (Tri-State PORTD) 147 CMxCON1 (Cx Control 1) 186 TRISC (Tri-State PORTD) 147 CMxCON1 (Cx Control 1) 186 TRISC (Tri-State PORTD) 147 CMxCON1 (Cx Control 1) 186 TRISC (Tri-State PORTE) 150 Configuration Word 1 64 TXSTA (Transmit Status and Control) 302   |   | PORTC  | 135<br>140<br>144  |
| ADCON0 (ADC Control 0) 165 PWMxCON (Enhanced PWM Control) 239 ADCON1 (ADC Control 1) 166 RCSTA (Receive Status and Control) 303 ADRESH (ADC Result High) with ADFM = 0) 167 Special Function, Summary 39 ADRESH (ADC Result Low) with ADFM = 1) 168 SRCON0 (SR Latch Control 0) 191 ADRESL (ADC Result Low) with ADFM = 0) 167 SRCON1 (SR Latch Control 1) 192 ADRESL (ADC Result Low) with ADFM = 1) 168 SPADD (MSSP Address and Baud Rate, ANSELA (PORTA Analog Select) 136 SPADD (MSSP Address and Baud Rate, ANSELA (PORTB Analog Select) 141 SSPCON1 (MSSP Control 1) 289 ANSELB (PORTB Analog Select) 148 SPCON2 (SSP Control 2) 290 ANSELE (PORTE Analog Select) 151 SSPCON3 (SSP Control 3) 291 APFCON (Alternate Pin Function Control) 133 SSPMSK (SSP Mask) 292 BAUDCON (Baud Rate Control) 304 SSPSTAT (SSP Status) 288 BORCON Brown-out Reset Control) 89 STATUS 29 CCPTMRS0 (PWM Timer Selection Control 0) 237 T1CON (Timer1 Control) 205 CCPTMRS1 (PWM Timer Selection Control 1) 237 T1GCON (Timer1 Gate Control) 206 CCPXAS (CCPx Auto-Shutdown Control) 238 TRISA (Tri-State PORTA) 135 CCPxCON (ECCPx Control) 236 TRISB (Tri-State PORTA) 135 CCPxCON (ECCPx Control) 186 TRISC (Tri-State PORTD) 147 CMxCON1 (Cx Control 1) 186 TRISC (Tri-State PORTD) 147 CMxCON1 (Cx Control 1) 186 TRISC (Tri-State PORTD) 147 CMxCON1 (Cx Control 1) 186 TRISC (Tri-State PORTE) 150 Configuration Word 1 64 TXSTA (Transmit Status and Control) 302   | Register  | PORTC  | 135<br>140<br>144<br>147   |
| ADCON1 (ADC Control 1)   | Register RCREG Register310 Registers  | PORTC<br>PORTD<br>PORTE  | 135<br>140<br>144<br>147<br>150  |
| ADRESH (ADC Result High) with ADFM = 0)  | Register RCREG Register310 Registers  | PORTC PORTD PORTE PSTRxCON (PWM Steering Control)  | 135<br>140<br>144<br>147<br>150<br>240   |
| ADRESH (ADC Result High) with ADFM = 1)  | Register         310           Registers         ADCON0 (ADC Control 0)         165   | PORTC PORTD PORTE PSTRxCON (PWM Steering Control) PWMxCON (Enhanced PWM Control)   | 135<br>140<br>144<br>147<br>150<br>240<br>239  |
| ADRESL (ADC Result Low) with ADFM = 1)   | Register       310         Registers       310         ADCON0 (ADC Control 0)       165         ADCON1 (ADC Control 1)       166  | PORTC  PORTD  PORTE  PSTRxCON (PWM Steering Control)  PWMxCON (Enhanced PWM Control)  RCSTA (Receive Status and Control)   | 135<br>140<br>144<br>147<br>150<br>240<br>239<br>303   |
| ADRESL (ADC Result Low) with ADFM = 1)   | Register       310         Registers       310         ADCON0 (ADC Control 0)       165         ADCON1 (ADC Control 1)       166         ADRESH (ADC Result High) with ADFM = 0)       167  | PORTC  PORTD  PORTE  PSTRxCON (PWM Steering Control)  PWMxCON (Enhanced PWM Control)  RCSTA (Receive Status and Control)  Special Function, Summary  | 135<br>140<br>144<br>147<br>150<br>240<br>239<br>303   |
| ANSELA (PORTA Analog Select)   | Register       310         Registers       310         ADCON0 (ADC Control 0)       165         ADCON1 (ADC Control 1)       166         ADRESH (ADC Result High) with ADFM = 0)       167         ADRESH (ADC Result High) with ADFM = 1)       168  | PORTC  | 135<br>140<br>144<br>150<br>240<br>239<br>303<br>39<br>191   |
| ANSELD (PORTD Analog Select)       148       SSPCON2 (SSP Control 2)       290         ANSELE (PORTE Analog Select)       151       SSPCON3 (SSP Control 3)       291         APFCON (Alternate Pin Function Control)       133       SSPMSK (SSP Mask)       292         BAUDCON (Baud Rate Control)       304       SSPSTAT (SSP Status)       288         BORCON Brown-out Reset Control)       89       STATUS       29         CCPTMRS0 (PWM Timer Selection Control 0)       237       T1CON (Timer1 Control)       205         CCPTMRS1 (PWM Timer Selection Control 1)       237       T1GCON (Timer1 Gate Control)       206         CCPxAS (CCPx Auto-Shutdown Control)       238       TRISA (Tri-State PORTA)       135         CCPxCON (ECCPx Control)       236       TRISB (Tri-State PORTB)       140         CMOUT (Comparator Output)       186       TRISC (Tri-State PORTC)       144         CMxCON0 (Cx Control)       185       TRISD (Tri-State PORTD)       147         CMxCON1 (Cx Control 1)       186       TRISE (Tri-State PORTE)       150         Configuration Word 1       62       TXCON       211         Configuration Word 2       64       TXSTA (Transmit Status and Control)       302  | Register       310         Registers       310         ADCON0 (ADC Control 0)       165         ADCON1 (ADC Control 1)       166         ADRESH (ADC Result High) with ADFM = 0)       167         ADRESH (ADC Result High) with ADFM = 1)       168         ADRESL (ADC Result Low) with ADFM = 0)       167   | PORTC PORTD PORTE PSTRxCON (PWM Steering Control) PWMxCON (Enhanced PWM Control) RCSTA (Receive Status and Control) Special Function, Summary SRCON0 (SR Latch Control 0) SRCON1 (SR Latch Control 1)  | 135<br>140<br>144<br>150<br>240<br>239<br>303<br>39<br>191   |
| ANSELD (PORTD Analog Select)       148       SSPCON2 (SSP Control 2)       290         ANSELE (PORTE Analog Select)       151       SSPCON3 (SSP Control 3)       291         APFCON (Alternate Pin Function Control)       133       SSPMSK (SSP Mask)       292         BAUDCON (Baud Rate Control)       304       SSPSTAT (SSP Status)       288         BORCON Brown-out Reset Control)       89       STATUS       29         CCPTMRS0 (PWM Timer Selection Control 0)       237       T1CON (Timer1 Control)       205         CCPTMRS1 (PWM Timer Selection Control 1)       237       T1GCON (Timer1 Gate Control)       206         CCPxAS (CCPx Auto-Shutdown Control)       238       TRISA (Tri-State PORTA)       135         CCPxCON (ECCPx Control)       236       TRISB (Tri-State PORTB)       140         CMOUT (Comparator Output)       186       TRISC (Tri-State PORTC)       144         CMxCON0 (Cx Control)       185       TRISD (Tri-State PORTD)       147         CMxCON1 (Cx Control 1)       186       TRISE (Tri-State PORTE)       150         Configuration Word 1       62       TXCON       211         Configuration Word 2       64       TXSTA (Transmit Status and Control)       302  | Register       310         Registers       310         ADCON0 (ADC Control 0)       165         ADCON1 (ADC Control 1)       166         ADRESH (ADC Result High) with ADFM = 0)       167         ADRESH (ADC Result High) with ADFM = 1)       168         ADRESL (ADC Result Low) with ADFM = 0)       167         ADRESL (ADC Result Low) with ADFM = 1)       168  | PORTC PORTD PORTE PSTRxCON (PWM Steering Control) PWMxCON (Enhanced PWM Control) RCSTA (Receive Status and Control) Special Function, Summary SRCON0 (SR Latch Control 0) SRCON1 (SR Latch Control 1) SSPADD (MSSP Address and Baud Rate,  | 135<br>140<br>144<br>147<br>150<br>240<br>239<br>303<br>39<br>191<br>192                             |
| APFCON (Alternate Pin Function Control)       133       SSPMSK (SSP Mask)       292         BAUDCON (Baud Rate Control)       304       SSPSTAT (SSP Status)       288         BORCON Brown-out Reset Control)       89       STATUS       29         CCPTMRS0 (PWM Timer Selection Control 0)       237       T1CON (Timer1 Control)       205         CCPTMRS1 (PWM Timer Selection Control 1)       237       T1GCON (Timer1 Gate Control)       206         CCPxAS (CCPx Auto-Shutdown Control)       238       TRISA (Tri-State PORTA)       135         CCPxCON (ECCPx Control)       236       TRISB (Tri-State PORTB)       140         CMOUT (Comparator Output)       186       TRISC (Tri-State PORTC)       144         CMxCON0 (Cx Control)       185       TRISD (Tri-State PORTD)       147         CMxCON1 (Cx Control 1)       186       TRISE (Tri-State PORTE)       150         Configuration Word 1       62       TXCON       211         Configuration Word 2       64       TXSTA (Transmit Status and Control)       302  | Register       310         Registers       310         ADCON0 (ADC Control 0)       165         ADCON1 (ADC Control 1)       166         ADRESH (ADC Result High) with ADFM = 0)       167         ADRESH (ADC Result High) with ADFM = 1)       168         ADRESL (ADC Result Low) with ADFM = 0)       167         ADRESL (ADC Result Low) with ADFM = 1)       168         ANSELA (PORTA Analog Select)       136   | PORTC PORTD PORTE PSTRxCON (PWM Steering Control) PWMxCON (Enhanced PWM Control) RCSTA (Receive Status and Control) Special Function, Summary SRCON0 (SR Latch Control 0) SRCON1 (SR Latch Control 1) SSPADD (MSSP Address and Baud Rate, I <sup>2</sup> C Mode)   | 135<br>140<br>144<br>147<br>150<br>240<br>239<br>303<br>39<br>191<br>192                             |
| APFCON (Alternate Pin Function Control)       133       SSPMSK (SSP Mask)       292         BAUDCON (Baud Rate Control)       304       SSPSTAT (SSP Status)       288         BORCON Brown-out Reset Control)       89       STATUS       29         CCPTMRS0 (PWM Timer Selection Control 0)       237       T1CON (Timer1 Control)       205         CCPTMRS1 (PWM Timer Selection Control 1)       237       T1GCON (Timer1 Gate Control)       206         CCPxAS (CCPx Auto-Shutdown Control)       238       TRISA (Tri-State PORTA)       135         CCPxCON (ECCPx Control)       236       TRISB (Tri-State PORTB)       140         CMOUT (Comparator Output)       186       TRISC (Tri-State PORTC)       144         CMxCON0 (Cx Control)       185       TRISD (Tri-State PORTD)       147         CMxCON1 (Cx Control 1)       186       TRISE (Tri-State PORTE)       150         Configuration Word 1       62       TXCON       211         Configuration Word 2       64       TXSTA (Transmit Status and Control)       302  | Register       310         Registers       310         ADCON0 (ADC Control 0)       165         ADCON1 (ADC Control 1)       166         ADRESH (ADC Result High) with ADFM = 0)       167         ADRESH (ADC Result High) with ADFM = 1)       168         ADRESL (ADC Result Low) with ADFM = 0)       167         ADRESL (ADC Result Low) with ADFM = 1)       168         ANSELA (PORTA Analog Select)       136         ANSELB (PORTB Analog Select)       141  | PORTC  PORTD  PORTE  PSTRxCON (PWM Steering Control)  PWMxCON (Enhanced PWM Control)  RCSTA (Receive Status and Control)  Special Function, Summary  SRCON0 (SR Latch Control 0)  SRCON1 (SR Latch Control 1)  SPADD (MSSP Address and Baud Rate, I <sup>2</sup> C Mode)  SSPCON1 (MSSP Control 1)   | 135<br>140<br>144<br>147<br>150<br>240<br>239<br>303<br>39<br>191<br>192<br>292<br>289               |
| BORCON Brown-out Reset Control)         89         STATUS         29           CCPTMRS0 (PWM Timer Selection Control 0)         237         T1CON (Timer1 Control)         205           CCPTMRS1 (PWM Timer Selection Control 1)         237         T1GCON (Timer1 Gate Control)         206           CCPxAS (CCPx Auto-Shutdown Control)         238         TRISA (Tri-State PORTA)         135           CCPxCON (ECCPx Control)         236         TRISB (Tri-State PORTB)         140           CMOUT (Comparator Output)         186         TRISC (Tri-State PORTC)         144           CMxCON0 (Cx Control)         185         TRISD (Tri-State PORTD)         147           CMxCON1 (Cx Control 1)         186         TRISE (Tri-State PORTE)         150           Configuration Word 1         62         TXCON         211           Configuration Word 2         64         TXSTA (Transmit Status and Control)         302   | Register       310         Registers       310         ADCON0 (ADC Control 0)       165         ADCON1 (ADC Control 1)       166         ADRESH (ADC Result High) with ADFM = 0)       167         ADRESH (ADC Result High) with ADFM = 1)       168         ADRESL (ADC Result Low) with ADFM = 0)       167         ADRESL (ADC Result Low) with ADFM = 1)       168         ANSELA (PORTA Analog Select)       136         ANSELB (PORTB Analog Select)       141         ANSELD (PORTD Analog Select)       148   | PORTC  | 135<br>140<br>144<br>150<br>240<br>239<br>303<br>39<br>191<br>192<br>292<br>289<br>290               |
| BORCON Brown-out Reset Control)         89         STATUS         29           CCPTMRS0 (PWM Timer Selection Control 0)         237         T1CON (Timer1 Control)         205           CCPTMRS1 (PWM Timer Selection Control 1)         237         T1GCON (Timer1 Gate Control)         206           CCPxAS (CCPx Auto-Shutdown Control)         238         TRISA (Tri-State PORTA)         135           CCPxCON (ECCPx Control)         236         TRISB (Tri-State PORTB)         140           CMOUT (Comparator Output)         186         TRISC (Tri-State PORTC)         144           CMxCON0 (Cx Control)         185         TRISD (Tri-State PORTD)         147           CMxCON1 (Cx Control 1)         186         TRISE (Tri-State PORTE)         150           Configuration Word 1         62         TXCON         211           Configuration Word 2         64         TXSTA (Transmit Status and Control)         302   | Register       310         Registers       310         ADCON0 (ADC Control 0)       165         ADCON1 (ADC Control 1)       166         ADRESH (ADC Result High) with ADFM = 0)       167         ADRESH (ADC Result High) with ADFM = 1)       168         ADRESL (ADC Result Low) with ADFM = 0)       167         ADRESL (ADC Result Low) with ADFM = 1)       168         ANSELA (PORTA Analog Select)       136         ANSELB (PORTB Analog Select)       141         ANSELD (PORTD Analog Select)       148         ANSELE (PORTE Analog Select)       151  | PORTC  | 135<br>140<br>144<br>147<br>150<br>240<br>239<br>303<br>39<br>191<br>192<br>292<br>289<br>290        |
| CCPTMRS0 (PWM Timer Selection Control 0)       237       T1CON (Timer1 Control)       205         CCPTMRS1 (PWM Timer Selection Control 1)       237       T1GCON (Timer1 Gate Control)       206         CCPxAS (CCPx Auto-Shutdown Control)       238       TRISA (Tri-State PORTA)       135         CCPxCON (ECCPx Control)       236       TRISB (Tri-State PORTB)       140         CMOUT (Comparator Output)       186       TRISC (Tri-State PORTC)       144         CMxCON0 (Cx Control)       185       TRISD (Tri-State PORTD)       147         CMxCON1 (Cx Control 1)       186       TRISE (Tri-State PORTE)       150         Configuration Word 1       62       TXCON       211         Configuration Word 2       64       TXSTA (Transmit Status and Control)       302  | Register       310         Registers       310         ADCON0 (ADC Control 0)       165         ADCON1 (ADC Control 1)       166         ADRESH (ADC Result High) with ADFM = 0)       167         ADRESH (ADC Result High) with ADFM = 1)       168         ADRESL (ADC Result Low) with ADFM = 0)       167         ADRESL (ADC Result Low) with ADFM = 1)       168         ANSELA (PORTA Analog Select)       136         ANSELB (PORTB Analog Select)       141         ANSELD (PORTD Analog Select)       148         ANSELE (PORTE Analog Select)       151         APFCON (Alternate Pin Function Control)       133  | PORTC  | 135<br>140<br>144<br>147<br>150<br>240<br>239<br>303<br>39<br>191<br>192<br>292<br>289<br>290<br>291 |
| CCPTMRS1 (PWM Timer Selection Control 1)       237       T1GCON (Timer1 Gate Control)       206         CCPxAS (CCPx Auto-Shutdown Control)       238       TRISA (Tri-State PORTA)       135         CCPxCON (ECCPx Control)       236       TRISB (Tri-State PORTB)       140         CMOUT (Comparator Output)       186       TRISC (Tri-State PORTC)       144         CMxCON0 (Cx Control)       185       TRISD (Tri-State PORTD)       147         CMxCON1 (Cx Control 1)       186       TRISE (Tri-State PORTE)       150         Configuration Word 1       62       TXCON       211         Configuration Word 2       64       TXSTA (Transmit Status and Control)       302  | Register       310         Registers       310         ADCON0 (ADC Control 0)       165         ADCON1 (ADC Control 1)       166         ADRESH (ADC Result High) with ADFM = 0)       167         ADRESH (ADC Result High) with ADFM = 1)       168         ADRESL (ADC Result Low) with ADFM = 0)       167         ADRESL (ADC Result Low) with ADFM = 1)       168         ANSELA (PORTA Analog Select)       136         ANSELB (PORTB Analog Select)       141         ANSELD (PORTD Analog Select)       148         ANSELE (PORTE Analog Select)       151         APFCON (Alternate Pin Function Control)       133         BAUDCON (Baud Rate Control)       304  | PORTC  | 135 140 144 147 150 240 239 303 39 191 192 292 289 291 292 288                                       |
| CCPxAS (CCPx Auto-Shutdown Control)       238       TRISA (Tri-State PORTA)       135         CCPxCON (ECCPx Control)       236       TRISB (Tri-State PORTB)       140         CMOUT (Comparator Output)       186       TRISC (Tri-State PORTC)       144         CMxCON0 (Cx Control)       185       TRISD (Tri-State PORTD)       147         CMxCON1 (Cx Control 1)       186       TRISE (Tri-State PORTE)       150         Configuration Word 1       62       TXCON       211         Configuration Word 2       64       TXSTA (Transmit Status and Control)       302  | Register       310         Registers       310         ADCON0 (ADC Control 0)       165         ADCON1 (ADC Control 1)       166         ADRESH (ADC Result High) with ADFM = 0)       167         ADRESH (ADC Result High) with ADFM = 1)       168         ADRESL (ADC Result Low) with ADFM = 0)       167         ADRESL (ADC Result Low) with ADFM = 1)       168         ANSELA (PORTA Analog Select)       136         ANSELB (PORTB Analog Select)       141         ANSELD (PORTD Analog Select)       148         ANSELE (PORTE Analog Select)       151         APFCON (Alternate Pin Function Control)       133         BAUDCON (Baud Rate Control)       304         BORCON Brown-out Reset Control)       89   | PORTC  | 135 140 144 147 150 240 239 303 39 191 192 292 289 291 292 288 29                                    |
| CCPxCON (ECCPx Control)       236       TRISB (Tri-State PORTB)       140         CMOUT (Comparator Output)       186       TRISC (Tri-State PORTC)       144         CMxCON0 (Cx Control)       185       TRISD (Tri-State PORTD)       147         CMxCON1 (Cx Control 1)       186       TRISE (Tri-State PORTE)       150         Configuration Word 1       62       TXCON       211         Configuration Word 2       64       TXSTA (Transmit Status and Control)       302  | Register       310         Registers       310         ADCON0 (ADC Control 0)       165         ADCON1 (ADC Control 1)       166         ADRESH (ADC Result High) with ADFM = 0)       167         ADRESH (ADC Result Low) with ADFM = 1)       168         ADRESL (ADC Result Low) with ADFM = 0)       167         ADRESL (ADC Result Low) with ADFM = 1)       168         ANSELA (PORTA Analog Select)       136         ANSELB (PORTB Analog Select)       141         ANSELD (PORTD Analog Select)       148         ANSELE (PORTE Analog Select)       151         APFCON (Alternate Pin Function Control)       133         BAUDCON (Baud Rate Control)       304         BORCON Brown-out Reset Control)       89         CCPTMRS0 (PWM Timer Selection Control 0)       237   | PORTC  | 135 140 144 147 150 240 239 303 39 191 192 292 289 291 292 288 29 205                                |
| CMOUT (Comparator Output)       186       TRISC (Tri-State PORTC)       144         CMxCON0 (Cx Control)       185       TRISD (Tri-State PORTD)       147         CMxCON1 (Cx Control 1)       186       TRISE (Tri-State PORTE)       150         Configuration Word 1       62       TXCON       211         Configuration Word 2       64       TXSTA (Transmit Status and Control)       302  | Register       310         Registers       ADCON0 (ADC Control 0)       165         ADCON1 (ADC Control 1)       166         ADRESH (ADC Result High) with ADFM = 0)       167         ADRESH (ADC Result Low) with ADFM = 1)       168         ADRESL (ADC Result Low) with ADFM = 0)       167         ADRESL (ADC Result Low) with ADFM = 1)       168         ANSELA (PORTA Analog Select)       136         ANSELB (PORTB Analog Select)       141         ANSELD (PORTD Analog Select)       148         ANSELE (PORTE Analog Select)       151         APFCON (Alternate Pin Function Control)       133         BAUDCON (Baud Rate Control)       304         BORCON Brown-out Reset Control)       89         CCPTMRS0 (PWM Timer Selection Control 0)       237         CCPTMRS1 (PWM Timer Selection Control 1)       237  | PORTC  | 135 140 144 147 150 240 239 303 39 191 192 292 289 291 292 288 29 205 206                            |
| CMxCON0 (Cx Control)       185       TRISD (Tri-State PORTD)       147         CMxCON1 (Cx Control 1)       186       TRISE (Tri-State PORTE)       150         Configuration Word 1       62       TXCON       211         Configuration Word 2       64       TXSTA (Transmit Status and Control)       302  | Register       310         Registers       ADCON0 (ADC Control 0)       165         ADCON1 (ADC Control 1)       166         ADRESH (ADC Result High) with ADFM = 0)       167         ADRESH (ADC Result High) with ADFM = 1)       168         ADRESL (ADC Result Low) with ADFM = 0)       167         ADRESL (ADC Result Low) with ADFM = 1)       168         ANSELA (PORTA Analog Select)       136         ANSELB (PORTB Analog Select)       141         ANSELD (PORTD Analog Select)       148         ANSELE (PORTE Analog Select)       151         APFCON (Alternate Pin Function Control)       133         BAUDCON (Baud Rate Control)       304         BORCON Brown-out Reset Control)       89         CCPTMRS0 (PWM Timer Selection Control 0)       237         CCPTMRS1 (PWM Timer Selection Control 1)       237         CCPXAS (CCPx Auto-Shutdown Control)       238         CCPXCON (ECCPx Control)       236   | PORTC  | 135 140 144 147 150 240 239 303 39 191 192 292 289 291 292 288 29 205 206 135                        |
| CMxCON1 (Cx Control 1)       186       TRISE (Tri-State PORTE)       150         Configuration Word 1       62       TXCON       211         Configuration Word 2       64       TXSTA (Transmit Status and Control)       302   | Register       310         Registers       ADCON0 (ADC Control 0)       165         ADCON1 (ADC Control 1)       166         ADRESH (ADC Result High) with ADFM = 0)       167         ADRESH (ADC Result High) with ADFM = 1)       168         ADRESL (ADC Result Low) with ADFM = 0)       167         ADRESL (ADC Result Low) with ADFM = 1)       168         ANSELA (PORTA Analog Select)       136         ANSELB (PORTB Analog Select)       141         ANSELD (PORTD Analog Select)       148         ANSELE (PORTE Analog Select)       151         APFCON (Alternate Pin Function Control)       133         BAUDCON (Baud Rate Control)       304         BORCON Brown-out Reset Control)       89         CCPTMRS0 (PWM Timer Selection Control 0)       237         CCPTMRS1 (PWM Timer Selection Control 1)       237         CCPXAS (CCPx Auto-Shutdown Control)       238         CCPXCON (ECCPx Control)       236   | PORTC  | 135 140 144 147 150 240 239 303 39 191 192 292 289 291 292 288 29 205 206 135 140                    |
| Configuration Word 1         62         TXCON         211           Configuration Word 2         64         TXSTA (Transmit Status and Control)         302  | Register       310         Registers       ADCON0 (ADC Control 0)       165         ADCON1 (ADC Control 1)       166         ADRESH (ADC Result High) with ADFM = 0)       167         ADRESH (ADC Result Low) with ADFM = 1)       168         ADRESL (ADC Result Low) with ADFM = 0)       167         ADRESL (ADC Result Low) with ADFM = 1)       168         ANSELA (PORTA Analog Select)       136         ANSELB (PORTB Analog Select)       141         ANSELD (PORTD Analog Select)       148         ANSELE (PORTE Analog Select)       151         APFCON (Alternate Pin Function Control)       133         BAUDCON (Baud Rate Control)       304         BORCON Brown-out Reset Control)       89         CCPTMRS0 (PWM Timer Selection Control 0)       237         CCPTMRS1 (PWM Timer Selection Control 1)       237         CCPXAS (CCPx Auto-Shutdown Control)       238         CCPXCON (ECCPx Control)       236         CMOUT (Comparator Output)       186  | PORTC  | 135 140 144 147 150 240 239 303 39 191 192 292 289 291 292 288 29 205 206 135 140 144                |
|  | Register       310         Registers       ADCON0 (ADC Control 0)       165         ADCON1 (ADC Control 1)       166         ADRESH (ADC Result High) with ADFM = 0)       167         ADRESH (ADC Result Low) with ADFM = 1)       168         ADRESL (ADC Result Low) with ADFM = 0)       167         ADRESL (ADC Result Low) with ADFM = 1)       168         ANSELA (PORTA Analog Select)       136         ANSELB (PORTB Analog Select)       141         ANSELD (PORTD Analog Select)       148         ANSELE (PORTE Analog Select)       151         APFCON (Alternate Pin Function Control)       133         BAUDCON (Baud Rate Control)       304         BORCON Brown-out Reset Control)       89         CCPTMRS0 (PWM Timer Selection Control 0)       237         CCPTMRS1 (PWM Timer Selection Control 1)       237         CCPXAS (CCPx Auto-Shutdown Control)       238         CMCON (ECCPx Control)       236         CMOUT (Comparator Output)       186         CMXCON0 (Cx Control)       185                                   | PORTC PORTD PORTE PSTRxCON (PWM Steering Control) PWMxCON (Enhanced PWM Control) RCSTA (Receive Status and Control) Special Function, Summary SRCON0 (SR Latch Control 0) SRCON1 (SR Latch Control 1) SSPADD (MSSP Address and Baud Rate, I <sup>2</sup> C Mode) SSPCON1 (MSSP Control 1) SSPCON2 (SSP Control 2) SSPCON3 (SSP Control 3) SSPCON3 (SSP Control 3) SSPSTAT (SSP Status) STATUS T1CON (Timer1 Control) T1GCON (Timer1 Gate Control) TRISA (Tri-State PORTA). TRISB (Tri-State PORTB) TRISC (Tri-State PORTC) TRISD (Tri-State PORTD) | 135 140 144 147 150 240 239 303 39 191 192 292 299 291 292 293 291 292 295 206 135 140 144 147       |
|  | Register       310         Registers       310         ADCON0 (ADC Control 0)       165         ADCON1 (ADC Control 1)       166         ADRESH (ADC Result High) with ADFM = 0)       167         ADRESH (ADC Result Low) with ADFM = 1)       168         ADRESL (ADC Result Low) with ADFM = 1)       168         ANSELA (PORTA Analog Select)       136         ANSELB (PORTB Analog Select)       141         ANSELB (PORTD Analog Select)       148         ANSELE (PORTE Analog Select)       151         APFCON (Alternate Pin Function Control)       133         BAUDCON (Baud Rate Control)       304         BORCON Brown-out Reset Control)       89         CCPTMRS0 (PWM Timer Selection Control 0)       237         CCPTMRS1 (PWM Timer Selection Control 1)       237         CCPxAS (CCPx Auto-Shutdown Control)       238         CCPxCON (ECCPx Control)       236         CMOUT (Comparator Output)       186         CMxCON1 (Cx Control)       185         CMxCON1 (Cx Control)       186         Configuration Word 1       62 | PORTC PORTD PORTE PSTRxCON (PWM Steering Control) PWMxCON (Enhanced PWM Control) RCSTA (Receive Status and Control) Special Function, Summary SRCON0 (SR Latch Control 0) SRCON1 (SR Latch Control 1) SSPADD (MSSP Address and Baud Rate, I <sup>2</sup> C Mode) SSPCON1 (MSSP Control 1) SSPCON2 (SSP Control 2) SSPCON3 (SSP Control 3) SSPCON3 (SSP Control 3) SSPTAT (SSP Status) STATUS T1CON (Timer1 Control) T1GCON (Timer1 Gate Control) TRISA (Tri-State PORTA) TRISB (Tri-State PORTD) TRISD (Tri-State PORTD) TRISE (Tri-State PORTE)   | 135 140 144 147 150 240 239 303 39 191 192 292 298 291 292 298 291 292 298 291 135 140 144 147       |

| WDTCON (Watchdog Timer Control)              | 115     | TMR1L Register   | . 197 |
|--|---------|--|-------|
| WPUB (Weak Pull-up PORTB)                    |         | Timer2   |       |
| RESET  | 377     | Associated registers                                     | . 212 |
| Reset  | 87      | Timer2/4/6   |       |
| Reset Instruction                            | 90      | Associated registers                                     | . 212 |
| Resets                                       | 87      | Timers   |       |
| Associated Registers                         | 94      | Timer1   |       |
| Revision History                             | 461     | T1CON  | . 20  |
| ·  |         | T1GCON   |       |
| S  |         | Timer2/4/6   |       |
| Shoot-through Current                        | 232     | TXCON  | 21    |
| Software Simulator (MPLAB SIM)               |         | Timing Diagrams  |       |
| SPBRG Register                               |         | A/D Conversion   | 404   |
| SPBRGH                                       | ,       | A/D Conversion (Sleep Mode)                              |       |
| SPBRGL                                       |         | Acknowledge Sequence                                     |       |
| Special Event Trigger                        |         | Asynchronous Reception                                   |       |
| Special Function Registers (SFRs)            |         | Asynchronous Transmission                                |       |
| SPI Mode (MSSP)                              |         | Asynchronous Transmission (Back to Back)                 |       |
| Associated Registers                         | 251     | Auto Wake-up Bit (WUE) During Normal Operation           |       |
| SPI Clock                                    |         | Auto Wake-up Bit (WUE) During Sleep                      |       |
| SR Latch                                     |         | Automatic Baud Rate Calibration                          |       |
| Associated registers w/ SR Latch             |         | Baud Rate Generator with Clock Arbitration               |       |
| SRCON0 Register                              |         |  | . 21  |
| S .  |         | BRG Reset Due to SDA Arbitration During Start            | 000   |
| SRCON1 Register                              |         | Condition  |       |
| SSPADD Register                              |         | Brown-out Reset (BOR)                                    |       |
| SSPBUF Register                              |         | Brown-out Reset Situations                               | 89    |
| SSPCON Register                              |         | Bus Collision During a Repeated Start Condition          |       |
| SSPCON1 Register                             |         | (Case 1)   | . 284 |
| SSPCON2 Register                             |         | Bus Collision During a Repeated Start Condition          |       |
| SSPCON3 Register                             |         | (Case 2)   |       |
| SSPMSK Register                              |         | Bus Collision During a Start Condition (SCL = 0)         |       |
| SSPOV  |         | Bus Collision During a Stop Condition (Case 1)           |       |
| SSPOV Status Flag                            |         | Bus Collision During a Stop Condition (Case 2)           |       |
| SSPSTAT Register                             | ·       | Bus Collision During Start Condition (SDA only)          | . 282 |
| R/W Bit                                      | 257     | Bus Collision for Transmit and Acknowledge               | . 28′ |
| Stack  | 54      | CLKOUT and I/O   | . 398 |
| Accessing                                    | 54      | Clock Synchronization                                    | . 270 |
| Reset  | 56      | Clock Timing   | . 396 |
| Stack Overflow/Underflow                     | 90      | Comparator Output  | . 179 |
| STATUS Register                              | 29      | Enhanced Capture/Compare/PWM (ECCP)                      | . 402 |
| SUBWFB                                       | 379     | Fail-Safe Clock Monitor (FSCM)                           |       |
| <b>-</b>                                     |         | First Start Bit Timing                                   |       |
| Т  |         | Full-Bridge PWM Output                                   |       |
| T1CON Register                               | 39, 205 | Half-Bridge PWM Output225                                |       |
| T1GCON Register                              | 206     | I <sup>2</sup> C Bus Data                                |       |
| T2CON Register                               | 39, 47  | I <sup>2</sup> C Bus Start/Stop Bits                     |       |
| Temperature Indicator Module                 | 173     | I <sup>2</sup> C Master Mode (7-Bit Reception)           |       |
| Thermal Considerations (PIC16F/LF1934/36/37) | 394     | I <sup>2</sup> C Stop Condition Receive or Transmit Mode |       |
| Timer0                                       |         | INT Pin Interrupt  |       |
| Associated Registers                         | 195     | Internal Oscillator Switch Timing                        |       |
| Operation                                    |         | LCD Interrupt Timing in Quarter-Duty Cycle Drive         |       |
| Specifications                               |         | LCD Sleep Entry/Exit when SLPEN = 1 or CS = 00           |       |
| Timer1                                       |         | PWM Auto-shutdown  |       |
| Associated registers                         |         | Firmware Restart   |       |
| Asynchronous Counter Mode                    |         |  |       |
| Reading and Writing                          |         | PWM Direction Change                                     |       |
| Clock Source Selection                       |         | PWM Direction Change at Near 100% Duty Cycle             |       |
| Interrupt                                    |         | PWM Output (Active-High)                                 |       |
| •  |         | PWM Output (Active-Low)                                  |       |
| Operation                                    |         | Repeat Start Condition                                   |       |
| Operation During Sleep                       |         | Reset Start-up Sequence                                  |       |
| Oscillator                                   |         | Reset, WDT, OST and Power-up Timer                       |       |
| Prescaler                                    |         | Send Break Character Sequence                            |       |
| Specifications                               | 402     | SPI Master Mode (CKE = 1, SMP = 1)                       |       |
| Timer1 Gate                                  |         | SPI Mode (Master Mode)                                   |       |
| Selecting Source                             |         | SPI Slave Mode (CKE = 0)                                 |       |
| TMR1H Register                               | 197     |  |       |

| SPI Slave Mode (CKE = 1)408                        |
|--|
| Synchronous Reception (Master Mode, SREN) 317      |
| Synchronous Transmission315                        |
| Synchronous Transmission (Through TXEN) 315        |
| Timer0 and Timer1 External Clock                   |
| Timer1 Incrementing Edge201                        |
| Two Speed Start-up80                               |
| Type-A in 1/2 MUX, 1/2 Bias Drive                  |
| Type-A in 1/2 MUX, 1/3 Bias Drive                  |
| Type-A in 1/3 MUX, 1/2 Bias Drive                  |
| Type-A in 1/3 MUX, 1/3 Bias Drive                  |
| Type-A in 1/3 MOX, 1/3 Bias Drive                  |
| Type-A/Type-B in Static Drive                      |
|  |
| Type-B in 1/2 MUX, 1/2 Bias Drive                  |
| Type-B in 1/2 MUX, 1/3 Bias Drive                  |
| Type-B in 1/3 MUX, 1/2 Bias Drive                  |
| Type-B in 1/3 MUX, 1/3 Bias Drive                  |
| Type-B in 1/4 MUX, 1/3 Bias Drive                  |
| USART Synchronous Receive (Master/Slave) 406       |
| USART Synchronous Transmission (Master/Slave). 405 |
| Wake-up from Interrupt112                          |
| Timing Diagrams and Specifications                 |
| PLL Clock  |
| Timing Parameter Symbology                         |
| Timing Requirements                                |
| I <sup>2</sup> C Bus Data411                       |
| I2C Bus Start/Stop Bits410                         |
| SPI Mode409  |
| TMR0 Register39                                    |
| TMR1H Register39                                   |
| TMR1L Register                                     |
| TMR2 Register                                      |
| TRIS   |
| TRISA Register                                     |
| TRISB  |
| TRISB Register                                     |
| TRISC  |
| TRISC Register                                     |
| TRISD  |
| TRISD  |
|  |
| TRISE  |
| TRISE Register                                     |
| Two-Speed Clock Start-up Mode                      |
| TXCON (Timer2/4/6) Register211                     |
| TXREG  |
| TXREG Register42                                   |
| TXSTA Register                                     |
| BRGH Bit   |
| U  |
| _  |
| USART  |
| Synchronous Master Mode                            |
| Requirements, Synchronous Receive406               |
| Requirements, Synchronous Transmission 406         |
| Timing Diagram, Synchronous Receive 406            |
| Timing Diagram, Synchronous Transmission 405       |

| ١ | ľ | V |
|---|---|---|

| 311              |
|------------------|
| 112              |
| 90               |
| 116              |
| 116              |
| 114              |
| 401              |
| 3, 276, 278, 280 |
| 3, 276, 278, 280 |
| 115              |
| 141              |
| 65               |
| 471              |
| 14               |
|                  |

VREF. SEE ADC Reference Voltage

**NOTES:** 

#### THE MICROCHIP WEB SITE

Microchip provides online support via our WWW site at www.microchip.com. This web site is used as a means to make files and information easily available to customers. Accessible by using your favorite Internet browser, the web site contains the following information:

- Product Support Data sheets and errata, application notes and sample programs, design resources, user's guides and hardware support documents, latest software releases and archived software
- General Technical Support Frequently Asked Questions (FAQ), technical support requests, online discussion groups, Microchip consultant program member listing
- Business of Microchip Product selector and ordering guides, latest Microchip press releases, listing of seminars and events, listings of Microchip sales offices, distributors and factory representatives

# CUSTOMER CHANGE NOTIFICATION SERVICE

Microchip's customer notification service helps keep customers current on Microchip products. Subscribers will receive e-mail notification whenever there are changes, updates, revisions or errata related to a specified product family or development tool of interest.

To register, access the Microchip web site at www.microchip.com. Under "Support", click on "Customer Change Notification" and follow the registration instructions.

#### CUSTOMER SUPPORT

Users of Microchip products can receive assistance through several channels:

- · Distributor or Representative
- · Local Sales Office
- Field Application Engineer (FAE)
- · Technical Support
- · Development Systems Information Line

Customers should contact their distributor, representative or field application engineer (FAE) for support. Local sales offices are also available to help customers. A listing of sales offices and locations is included in the back of this document.

Technical support is available through the web site at: http://microchip.com/support

#### READER RESPONSE

It is our intention to provide you with the best documentation possible to ensure successful use of your Microchip product. If you wish to provide your comments on organization, clarity, subject matter, and ways in which our documentation can better serve you, please FAX your comments to the Technical Publications Manager at (480) 792-4150.

Please list the following information, and use this outline to provide us with your comments about this document.

| TO:<br>RE: | Technical Publications Manager Reader Response          | Total Pages Sent                     |
|------------|---|--------------------------------------|
|            | •   |                                      |
| FIOIII.    | Name  |                                      |
|            | CompanyAddress  | ·                                    |
|            | City / State / ZIP / Country                            |                                      |
|            | Telephone: (  | FAX: ()                              |
| Applic     | eation (optional):                                      | ·                                    |
| Would      | I you like a reply? Y N                                 |                                      |
|            | e: PIC16(L)F1934/6/7                                    | Literature Number: DS41364E          |
| Quest      | ions:   |                                      |
| 1. W       | hat are the best features of this document?             |                                      |
| _          |   |                                      |
| 2. H       | ow does this document meet your hardware and softw      | are development needs?               |
| _          |   |                                      |
| 3. D       | o you find the organization of this document easy to fo | llow? If not, why?                   |
| _          |   |                                      |
| 4. W       | hat additions to the document do you think would enha   | ance the structure and subject?      |
| _          |   |                                      |
| 5. W       | hat deletions from the document could be made witho     | ut affecting the overall usefulness? |
| _          |   | -                                    |
|            |   |                                      |
| 6. Is      | there any incorrect or misleading information (what ar  | nd where)?                           |
| _          |   |                                      |
| 7. H       | ow would you improve this document?                     |                                      |
| _          |   |                                      |
| _          |   |                                      |

### PRODUCT IDENTIFICATION SYSTEM

To order or obtain information, e.g., on pricing or delivery, refer to the factory or the listed sales office.

| PART NO.<br>Device       | T T   |
|--------------------------|---|
| Device:                  | PIC16F1934, PIC16LF1934, PIC16F1934, PIC16LF1934<br>PIC16F1936, PIC16LF1936, PIC16F1936, PIC16LF1936<br>PIC16F1937, PIC16LF1937, PIC16F1937, PIC16LF1937      |
| Tape and Reel<br>Option: | Blank = Standard packaging (tube or tray) T = Tape and Reel <sup>(1)</sup>  |
| Temperature<br>Range:    | I = -40°C to +85°C<br>E = -40°C to +125°C   |
| Package:                 | ML = Micro Lead Frame (QFN)  MV = Micro Lead Frame (UQFN) 4x4  P = Plastic DIP  PT = TQFP (Thin Quad Flatpack)  SO = SOIC  SP = Skinny Plastic DIP  SS = SSOP |
| Pattern:                 | 3-Digit Pattern Code for QTP (blank otherwise)  |

#### Examples:

- a) PIC16LF1937 I/P = Industrial temp., Plastic DIP package, low-voltage VDD limits.
- b) PIC16F1934 I/PT = Industrial temp., TQFP package, standard VDD limits.

Note 1: Tape and Reel identifier only appears in the catalog part number description. This identifier is used for ordering purposes and is not printed on the device package. Check with your Microchip Sales Office for package availability with the Tape and Reel option.



# **Worldwide Sales and Service**

#### **AMERICAS**

Corporate Office 2355 West Chandler Blvd.

Chandler, AZ 85224-6199 Tel: 480-792-7200 Fax: 480-792-7277 Technical Support:

http://www.microchip.com/

support Web Address:

www.microchip.com

Atlanta Duluth, GA

Tel: 678-957-9614 Fax: 678-957-1455

**Boston** 

Westborough, MA Tel: 774-760-0087 Fax: 774-760-0088

Chicago Itasca, IL

Tel: 630-285-0071 Fax: 630-285-0075

Cleveland

Independence, OH Tel: 216-447-0464 Fax: 216-447-0643

**Dallas** 

Addison, TX Tel: 972-818-7423 Fax: 972-818-2924

Detroit

Farmington Hills, MI Tel: 248-538-2250 Fax: 248-538-2260

Indianapolis Noblesville, IN

Tel: 317-773-8323 Fax: 317-773-5453

Los Angeles

Mission Viejo, CA Tel: 949-462-9523 Fax: 949-462-9608

Santa Clara

Santa Clara, CA Tel: 408-961-6444 Fax: 408-961-6445

Toronto

Mississauga, Ontario,

Canada

Tel: 905-673-0699 Fax: 905-673-6509

#### ASIA/PACIFIC

**Asia Pacific Office** 

Suites 3707-14, 37th Floor Tower 6, The Gateway Harbour City, Kowloon Hong Kong

Tel: 852-2401-1200 Fax: 852-2401-3431

**Australia - Sydney** Tel: 61-2-9868-6733 Fax: 61-2-9868-6755

China - Beijing Tel: 86-10-8569-7

Tel: 86-10-8569-7000 Fax: 86-10-8528-2104

**China - Chengdu** Tel: 86-28-8665-5511 Fax: 86-28-8665-7889

China - Chongqing Tel: 86-23-8980-9588 Fax: 86-23-8980-9500

**China - Hangzhou** Tel: 86-571-2819-3180 Fax: 86-571-2819-3189

China - Hong Kong SAR Tel: 852-2401-1200 Fax: 852-2401-3431

**China - Nanjing** Tel: 86-25-8473-2460

Fax: 86-25-8473-2470

**China - Qingdao** Tel: 86-532-8502-7355 Fax: 86-532-8502-7205

**China - Shanghai** Tel: 86-21-5407-5533 Fax: 86-21-5407-5066

**China - Shenyang** Tel: 86-24-2334-2829 Fax: 86-24-2334-2393

**China - Shenzhen** Tel: 86-755-8203-2660 Fax: 86-755-8203-1760

**China - Wuhan** Tel: 86-27-5980-5300 Fax: 86-27-5980-5118

**China - Xian** Tel: 86-29-8833-7252

Fax: 86-29-8833-7256 **China - Xiamen** Tel: 86-592-2388138

Fax: 86-592-2388130 China - Zhuhai

Tel: 86-756-3210040 Fax: 86-756-3210049

#### ASIA/PACIFIC

India - Bangalore

Tel: 91-80-3090-4444 Fax: 91-80-3090-4123

India - New Delhi

Tel: 91-11-4160-8631 Fax: 91-11-4160-8632

India - Pune

Tel: 91-20-2566-1512 Fax: 91-20-2566-1513

**Japan - Yokohama** Tel: 81-45-471- 6166 Fax: 81-45-471-6122

**Korea - Daegu** Tel: 82-53-744-4301 Fax: 82-53-744-4302

**Korea - Seoul** Tel: 82-2-554-7200 Fax: 82-2-558-5932 or 82-2-558-5934

Malaysia - Kuala Lumpur Tel: 60-3-6201-9857

Fax: 60-3-6201-9859

Malaysia - Penang

Tel: 60-4-227-8870 Fax: 60-4-227-4068

**Philippines - Manila** Tel: 63-2-634-9065 Fax: 63-2-634-9069

Singapore

Tel: 65-6334-8870 Fax: 65-6334-8850

**Taiwan - Hsin Chu** Tel: 886-3-6578-300 Fax: 886-3-6578-370

**Taiwan - Kaohsiung** Tel: 886-7-213-7830 Fax: 886-7-330-9305

**Taiwan - Taipei** Tel: 886-2-2500-6610 Fax: 886-2-2508-0102

**Thailand - Bangkok** Tel: 66-2-694-1351 Fax: 66-2-694-1350

#### **EUROPE**

Austria - Wels

Tel: 43-7242-2244-39 Fax: 43-7242-2244-393 Denmark - Copenhagen

Tel: 45-4450-2828

France - Paris

Tel: 33-1-69-53-63-20 Fax: 33-1-69-30-90-79

**Germany - Munich** Tel: 49-89-627-144-0 Fax: 49-89-627-144-44

Italy - Milan

Tel: 39-0331-742611 Fax: 39-0331-466781

**Netherlands - Drunen** Tel: 31-416-690399 Fax: 31-416-690340

**Spain - Madrid** Tel: 34-91-708-08-90 Fax: 34-91-708-08-91

**UK - Wokingham** Tel: 44-118-921-5869 Fax: 44-118-921-5820

05/02/11