## **Open-Drain Output Sub-Microamp Comparators**

#### **Features**

- · Low Quiescent Current: 600 nA/Comparator (typical)
- Rail-to-Rail Input:  $V_{SS}$  0.3V to  $V_{DD}$  + 0.3V
- Open-Drain Output: V<sub>OUT</sub> ≤ 10V
- Propagation Delay: 4 µs (typical, 100 mV Overdrive)
- Wide Supply Voltage Range: 1.6V to 5.5V
- Single Available in SOT-23-5, SC-70-5\* Packages
- · Available in Single, Dual and Quad
- Chip Select (CS) with MCP6548
- · Low Switching Current
- Internal Hysteresis: 3.3 mV (typical)
- Temperature Range:
  - Industrial: -40°C to +85°C
  - Extended: -40°C to +125°C

#### **Typical Applications**

- · Laptop Computers
- Mobile Phones
- Metering Systems
- Hand-held Electronics
- · RC Timers
- · Alarm and Monitoring Circuits
- Windowed Comparators
- Multi-vibrators

#### **Related Devices**

• CMOS/TTL-Compatible Output: MCP6541/2/3/4

#### **Description**

The Microchip Technology Inc. MCP6546/6R/6U/7/8/9 family of comparators, is offered in single (MCP6546, MCP6546R, MCP6546U), single with chip select (CS) (MCP6548), dual (MCP6547) and quad (MCP6549) configurations. The outputs are open-drain and are capable of driving heavy DC or capacitive loads.


These comparators are optimized for low power, single-supply application with greater than rail-to-rail input operation. The output limits supply current surges and dynamic power consumption while switching. The open-drain output of the MCP6546/6R/6U/7/8/9 family can be used as a level-shifter for up to 10V using a pull-up resistor. It can also be used as a wired-OR logic. The internal Input hysteresis eliminates output switching due to internal noise voltage, reducing current draw. These comparators operate with a single-supply voltage as low as 1.6V and draw a quiescent current of less than 1 µA/comparator.

The related MCP6541/2/3/4 family of comparators from Microchip has a push-pull output that supports rail-to-rail output swing and interfaces with CMOS/TTL logic.

\* SC-70-5 E-Temp parts are not available at this release of the data sheet.

MCP6546U SOT-23-5 is E-Temp only.

#### **Package Types**



#### 1.0 **ELECTRICAL CHARACTERISTICS**

### **Absolute Maximum Ratings †**

† Notice: Stresses above those listed under "Absolute Maximum Ratings" may cause permanent damage to the device. This is a stress rating only, and functional operation of the device, at those or any other conditions above those indicated in the operational listings of this specification, is not implied. Exposure to maximum rating conditions for extended periods may affect device reliability.

†† See Section 4.1.2 "Input Voltage and Current

#### DC CHARACTERISTICS

<b>Electrical Specifications:</b> Unless otherwise indicated, $V_{DD}$ = +1.6V to +5.5V, $V_{SS}$ = GND, $T_A$ = 25°C, $V_{IN}$ + = $V_{DD}$ /2, $V_{IN}$ - = $V_{SS}$ , $R_{PU}$ = 2.74 kΩ to $V_{PU}$ = $V_{DD}$ (Refer to Figure 1-3).								
Parameters	Sym	Min	Тур	Max	Units	Conditions		
Power Supply								
Supply Voltage	$V_{DD}$	1.6	_	5.5	V	$V_{PU} \ge V_{DD}$		
Quiescent Current (per comparator)	ΙQ	0.3	0.6	1	μA	I <sub>OUT</sub> = 0		
Input								
Input Voltage Range	$V_{CMR}$	V <sub>SS</sub> - 0.3	_	V <sub>DD</sub> + 0.3	V			
Common Mode Rejection Ratio	CMRR	55	70	_	dB	$V_{DD} = 5V$ , $V_{CM} = -0.3V$ to 5.3V		
Common Mode Rejection Ratio	CMRR	50	65	_	dB	$V_{DD} = 5V$ , $V_{CM} = 2.5V$ to 5.3V		
Common Mode Rejection Ratio	CMRR	55	70	_	dB	$V_{DD} = 5V$ , $V_{CM} = -0.3V$ to 2.5V		
Power Supply Rejection Ratio	PSRR	63	80	_	dB	$V_{CM} = V_{SS}$		
Input Offset Voltage	Vos	-7.0	±1.5	+7.0	mV	V <sub>CM</sub> = V <sub>SS</sub> (Note 1)		
Drift with Temperature	$\Delta V_{OS}/\Delta T_{A}$	_	±3	_	μV/°C	$T_A = -40$ °C to +125°C, $V_{CM} = V_{SS}$		
Input Hysteresis Voltage	V <sub>HYST</sub>	1.5	3.3	6.5	mV	V <sub>CM</sub> = V <sub>SS</sub> (Note 1)		
Linear Temp. Co.	TC <sub>1</sub>	_	6.7	_	μV/°C	$T_A = -40$ °C to +125°C, $V_{CM} = V_{SS}$ (Note 2)		
Quadratic Temp. Co.	TC <sub>2</sub>	_	-0.035	_	μV/°C <sup>2</sup>	$T_A = -40^{\circ}\text{C to } +125^{\circ}\text{C}, V_{CM} = V_{SS}$ (Note 2)		
Input Bias Current	Ι <sub>Β</sub>	_	1	_	pА	V <sub>CM</sub> = V <sub>SS</sub>		
At Temperature (I-Temp parts)	Ι <sub>Β</sub>	_	25	100	pА	$T_A = +85^{\circ}C, V_{CM} = V_{SS}$ (Note 3)		
At Temperature (E-Temp parts)	I <sub>B</sub>		1200	5000	pА	$T_A = +125$ °C, $V_{CM} = V_{SS}$ (Note 3)		
Input Offset Current	Ios		±1	_	pА	V <sub>CM</sub> = V <sub>SS</sub>		

- Note 1: The input offset voltage is the center of the input-referred trip points. The input hysteresis is the difference between the input-referred trip points.
  - 2: V<sub>HYST</sub> at differential temperatures is estimated using:  $V_{HYST}$  (T<sub>A</sub>) =  $V_{HYST}$  + (T<sub>A</sub> -25°C) TC<sub>1</sub> + (T<sub>A</sub> - 25°C)<sup>2</sup>TC<sub>2</sub>. 3: Input bias current at temperature is not tested for the SC-70-5 package.

  - 4: Do not short the output above V<sub>SS</sub> + 10V. Limit the output current to Absolute Maximum Rating of 30 mA. The minimum  $V_{PU}$  test limit was  $V_{DD}$  before Dec. 2004 (week code 52).

## DC CHARACTERISTICS (CONTINUED)

**Electrical Specifications:** Unless otherwise indicated,  $V_{DD} = +1.6V$  to +5.5V,  $V_{SS} = GND$ ,  $T_A = 25^{\circ}C$ ,  $V_{IN} + = V_{DD}/2$ ,  $V_{IN} - = V_{SS}$ ,  $R_{PLI} = 2.74$  k $\Omega$  to  $V_{PLI} = V_{DD}$  (Refer to Figure 1-3).

VIN = VSS, 1750 = 2.74 122 to Vpg = VDD (17clet to 11gate 1 σ).								
Parameters	Sym	Min	Тур	Max	Units	Conditions		
Common Mode Input Impedance	Z <sub>CM</sub>	_	10 <sup>13</sup>   4	_	$\Omega    pF$			
Differential Input Impedance	Z <sub>DIFF</sub>	_	10 <sup>13</sup>   2	_	Ω  pF			
Open-Drain Output								
Output Pull-Up Voltage	V <sub>PU</sub>	1.6		10	V	(Note 4)		
High-Level Output Current	Іон	-100	_	_	nA	$V_{DD} = 1.6V \text{ to } 5.5V, V_{PU} = 10V$ (Note 4)		
Low-Level Output Voltage	$V_{OL}$	$V_{SS}$		$V_{SS} + 0.2$	V	$I_{OUT} = 2 \text{ mA}, V_{PU} = V_{DD} = 5V$		
Short-Circuit Current	I <sub>SC</sub>	_	±1.5	_	mΑ	$V_{PU} = V_{DD} = 1.6V$ (Note 4)		
	I <sub>SC</sub>	_	30	_	mA	$V_{PU} = V_{DD} = 5.5V$ (Note 4)		
Output Pin Capacitance	C <sub>OUT</sub>	_	8	_	pF			

- **Note 1:** The input offset voltage is the center of the input-referred trip points. The input hysteresis is the difference between the input-referred trip points.
  - 2:  $V_{HYST}$  at differential temperatures is estimated using:  $V_{HYST}$  ( $T_A$ ) =  $V_{HYST}$  + ( $T_A$  -25°C)  $TC_1$  + ( $T_A$  25°C) $^2TC_2$ .
  - 3: Input bias current at temperature is not tested for the SC-70-5 package.
  - **4:** Do not short the output above V<sub>SS</sub> + 10V. Limit the output current to Absolute Maximum Rating of 30 mA. The minimum V<sub>PU</sub> test limit was V<sub>DD</sub> before Dec. 2004 (week code 52).

#### **AC CHARACTERISTICS**

**Electrical Specifications:** Unless otherwise indicated,  $V_{DD}$  = +1.6V to +5.5V,  $V_{SS}$  = GND,  $T_A$  = 25°C,  $V_{IN}$ + =  $V_{DD}$ /2, Step = 200 mV, Overdrive = 100 mV,  $R_{PU}$  = 2.74 k $\Omega$  to  $V_{PU}$  =  $V_{DD}$ , and  $C_L$  = 36 pF (Refer to Figure 1-2 and Figure 1-3).

Parameters	Sym	Min	Тур	Max	Units	Conditions
Fall Time	t <sub>F</sub>	_	0.7	_	μs	(Note 1)
Propagation Delay (High-to-Low)	t <sub>PHL</sub>	_	4.0	8.0	μs	
Propagation Delay (Low-to-High)	t <sub>PLH</sub>	_	3.0	8.0	μs	(Note 1)
Propagation Delay Skew	t <sub>PDS</sub>	_	-1.0	_	μs	(Notes 1 and 2)
Maximum Toggle Frequency	$f_{MAX}$	_	225	_	kHz	V <sub>DD</sub> = 1.6V
	$f_{MAX}$	_	165	_	kHz	V <sub>DD</sub> = 5.5V
Input Noise Voltage	E <sub>ni</sub>	_	200	_	$\mu V_{P-P}$	10 Hz to 100 kHz

Note 1: t<sub>R</sub> and t<sub>PLH</sub> depend on the load (R<sub>L</sub> and C<sub>L</sub>); these specifications are valid for the indicated load only.

**2:** Propagation Delay Skew is defined as:  $t_{PDS} = t_{PLH} - t_{PHL}$ .

## MCP6548 CHIP SELECT (CS) CHARACTERISTICS

**Electrical Specifications:** Unless otherwise indicated,  $V_{DD}$  = +1.6V to +5.5V,  $V_{SS}$  = GND,  $T_A$  = 25°C,  $V_{IN}$ + =  $V_{DD}$ /2,  $V_{IN}$ - =  $V_{SS}$ ,  $R_{PU}$  = 2.74 kΩ to  $V_{PU}$  =  $V_{DD}$ , and  $C_L$  = 36 pF (Refer to Figures 1-1 and 1-3).

<b>Parameters</b>	Sym	Min	Тур	Max	Units	Conditions			
	CS Low Specifications								
-	1				T	I			
CS Logic Threshold, Low	V <sub>IL</sub>	$V_{SS}$		0.2 V <sub>DD</sub>	V				
CS Input Current, Low	I <sub>CSL</sub>		5	-	pА	CS = V <sub>SS</sub>			
CS High Specifications									
CS Logic Threshold, High	V <sub>IH</sub>	0.8 V <sub>DD</sub>	_	$V_{DD}$	V				
CS Input Current, High	I <sub>CSH</sub>	_	1	_	pА	$\overline{\text{CS}} = V_{\text{DD}}$			
CS Input High, V <sub>DD</sub> Current	I <sub>DD</sub>	_	18	_	pА	$\overline{\text{CS}} = V_{\text{DD}}$			
CS Input High, GND Current	I <sub>SS</sub>	_	-20	_	pА	$\overline{\text{CS}} = V_{\text{DD}}$			
Comparator Output Leakage	I <sub>O(LEAK)</sub>	_	1	_	pА	$V_{OUT} = V_{SS} + 10V, \overline{CS} = V_{DD}$			
CS Dynamic Specifications									
CS Low to Comparator Output Low Turn-on Time	t <sub>ON</sub>	1	2	50	ms	$\overline{\text{CS}} = 0.2 \text{V}_{\text{DD}} \text{ to V}_{\text{OUT}} = \text{V}_{\text{DD}}/2,$ $\text{V}_{\text{IN}} = \text{V}_{\text{DD}}$			
CS High to Comparator Output High Z Turn-off Time	t <sub>OFF</sub>	_	10	_	μs	$\overline{\text{CS}}$ = 0.8V <sub>DD</sub> to V <sub>OUT</sub> = V <sub>DD</sub> /2, V <sub>IN</sub> -= V <sub>DD</sub>			
CS Hysteresis	V <sub>CS_HYST</sub>	_	0.6	_	V	$V_{DD} = 5V$			




FIGURE 1-1: Timing Diagram for the CS pin on the MCP6548.




FIGURE 1-2: Propagation Delay Timing Diagram.


#### **TEMPERATURE CHARACTERISTICS**

Electrical Specifications: Unless otherwise indicated, $V_{DD} = +1.6V$ to +5.5V and $V_{SS} = GND$ .									
Parameters	Sym	Min	Тур	Max	Units	Conditions			
Temperature Ranges									
Specified Temperature Range	T <sub>A</sub>	-40	_	+85	°C				
Operating Temperature Range	T <sub>A</sub>	-40		+125	°C	Note			
Storage Temperature Range	T <sub>A</sub>	-65	_	+150	°C				
Thermal Package Resistances									
Thermal Resistance, 5L-SC-70	$\theta_{JA}$	_	331	_	°C/W				
Thermal Resistance, 5L-SOT-23	$\theta_{JA}$	_	220.7	_	°C/W				
Thermal Resistance, 8L-MSOP	$\theta_{JA}$	_	211	_	°C/W				
Thermal Resistance, 8L-PDIP	$\theta_{JA}$	_	89.3	_	°C/W				
Thermal Resistance, 8L-SOIC	$\theta_{JA}$	_	149.5	_	°C/W				
Thermal Resistance, 14L-PDIP	$\theta_{JA}$	_	70	_	°C/W				
Thermal Resistance, 14L-SOIC	$\theta_{JA}$	_	95.3	_	°C/W				
Thermal Resistance, 14L-TSSOP	$\theta_{\sf JA}$	_	100	_	°C/W				

**Note:** The MCP6546/6R/6U/7/8/9 I-temp family operates over this extended temperature range, but with reduced performance. In any case, the Junction Temperature  $(T_J)$  must not exceed the absolute maximum specification of +150°C.

## 1.1 Test Circuit Configuration


This test circuit configuration is used to determine the AC and DC specifications.




**FIGURE 1-3:** AC and DC Test Circuit for the Open-Drain Output Comparators.

#### 2.0 TYPICAL PERFORMANCE CURVES

**Note:** The graphs and tables provided following this note are a statistical summary based on a limited number of samples and are provided for informational purposes only. The performance characteristics listed herein are not tested or guaranteed. In some graphs or tables, the data presented may be outside the specified operating range (e.g., outside specified power supply range) and therefore outside the warranted range.



**FIGURE 2-1:** Input Offset Voltage at  $V_{CM} = V_{SS}$ .



**FIGURE 2-2:** Input Offset Voltage Drift at  $V_{CM} = V_{SS}$ .







FIGURE 2-3: The MCP6546/6R/6U/7/8/9 Comparators Show No Phase Reversal.




**FIGURE 2-4:** Input Hysteresis Voltage at  $V_{CM} = V_{SS}$ .




**FIGURE 2-5:** Input Hysteresis Voltage Linear Temp. Co.  $(TC_1)$  at  $V_{CM} = V_{SS}$ .




**FIGURE 2-6:** Input Hysteresis Voltage Quadratic Temp. Co.  $(TC_2)$  at  $V_{CM} = V_{SS}$ .




**FIGURE 2-7:** Input Offset Voltage vs. Ambient Temperature at  $V_{CM} = V_{SS}$ .




**FIGURE 2-8:** Input Offset Voltage vs. Common Mode Input Voltage at  $V_{DD} = 1.6V$ .




**FIGURE 2-9:** Input Offset Voltage vs. Common Mode Input Voltage at  $V_{DD} = 5.5V$ .




**FIGURE 2-10:** Input Hysteresis Voltage vs. Ambient Temperature at  $V_{CM} = V_{SS}$ .




**FIGURE 2-11:** Input Hysteresis Voltage vs. Common Mode Input Voltage at  $V_{DD} = 1.6V$ .




**FIGURE 2-12:** Input Hysteresis Voltage vs. Common Mode Input Voltage at  $V_{DD} = 5.5V$ .



**FIGURE 2-13:** CMRR,PSRR vs. Ambient Temperature.



**FIGURE 2-14:** Input Bias Current, Input Offset Current vs. Ambient Temperature.



**FIGURE 2-15:** Quiescent Current vs. Common Mode Input Voltage at  $V_{DD} = 1.6V$ .






FIGURE 2-16: Input Bias Current, Input Offset Current vs. Common Mode Input Voltage.



**FIGURE 2-17:** Quiescent Current vs. Power Supply Voltage.



**FIGURE 2-18:** Quiescent Current vs. Common Mode Input Voltage at  $V_{DD} = 5.5V$ .




FIGURE 2-19: Supply Current vs. Pull-Up Voltage.






FIGURE 2-20: Supply Current vs. Toggle Frequency.



**FIGURE 2-21:** Output Voltage Headroom vs. Output Current at  $V_{DD} = 1.6V$ .



**FIGURE 2-22:** Supply Current vs. Pull-Up to Supply Voltage Difference.






FIGURE 2-23: Output Short Circuit Current Magnitude vs. Power Supply Voltage.



**FIGURE 2-24:** Output Voltage Headroom vs. Output Current at  $V_{DD} = 5.5V$ .


**Note:** Unless otherwise indicated,  $V_{DD}$  = +1.6V to +5.5V,  $V_{SS}$  = GND,  $T_A$  = +25°C,  $V_{IN}$ + =  $V_{DD}$ /2,  $V_{IN}$ - = GND,  $R_{PU} = 2.74 \text{ k}\Omega$  to  $V_{PU} = V_{DD}$ , and  $C_L = 36 \text{ pF}$ .



**FIGURE 2-25:** 


High-to-Low Propagation

Delay.




**FIGURE 2-26:** 

Propagation Delay Skew.




Power Supply Voltage.



**FIGURE 2-28:** 

Low-to-High Propagation


Delay.



**FIGURE 2-29:** 

Propagation Delay vs.


Ambient Temperature.




**FIGURE 2-30:** 

Propagation Delay vs. Input


Overdrive.




**FIGURE 2-31:** Propagation Delay vs. Common Mode Input Voltage at  $V_{DD} = 1.6V$ .



**FIGURE 2-32:** Propagation Delay vs. Pull-up Resistor.



**FIGURE 2-33:** Propagation Delay vs. Pull-up Voltage.



**FIGURE 2-34:** Propagation Delay vs. Common Mode Input Voltage at  $V_{DD} = 5.5V$ .




FIGURE 2-35: Propagation Delay vs. Load Capacitance.







FIGURE 2-36: Output Leakage Current  $(\overline{CS} = V_{DD})$  vs. Output Voltage (MCP6548 only).




**FIGURE 2-37:** Supply Current (Shoot-through Current) vs. Chip Select (CS) Voltage at  $V_{DD} = 1.6V$  (MCP6548 only).




**FIGURE 2-38:** Supply Current (Charging Current) vs. Chip Select (CS) pulse at  $V_{DD} = 1.6V$  (MCP6548 only).



**FIGURE 2-39:** Chip Select (CS) Step Response (MCP6548 only).



**FIGURE 2-40:** Supply Current (Shoot-through Current) vs. Chip Select (CS) Voltage at  $V_{DD} = 5.5V$  (MCP6548 only).



**FIGURE 2-41:** Supply Current (Charging Current) vs. Chip Select (CS) pulse at  $V_{DD} = 5.5V$  (MCP6548 only).




FIGURE 2-42: Input Bias Current vs. Input Voltage.

#### 3.0 PIN DESCRIPTIONS

Descriptions of the pins are listed in Table 3-1.

TABLE 3-1: PIN FUNCTION TABLE

								<del>i</del>
MCP6546	MCP6546	MCP6546R	MCP6546U	MCP6547	MCP6548	MCP6549	Symbol	Description
PDIP, SOIC, MSOP	SC-70, SOT-23	SOT-23-5	SC-70, SOT-23-5	PDIP, SOIC, MSOP	PDIP, SOIC, MSOP	PDIP, SOIC, TSSOP		
6	1	1	4	1	6	1	OUT, OUTA	Digital Output (comparator A)
2	4	4	3	2	2	2	V <sub>IN</sub> –, V <sub>INA</sub> –	Inverting Input (comparator A)
3	3	3	1	3	3	3	V <sub>IN</sub> +, V <sub>INA</sub> +	Non-inverting Input (comparator A)
7	5	2	5	8	7	4	V <sub>DD</sub>	Positive Power Supply
_	_	_	_	5	_	5	V <sub>INB</sub> +	Non-inverting Input (comparator B)
_	_	_	_	6	_	6	V <sub>INB</sub> -	Inverting Input (comparator B)
_	_	_	_	7	_	7	OUTB	Digital Output (comparator B)
_	_	_	_			8	OUTC	Digital Output (comparator C)
_	_	_	_			9	V <sub>INC</sub> -	Inverting Input (comparator C)
_	_	_				10	V <sub>INC</sub> +	Non-inverting Input (comparator C)
4	2	5	2	4	4	11	V <sub>SS</sub>	Negative Power Supply
_	_	_	_	_	_	12	V <sub>IND</sub> +	Non-inverting Input (comparator D)
						13	V <sub>IND</sub> -	Inverting Input (comparator D)
					_	14	OUTD	Digital Output (comparator D)
_	_	_	_		8		S	Chip Select
1, 5, 8	_	_	_	_	1, 5	_	NC	No Internal Connection

## 3.1 Analog Inputs

The comparator non-inverting and inverting inputs are high-impedance CMOS inputs with low bias currents.

## 3.2 CS Digital Input

This is a CMOS, Schmitt-triggered input that places the part into a low power mode of operation.

#### 3.3 Digital Outputs

The comparator outputs are CMOS, open-drain digital outputs. They are designed to make level shifting and wired-OR easy to implement.

## 3.4 Power Supply ( $V_{SS}$ and $V_{DD}$ )

The positive power supply pin ( $V_{DD}$ ) is 1.6V to 5.5V higher than the negative power supply pin ( $V_{SS}$ ). For normal operation, the other pins are at voltages between  $V_{SS}$  and  $V_{DD}$ , except the output pins which can be as high as 10V above  $V_{SS}$ .

Typically, these parts are used in a single (positive) supply configuration. In this case,  $V_{SS}$  is connected to ground and  $V_{DD}$  is connected to the supply.  $V_{DD}$  will need a local bypass capacitor (typically 0.01  $\mu$ F to 0.1  $\mu$ F) within 2 mm of the  $V_{DD}$  pin. These can share a bulk capacitor with nearby analog parts (within 100 mm), but it is not required.

**NOTES:** 

#### 4.0 APPLICATIONS INFORMATION

The MCP6546/6R/6U/7/8/9 family of push-pull output comparators are fabricated on Microchip's state-of-theart CMOS process. They are suitable for a wide range of applications requiring very low power consumption.

#### 4.1 Comparator Inputs

#### 4.1.1 PHASE REVERSAL

The MCP6546/6R/6U/7/8/9 comparator family uses CMOS transistors at the input. They are designed to prevent phase inversion when the input pins exceed the supply voltages. Figure 2-3 shows an input voltage exceeding both supplies with no resulting phase inversion.

# 4.1.2 INPUT VOLTAGE AND CURRENT LIMITS

The ESD protection on the inputs can be depicted as shown in Figure 4-1. This structure was chosen to protect the input transistors, and to minimize input bias current (IB). The input ESD diodes clamp the inputs when they try to go more than one diode drop below  $V_{SS}.$  They also clamp any voltages that go too far above  $V_{DD};$  their breakdown voltage is high enough to allow normal operation, and low enough to bypass ESD events within the specified limits.




FIGURE 4-1: Simplified Analog Input ESD Structures.

In order to prevent damage and/or improper operation of these amplifiers, the circuits they are in must limit the currents (and voltages) at the  $V_{IN}+$  and  $V_{IN}-$  pins (see Absolute Maximum Ratings  $\dagger$  at the beginning of Section 1.0 "Electrical Characteristics"). Figure 4-3 shows the recommended approach to protecting these inputs. The internal ESD diodes prevent the input pins  $(V_{IN}+$  and  $V_{IN}-)$  from going too far below ground, and the resistors  $R_1$  and  $R_2$  limit the possible current drawn out of the input pin. Diodes  $D_1$  and  $D_2$  prevent the input pin  $(V_{IN}+$  and  $V_{IN}-)$  from going too far above  $V_{DD}.$  When implemented as shown, resistors  $R_1$  and  $R_2$  also limit the current through  $D_1$  and  $D_2.$ 




FIGURE 4-2: Protecting the Analog Inputs.

It is also possible to connect the diodes to the left of resistors  $R_1$  and  $R_2.$  In this case, the currents through diodes  $D_1$  and  $D_2$  need to be limited by some other mechanism. The resistor then serves as in-rush current limiter; the DC current into the input pins (V $_{\rm IN}+$  and V $_{\rm IN}-$ ) should be very small.

A significant amount of current can flow out of the inputs when the common mode voltage ( $V_{CM}$ ) is below ground ( $V_{SS}$ ); see Figure 2-42. Applications that are high impedance may need to limit the usable voltage range.

#### 4.1.3 NORMAL OPERATION

The input stage of this family of devices uses two differential input stages in parallel, one operates at low input voltages, and the other at high input voltages. With this topology, the input voltage is 0.3V above  $V_{DD}$  and 0.3V below  $V_{SS}.$  The input offset voltage is measured at both  $V_{SS}$ - 0.3V and  $V_{DD}$ + 0.3V to ensure proper operation.

The MCP6546/6R/6U/7/8/9 family has internally-set hysteresis that is small enough to maintain input offset accuracy (<7 mV), and large enough to eliminate output chattering caused by the comparator's own input noise voltage (200  $\mu V_{P-P}$ ). Figure 4-3 illustrates this capability.




FIGURE 4-3: The MCP6546/6R/6U/7/8/9 Comparators' Internal Hysteresis Eliminates Output Chatter Caused By Input Noise Voltage.

#### 4.2 Open-Drain Output

The open-drain output is designed to make level-shifting and wired-OR logic easy to implement. The output can go as high as 10V for 9V battery-powered applications. The output stage minimizes switching current (shoot-through current from supply-to-supply) when the output changes state. See Figures 2-15, 2-18 and 2-37 through 2-41, for more information.

## 4.3 MCP6548 Chip Select (CS)

The MCP6548 is a single comparator with a Chip Select ( $\overline{\text{CS}}$ ) pin. When  $\overline{\text{CS}}$  is pulled high, the total current consumption drops to 20 pA (typical). 1 pA (typical) flows through the  $\overline{\text{CS}}$  pin, 1 pA (typical) flows through the output pin and 18 pA (typical) flows through the V<sub>DD</sub> pin, as shown in Figure 1-1. When this happens, the comparator output is put into a high-impedance state. By pulling  $\overline{\text{CS}}$  low, the comparator is enabled. If the  $\overline{\text{CS}}$  pin is left floating, the comparator will not operate properly. Figure 1-1 shows the output voltage and supply current response to a  $\overline{\text{CS}}$  pulse.

The internal  $\overline{\text{CS}}$  circuitry is designed to minimize glitches when cycling the  $\overline{\text{CS}}$  pin. This helps conserve power, which is especially important in battery-powered applications.

#### 4.4 Externally Set Hysteresis

Greater flexibility in selecting hysteresis, or input trip points, is achieved by using external resistors.

Input offset voltage ( $V_{OS}$ ) is the center (average) of the (input-referred) low-high and high-low trip points. Input hysteresis voltage ( $V_{HYST}$ ) is the difference between the same trip points. Hysteresis reduces output chattering when one input is slowly moving past the other, thus reducing dynamic supply current. It also helps in systems where it is best not to cycle between states too frequently (e.g., air conditioner thermostatic control).

#### 4.4.1 INVERTING CIRCUIT

Figure 4-4 shows an inverting circuit for a single-supply application using three resistors, besides the pull-up resistor. The resulting hysteresis diagram is shown in Figure 4-5.




FIGURE 4-4: Inverting Circuit with Hysteresis.




FIGURE 4-5: Hysteresis Diagram for the Inverting Circuit.

In order to determine the trip voltages ( $V_{THL}$  and  $V_{TLH}$ ) for the circuit shown in Figure 4-4,  $R_2$  and  $R_3$  can be simplified to the Thevenin equivalent circuit with respect to  $V_{DD}$ , as shown in Figure 4-6.




FIGURE 4-6: Thevenin Equivalent Circuit.

#### **EQUATION 4-1:**

$$R_{23} = \frac{R_2 R_3}{R_2 + R_3}$$

$$V_{23} = \frac{R_3}{R_2 + R_3} \times V_{DD}$$

Using this simplified circuit, the trip voltage can be calculated using the following equation:

#### **EQUATION 4-2:**

$$\begin{split} V_{THL} &= V_{PU} \bigg( \frac{R_{23}}{R_{23} + R_F + R_{PU}} \bigg) + V_{23} \bigg( \frac{R_F + R_{PU}}{R_{23} + R_F + R_{PU}} \bigg) \\ V_{TLH} &= V_{OL} \bigg( \frac{R_{23}}{R_{23} + R_F} \bigg) + V_{23} \bigg( \frac{R_F}{R_{23} + R_F} \bigg) \end{split}$$

 $V_{TLH}$  = trip voltage from low to high

 $V_{THI}$  = trip voltage from high to low

Figures 2-21 and 2-24 can be used to determine typical values for  $V_{OL}$ . This voltage is dependent on the output current  $I_{OL}$  as shown in Figure 4-4. This current can be determined using the equation below:

#### **EQUATION 4-3:**

$$\begin{split} I_{OL} &= I_{PU} + I_{RF} \\ I_{OL} &= \left( \frac{V_{PU} - V_{OL}}{R_{PU}} \right) + \left( \frac{V_{23} - V_{OL}}{R_{23} + R_F} \right) \end{split}$$

V<sub>OH</sub> can be calculated using the equation below:

#### **EQUATION 4-4:**

$$V_{OH} = (V_{PU} - V_{23}) \times \left(\frac{R_{23} + R_F}{R_{23} + R_F + R_{PU}}\right)$$

As explained in **Section 4.1 "Comparator Inputs"**, it is important to keep the non-inverting input below  $V_{DD}$ +0.3V when  $V_{PU} > V_{DD}$ .

#### 4.5 Supply Bypass

With this family of comparators, the power supply pin ( $V_{DD}$  for single supply) should have a local bypass capacitor (i.e., 0.01  $\mu F$  to 0.1  $\mu F$ ) within 2 mm for good edge-rate performance.

#### 4.6 Capacitive Loads

Reasonable capacitive loads (e.g., logic gates) have little impact on propagation delay (see Figure 2-27). The supply current increases with increasing toggle frequency (Figure 2-30), especially with higher capacitive loads.

#### 4.7 Battery Life

In order to maximize battery life in portable applications, use large resistors and small capacitive loads. Avoid toggling the output more than necessary. Do not use Chip Select ( $\overline{\text{CS}}$ ) too frequently, in order to conserve power. Capacitive loads will draw additional power at start-up.

#### 4.8 PCB Surface Leakage

In applications where low input bias current is critical, PCB (Printed Circuit Board) surface leakage effects need to be considered. Surface leakage is caused by humidity, dust or other contamination on the board. Under low-humidity conditions, a typical resistance between nearby traces is  $10^{12}\Omega$ . A 5V difference would cause 5 pA of current to flow. This is greater than the MCP6546/6R/6U/7/8/9 family's bias current at 25°C (1 pA, typical).

The easiest way to reduce surface leakage is to use a guard ring around sensitive pins (or traces). The guard ring is biased at the same voltage as the sensitive pin. An example of this type of layout is shown in Figure 4-7.




FIGURE 4-7: Example Guard Ring Layout for Inverting Circuit.

- For the Inverting Configuration (Figures 4-4 and 4-7):
  - a) Connect the guard ring to the non-inverting input pin (V<sub>IN</sub>+). This biases the guard ring to the same reference voltage as the comparator (e.g., V<sub>DD</sub>/2 or ground).
  - b) Connect the inverting pin (V<sub>IN</sub>–) to the input pad, without touching the guard ring.

#### 4.9 Unused Comparators

An unused amplifier in a quad package (MCP6549) should be configured as shown in Figure 4-8. This circuit prevents the output from toggling and causing crosstalk. It uses the minimum number of components and draws minimal current (see Figure 2-15 and Figure 2-18).




FIGURE 4-8: Unused Comparators.

#### 4.10 Typical Applications

#### 4.10.1 PRECISE COMPARATOR

Some applications require higher DC precision. An easy way to solve this problem is to use an amplifier (such as the MCP6041) to gain-up the input signal before it reaches the comparator. Figure 4-9 shows an example of this approach.




FIGURE 4-9: Precise Inverting Comparator.

#### 4.10.2 WINDOWED COMPARATOR

Figure 4-10 shows one approach to designing a windowed comparator. The wired-OR connection produces a high output (logic 1) when the input voltage is between  $V_{RB}$  and  $V_{RT}$  (where  $V_{RT} > V_{RB}$ ).




FIGURE 4-10: Windowed Comparator.

#### 5.0 PACKAGING INFORMATION

#### 5.1 Package Marking Information


#### 5-Lead SC-70 (MCP6546, MCP6546U)




Device	I-Temp Code	E-Temp Code
MCP6546	ACNN	Note 2
MCP6546U	BBNN	Note 2

Note 1: I-Temp parts prior to March 2005 are marked "ACN"

**2:** SC-70-5 E-Temp parts not available at this release of the data sheet.




#### 5-Lead SOT-23 (MCP6546, MCP6546R, MCP6546U)




Device	I-Temp Code	E-Temp Code
MCP6546	ACNN	GWNN
MCP6546R	AHNN	GXNN
MCP6546U		AWNN

Note: Applies to 5-Lead SOT-23



#### 8-Lead PDIP (300 mil) (MCP6546, MCP6547, MCP6548, MCP6549)






OR

Examples:




#### 8-Lead SOIC (150 mil) (MCP6546, MCP6547, MCP6548, MCP6549)





OR



Legend: XX...X Customer-specific information

Y Year code (last digit of calendar year)
YY Year code (last 2 digits of calendar year)
WW Week code (week of January 1 is week '01')

NNN Alphanumeric traceability code

e3 Pb-free JEDEC designator for Matte Tin (Sn)


This package is Pb-free. The Pb-free JEDEC designator (e3)

**Note**: In the event the full Microchip part number cannot be marked on one line, it will be carried over to the next line, thus limiting the number of available characters for customer-specific information.


### **Package Marking Information (Continued)**

8-Lead MSOP (MCP6546, MCP6547, MCP6548)








14-Lead PDIP (300 mil) (MCP6549)











Legend: XX...X Customer-specific information
Y Year code (last digit of calendar year)

YY Year code (last 2 digits of calendar year)
WW Week code (week of January 1 is week '01')

NNN Alphanumeric traceability code


e3 Pb-free JEDEC designator for Matte Tin (Sn)

\* This package is Pb-free. The Pb-free JEDEC designator (e3)


**Note**: In the event the full Microchip part number cannot be marked on one line, it will be carried over to the next line, thus limiting the number of available characters for customer-specific information.

### **Package Marking Information (Continued)**


14-Lead SOIC (150 mil) (MCP6549)




#### Example:




OR



14-Lead TSSOP (MCP6549)



Example:



Legend: XX...X Customer-specific information

Y Year code (last digit of calendar year)
YY Year code (last 2 digits of calendar year)
WW Week code (week of January 1 is week '01')

NNN Alphanumeric traceability code

e3 Pb-free JEDEC designator for Matte Tin (Sn)


This package is Pb-free. The Pb-free JEDEC designator (e3)

**Note**: In the event the full Microchip part number cannot be marked on one line, it will be carried over to the next line, thus limiting the number of available characters for customer-specific information.

© 2002-2012 Microchip Technology Inc.

## 5-Lead Plastic Small Outline Transistor (LT) [SC70]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



	Units		MILLIMETERS	3		
	Dimension Limits	MIN	NOM	MAX		
Number of Pins	N		5			
Pitch	е		0.65 BSC			
Overall Height	A	0.80	_	1.10		
Molded Package Thickness	A2	0.80	_	1.00		
Standoff	A1	0.00	_	0.10		
Overall Width	E	1.80	2.10	2.40		
Molded Package Width	E1	1.15	1.25	1.35		
Overall Length	D	1.80	2.00	2.25		
Foot Length	L	0.10	0.20	0.46		
Lead Thickness	С	0.08	_	0.26		
Lead Width	b	0.15	_	0.40		

#### Notes:


- 1. Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed 0.127 mm per side.
- 2. Dimensioning and tolerancing per ASME Y14.5M.

BSC: Basic Dimension. Theoretically exact value shown without tolerances.

Microchip Technology Drawing C04-061B

## 5-Lead Plastic Small Outline Transistor (LT) [SC70]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



RECOMMENDED LAND PATTERN

	Units	MILLIMETERS			
Dimension	Dimension Limits		NOM	MAX	
Contact Pitch	E		0.65 BSC		
Contact Pad Spacing	С		2.20		
Contact Pad Width	Х			0.45	
Contact Pad Length	Υ			0.95	
Distance Between Pads	G	1.25			
Distance Between Pads	Gx	0.20			

#### Notes:


1. Dimensioning and tolerancing per ASME Y14.5M

BSC: Basic Dimension. Theoretically exact value shown without tolerances.

Microchip Technology Drawing No. C04-2061A

## 5-Lead Plastic Small Outline Transistor (OT) [SOT-23]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



	Units		MILLIMETERS			
	Dimension Limits	MIN	NOM	MAX		
Number of Pins	N		5			
Lead Pitch	е		0.95 BSC			
Outside Lead Pitch	e1		1.90 BSC			
Overall Height	А	0.90	_	1.45		
Molded Package Thickness	A2	0.89	_	1.30		
Standoff	A1	0.00	_	0.15		
Overall Width	E	2.20	_	3.20		
Molded Package Width	E1	1.30	_	1.80		
Overall Length	D	2.70	_	3.10		
Foot Length	L	0.10	_	0.60		
Footprint	L1	0.35	_	0.80		
Foot Angle	ф	0°	_	30°		
Lead Thickness	С	0.08	_	0.26		
Lead Width	b	0.20	_	0.51		

#### Notes:


- 1. Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed 0.127 mm per side.
- 2. Dimensioning and tolerancing per ASME Y14.5M.

BSC: Basic Dimension. Theoretically exact value shown without tolerances.

Microchip Technology Drawing C04-091B

## 5-Lead Plastic Small Outline Transistor (OT) [SOT-23]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



	MILLIMETERS			
Dimension Limits		MIN	NOM	MAX
Contact Pitch	Е	0.95 BSC		
Contact Pad Spacing	С	2.80		
Contact Pad Width (X5)	Х			0.60
Contact Pad Length (X5)	Υ			1.10
Distance Between Pads	G	1.70		
Distance Between Pads	GX	0.35		
Overall Width	Z			3.90

#### Notes:


1. Dimensioning and tolerancing per ASME Y14.5M

BSC: Basic Dimension. Theoretically exact value shown without tolerances.

Microchip Technology Drawing No. C04-2091A

## 8-Lead Plastic Dual In-Line (P) - 300 mil Body [PDIP]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



	Units				
	Dimension Limits	MIN	NOM	MAX	
Number of Pins	N		8		
Pitch	е		.100 BSC		
Top to Seating Plane	A	-	_	.210	
Molded Package Thickness	A2	.115	.130	.195	
Base to Seating Plane	A1	.015	_	_	
Shoulder to Shoulder Width	E	.290	.310	.325	
Molded Package Width	E1	.240	.250	.280	
Overall Length	D	.348	.365	.400	
Tip to Seating Plane	L	.115	.130	.150	
Lead Thickness	С	.008	.010	.015	
Upper Lead Width	b1	.040	.060	.070	
Lower Lead Width	b	.014	.018	.022	
Overall Row Spacing §	eB	_	_	.430	

#### Notes:


- 1. Pin 1 visual index feature may vary, but must be located with the hatched area.
- 2. § Significant Characteristic.
- 3. Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed .010" per side.
- 4. Dimensioning and tolerancing per ASME Y14.5M.

BSC: Basic Dimension. Theoretically exact value shown without tolerances.

Microchip Technology Drawing C04-018B

#### 8-Lead Plastic Small Outline (SN) - Narrow, 3.90 mm Body [SOIC]


**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



Microchip Technology Drawing No. C04-057C Sheet 1 of 2

## 8-Lead Plastic Small Outline (SN) - Narrow, 3.90 mm Body [SOIC]

**Ste:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



Units		MILLIMETERS		
Dimension Limits		MIN	NOM	MAX
Number of Pins	N		8	
Pitch	е		1.27 BSC	
Overall Height	Α	İ	i	1.75
Molded Package Thickness	A2	1.25	i	=
Standoff §	A1	0.10	i	0.25
Overall Width	Е	6.00 BSC		
Molded Package Width	E1	3.90 BSC		
Overall Length	D	4.90 BSC		
Chamfer (Optional)	h	0.25 - 0.50		
Foot Length	L	0.40	i	1.27
Footprint	L1	1.04 REF		
Foot Angle	$\varphi$	0°	i	8°
Lead Thickness	С	0.17 - 0.25		
Lead Width	b	0.31	i	0.51
Mold Draft Angle Top	α	5° - 15°		
Mold Draft Angle Bottom	β	5°	-	15°

#### Notes:

- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. § Significant Characteristic
- 3. Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed 0.15mm per side.
- 4. Dimensioning and tolerancing per ASME Y14.5M


BSC: Basic Dimension. Theoretically exact value shown without tolerances.

REF: Reference Dimension, usually without tolerance, for information purposes only.

Microchip Technology Drawing No. C04-057C Sheet 2 of 2

## 8-Lead Plastic Small Outline (SN) - Narrow, 3.90 mm Body [SOIC]

**ote:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



RECOMMENDED LAND PATTERN

Units		MILLIMETERS		
Dimension Limits		MIN	NOM	MAX
Contact Pitch	E	1.27 BSC		
Contact Pad Spacing	С		5.40	
Contact Pad Width (X8)	X1			0.60
Contact Pad Length (X8)	Y1			1.55

#### Notes:


1. Dimensioning and tolerancing per ASME Y14.5M

BSC: Basic Dimension. Theoretically exact value shown without tolerances.

Microchip Technology Drawing No. C04-2057A

## 8-Lead Plastic Micro Small Outline Package (MS) [MSOP]


**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



Microchip Technology Drawing C04-111C Sheet 1 of 2

## 8-Lead Plastic Micro Small Outline Package (MS) [MSOP]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



	MILLIMETERS			
Dimensior	Limits	MIN	NOM	MAX
Number of Pins	N	8		
Pitch	е		0.65 BSC	
Overall Height	Α	-	-	1.10
Molded Package Thickness	A2	0.75	0.85	0.95
Standoff	A1	0.00	-	0.15
Overall Width	E	4.90 BSC		
Molded Package Width	E1	3.00 BSC		
Overall Length	D	3.00 BSC		
Foot Length	L	0.40	0.60	0.80
Footprint	L1	0.95 REF		
Foot Angle	φ	0° - 8°		
Lead Thickness	С	0.08 - 0.23		
Lead Width	b	0.22	-	0.40

#### Notes:

- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed 0.15mm per side.
- 3. Dimensioning and tolerancing per ASME Y14.5M.


BSC: Basic Dimension. Theoretically exact value shown without tolerances.

REF: Reference Dimension, usually without tolerance, for information purposes only.

Microchip Technology Drawing C04-111C Sheet 2 of 2

## 14-Lead Plastic Small Outline (SL) - Narrow, 3.90 mm Body [SOIC]


**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



Microchip Technology Drawing No. C04-065C Sheet 1 of 2

## 14-Lead Plastic Small Outline (SL) - Narrow, 3.90 mm Body [SOIC]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



Units		MILLIMETERS		
Dimension Limits		MIN	NOM	MAX
Number of Pins	N		14	
Pitch	е		1.27 BSC	
Overall Height	Α	i	-	1.75
Molded Package Thickness	A2	1.25	-	-
Standoff §	A1	0.10	-	0.25
Overall Width	Е	6.00 BSC		
Molded Package Width	E1	3.90 BSC		
Overall Length	D	8.65 BSC		
Chamfer (Optional)	h	0.25	-	0.50
Foot Length	L	0.40	-	1.27
Footprint	L1		1.04 REF	
Lead Angle	Θ	0°	-	-
Foot Angle	φ	0° - 8°		
Lead Thickness	С	0.10 - 0.25		
Lead Width	b	0.31	_	0.51
Mold Draft Angle Top	α	5°	-	15°
Mold Draft Angle Bottom	β	5°	-	15°

#### Notes:

- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. § Significant Characteristic
- Dimension D does not include mold flash, protrusions or gate burrs, which shall not exceed 0.15 mm per end. Dimension E1 does not include interlead flash or protrusion, which shall not exceed 0.25 mm per side.
- 4. Dimensioning and tolerancing per ASME Y14.5M

BSC: Basic Dimension. Theoretically exact value shown without tolerances.


REF: Reference Dimension, usually without tolerance, for information purposes only.

5. Datums A & B to be determined at Datum H.

Microchip Technology Drawing No. C04-065C Sheet 2 of 2

14-Lead Plastic Small Outline (SL) - Narrow, 3.90 mm Body [SOIC]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



RECOMMENDED LAND PATTERN

	Units		MILLIMETERS		
Dimension	Dimension Limits		NOM	MAX	
Contact Pitch	E	1.27 BSC			
Contact Pad Spacing	С		5.40		
Contact Pad Width	Х			0.60	
Contact Pad Length	Υ			1.50	
Distance Between Pads	Gx	0.67			
Distance Between Pads	G	3.90			

#### Notes:


1. Dimensioning and tolerancing per ASME Y14.5M


BSC: Basic Dimension. Theoretically exact value shown without tolerances.


Microchip Technology Drawing No. C04-2065A

## 14-Lead Plastic Thin Shrink Small Outline (ST) - 4.4 mm Body [TSSOP]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging








Microchip Technology Drawing C04-087C Sheet 1 of 2

## 14-Lead Plastic Thin Shrink Small Outline (ST) - 4.4 mm Body [TSSOP]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



	Units MILLIMETERS			S
Dimension Limits		MIN	NOM	MAX
Number of Pins	N		14	
Pitch	е		0.65 BSC	
Overall Height	Α	-	-	1.20
Molded Package Thickness	A2	0.80	1.00	1.05
Standoff	A1	0.05	-	0.15
Overall Width	E	6.40 BSC		
Molded Package Width	E1	4.30	4.40	4.50
Molded Package Length	D	4.90	5.00	5.10
Foot Length	L	0.45	0.60	0.75
Footprint	(L1)	1.00 REF		
Foot Angle	φ	0°	-	8°
Lead Thickness	С	0.09	-	0.20
Lead Width	b	0.19	-	0.30

#### Notes:

- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed 0.15mm per side.
- 3. Dimensioning and tolerancing per ASME Y14.5M


BSC: Basic Dimension. Theoretically exact value shown without tolerances.

 $\label{eq:REF:Reference} \textbf{REF: Reference Dimension, usually without tolerance, for information purposes only.}$ 

Microchip Technology Drawing No. C04-087C Sheet 2 of 2  $\,$ 

## 14-Lead Plastic Thin Shrink Small Outline (ST) - 4.4 mm Body [TSSOP]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



## RECOMMENDED LAND PATTERN

Units	N	<b>IILLIMETER</b>	S
Dimension Limits		NOM	MAX
Е	0.65 BSC		
C1		5.90	
X1			0.45
Y1			1.45
G	0.20		
	Limits E C1 X1 Y1	Limits MIN E C1 X1 Y1	Limits         MIN         NOM           E         0.65 BSC           C1         5.90           X1         Y1

#### Notes:

1. Dimensioning and tolerancing per ASME Y14.5M

BSC: Basic Dimension. Theoretically exact value shown without tolerances.

Microchip Technology Drawing No. C04-2087A

**NOTES:** 

#### APPENDIX A: REVISION HISTORY

#### **Revision G (February 2012)**

The following is the list of modifications:

- Updated the Package Types drawing to correct the device representation of the SC-70 package.
- Updated package temperatures in the Temperature Characteristics table.
- Corrected the marking information table for the 5-Lead SC-70 package (MCP6546 and MCP6546U) in Section 5.1, Package Marking Information.
- Updated the package outline drawings in Section 5.1 "Package Marking Information", to show all views for each package.
- 5. Minor editorial changes.

#### **Revision F (September 2007)**

The following is the list of modifications:

- Corrected polarity of MCP6546U SOT-23-5 pinout diagram on the first page.
- Updated package outline drawings in Section 5.1 "Package Marking Information" per Marcom.

#### Revision E (September 2006)

The following is the list of modifications:

- Added MCP6546U pinout for the SOT-23-5 package.
- 2. Clarified Absolute Maximum Analog Input Voltage and Current Specifications.
- Added application information on unused comparators.
- 4. Added disclaimer to package outline drawings.

#### Revision D (May 2006)

The following is the list of modifications:

- 1. Added E-temp parts.
- Changed minimum pull-up voltage specification (V<sub>PU</sub>) to 1.6V for parts starting Dec. 2004 (week code 52); previous parts are specified at a minimum of V<sub>DD</sub>.
- Changed V<sub>HYST</sub> temperature specifications to linear and quadratic temperature coefficients.
- Changed specifications and plots to include E-Temp parts.
- 5. Added Section 3.0 "Pin Descriptions".
- Corrected package markings (Section 5.1 "Package Marking Information").
- 7. Added Appendix A: "Revision History".

#### Revision C (May 2003)

· Undocumented changes.

#### **Revision B (December 2002)**

· Undocumented changes.

#### **Revision A (February 2002)**

· Original Release of this Document.

**NOTES:** 

## PRODUCT IDENTIFICATION SYSTEM

 $\underline{\text{To order or obtain information, e.g., on pricing or delivery, refer to the factory or the listed sales of fice.}\\$ 

PART NO.	<del>-</del> ×	Exa	ımples:	
	 perature Package ange	a)	MCP6546T-I/LT:	Tape and Reel, Industrial Temperature, 5LD SC-70.
		b)	MCP6546T-I/OT:	Tape and Reel, Industrial Temperature, 5LD SOT-23.
Device:	MCP6546: Single Comparator MCP6546T: Single Comparator (Tape and Reel) (SC-70, SOT-23, SOIC, MSOP)	c)	MCP6546-I/MS:	Tape and Reel, Industrial Temperature, 8LD MSOP.
	MCP6546RT: Single Comparator (Rotated - Tape and Reel) (SOT-23 only)	d)	MCP6546-E/P:	Extended Temperature, 8LD PDIP.
	MCP6546UT: Single Comparator (Tape and Reel) (SC-70, SOT-23)(SOT-23-5 is E-Temp only) MCP6547: Dual Comparator	e)	MCP6546-E/SN:	Extended Temperature, 8LD SOIC.
	MCP6547T: Dual Comparator (Tape and Reel for SOIC and MSOP)  MCP6548: Single Comparator with CS (Tape and Reel for SOIC and MSOP)  MCP6549: Quad Comparator  MCP6549: Quad Comparator	a)	MCP6546RT-I/OT:	Tape and Reel, Industrial Temperature, 5LD SOT23.
	MCP6549T: Quad Comparator (Tape and Reel for SOIC and TSSOP)	a)	MCP6546UT-E/LT:	Tape and Reel, Industrial Temperature, 5LD SC-70
Temperature Range:	I = -40°C to +85°C E* = -40°C to +125°C * SC-70-5 E-Temp parts not available at this release of the data sheet.	b)	MCP6546UT-E/OT:	Tape and Reel, Extended Temperature, 5LD SOT23.
Package:	LT = Plastic Package (SC-70), 5-lead OT = Plastic Small Outline Transistor (SOT-23), 5-lead	a)	MCP6547-I/MS:	Industrial Temperature, 8LD MSOP.
	MS = Plastic MSOP, 8-lead P = Plastic DIP (300 mil Body), 8-lead, 14-lead SN = Plastic SOIC (150 mil Body), 8-lead	b)	MCP6547T-I/MS:	Tape and Reel, Industrial Temperature, 8LD MSOP.
	SL = Plastic SOIC (150 mil Body), 14-lead (MCP6549) ST = Plastic TSSOP (4.4mm Body), 14-lead (MCP6549)	c)	MCP6547-I/P:	Industrial Temperature, 8LD PDIP.
		d)	MCP6547-E/SN:	Extended Temperature, 8LD SOIC.
		a)	MCP6548-I/SN:	Industrial Temperature, 8LD SOIC.
		b)	MCP6548T-I/SN:	Tape and Reel, Industrial Temperature, 8LD SOIC.
		c)	MCP6548-I/P:	Industrial Temperature, 8LD PDIP.
		d)	MCP6548-E/SN:	Extended Temperature, 8LD SOIC.
		a)	MCP6549T-I/SL:	Tape and Reel, Industrial Temperature, 14LD SOIC.
		b)	MCP6549T-E/SL:	Tape and Reel, Extended Temperature, 14LD SOIC.
		c)	MCP6549-I/P:	Industrial Temperature, 14LD PDIP.
		d)	MCP6549-E/ST:	Extended Temperature, 14LD TSSOP.

**NOTES:** 

#### Note the following details of the code protection feature on Microchip devices:

- · Microchip products meet the specification contained in their particular Microchip Data Sheet.
- Microchip believes that its family of products is one of the most secure families of its kind on the market today, when used in the
  intended manner and under normal conditions.
- There are dishonest and possibly illegal methods used to breach the code protection feature. All of these methods, to our
  knowledge, require using the Microchip products in a manner outside the operating specifications contained in Microchip's Data
  Sheets. Most likely, the person doing so is engaged in theft of intellectual property.
- Microchip is willing to work with the customer who is concerned about the integrity of their code.
- Neither Microchip nor any other semiconductor manufacturer can guarantee the security of their code. Code protection does not mean that we are guaranteeing the product as "unbreakable."

Code protection is constantly evolving. We at Microchip are committed to continuously improving the code protection features of our products. Attempts to break Microchip's code protection feature may be a violation of the Digital Millennium Copyright Act. If such acts allow unauthorized access to your software or other copyrighted work, you may have a right to sue for relief under that Act.

Information contained in this publication regarding device applications and the like is provided only for your convenience and may be superseded by updates. It is your responsibility to ensure that your application meets with your specifications. MICROCHIP MAKES NO REPRESENTATIONS OR WARRANTIES OF ANY KIND WHETHER EXPRESS OR IMPLIED, WRITTEN OR ORAL, STATUTORY OR OTHERWISE, RELATED TO THE INFORMATION, INCLUDING BUT NOT LIMITED TO ITS CONDITION, QUALITY, PERFORMANCE, MERCHANTABILITY OR FITNESS FOR PURPOSE. Microchip disclaims all liability arising from this information and its use. Use of Microchip devices in life support and/or safety applications is entirely at the buyer's risk, and the buyer agrees to defend, indemnify and hold harmless Microchip from any and all damages, claims, suits, or expenses resulting from such use. No licenses are conveyed, implicitly or otherwise, under any Microchip intellectual property rights.

#### **Trademarks**

The Microchip name and logo, the Microchip logo, dsPIC, KEELOQ, KEELOQ logo, MPLAB, PIC, PICmicro, PICSTART, PIC<sup>32</sup> logo, rfPIC and UNI/O are registered trademarks of Microchip Technology Incorporated in the U.S.A. and other countries.

FilterLab, Hampshire, HI-TECH C, Linear Active Thermistor, MXDEV, MXLAB, SEEVAL and The Embedded Control Solutions Company are registered trademarks of Microchip Technology Incorporated in the U.S.A.

Analog-for-the-Digital Age, Application Maestro, chipKIT, chipKIT logo, CodeGuard, dsPICDEM, dsPICDEM.net, dsPICworks, dsSPEAK, ECAN, ECONOMONITOR, FanSense, HI-TIDE, In-Circuit Serial Programming, ICSP, Mindi, MiWi, MPASM, MPLAB Certified logo, MPLIB, MPLINK, mTouch, Omniscient Code Generation, PICC, PICC-18, PICDEM, PICDEM.net, PICkit, PICtail, REAL ICE, rfLAB, Select Mode, Total Endurance, TSHARC, UniWinDriver, WiperLock and ZENA are trademarks of Microchip Technology Incorporated in the U.S.A. and other countries.

SQTP is a service mark of Microchip Technology Incorporated in the U.S.A.

All other trademarks mentioned herein are property of their respective companies.

© 2002-2012, Microchip Technology Incorporated, Printed in the U.S.A., All Rights Reserved.

Printed on recycled paper.

ISBN: 978-1-62076-019-2

QUALITY MANAGEMENT SYSTEM

CERTIFIED BY DNV

ISO/TS 16949:2009

Microchip received ISO/TS-16949:2009 certification for its worldwide headquarters, design and wafer fabrication facilities in Chandler and Tempe, Arizona; Gresham, Oregon and design centers in California and India. The Company's quality system processes and procedures are for its PIC® MCUs and dsPIC® DSCs, KEELOQ® code hopping devices, Serial EEPROMs, microperipherals, nonvolatile memory and analog products. In addition, Microchip's quality system for the design and manufacture of development systems is ISO 9001:2000 certified.



## **Worldwide Sales and Service**

#### **AMERICAS**

**Corporate Office** 

2355 West Chandler Blvd. Chandler, AZ 85224-6199 Tel: 480-792-7200 Fax: 480-792-7277 Technical Support:

http://www.microchip.com/

support

Web Address: www.microchip.com

Atlanta

Duluth, GA Tel: 678-957-9614 Fax: 678-957-1455

**Boston** 

Westborough, MA Tel: 774-760-0087 Fax: 774-760-0088

Chicago Itasca, IL

Tel: 630-285-0071 Fax: 630-285-0075

Cleveland

Independence, OH Tel: 216-447-0464 Fax: 216-447-0643

**Dallas** 

Addison, TX Tel: 972-818-7423 Fax: 972-818-2924

Detroit

Farmington Hills, MI Tel: 248-538-2250 Fax: 248-538-2260

Indianapolis Noblesville, IN

Tel: 317-773-8323 Fax: 317-773-5453

Los Angeles

Mission Viejo, CA Tel: 949-462-9523 Fax: 949-462-9608

Santa Clara

Santa Clara, CA Tel: 408-961-6444 Fax: 408-961-6445

Toronto

Mississauga, Ontario,

Canada

Tel: 905-673-0699 Fax: 905-673-6509

#### ASIA/PACIFIC

**Asia Pacific Office** 

Suites 3707-14, 37th Floor Tower 6, The Gateway Harbour City, Kowloon Hong Kong

Tel: 852-2401-1200 Fax: 852-2401-3431

**Australia - Sydney** Tel: 61-2-9868-6733

Fax: 61-2-9868-6755

China - Beijing

Tel: 86-10-8569-7000 Fax: 86-10-8528-2104

China - Chengdu

Tel: 86-28-8665-5511 Fax: 86-28-8665-7889

China - Chongqing

Tel: 86-23-8980-9588 Fax: 86-23-8980-9500

China - Hangzhou

Tel: 86-571-2819-3187 Fax: 86-571-2819-3189

China - Hong Kong SAR

Tel: 852-2401-1200 Fax: 852-2401-3431

China - Nanjing Tel: 86-25-8473-2460

Fax: 86-25-8473-2470

China - Qingdao

Tel: 86-532-8502-7355 Fax: 86-532-8502-7205

China - Shanghai Tel: 86-21-5407-5533

Fax: 86-21-5407-5066

China - Shenyang

Tel: 86-24-2334-2829 Fax: 86-24-2334-2393

China - Shenzhen

Tel: 86-755-8203-2660 Fax: 86-755-8203-1760

China - Wuhan

Tel: 86-27-5980-5300 Fax: 86-27-5980-5118

China - Xian

Tel: 86-29-8833-7252 Fax: 86-29-8833-7256

China - Xiamen

Tel: 86-592-2388138 Fax: 86-592-2388130

China - Zhuhai

Tel: 86-756-3210040 Fax: 86-756-3210049

#### ASIA/PACIFIC

India - Bangalore

Tel: 91-80-3090-4444 Fax: 91-80-3090-4123

India - New Delhi

Tel: 91-11-4160-8631 Fax: 91-11-4160-8632

India - Pune

Tel: 91-20-2566-1512 Fax: 91-20-2566-1513

Japan - Osaka

Tel: 81-66-152-7160 Fax: 81-66-152-9310

Japan - Yokohama

Tel: 81-45-471- 6166 Fax: 81-45-471-6122

Korea - Daegu

Tel: 82-53-744-4301 Fax: 82-53-744-4302

Korea - Seoul

Tel: 82-2-554-7200 Fax: 82-2-558-5932 or 82-2-558-5934

Malaysia - Kuala Lumpur

Tel: 60-3-6201-9857 Fax: 60-3-6201-9859

Malaysia - Penang Tel: 60-4-227-8870

Fax: 60-4-227-4068

Philippines - Manila

Tel: 63-2-634-9065 Fax: 63-2-634-9069

Singapore

Tel: 65-6334-8870 Fax: 65-6334-8850

Taiwan - Hsin Chu

Tel: 886-3-5778-366 Fax: 886-3-5770-955

Taiwan - Kaohsiung

Tel: 886-7-536-4818 Fax: 886-7-330-9305

Taiwan - Taipei

Tel: 886-2-2500-6610 Fax: 886-2-2508-0102

Thailand - Bangkok

Tel: 66-2-694-1351 Fax: 66-2-694-1350

#### **EUROPE**

Austria - Wels

Tel: 43-7242-2244-39 Fax: 43-7242-2244-393 Denmark - Copenhagen

Tel: 45-4450-2828

Fax: 45-4485-2829

France - Paris

Tel: 33-1-69-53-63-20 Fax: 33-1-69-30-90-79

**Germany - Munich** 

Tel: 49-89-627-144-0 Fax: 49-89-627-144-44

Italy - Milan

Tel: 39-0331-742611 Fax: 39-0331-466781

Netherlands - Drunen

Tel: 31-416-690399 Fax: 31-416-690340

Spain - Madrid

Tel: 34-91-708-08-90 Fax: 34-91-708-08-91

**UK - Wokingham** Tel: 44-118-921-5869 Fax: 44-118-921-5820

11/29/11

## **Mouser Electronics**

**Authorized Distributor** 

Click to View Pricing, Inventory, Delivery & Lifecycle Information:

## Microchip:

MCP6548-I/P MCP6549T-I/SL MCP6549T-I/ST MCP6548T-I/SN MCP6547-I/P MCP6548T-I/MS MCP6547-I/MS MCP6547-I/SN MCP6549-I/P MCP6546RT-I/OT MCP6549-I/ST MCP6549-I/SL MCP6546-I/P MCP6546-I/MS MCP6546-I/SN MCP6546T-I/LT MCP6546T-I/SN MCP6547T-I/SN MCP6546T-I/OT MCP6546T-I/MS MCP6548T-I/MS MCP6546T-I/MS MCP6546T-I/MS MCP6548T-I/MS MCP6548T-I/MS MCP6549T-I/MS M